The pdp64 Architecture Manual

A 64-bit extension of the PDP-11

Digital Equity Collective's Pragmatic Digital Processor, 64 bit

David Walther

Copyright © 2026 David Walther. Released under the BSD 2-Clause licence (the file `COPYING` of the repository).
The source of this book is https://github.com/moebiusV/pdp64 (`docs/manual/`, the manual of each member in `docs/manual/pdp64-r20/`, `pdp64-16/`, `pdp64-32/`); the instruction dictionary is generated from the machine-readable specification. Typeset with Typst in EB Garamond and DejaVu Sans Mono.

CONTENTS

About this manual ..... **ii**
Part I — The architecture **1**
Chapter 1 — Introduction 2
Chapter 2 — The bus 7
Chapter 3 — Graphics: the terminal and its devices 24
Chapter 4 — Boot, the BIOS, the disk label and the GPT 58
Chapter 5 — The device driver model 79
Chapter 6 — The kernel: modes, exceptions and memory management 97
Chapter 7 — Multiple processors 117
Chapter 8 — Vector work, AI and array languages: the device route 122
Chapter 9 — The instruction set 126
Chapter 10 — Conclusion: from FPGA to silicon 454
Part II — The instruction reference tables **457**
The instruction reference tables 458
The second page: one-parcel abbreviations 459
Assembler aliases and old spellings 461
The architectural constants 462
The mnemonics, alphabetically 465
The opcodes, in order 471
The bit layouts of every opcode 474
Part III — Appendices **511**
Appendix A — Possible improvements not decided on 512
Appendix B — Decisions pending 515
Appendix C — Glossary 521
Appendix D — The ABI, version 1 525
Appendix E — The assembly language and the object format 526
Appendix F — The evidence behind the manual 528
Appendix G — The evolution of the design 530

About this manual

Each section is a few numbered aphorisms followed by a commentary. The aphorisms say what is true of the machine, in plain short statements, and read on their own as the main text. The commentary under them gives, as they apply: the *Precedent* (what earlier machines did), the *Trade-offs* (what the choice costs), the *Improvements* (how the pdp64 departs from the precedent), the *Benefits*, the *Modern comparables* (what current architectures do), and, for an instruction that is not obvious, its *Use*. Every decision also carries an *Impact* line saying what it means for an efficient **kernel**, for efficient **compilation** and for an efficient **hardware layout**: the three things a processor designer asks of a choice. An instruction as plain as `MOV` or `ADD` needs no statement of use. The reference entries follow the layout of the classic CPU manuals, in which every instruction has its encoding diagram, its operation and its effects.

Each aphorism carries a status. *(D)* means decided. *(P)* means a proposal that is not decided. *(S)* means a stub: the statement names what is left unspecified. An aphorism with no tag describes the architecture as it is built and tested.

Numbers. Where a figure is measured, the text says what was measured; where it is an estimate, it says so. Claims about other machines are checked against the fact-check record listed in appendix F.

The PDF. The same text as a book, `book/pdp64-r20.pdf`, built by buildabook and Typst from the sources of this directory (`tools/mkbook.sh`; see `book/README.md`).

Evidence documents. All of them are listed in appendix F: the full instruction set text (`../pdp64-isa.md`), the record of decisions (`../errata.md`) and the open decisions with five options each (`../decisions-pending.md`).

Part I — The architecture

Chapter 1 — Introduction

The pdp64 is a 64-bit successor to the PDP-11, designed to be as pleasant to program as the PDP-11 and the VAX-11 were, and as small to build as the PDP-11 was. It is a little-endian machine with sixteen 64-bit registers, instructions of two, four or six bytes, and the PDP-11's addressing modes and branches, brought up to date with what fifty years of compilers and operating systems have shown to matter. It is a 64-bit machine that supports several cores from the start (symmetric multiprocessing, chapter 7), and it is designed to be efficient with in-order and out-of-order execution implementations (1.4.4). Sections 1.1 to 1.4 give the reasons for the machine, what made its ancestors good, and the principles the rest of the manual follows; section 1.8 says how the pdp64 and the encodings tested against it relate.

1.1 Why the machine exists

1.1.1 The PDP-11 and the VAX-11 were pleasant, even fun, to program in assembly language.

1.1.2 Afterward computer design went in many directions, and that pleasure was largely lost.

1.1.3 The pdp64 carries it forward, using the lessons of the last fifty years: which instructions are needed to get things done and which are not, what a processor is used for, and which instructions it needs the most.

1.1.4 The PDP-11 is a source, not an obligation. What earned its place is kept, what did not is dropped, and what fifty years showed to be missing is added.

Commentary. **Precedent.** The claim in 1.1.1 is old and widely made of the PDP-11: a small, regular instruction set that a programmer could learn in a week and keep in mind, with a set of addressing modes that fit the C language so closely that the language and the machine seem to have grown together. **Improvements.** Measurements contradict several received ideas. A second unsigned multiply is the same instruction as the first, while the instruction that returns the *high half* of a product is the one multi-precision arithmetic needs. A rotate by a register count has almost no users, because cryptographic code rotates by constants. A divide is rare, because compilers turn division by a constant into a multiply and a shift. Dedicated absolute-value, minimum and maximum instructions are worth under a tenth of a percent of compiled code. And CRC instructions become unnecessary once a carry-less multiply exists. **Benefits.** A machine built on these findings is small enough for a single engineer to hold in mind, and, as later chapters show, small enough to fit in a modest FPGA. **Modern comparables.** The same re-examination produced the RISC designs of the 1980s and, more recently, the compact RISC-V and LoongArch instruction sets; the pdp64 differs by keeping the PDP-11's memory operands, addressing modes and variable-length encoding where those were found to save code and to cost little. **A thread between the two lineages.** The pdp64 joins a DEC machine's instruction set to a Commodore machine's devices, and the two companies are linked by at least one person: Ira Velinsky, the industrial designer credited with modifying the Commodore 64's case, had earlier worked at Digital Equipment Corporation (he is credited there with the Rainbow 100 of 1981), and a Commodore history credits his DEC work with drawing the attention of Commodore's management. The author predicted such a link before finding it. The hypothesis he draws from it is that personnel passed between the two companies and that the similarities between the C64 and the PDP-11 are too many to be chance *(P)*; the source itself claims only the person, and no influence of DEC designs on Commodore's, and the similarities are not yet listed with sources (the record is in `docs/c64-devices-from-chat.md`, section 8).

1.2 What made the PDP-10, the PDP-11 and the VAX-11 good to program

1.2.1 The PDP-10 gave a programmer one word per instruction that said everything: the operation, the register, the index register, the indirect bit and the address.

1.2.2 The PDP-10's registers were also memory: the sixteen accumulators answered to the addresses 0 to 15.

1.2.3 The PDP-10 had half-word and byte operations, stack and skip instructions, and a procedure call that was one instruction.

1.2.4 The PDP-11 made every instruction and every addressing mode available with every register, so that the language had few exceptions to remember.

1.2.5 The PDP-11's program counter and stack pointer were ordinary registers, and its autoincrement and autodecrement modes made `*p++` and `*--p` single instructions.

1.2.6 The PDP-11 had no input or output instructions: a device was a few memory locations, and a driver was an ordinary program.

1.2.7 The VAX-11 widened the PDP-11 to 32 bits and added three-operand arithmetic, a complete virtual-memory system, and instructions for the jobs programs actually do: procedure calls, queues, character strings, array indexing and polynomial evaluation.

Commentary. **Precedent.** These are the qualities the design starts from. The PDP-10's simplicity of format and its habit of making the machine's own state addressable (1.2.1, 1.2.2) are the origin of the idea that the machine should hold together in the head. The PDP-11's orthogonality (1.2.4) is the property that mattered most to assembly programmers and, later, to compiler writers: an instruction that takes a register takes an address, an immediate or a stack slot with the same syntax. Its memory-mapped devices (1.2.6) are the reason the pdp64's devices are still memory locations in the one address space (chapters 2 and 5). **Trade-offs.** Each of these qualities had a price that the later machines paid. The VAX-11's richness (1.2.7) bought programmability and cost an unbounded amount of hidden state in its longest instructions, so that a page fault in the middle of a character move could not be resumed without a special bit in the status word. The Motorola 68000, which took the PDP-11's orthogonality and widened it, could not restart an instruction after a bus error and so could not support demand-paged virtual memory until its successor patched the problem. **Improvements.** The pdp64 keeps what made programming pleasant and removes what made implementation hard: no hidden instruction state (every instruction can be restarted), at most one memory operand, a fixed small maximum instruction length, and no mode bits that change what unrelated instructions mean unless their benefit outweighs the cost. **Benefits.** The measurements in the instruction-set chapter show where this paid off: the processor fits in about 16,000 FPGA lookup tables and the compiler's code is the size of `gcc -Os`. **Modern comparables.** Of today's architectures, x86-64 kept the memory operands and variable-length encoding of this lineage; AArch64 and RISC-V chose fixed-length register-to-register encodings; the pdp64 sits between them, closer to x86 in the form of its instructions and closer to RISC-V in the discipline of its encoding.

1.3 More minimal than its ancestors, where hindsight allows

1.3.1 In several ways the pdp64 is more minimal than the PDP-11 and the VAX-11: it gives up theoretical completeness where fifty years of use showed the completeness was never exercised, and it spends what that saves on power that was.

1.3.2 Not every instruction works with every addressing mode on every operand: at most one operand of an instruction is a memory reference. *(D)*

1.3.3 The deferred addressing modes are gone; an indirection is a `JMPI`, a `CALLI` or an ordinary load. *(D)*

1.3.4 The ALU has one width, there is no arithmetic in the narrow sizes, and there is no conversion opcode group: conversions are moves. *(D)*

1.3.5 There is one rotate direction, and no slot exists only to complete a table.

1.3.6 The VAX's packed decimal, string editing and `CALLS`/`CALLG` procedure-call instructions are absent. *(D)*

1.3.7 There are no transcendental instructions, no separate floating-point register file and no rounding-mode bits. *(D)*

1.3.8 What the saving buys is power that programs use: a bit unit (population count, count of leading and trailing zeros, byte reversal, bitfields, a carry-less multiply), block operations that restart from their registers, a fused multiply-add with the IEEE exception flags, the full set of atomics, UTF-8 instructions, and a user-memory guard. *(D)*

Commentary. **Precedent.** The PDP-11 was orthogonal, any operation with any mode on any register, and the VAX carried that to completeness: every operation in every data type, with up to six operands, each operand of any mode. Both were designed when memory was dear and compilers were weak, and the completeness did two things at once: it made assembly programming regular and pleasant, and it made a compiler's job simple. **Trade-offs.** The completeness was never free. It bought a decoder that had to parse specifier after specifier before the next instruction's address was known, and an instruction that could fault in the middle with unbounded state to save. What hindsight lets the pdp64 do is separate the two benefits: keep the regularity that programmers and compilers use (every register is general, every mode means the same thing everywhere it is allowed) and drop the completeness that nobody exercised (a memory-to-memory arithmetic instruction,

a deferred mode on every operand, a sized version of every operation). The price is a few more instructions in rare cases, such as a load and a store where the VAX had one memory-to-memory move. **Improvements.** Each piece of dropped completeness was weighed against what it freed: the one memory operand lets the fault matrix collapse to three rows with the third empty and pays for sixteen registers and a 12-bit displacement in the same parcel; dropping the sized ALU removes byte-lane multiplexing and partial-register writes altogether; dropping the transcendentals leaves the `FMA` datapath, which is what accurate library maths is built from. **Benefits.** The decoder is small, the exception machinery is small, and the die area that completeness would have used goes to a bit unit and a block-move sequencer that together cost less than 5% of the core. **Modern comparables.** The RISC machines of the 1980s went further and made every instruction register to register except loads and stores; x86 kept one memory operand and survived on it; the pdp64 takes the middle position, which keeps the compact code of a memory operand and the restartability of a load/store design.

1.4 The principles

1.4.1 The design follows these priorities, in this order: **security and safety**, meaning errors that can never arise, then errors that are easy to detect, then errors that are cheap to recover from (restart and recovery go together, and an instruction does what its name says and nothing else); **opcode choice**, so that fewer instructions executed means fewer memory fetches; **opcode encoding**, dense, with rare instructions in longer encodings; **speed and power**, served by a low gate count; a **good compiler target**; and **pleasant in assembler**. *(D)*

1.4.2 All the rules are soft rules: a rule gives way when breaking it is worth more than it costs, with the cost written down. *(D)*

1.4.3 Between two designs that both work, prefer by this order: the one with no strange side effects (an instruction does what its name says and nothing else); the one that does not push an existing instruction into a longer encoding. Beside the ranking, at every level, do not multiply entities without benefit. Mode bits are decided case by case: by default a mode is visible state, and a bit in a register that is saved anyway costs nothing extra.

1.4.4 The architecture is designed to be efficient with in-order and out-of-order implementations. The first implementations are in order; nothing is specified in a way that is safe only because the core does not speculate or reorder, and nothing is specified that an out-of-order core could implement only at a large cost. *(D)*

1.4.5 An instruction is judged by its weight in the loops where it is used, not by how often it appears: a rarely used instruction that sits inside a critical, tight hot loop can earn its place. The measure is profile-weighted (executions multiplied by the instructions and bytes it saves), not a static count. *(D)*

Commentary. **Precedent.** Security and safety rank first; opcode choice and encoding, which cut memory fetches, rank next, then speed and power with the gate count that serves them. The priorities agree on almost everything, because a small, regular machine is also compact in code and cheap in gates; the stated order decides which wins when they conflict. Code size here means the instructions a program executes and the bytes it fetches, not the number of opcodes the machine has. **Trade-offs.** Error prevention, detection and recovery is the principle that most often changes a decision. It means counting the cost of an option not only in gates and bytes but in the code a kernel must write to handle its failures: a feature that adds a new fault, a new error return or a new half-finished state costs recovery code in every system that uses it, and a feature that makes an operation repeatable from the start costs none. **Improvements.** The soft-rules principle covers the two strongest defaults, "no mode bits" and "natural alignment of quad accesses". Breaking either has a large cost, but each is weighed like any other choice. Three mode bits are accepted in the design on those terms: the translation-enable bit that is set once at boot, the user-memory guard that lives in the status word, and the sticky floating-point flags, which never change what an instruction does. **Benefits.** A reader can tell why a choice was made by asking which principle it serves. **Modern comparables.** Most architectures state no priorities; the RISC-V project's published principle of keeping the base small and the extensions optional is the nearest in spirit.

1.5 What has been built and measured

1.5.1 The machine is specified by machine-readable grammars; the assembler, linker, simulator, a compiler back end and the QEMU target are generated from or checked against them, so that the numbers cannot drift apart.

1.5.2 On 827 real source files that every compiler accepts, the first compiler's output, in code and data, is within 0.2% of `gcc -Os` and 6.5% smaller than `clang -Os` on amd64, using 1.19 and 1.10 times as many (shorter) instructions.

1.5.3 516 C test programs pass on the simulator and on QEMU.

1.5.4 The finish line before silicon is an assembler, a linker, an LLVM compiler back end, an emulator, and a port of OpenBSD that can be logged into with `ssh`. *(D)*

Commentary. **Precedent.** The habit of generating every tool from one description, rather than writing each and hoping they agree, is the discipline that other instruction-set projects adopted late; the pdp64 follows it from the start, which is why a change to an opcode number is made once. **Trade-offs.** The measurements are of compiled C at the compiler's size-optimising setting; they are static counts of what is written, not run-time measurements, and the compiler is one of two (the LLVM back end, which OpenBSD needs, has an assembler and object writer that agree with the project's own on every form tested). **Benefits.** The comparison gives the architecture a number against which later changes are measured: the flag rules cost 0.39% in code size, accepted for the benefit they give to faster implementations. **Modern comparables.** `gcc` and `clang` at `-Os` are the standard measuring sticks for code size on x86-64 and AArch64; the pdp64 figure is compared with them on the same source files.

1.6 Does the instruction set matter?

1.6.1 The instruction set is not interchangeable with any other: it fixes what every implementation must preserve, and so what a processor costs to build, to verify, to program and to secure.

1.6.2 The common view, that a good implementation hides the instruction set, is true of one thing: the peak speed of a very large core, where a great deal of hardware can absorb almost any encoding.

1.6.3 It is not true of the cost of a small core, the size of the code, the amount of software a system needs, or the number of ways a system can fail; those follow the instruction set, and they can be measured.

1.6.4 Each of the rows below is a measurement or an estimate from this project, and each is explained in the chapter named beside it.

What differs	The figure	Where
The logic of a complete implementation, same company and era	the PDP-11's T-11, a full integer core, was about 12,000 transistors; the MicroVAX 78032, a subset of the VAX with no floating point, about 125,000	10.1, 10.2
What it takes to find where the next instruction starts	pdp64: two bits of the first parcel; PDP-11: both operand specifiers; x86: prefixes, opcode, ModR/M and SIB in sequence; VAX: every specifier in order	9.4
Whether flags block a faster implementation	68.2% of compiled instructions wrote a flag and 1.5% read one, so the flag rules are set at a measured cost of 0.39% in code size	9.3, 10.3
Size of compiled code	for the same 827 source files and the same compiler family, the pdp64 output is 0.86 times the size of its amd64 output, and 1.002 times `gcc -Os`	1.5
System-call path, instructions in and out (paper estimates)	x86-64 Linux about 45 and 30; AArch64 about 60 and 45; RISC-V about 66 and 45; VAX about 11 and 8; m68k 6 and 8; pdp64 4 to 5 and 4	6.5
Lines of kernel code to start a second core	x86: 1,528 plus 1,258 of real-mode code; arm64: 124 or 127; RISC-V: 108 or 58; pdp64: one register write	4.5, 7.8
Machine-dependent code in an OpenBSD port	riscv64 35,600 lines; arm64 61,613; amd64 79,167	10.4
Errata, workaround and quirk lines per 1,000 code lines in Linux's architecture directories	x86 0.8; arm64 0.7; arm 0.5; powerpc 0.4; mips 0.3; m68k 0.1; riscv 0.1; s390 0.0	pain-points report
Hardware-erratum options in Linux's configuration	arm64 64; arm 32; riscv 14	pain-points report

Commentary. **Precedent.** The view that instruction sets are equivalent has real support. Published comparisons of x86 and ARM implementations (the 2013 study usually cited is "Power Struggles: Revisiting the RISC vs. CISC Debate on Contemporary ARM and x86 Architectures", a citation not verified) found that at the same performance level the instruction set explains little of the difference in power or speed, and the very large cores of both families have converged. The pdp64 does not dispute that. **Trade-offs.** The claim is about steady-state performance of comparable large cores, and the table is about other costs. The table's figures are measurements of real machines and real software, not controlled experiments: some of the differences between architectures in the Linux figures are partly a matter of age and deployment (x86 is the oldest and most widely deployed), and the system-call and start-up figures are estimates and line counts of what is written, not run times. They show that the instruction set is correlated with these costs, and the chapters show the mechanism in each case. **Improvements.** Each row is a place where this design made a different choice from the architecture it is compared with, and the choices were made against these costs, not against peak speed. **Benefits.** A reader who thinks the instruction

set does not matter can check any row against its chapter: the answer is in what the instruction set obliges an implementation to do (precise exceptions, ordering, flag behaviour, instruction length, restart) and in the code a system must then write. **Modern comparables.** RISC-V's own case for a clean base instruction set and x86's survival by microarchitecture are the two sides of the argument.

1.7 How the manual is organised

1.7.1 Chapter 2 is the bus. Chapter 3 is graphics: the terminal, based on the C64 and the Blit and modernised, and how it drives HDMI and the other ports. Chapter 4 is boot. Chapter 5 is the device driver model. Chapter 6 is the kernel: modes, exceptions and memory management. Chapter 7 is multiple processors. Chapter 8 is vector work, AI and array languages, done by devices. Chapter 9 is the instruction set. Chapter 10 is the path to silicon.

1.7.2 Each section states its aphorisms first and its commentary after; the status tag *(D)* or *(P)* marks what is decided and what is proposed.

Commentary. **Precedent.** The form follows the old commentary traditions, in which a short text can be read straight through and the discussion of each line sits beneath it; and the layout of the classic CPU manuals for the reference material, in which every instruction has a fixed entry. **Benefits.** A designer who wants only the architecture reads the aphorisms; one who wants the reasons reads on.

1.8 The pdp64 and the encodings tested against it

1.8.1 The pdp64 is pdp64/32: thirty-two registers and an instruction encoded by a prefix code over the first parcel, with 5-bit register fields in the one-parcel forms. Two earlier encodings, pdp64/r20 (the original: sixteen registers, a first parcel of `len`, opcode, `reg` and `low`) and pdp64/16 (sixteen registers, a prefix code), were built and measured against it; they are tested alternatives, not products, and each keeps its own manual so that the comparison can be read. They share with the pdp64 the roles of the registers, the memory model, the exception mechanism, the page tables, the bus and the devices, the calling convention and the assembly language, and differ in how an instruction is encoded and in the size of the register file. *(D)*

1.8.2 This manual is the manual of pdp64/r20, a tested alternative; the manual of the pdp64 is that of pdp64/32. *(D)*

1.8.3 The three manuals are generated from one text, so that what is common is written once. The assembler selects the encoding (`-m pdp64/r20`, `-m pdp64/16`, `-m pdp64/32`), the object records it, and the linker refuses to link objects of different encodings. *(D)*

1.8.4 This CPU has 106 instruction entries (270 mnemonic words with the aliases); pdp64/16 and pdp64/32 have the same instructions and 70 more words, the fused pairs, the selects, the checked arithmetic, `TRAPCC`, the deferred and user-qualified moves and the AES and SHA words, none of which this CPU accepts. *(D for the fused pairs, the selects, `MOVQL`, the checked arithmetic and `TRAPCC`; P for the rest, tagged in their entries)*

1.8.5 pdp64/32 was chosen for performance, by testing against the other two on the same programs. Over six programs (lz4, zlib, Lua and three BearSSL kernels) compiled for each and run on the simulator, pdp64/32 executes 572,801,956 instructions against 609,755,229 for pdp64/16 and 755,816,022 for pdp64/r20 (the original compiler for the latter); its frame loads and stores fall to 24,276,195 against 65,203,703 and 68,936,548; and on the in-order timing model (an ideal memory, no branch predictor, issue width 1 or 2) its cycle counts are 22 to 28% below pdp64/r20's and, with a fetch window of 4 bytes or more, 7 to 8% below pdp64/16's (the model is a check of the pipeline it states, not hardware). Its code is larger than pdp64/16's: 3.18% in instruction bytes over the 841-file corpus and 2.92% in bytes fetched over the six programs. *(measured; the record is `../encoding-work/integration.md`, section 4)*

The manuals of the tested alternatives: pdp64/16; the manual of the pdp64 is pdp64/32; the landing page is `docs/manual/`.

Commentary. **Precedent.** One architecture with more than one encoding is not new: AArch32 has the ARM and Thumb encodings and RISC-V a compressed extension; the PDP-11 family had many implementations of one instruction set. **Trade-offs.** Three manuals cost the maintainers a generator; one manual with a line of availability on every instruction would have mixed three layouts on every page, and the author decided against it. **Benefits.** A reader of one manual meets only the encoding of that CPU; the bus, the kernel and the devices are the same text in all three, and the reader who wants the evidence for the choice of pdp64/32 has the other two manuals to compare with. **Impact.** *Kernel:* the system architecture is common, so one kernel serves all three. *Compiler:* one back end with three targets (`ccom -m`), a different set of instructions on pdp64/r20. *Hardware:* the CPUs have different decoders and register files and the same programming model above the instruction set.

Chapter 2 — The bus

The processor reaches the world through one bus, Q64, which is PCI Express with convenience and security circuitry added; every standard device is a virtio device (the disk is virtio-blk) or a USB controller, and any other PCI Express device may be attached, all found by PCI Express enumeration; every transfer of data is a descriptor in a queue in memory that the device carries out and marks done.

The chapter starts from the Unibus of the PDP-11 and explains each later idea by contrast with it: the PCI Express link, the configuration space, base-address registers, bus-mastering DMA, virtio, message-signalled interrupts and the IOMMU. Between the PDP-11 and the pdp64 it names the intermediate steps that changed the idea (the VAX interconnect, PCI, PCI Express, virtio), each with the one thing it contributed; section 2.1 gives the route in a table, and each commentary repeats the part of it that concerns its topic. The numbered statements are the rules; the rest is explanation. Tags: *(D)* decided, *(P)* proposed, *(S)* unspecified. A fact about PCI Express or virtio that could not be checked on this machine is marked *unverified* and listed in section 2.12. How a driver talks to a device, the virtio transport and the default devices are in chapter 5; interrupts and modes are chapter 6; the other cores are chapter 7. The full discussion is in `../pdp64-q64-bus.md`; the open options are in `../decisions-pending.md`.


A term is defined where it first appears, as the technical word followed by a plain restatement. The boxes-and-arrows figures are the kind a textbook draws for a linked list: a box is a piece of memory, an arrow is an address stored in it. Code blocks are pseudocode (C-like; `mmio_read16(address)` and the like are ordinary loads and stores to a device register, section 2.3); the PDP-11 assembly is quoted from a 2.11BSD driver or written in its style.

2.1 What you already know: the Unibus

A PDP-11 reaches everything outside the processor over its **bus** (a set of shared wires that every part of the machine hangs on), the Unibus. Four ideas of it matter here, because each later idea in this chapter keeps or replaces one of them.

Registers at fixed addresses. The Unibus has 18 address lines, so 256 KB of **address space** (the set of numbers that name locations). The top 8 KB of it is the **I/O page** (the region where devices, not memory, answer). A device is a handful of 16-bit **registers** (small storage cells in the device that the processor can read or write) at addresses that were set by switches on the card. Nothing tells the processor what is plugged in. 2.11BSD's standalone boot code has the RK11 at `0177400` written into it (`pdpstand/rk.c`), and the kernel's autoconfiguration has a probe routine per device that pokes the controller (`rkprobe` in `autoconfig/rkauto.c` writes a drive reset with interrupt enable and returns `ACP_IFINTR`, a flag meaning "present if it interrupts"). A driver is written against a C structure laid over those addresses; this is the whole of 2.11BSD's declaration for the RK05 disk controller (`rkreg.h`):

```
struct rkdevice {
        short   rkds;   /* drive status        */
        short   rker;   /* error bits          */
        short   rkcs;   /* control and status  */
        short   rkwc;   /* word count          */
        caddr_t rkba;   /* bus address         */
        short   rkda;   /* disk address        */
};
```



a driver holds one pointer, the address of RKDS; each register is a field
(the wiring, the vector and the CSR address, was set by switches on the card)

The CSR convention. Most devices have a **CSR** (control and status register: one word whose bits both command the device and report on it). The RK11's has GO in bit 0 (do it now), READY in bit 7 (the device is idle and may be given work), IDE in bit 6 (interrupt on done enable) and ERROR in bit 15 (`rkreg.h`: `RKCS_GO` 01, `RKCS_RDY` 0200, `RKCS_IDE` 0100, `RKCS_ERR` 0100000). The console serial line has the same shape: its status register is at `0177560` in `pdp/cons.c`. Other devices with a **DBR** (data buffer register: the word the data passes through) beside the CSR are *unverified* here.

DMA. To move a block, the processor does not copy words: it writes the memory address into a register (`rkba`), a negative count into another (`rkwc`), the disk address into a third and then GO. The controller becomes a **bus master** (a part that is allowed to start transfers itself, not only answer them) and **DMA** (direct memory access: moving data between a device and memory without the processor's help) does the copying, requesting the bus by **NPR** (non-processor request: the Unibus line a device raises to be given the bus for a data transfer at once, at a priority above every interrupt). The 18-bit bus address was too narrow once memory grew, and a **map register** (a table entry that translates a device's address to a memory address) appears in 2.11BSD as the UNIBUS map: `struct ubmap` (two 16-bit words per register) at `0170200`, allocated by `mapalloc` (`h/uba.h`, `pdp/machdep.c`). It is the ancestor of the IOMMU of section 2.11.

Interrupts. A device that wants attention asserts one of four **BR** lines (bus request, levels 4 to 7: the priority at which it wishes to interrupt; `br4` to `br7` in 2.11BSD's `pdp/scb.s`); when the processor's priority is lower, it grants the bus, and the device places its own **interrupt vector** (the address of a pair of words, new program counter and new status word, that the processor loads) on the data lines. The vector too was set by switches on the card; the RK11's is `0220` at level 5 (`DEVTRAP(220, rkintr, br5)` in `pdp/scb.s`). The interrupt routine returns with `RTI` (return from interrupt). A driver that does not want interrupts **polls** (reads the status register again and again until the bit it wants changes).

Here is the RK11 driver in the two styles, both real or in the style of the real code. The interrupt-driven start, from 2.11BSD `pdpuba/rk.c`:

```
rkaddr->rkda = (dn << 13) | (cn << 4) | sn;     /* disk address     */
rkaddr->rkba = bp->b_un.b_addr;                  /* where in memory  */
rkaddr->rkwc = -(bp->b_bcount >> 1);             /* words, negative  */
com = ((bp->b_xmem & 3) << 4) | RKCS_IDE | RKCS_GO;
com |= (bp->b_flags & B_READ) ? RKCS_RCOM : RKCS_WCOM;
rkaddr->rkcs = com;                              /* go; return; rkintr() runs when done */
```

and the same command polled, in PDP-11 assembly (the registers are at `0177400` plus the structure's offsets: `rkds` 0, `rker` 2, `rkcs` 4, `rkwc` 6, `rkba` 010, `rkda` 012; `RCOM` is `RKCS_RCOM`, 04):

```
        MOV  #<disk address>, @#177412     ; RKDA
        MOV  #<buffer>,       @#177410     ; RKBA
        MOV  #-256.,          @#177406     ; RKWC: 256 words, negative
        MOV  #RCOM+GO,        @#177404     ; RKCS: read, go, no interrupt enable
1$:     TSTB @#177404                      ; bit 7 of the low byte is READY
        BPL  1$                            ; plus means not yet: look again
```

```
        TST  @#177404                   ; bit 15 is ERROR
        BMI  error
```

The processor knows the register layout, loads each register, waits, and knows the meaning of every bit of that one device. A device with different registers needs a new driver. The rest of the chapter is the answer the pdp64 adopts: every device has the same shape.

Gone in Q64: the fixed I/O page, the switches, the vectors on the data lines, the bus request levels, and the single shared set of wires (with it the locked read-modify-write `DATIP`/`DATO`, section 2.10). Kept: devices are locations in the one address space, reached by ordinary loads and stores with no I/O instructions (2.3.2); the device moves its own data by DMA; the interrupt says only "look at the device"; polling stays allowed (2.7.4).

The route from the Unibus to Q64. Each row is one step and what it contributed; the later sections say where the contribution is used.

step	what it contributed	basis
PDP-11 Unibus	registers in one address space, CSR, DMA by NPR, vectors and BR levels, map registers	2.11BSD sources
VAX-11/780	devices behind adapters on an interconnect whose slots report their type in a status register, so the kernel scans instead of being told; the Unibus adapter keeps the map registers and adds buffered data paths that a driver purges; a Massbus adapter is a second kind of adapter (`NEX_MBA`, `NEX_UBA0`)	4.3BSD `nexus.h`, `ubareg.h`, `autoconf.c`
PCI	every function describes itself in a configuration space, and windows are placed by software through base-address registers	the layout is checked in `pci_regs.h`; the date and history are *unverified*
PCI Express	the same software model over point-to-point links and packets; MSI-X interrupts as memory writes; bus mastering as a command bit	`pci_regs.h`, QEMU `docs/pcie.txt`
virtio	one transport and one queue structure for every device kind	`virtio_*.h`, QEMU
Q64	the above, with no device-space address bit, an IOMMU, precise faults and one fence rule	the decisions of errata 75, 80, 95, 97, 101, 102, 104

The name Q64 echoes the PDP-11 Q-bus, which no source on this machine describes (*unverified*; statement 2.3.1 uses it as the model for "devices as memory locations").


2.2 PCI Express: links, packets and configuration space

PCI Express (written PCIe) descends from PCI, the 1990s parallel bus (*unverified*: dates and lineage are not in any source here) whose configuration space and software model it kept. Its ideas, each against the Unibus.

A link, not a shared bus. A Unibus is one set of wires that all devices share, so only one transfer happens at a time and every card loads the wires. PCI Express uses **point-to-point links** (a connection between exactly two ends; nothing else is on it). A **lane** is the unit of width: a pair of wires carrying data one way and a second pair the other way, so a lane sends and receives at the same time. A link of more lanes is faster: `pci_regs.h` defines negotiated widths x1, x2, x4 and x8 and has a six-bit width field (x16 and wider are *unverified*). The speed codes of `pci_regs.h` are 2.5, 5, 8, 16, 32 and 64 **GT/s** (gigatransfers a second: signal changes, not yet bytes); each generation is faster than the last. Software sees none of this; it sees addresses.

A tree. Because links are point-to-point, a machine is a tree. The root is the **root complex** (the part, in the processor chip or beside it, that connects the processor and memory to the tree and is the PCI Express counterpart of the Unibus's processor-side logic); below it are **root ports** (its links to the outside), **switches** and **bridges** (parts with one link up and several down, which pass traffic between them; to software a switch is a set of bridges) and at the leaves **endpoints** (the devices). QEMU's `docs/pcie.txt` uses these words: root complex, root port, downstream port, bridge, integrated endpoint.


a PCI Express tree: a bus of point-to-point links, not a shared set of wires



each line is a link: one or more lanes, each a pair of one-way wire pairs
Bus numbers and the shape are examples.

Packets. Where the Unibus signals on dedicated wires, PCI Express sends everything as a **packet** (a small message with a header that says what it is, where it goes and how much data follows). The packets that carry reads and writes are **TLPs** (transaction layer packets: the unit software sees, above the layers that frame bytes and retry on error). The kinds a programmer meets (*unverified*; the specification is not on this machine): a memory write (address and data, with no answer, called **posted**: the sender has handed it over and moves on); a memory read (address and length), answered later by a **completion** (a packet carrying the data back); configuration reads and writes; and messages. A read is a **split transaction** (request and answer are separate packets, and the link is free in between); on the Unibus the bus master held the bus, with `MSYN` asserted, until the slave replied with `SSYN` (*unverified* here). Two consequences: a write has "happened" in the program's mind while it is still on its way, which is why section 2.8 has a `FENCE`; and an interrupt (section 2.7) can be a packet like any other.

Configuration space: the device describes itself. The Unibus had nothing like it. Every device, which PCI Express calls a **function** (one logical device; a card may carry several), has a **configuration space** (a block of 4096 bytes of registers, separate from the device's working registers, that says who made the device, what it is and how much address space it wants). The first 256 bytes are the older PCI part, with a 64-byte header; the 4096 bytes in all are the PCI Express part (`PCI_CFG_SPACE_SIZE` 256 and `PCI_CFG_SPACE_EXP_SIZE` 4096). A function is named by three numbers, its **bus**, **device** and **function** numbers (the position in the tree). The processor reaches the configuration space of function (b, d, f) with ordinary loads and stores to one address range: byte `offset` of function (b, d, f) is at `base + (b << 20) + ((d << 3) + f) << 12) + offset` (this is **ECAM**, enhanced configuration access mechanism; the shifts are from QEMU's `pcie_host.h`, `PCIE_MMCFG_BUS_BIT` 20 and `PCIE_MMCFG_DEVFN_BIT` 12). Where `base` is on the pdp64 is not specified (2.4.8).




The 64-byte header of an ordinary function (type 0) holds, as the figure shows and `pci_regs.h` defines: the **vendor ID** and **device ID** (two 16-bit numbers that name the maker and the product; 0xFFFF as a vendor ID means that no function answers), the **command** register (bit 1 lets the function answer memory addresses, bit 2 lets it be a bus master, bit 10 turns off its old-style interrupt pin), the **status** register, the **class code** (what kind of device), the **header type** at 0x0E (0 for an ordinary function, 1 for a bridge, with bit 7 set when the card has several functions) and six **base-address registers** at 0x10 to 0x24 (section 2.4). A pointer to the capability list is at 0x34. A bridge's header (type 1) has a different layout after the first 16 bytes; the bus-number bytes at 0x18 to 0x1A are its.

Capabilities. The header is fixed; everything optional hangs off a **capability list**: a linked list, inside the configuration space, of small records, each starting with an identifier byte and a byte holding the offset of the next record (0 ends the list). It is a linked list of the kind drawn in section 2.6. The records a pdp64 driver looks for are the MSI-X record (identifier 0x11, section 2.7), the PCI Express record (0x10) and the vendor-specific record (0x09) which virtio uses to say where its structures are (section 2.6).

What the pdp64 adds. A PCI Express endpoint looks to software like a PCI device, so one driver model serves both (*unverified* as history). The author's decision (errata 80) is that Q64 is PCI Express, so an ordinary card works on it unchanged, with circuitry added on the processor side for convenience and security (2.3.5).

2.3 Q64 and the address space

Memory-mapped registers. On the PDP-11 the registers of a device are **memory-mapped** (they have addresses in the same address space as memory, so the instruction that reads memory reads a register). Q64 keeps this and widens it: a function's registers are in **windows** (ranges of the physical address space that the function answers), and a driver reaches them with ordinary loads and stores, with no input or output instructions. What changed is who chooses the addresses. On the Unibus the switches on the card did. In PCI Express the function says how much room it needs, the system assigns an address, and the function answers there (section 2.4). The **base-address register** (BAR: a register in the configuration-space header that holds where a window starts and, by the trick of section 2.4, how big it is) places a window in the address map:



Against the Unibus, three things differ. The fixed I/O page at the top of the address space is gone (errata 97, 102: no address bit says "device"); the address is wider (40 to 64 bits, against 18); and a window may be placed anywhere except the first few pages, where the boot code and boot data are loaded.

2.3.1 Q64 is the system bus: PCI Express, so that an ordinary PCI Express device works on it unchanged, with the programming model of the PDP-11 Q-bus (devices as memory locations in the one address space) widened to 64-bit data and a physical address that is not limited to 40 bits (the simulator and the emulator implement 40), and with convenience and security circuitry added. *(D)*

2.3.2 Devices live in the ordinary address space; the processor has no input or output instructions. *(D)*

2.3.3 The windows of a device (the regions its base-address registers describe) start on 4 KB page boundaries and are a whole number of pages, so that one device can be mapped to one protection domain. *(P)*

2.3.4 Every page has a memory type: normal cached, normal uncached, device strongly ordered, or device weakly ordered. *(D)*

2.3.5 The transactions of Q64 are those of PCI Express; the circuitry the pdp64 adds is for convenience (overlays, helper registers) and security (the IOMMU, error and reset rules), and is measured against the list of pain points of `kernel-pain-points.md`. An extension is announced to a card, through a PCI Express extended capability, only if the card must take part in it; a mitigation that lives on the processor side is invisible to cards. *(D)* The detail of the extensions is not specified. *(S)*

2.3.6 No bit of the physical address selects device space: a device window is an ordinary range of physical addresses, found by enumeration (section 2.4), and the physical address is at least 40 bits and at most 64, an implementation choosing its width in that range, so that mappings of petabytes are possible. *(D)* A window can be mapped anywhere in the physical address space except the first few pages, where the boot code and boot data are loaded. *(D)* How many pages are "the first few" is not decided, *(P)* and nor is how software discovers the implemented width. *(S)* The simulator and the emulator place their devices in the upper half of a 40-bit space, from `0x8000000000`, and check the memory type of a page against that bit; these two arrangements belong to the present implementation, not to the architecture.

Commentary on 2.3.6. **Chain.** The PDP-11 put its devices in a fixed page at the top of the address space (a driver's pointer to its registers is a constant in that page: `cnaddr = 0177560` in 2.11BSD `pdp/cons.c`). The VAX-11/780 put them in nexus space from `0x20000000`, one 8 KB window (`NEXSIZE` 0x2000) per slot (`NEX780` in 4.3BSD `nexus.h`), and `nexus.h` gives the 11/750, 730 and 8600 different bases, so the VAX kept changing the map from model to model. PCI Express places each function's windows where enumeration assigns them. The pdp64 follows PCI Express. **Trade-off.** A decoding bit makes the first routing decision in the fabric trivial and makes a mapping of the wrong memory type detectable, at the cost of half the physical address space; the author dropped it because mapping petabytes needs those bits. Without it, a device's DMA into another device's window is refused by the IOMMU (errata 85), not by the address. **Impact.** The kernel maps devices where enumeration says and recognises a device mapping by its memory type and window; the root complex decodes the windows

it has assigned. Whether other systems split the map by platform-chosen ranges, and whether x86 has a separate port space, are *unverified* here.

2.4 Enumeration and hot-plug

Finding the devices. The PDP-11 kernel is told where each device is and probes the address (2.1); the VAX kernel scans the slots of its interconnect and reads each one's type; the Q64 kernel asks every function. **Enumeration** (walking the whole tree and reading each function's configuration space to find out what is there) goes: for every bus, for every device number 0 to 31 and function number 0 to 7, read the vendor ID; if a function answers, read its header type; if it is a bridge, give the bus behind it a number and walk that bus too; if it is an ordinary function, size and place its windows and record it. The pseudocode (the bus numbers follow the `PCI_PRIMARY_BUS`, `PCI_SECONDARY_BUS` and `PCI_SUBORDINATE_BUS` bytes at offsets 0x18 to 0x1A of a bridge's header):

```
next_bus = 1                                # bus 0 is the root complex's own

scan(bus):
    for dev in 0 .. 31:
        for fn in 0 .. 7:
            vendor = cfg_read16(bus, dev, fn, 0x00)
            if vendor == 0xFFFF:            # nothing here
                if fn == 0: break           # no function 0, no card: skip its other functions
                continue
            htype = cfg_read8(bus, dev, fn, 0x0E)
            if (htype & 0x7F) == 1:         # a bridge: a bus lies behind it
                secondary = next_bus++
                cfg_write8(bus, dev, fn, 0x18, bus)          # primary bus
                cfg_write8(bus, dev, fn, 0x19, secondary)    # secondary bus
                cfg_write8(bus, dev, fn, 0x1A, 255)          # subordinate: provisional
                scan(secondary)                              # the recursion
                cfg_write8(bus, dev, fn, 0x1A, next_bus - 1)  # now the real highest number
            else:
                size_and_place_bars(bus, dev, fn)
                add_to_device_list(bus, dev, fn, vendor, cfg_read16(bus, dev, fn, 0x02))
            if fn == 0 and not (htype & 0x80): break         # single-function card
```

(`cfg_read16` is a load from the ECAM address of section 2.2. A real PCI Express root complex and QEMU answer all ones for an empty position (*unverified* on real hardware); the pdp64's root complex does so by decision (2.4.9). The windows of a bridge must also be programmed so that traffic for the functions behind it passes; that step is omitted here.)

Sizing a window. The register must say how big its window is, and it is the same register that holds the address. The bits below the size are not storage: they always read as zero. So the system writes all ones, reads the register back, and the bits that stuck show the size (the header comment of `pci_regs.h` says the same: "writing a value of 0xffffffff to the register, and reading it back. Only 1 bits are decoded"; QEMU builds the answer as `~(size - 1)`). The low four bits of a memory BAR are not part of the address (the listing below handles memory BARs only): bit 0 is 0 for memory and 1 for an I/O port, bits 2:1 give the width (00 is a 32-bit address, 10 a 64-bit one that uses the **next** BAR as its high half), and bit 3 says the memory is **prefetchable** (reading it has no side effects, so it can be read ahead).

```
size_bar(bus, dev, fn, index):                      # returns (size, is_64bit)
    reg = 0x10 + 4 * index
    cmd = cfg_read16(bus, dev, fn, 0x04)
    cfg_write16(bus, dev, fn, 0x04, cmd & ~0x2)     # stop the function answering memory while we play
    old = cfg_read32(bus, dev, fn, reg)
    cfg_write32(bus, dev, fn, reg, 0xFFFFFFFF)
    got = cfg_read32(bus, dev, fn, reg)
    cfg_write32(bus, dev, fn, reg, old)             # put it back
    is64 = ((got >> 1) & 3) == 2
    if is64:                                        # the same dance on the high half
        oldh = cfg_read32(..., reg + 4)
        cfg_write32(..., reg + 4, 0xFFFFFFFF)
        goth = cfg_read32(..., reg + 4)
        cfg_write32(..., reg + 4, oldh)
        mask = (goth << 32) | (got & 0xFFFFFFF0)
```

```
        size = (~mask + 1) & 0xFFFFFFFFFFFFFFFF
    else:
        mask = got & 0xFFFFFFF0
        size = (~mask + 1) & 0xFFFFFFFF
    cfg_write16(bus, dev, fn, 0x04, cmd)            # restore the command register
    return (size, is64)

size_and_place_bars(bus, dev, fn):
    index = 0
    while index < 6:
        (size, is64) = size_bar(bus, dev, fn, index)
        if size != 0:
            base = allocate(size, align = size)     # a window starts on a multiple of its own size
            cfg_write32(bus, dev, fn, 0x10 + 4*index, base & 0xFFFFFFFF)
            if is64: cfg_write32(bus, dev, fn, 0x14 + 4*index, base >> 32)
        index += 2 if is64 else 1
    cmd = cfg_read16(bus, dev, fn, 0x04)
    cfg_write16(bus, dev, fn, 0x04, cmd | 0x2 | 0x4) # answer memory (bit 1); may be a bus master (bit 2)
```

The worked example of the figure: reading back 0xFFFFC000 means the low 14 bits are not storage, so the size is 2^{14} = 16 KB. On the pdp64 a window is at least a page, 4 KB, and a whole number of pages (2.3.3), so that one device can be given to one protection domain. The last line sets bit 2 of the command register; until it is set the function may not start a transfer of its own (section 2.5).

2.4.1 The processor finds the devices by PCI Express enumeration: it reads the configuration space of each function through the root complex, sizes the base-address registers of the function and assigns its windows in device space. *(D)*

2.4.2 A function is a virtio device when its configuration space says so (the virtio vendor identifier and a device identifier that carries the virtio device type); the capabilities in its configuration space locate the virtio structures in its windows (chapter 5). One transport driver serves every virtio device. *(D)*

2.4.3 A function may itself be a bus: a PCI Express bridge presents the functions behind it, and a USB host controller (itself a PCI Express function) enumerates its own tree of hubs and devices, so any bus can be attached to Q64 and its devices enumerated, to any depth. The kernel's enumeration is one recursive walk. *(D)*

2.4.4 The bus alerts the processor when a device enters or leaves, by an interrupt; the kernel then rescans the bus, which is also what it does at boot. *(P)*

2.4.5 When a device leaves, an access to its windows is at once a precise bus fault, not a read of all ones: a read of the window faults, a posted write is dropped and counted, and the device's in-flight bus transactions are aborted. *(P)*

2.4.6 The queued work of a departed device stays in memory untouched, so the driver can read, save, resend or fail it. *(P)*

2.4.7 A bus reset produces no removal events, so a reset is not mistaken for the removal of every device, and the identity of every function is defined after the bus has lost power. *(D)*

2.4.8 Where the configuration space and the windows of the functions sit in the physical address space (fixed bases and sizes) is unspecified, as is how a hot-plug event behind a bridge is reported. *(S)*

2.4.9 A read of a configuration position that never held a function completes normally and returns all ones in every byte, so a vendor ID of `0xFFFF` means that nothing is there; it is not a bus fault (the read of other non-existent addresses stays a precise `BUSFAULT`, 6.4.3). *(D)*

2.4.10 The root complex records such a miss in a sticky bit of its own status register, cleared by writing a one to it, so that a dead link can be told from an empty slot; the register and its place are not specified. *(D)*

Commentary. **Chain.** The PDP-11 had no enumeration: devices at switch-set addresses, found by probes such as `rkprobe`, and nothing told the kernel when a device left. The VAX scanned its interconnect: `probenexi()` in 4.3BSD `autoconf.c` reads each nexus slot's status register (`badaddr` first, then the type field, `NEX_MEM4`, `NEX_MBA`, `NEX_UBA0` and so on), and `unifind()` probes the devices behind each Unibus adapter. PCI added configuration space and sizing by writing all ones, so a card can be placed anywhere. PCI Express keeps that and adds hot-plug (*unverified*: the slot-status interrupt). The pdp64 uses standard enumeration, so an ordinary card works unchanged and the kernel needs one address, the root complex's. Amiga AutoConfig (each board announces itself at a fixed address and is told where to live) and NuBus (a fixed share of the address space per slot) are other answers (*unverified* here); assignment on demand supports any layout at the cost of a sizing step at boot, a fixed window per slot needs no assignment and limits the slot count. **Where the pdp64 differs.** On a surprise removal PCI returns all

ones, so every driver must treat all ones as a possible error (*unverified*); the pdp64 uses the precise bus fault the instruction set already defines (2.4.5), so a driver has one recovery path, and rescan on an event makes hot-plug and boot the same code. **Impact.** One recursive loop over the functions of each bus; hot-plug is an interrupt and a rescan; the root complex is a standard one plus the precise fault for an absent device.

Commentary on 2.4.3. **Chain.** The VAX did this: the Unibus hung off the 11/780's interconnect through a Unibus adapter, a nexus device whose registers include the map registers for DMA and whose Unibus memory (the devices' registers) appears in a window of its own (`UMEM780(i)` at `0x20100000 + i * 0x40000`, `vaxuba/ubareg.h`, 4.3BSD). PCI-to-PCI bridges nest buses, a USB host controller enumerates a tree of hubs and devices, and Thunderbolt tunnels PCI Express over a cable (*unverified*). The pdp64 allows any bus to be attached behind a bridge. **Trade-off.** Each level adds a mapping of windows and a hop of latency, and a departure deep in the tree must be reported to a driver that does not know the path; a bridge's windows are ordinary device windows (2.3.6). **Impact.** A new bus costs one bridge and no change to the processor, the kernel's walk or the driver model; a bridge is a standard PCI Express bridge.

2.5 DMA, coherence and the hand-off

Bus mastering. On the Unibus any device could become master by winning an NPR grant. In PCI Express a function is a **bus master** (it may originate memory reads and writes of its own, as packets, instead of only answering) once the processor sets bit 2 of its command register; until then it only answers. A DMA transfer is a function sending memory-write packets (to deliver data) or memory-read packets (to fetch it) to addresses in memory the processor gave it. There is no request line, no grant chain and no priority between devices; the switches of the tree carry the packets. The danger is the one the Unibus map registers hinted at: a device that can write anywhere can write into the kernel (section 2.11).

The hand-off. Telling each side that the data is ready is the harder half of DMA, and a queue in memory does it (section 2.6). Statement 2.5.3 gives the five steps in order.

2.5.1 Between processors the data caches are coherent without any software action, by snooping with three states (modified, shared, invalid), for two to four cores. *(D)*

2.5.2 Between a processor and a DMA device they are not: buffers are mapped uncached and the hand-off is explicit. *(D)*

2.5.3 The hand-off is five steps: the processor builds the descriptors and data in uncached memory, executes `FENCE`, writes the device's notification address; the device walks the descriptors, moves the data by DMA, writes the result and its used-ring entry, and raises an interrupt; the processor reads the result. *(D)*

2.5.4 The write that raises a device's interrupt (a message-signalled write) cannot overtake the data writes that precede it on the same path. *(D)*

Commentary. **Chain.** The RK11 driver of 2.1 contains no cache or ordering step. On the VAX the Unibus adapter had buffered data paths, and a driver had to purge them before reading what a device had written (`UBA_PURGE780` and `UBA_PURGE750` in 4.3BSD `ubareg.h`). That a PDP-11/70's cache watched Unibus writes so that DMA appeared coherent is *unverified* here. Modern x86 DMA is coherent, while ARM and MIPS systems with non-coherent DMA need a kernel layer that places cache maintenance (*unverified*). The pdp64 chooses two mechanisms, each where it is cheap: snooping between cores, which are few, and uncached buffers with an explicit hand-off for DMA, which is large and infrequent. **Trade-off.** The processor reads received data from uncached memory, which is slow; a cache-maintenance instruction would remove that cost for a non-coherent device that may come later. No driver can forget a cache clean or invalidate, because there is none. **Impact.** A snoop port on each data cache for core coherence only; none for DMA.

2.6 virtio: one shape for every device

The Unibus gave every device its own registers, and every driver learned them. **virtio** (a specification for devices meant to be imitated in software; the name is from "virtual I/O") gives every device the same few structures in memory, and only the meaning of the requests differs. A **driver** (the program that runs a device) and a **device** (the hardware, or the emulator that pretends to be it) talk by **shared memory** (both sides read and write the same region of memory under a fixed protocol, instead of passing values through registers). The author decided on virtio for every standard device (errata 95, 79, 101): the network card, the graphics device, the audio device and the disk are virtio-net, virtio-gpu, virtio-snd and virtio-blk. One transport driver (2.6.2) and a thin driver per device kind serve the machine, and the same devices run in QEMU, the simulator and the FPGA. The chain from the RK11: one register set per device (PDP-11); the VAX added a second adapter kind, the Massbus (`NEX_MBA`), beside the Unibus adapter, so its interconnect carried several device interfaces; PCI Express

made discovery and addressing uniform and left the device interface to each vendor (NVMe, which errata 75 first chose, is one such interface and may still be attached, errata 101); virtio makes the device interface uniform too. Chapter 5 states the rules; this section teaches the shape.

2.6.1 The five ideas, against the RK11

the RK11	virtio
the kernel is told where the device is	the device is found by enumeration, by vendor and device ID (2.6.2)
six registers, each with bits of its own	a standard set of registers of **feature bits** and a **status** byte, the same for every device (2.6.3)
one command at a time: load the registers, GO	a **virtqueue**, a queue of commands in memory, so many are outstanding at once (2.6.4)
the command is in the registers	the command is a **descriptor chain**, boxes in memory linked like a list (2.6.5)
READY bit, or an interrupt, says it is done	the device writes the finished chain into the **used ring** in memory, and may interrupt (2.6.6, 2.7)

2.6.2 Finding a virtio device

A virtio function is recognised by its identifiers: the vendor ID is 0x1AF4 (QEMU's `PCI_VENDOR_ID_REDHAT_QUMRANET`), and its device ID is 0x1040 plus the **device type** (QEMU's `PCI_DEVICE_ID_VIRTIO_10_BASE`). The types are in the Linux header `virtio_ids.h`: network 1, block 2, console 3, GPU 16, sound 25, so virtio-blk is device ID 0x1042, virtio-net 0x1041, virtio-gpu 0x1050 and virtio-snd 0x1059. (These are the "modern" device IDs. An older numbering exists; that it starts at 0x1000 is *unverified*, and it is not used, section 2.6.3.)

The registers are not at fixed places in the window. The function's **vendor-specific capabilities** (capability identifier 0x09 in the list of section 2.2) say where each structure is. Each record is the 16 bytes of `struct virtio_pci_cap`: the identifier, the next-record offset, the record length, a `cfg_type` byte that says which structure it describes, a `bar` byte (which of the six windows), an `id` byte, two bytes of padding, a 32-bit `offset` into that window and a 32-bit `length`. The `cfg_type` values are 1 common configuration, 2 notifications, 3 interrupt status, 4 device-specific configuration, 5 a PCI configuration access window, 8 shared memory, 9 vendor data (`virtio_pci.h`); a driver for the pdp64 needs 1 to 4. The notification record (`struct virtio_pci_notify_cap`) is four bytes longer: it ends with a 32-bit `notify_off_multiplier`.

```
find_virtio_structures(fn):
    cap = cfg_read8(fn, 0x34)                       # head of the capability list
    while cap != 0:
        if cfg_read8(fn, cap + 0) == 0x09:          # vendor-specific: could be virtio
            type   = cfg_read8 (fn, cap + 3)
            bar    = cfg_read8 (fn, cap + 4)
            offset = cfg_read32(fn, cap + 8)
            length = cfg_read32(fn, cap + 12)
            where[type] = bar_base(fn, bar) + offset        # the physical address of the structure
            if type == 2: notify_multiplier = cfg_read32(fn, cap + 16)
        cap = cfg_read8(fn, cap + 1)                # follow "next"
```

2.6.3 The handshake: status and features

The **common configuration** structure is a block of registers, the same in every device; chapter 5 (5.4.1) lists them with their offsets, from `device_feature_select` at 0x00 to `queue_device` at 0x30 (the Linux header `virtio_pci.h` spells the last three `queue_desc_lo`, `queue_avail_lo` and `queue_used_lo` with `_hi` halves, and the feature registers `guest_feature_select` and `guest_feature`; the offsets follow from its field order). Three are the handshake.

`device_status` is one byte whose bits the driver sets in order, each meaning "I have got this far": ACKNOWLEDGE (1, "I have seen you"), DRIVER (2, "I know how to drive you"), FEATURES_OK (8, "I have chosen my features"), DRIVER_OK (4, "I am running"); the device may set NEEDS_RESET (0x40) and the driver FAILED (0x80) (`virtio_config.h`). Writing 0 resets the device (*unverified*: the Linux headers do not say). The RK11's GO and READY, spread over a conversation, correspond to these bits.

Feature bits let two sides that were not written together agree. The device offers a 64-bit set of **features** (optional abilities, one bit each; for example indirect descriptors, bit 28), read 32 bits at a time through a window selected by `device_feature_select`; the driver writes back the subset it will use, and nothing outside that subset is used. A device can add a feature without breaking an old driver, which never asks for it. One feature is required of every device the pdp64 drives, `VIRTIO_F_VERSION_1` (bit 32: "modern layout"; errata 95 and 5.4.4). Two more matter to the processor and are open (2.13): `VIRTIO_F_ACCESS_PLATFORM`

(bit 33: device addresses go through the platform's translation, section 2.11) and VIRTIO_F_ORDER_PLATFORM (bit 36: the device respects the platform's ordering rules).

```
init_device(fn):
    status = 0;               write_status(0)                  # reset
    write_status(status |= ACKNOWLEDGE)                        # 1
    write_status(status |= DRIVER)                             # 2
    wanted = (1 << 32) | class_driver_features                 # VERSION_1 and what this driver uses
    offered = read_features_64()                               # 2 reads through device_feature_select
    if (offered & (1 << 32)) == 0: fail()
    write_features_64(wanted & offered)                        # 2 writes through the driver's feature-
select window
    write_status(status |= FEATURES_OK)                        # 8
    if (read_status() & FEATURES_OK) == 0: fail()              # the device may refuse the subset
    for q in 0 .. num_queues - 1: setup_queue(q)               # section 2.6.4
    write_status(status |= DRIVER_OK)                          # 4: go
```

2.6.4 A virtqueue: three areas of memory


A **virtqueue** (a queue of requests that lives in ordinary memory, shared by the driver and the device) is three arrays, each in memory the driver allocates: the **descriptor table** (the requests), the **available ring** (the driver's list of which requests are new) and the **used ring** (the device's list of which are finished). The size, a power of two, is a number of entries chosen by the driver up to the device's maximum. Sizes: a descriptor is 16 bytes aligned to 16, the available ring is aligned to 2 and the used ring to 4 (the VRING_*_ALIGN_SIZE of virtio_ring.h); all fields are little-endian (5.3.4). The driver tells the device where the three are by writing their physical addresses into queue_desc, queue_driver and queue_device (offsets 0x20, 0x28 and 0x30) after selecting the queue with queue_select, and then sets queue_enable.

```
setup_queue(q):
    write16(queue_select, q)
    n = min(read16(queue_size), 256)                # the device proposes a size; the driver may lower it
    write16(queue_size, n)
    desc  = alloc_uncached(16 * n, align = 16)      # the descriptor table
    avail = alloc_uncached(6 + 2 * n, align = 2)    # flags, idx, ring[n], one optional word
    used  = alloc_uncached(6 + 8 * n, align = 4)    # flags, idx, ring[n] of 8-byte elements
    zero(desc, avail, used)
    write64(queue_desc, desc);  write64(queue_driver, avail);  write64(queue_device, used)
    write16(queue_msix_vector, vector_for(q))       # section 2.7
    write16(queue_enable, 1)
    notify_addr[q] = where[2] + read16(queue_notify_off) * notify_multiplier    # the doorbell of this queue
    free_head = 0; link all n descriptors into a free list through their `next` fields
    avail_idx = 0; last_used = 0                    # the driver's private counters
```

(The queue memory is in uncached memory on the pdp64, 2.5.2, so no cache instructions appear anywhere. The sizes 6 + 2n and 6 + 8n follow from the structures struct vring_avail and struct vring_used of virtio_ring.h, each two 16-bit fields followed by the ring, and a final optional 16-bit field, section 2.6.9.)

2.6.5 The descriptor, and the chain

A **descriptor** is 16 bytes, four fields (struct vring_desc): addr, a 64-bit physical address of a buffer; len, a 32-bit length in bytes; flags, 16 bits; and next, a 16-bit index of another descriptor. The flags are NEXT (1: the request continues in the descriptor next names), WRITE (2: the device will write into this buffer; absent, the device only reads it) and INDIRECT (4: the buffer is itself a table of descriptors). One request is a **chain** (a sequence of descriptors, each pointing to the next by index, ending at one without NEXT): in the language of a textbook, a linked list whose nodes are the 16-byte descriptors, whose pointers are table indices and whose payloads are the buffers.




The cards are not in the table in order: the chain 2, 0, 4 is the order of the links, as in any linked list. Indices are examples.

The figure is a virtio-blk read of one sector. The first box is the header the driver filled in (`struct virtio_blk_outhdr`: a 32-bit request type, a 32-bit priority, a 64-bit sector number counted in 512-byte units; type 0 is a read, 1 a write, 4 a flush: `virtio_blk.h`); it has no `WRITE` flag because the device only reads it. The second is the 512-byte buffer for the data, with `WRITE`, because for a read the device fills it. The third is one byte the device writes with the result (0 is OK, 1 an I/O error, 2 unsupported). A chain may use any free slots of the table in any order; the free ones are kept on a list of the driver's own. A buffer that straddles a page is simply two descriptors (5.10.3). Compare the RK11: the whole request was in registers, and could not be more than one; here it is memory the device reads, and the table holds many.

2.6.6 The available ring and the used ring

The two rings are arrays of 16-bit and 32-bit numbers with an index each.



The driver offers a chain by writing its head into ring[idx mod size] and then adding 1 to idx.
The device reports it done by writing (head, bytes written) into the used ring and then adding 1 to its idx.
Each side keeps its own private count of how far it has read the other side's ring. Indices are examples.

The **available ring** (`struct vring_avail`) is a 16-bit `flags`, a 16-bit `idx` and `ring[]`, 16-bit entries. The driver puts the index of the **head** (first descriptor) of a chain into `ring[idx mod size]` and then adds 1 to `idx`; `idx` only ever increases and wraps at 65536, so that "how many have been offered in all" is the difference of two readings and no extra state is kept. The **used ring** (`struct vring_used`) is the mirror: `flags`, `idx` and `ring[]` of **used elements** (`struct vring_used_elem`), each a 32-bit `id` (the head of the finished chain) and a 32-bit `len` (the number of bytes the device wrote into the chain's buffers). The device writes the element and

then adds 1 to its own `idx`. Each side keeps a private count of how far it has read the other's ring (`last_used` for the driver); each ring has one writer, so neither side waits for the other and no lock is needed. This is the **producer-consumer ring** (a fixed circular array with one writer and one reader, each owning one index) that the 4.3BSD DEUNA's transmit and receive rings already were, except that the "own" bit of each DEUNA entry is replaced by the two indices.

2.6.7 Posting a buffer and reaping the completions

```
post(q, head):                                      # head: first descriptor of a built chain
    avail.ring[avail_idx mod n] = head              # 1. name the chain
    FENCE                                           # 2. the descriptors and the ring entry are visible...
    avail_idx = avail_idx + 1 (mod 65536)
    avail.idx = avail_idx                           # 3. ...before the device is told there is one more
    FENCE
    if (used.flags & NO_NOTIFY) == 0:               # the device may ask not to be rung (section 2.6.9)
        mmio_write16(notify_addr[q], q)             # 4. the doorbell

reap(q):                                            # called from the interrupt routine, or when polling
    while last_used != used.idx:                    # the device has added finished chains
        FENCE                                       # read the index first, then the element and the data
(5.10.4)
        e = used.ring[last_used mod n]              # e.id = head of chain, e.len = bytes written
        complete(e.id, e.len)                       # the class driver reads status, frees the chain
        free_chain(e.id)
        last_used = last_used + 1 (mod 65536)
```

The doorbell is an ordinary 16-bit write to a notification address: the address is the notification area's base plus `queue_notify_off` times the `notify_off_multiplier` (QEMU decodes the queue from the address, `addr / multiplier`; what value the specification asks the driver to write is *unverified*: the code above writes the queue number, which QEMU ignores). The `FENCE` between step 1 and step 3 is the pdp64's statement 2.8.2; the processor owes nothing else (2.8.1).

A complete read of one sector, from the driver's side, putting the pieces of this section together:

```
blk_read(sector, buf):                              # buf: a physical address of 512 bytes
    h = alloc_hdr();  h.type = 0; h.ioprio = 0; h.sector = sector      # 16 bytes
    s = alloc_status_byte()
    d0 = get_free();  d1 = get_free();  d2 = get_free()
    desc[d0] = { addr: h,   len: 16,  flags: NEXT,         next: d1 }
    desc[d1] = { addr: buf, len: 512, flags: NEXT | WRITE, next: d2 }
    desc[d2] = { addr: s,   len: 1,   flags: WRITE,        next: 0  }
    post(q, d0)
    wait_for_completion(d0)                         # polled or interrupt-driven
    return status_byte(s) == 0
```

2.6.8 The polled driver, two ways

The two loops side by side, the RK11 of section 2.1 and the same job as virtio-blk:

```
RK11 (the PDP-11 way)                       virtio-blk (the virtio way)
------------------------------------------  ----------------------------------------------
write RKDA, RKBA, RKWC                      build 3 descriptors in memory (blk_read above)
write RKCS = READ | GO                      post(q, head)           # one doorbell write
while (RKCS & READY) == 0 : spin            while last_used == used.idx : spin   # reads memory
if RKCS & ERROR : read RKER, reset          status = the byte the device wrote in d2
one command in flight                       up to `size` commands in flight
the registers are this device's             the structures are every device's
```

The polling loop differs only in what it reads: a word of memory, the used index, where the RK11 loop reads a register. The read is an ordinary load as the page's memory type says, not a transaction on the device's link.

2.6.9 Suppressing notifications and interrupts

Doorbells and interrupts cost time on both sides, so each side can ask the other to stay quiet. Both flags are in the rings' `flags` fields and both are **hints** (a request the other side may, for a short time, not honour; the driver must work either way). The device sets `VRING_USED_F_NO_NOTIFY` (bit 0 of `used.flags`) to say "do not ring the doorbell; I am looking at the available ring anyway". The driver sets `VRING_AVAIL_F_NO_INTERRUPT` (bit 0 of `avail.flags`) to say "do not interrupt; I am polling". A finer scheme


exists when feature bit 29 (`VIRTIO_RING_F_EVENT_IDX`) is agreed: each side writes into an extra 16-bit word at the end of its ring the **index** at which it wants to be woken, and the other side then rings or interrupts only when it crosses that number (`virtio_ring.h`: the driver "publishes the used index for which it expects an interrupt at the end of the avail ring"; the host "publishes the avail index for which it expects a kick at the end of the used ring"). Whether the pdp64 uses it is not decided (2.13). A driver may mask a device's interrupts and poll the used ring (2.7.4).

2.7 Interrupts that are writes: MSI and MSI-X

On the Unibus an interrupt was a signal: a BR line went up, the processor granted the bus, and the device put its vector on the data lines. A PCI Express link has no such lines to raise. The first answer, kept for old devices, was four shared **interrupt pins** per slot (`INTA` to `INTD`; the header's **interrupt line** and **interrupt pin** bytes at 0x3C and 0x3D describe them, and bit 10 of the command register turns the function's pin off), which several devices share, so that the handler must ask each in turn whether it was the one. PCI Express emulates the pins with messages for old software (*unverified*); the pdp64 does not use them for its standard devices.

The answer for new devices is that **an interrupt is a memory write**. A function that wants attention does not raise a signal; it performs a write, of a value the system chose, to an address the system chose, and the part of the machine that owns that address (the **interrupt controller**: the unit that decides which core runs which handler) takes the arrival of the write as the interrupt. **MSI** (message-signalled interrupts, capability identifier 0x05) gives a function one address and one data value; how it varies the data to give several interrupts is *unverified*. **MSI-X** (capability 0x11, the "extended" form, and the one the pdp64's virtio devices use, errata 95 and 5.9.1) gives a function a **table** (an array in one of its windows) of entries, up to 2048 of them (the table-size field is 11 bits, `PCI_MSIX_FLAGS_QSIZE` 0x07FF), each with a separate address and data, so that every queue of every device can have an interrupt of its own, aimed at a core of its own.

MSI-X: an interrupt is a table entry the device turns into one memory write



When the device has something to report on vector 1 and the entry is not masked, it performs

```
memory write: address = (high, low) data = Message data
```

The address is a location the interrupt controller watches; no wire, no vector number from the card, no BR level.
If the entry is masked the device sets the vector's bit in the pending-bit array and sends nothing until it is unmasked.
Offsets and bit positions as in pci_regs.h (PCI_MSIX_*). The entry numbers are examples.

The capability record (`pci_regs.h`, offsets from the record's start) is: the identifier and next byte; a 16-bit **message control** at 2, whose bit 15 enables MSI-X, bit 14 masks every vector of the function and bits 10:0 hold the table size minus one; a 32-bit word at 4 whose low three bits say which BAR holds the table (the **BIR**, BAR indicator register) and the rest an offset in it; and a 32-bit word at 8 of the same form for the **PBA**, the **pending-bit array** (one bit per vector, set by the function when it wanted to interrupt and could not because the entry was masked). An entry is 16 bytes: the message address, low half at 0 and high half at 4; the message data at 8; and at 12 the **vector control**, whose bit 0 is the **mask** (while it is set the function sends nothing for that vector and records the wish in the PBA).

```
enable_msix(fn, nvec):
    cap  = find_capability(fn, 0x11)
    ctrl = cfg_read16(fn, cap + 2)
    table_bar    = cfg_read32(fn, cap + 4) & 7
    table_offset = cfg_read32(fn, cap + 4) & ~7
```

```
    table = bar_base(fn, table_bar) + table_offset
    cfg_write16(fn, cap + 2, ctrl | 0x8000 | 0x4000)     # enable, but mask every vector for now
    for v in 0 .. nvec - 1:
        entry = table + 16 * v
        (addr, data) = interrupt_controller_allocate(core_for(v), handler_for(v))
        mmio_write32(entry + 0,  addr & 0xFFFFFFFF)
        mmio_write32(entry + 4,  addr >> 32)
        mmio_write32(entry + 8,  data)
        mmio_write32(entry + 12, 0)                      # unmask this vector
    cfg_write16(fn, cap + 2, (ctrl | 0x8000) & ~0x4000)  # lift the function-wide mask

# in virtio, each queue is told its vector, and the device-wide changes have one too:
write16(msix_config, 0);  write16(queue_msix_vector, 1)    # 0xFFFF means no vector
```

When the device raises vector *v*, it sends a write of `data[v]` to `address[v]`, if the entry is not masked; a handler then learns what happened by reading the used ring (2.6.7) and, for the device as a whole, the interrupt-status structure of the virtio capabilities (type 3, section 2.6.2). On the Unibus there were four levels and the RK11's vector was `0220` at level 5, so a handler for a level shared with other devices had to find out which had spoken; here there is a vector for each queue, assigned by software, and no wire.

2.7.1 A device interrupts by a message-signalled write (MSI-X): the configuration change and each queue have a vector that the driver sets in the common configuration, and the interrupt status structure says why. *(P)* (This is 5.9.1.)

2.7.2 The write that raises an interrupt cannot overtake the data writes that precede it on the same path, so a handler that runs because of the interrupt finds the data in memory (2.5.4). *(D)*

2.7.3 Which unit of the processor receives the writes, how a core is chosen, how a vector number reaches a handler and how the interrupt controller is programmed (the address and data that `interrupt_controller_allocate` returns above) are not specified. *(S)* This is the interrupt-controller decision R1 of appendix B; the pseudocode shows the shape that any choice has.

2.7.4 A driver may mask a device's interrupts and poll the used ring instead (2.6.9, 5.9.2). *(D)*

Commentary. **Chain.** PDP-11: four BR levels and switch-set vectors, a scarce shared resource (`pdp/scb.s`). PCI: four shared interrupt pins per slot, described by the header bytes at 0x3C and 0x3D (`pci_regs.h`). PCI Express adds MSI and MSI-X, an interrupt as a write (`pci_regs.h`, QEMU `hw/pci/msix.c`). virtio gives each queue its own vector. The pdp64 uses MSI-X for its standard devices. **Trade-off.** A message carries its own vector, so no switch and no assignment table are needed and there can be thousands; the interrupt controller must be an address that many devices write, and a confused device that writes to the wrong address causes an interrupt (the IOMMU of 2.11 can refuse a write to an address that is not allowed). That the x86 local APIC and the ARM GIC's translation service receive such writes is *unverified*. **Impact.** An interrupt routine reads the used ring and the status structure; the table is programmed once at attach; the hardware needs an MSI-X target in the interrupt controller.

2.8 What the processor owes the bus

2.8.1 The processor owes the bus exactly three things: a memory type per page, a `FENCE` instruction whose meaning against Q64 is defined, and atomics that can reach device memory. *(D)*

2.8.2 A driver can be sure a descriptor is visible before it notifies the device: it builds the descriptor and publishes it in the queue, executes `FENCE`, and writes the queue's notification address (the doorbell). *(D)*

Commentary. **Chain.** The RK11 driver of 2.1 contains no ordering step; its writes reach the device in program order over one bus (*unverified* for models with a cache). PCI Express posts writes, and the driver must order them (2.2); multi-core machines add the same need between cores. ARM's `DMB`/`DSB` and device-memory types, and RISC-V's `FENCE` with I/O bits, play the same part (*unverified*). The pdp64's contract has three items: a memory type per page, a `FENCE` whose meaning against Q64 is defined, and atomics that reach device memory. A virtio device is written against the virtio specification and these three promises alone, without knowing the processor's pipeline. **Impact.** One `FENCE` before the doorbell is the whole ordering rule; `FENCE` is a compiler intrinsic; the memory type is two bits per page-table entry (6.7.1) and the bus honours it.

2.9 When an access fails

2.9.1 A read or instruction fetch of non-existent memory is a precise abort with cause `BUSFAULT`, at the faulting instruction. *(D)*

2.9.2 A posted write that times out, and an uncorrectable memory error, are machine checks: imprecise and not restartable. A `FENCE` before a probe makes even a posted write precise at a known point. *(D)*

2.9.3 `PROBER` and `PROBEW` test whether an address can be read or written without faulting. *(D)*

2.9.4 Resetting the bus is a write to a register of the root complex, not an instruction. *(D)*

Commentary. **Chain.** On the PDP-11 a read of a missing address takes the bus-error trap through vector 4 (`T_BUSFLT`, `pdp/scb.s`), which the kernel could not restart; V7's `nofault` idiom (`m40.s`: set `nofault`, touch the address, clear it) existed to probe for devices without dying. The pdp64 makes the read timeout a precise, restartable abort, and `PROBER` and `PROBEW` do what the idiom did; a driver handles a missing device in a few lines of ordinary fault handling. x86 machine checks and ARM's `SError` correspond to the imprecise class, and PCI returns all ones for a read of a removed device (both *unverified*), which every driver must learn to distrust; the pdp64 avoids that for removal (2.4.5), and returns all ones only for an empty configuration position (2.4.9). **Impact.** A timeout counter in the bridge and a way to make a read abort precise.

2.10 Atomics on the bus

2.10.1 The atomics are defined on a monitor: a load-linked takes a reservation, a write by any initiator clears it, and a store-conditional succeeds only if it is intact; the Unibus's `DATIP`/`DATO` locked pair is not an architectural primitive. *(D)*

2.10.2 A device that writes memory shared with a core takes part by clearing reservations. *(D)*

Commentary. **Chain.** PDP-11: the locked read-modify-write `DATIP`/`DATO` (*unverified* here; `decisions-pending.md` records it). VAX: interlocked instructions (`BBSSI`, `BBCCI`, `ADAWI`, `INSQHI`, checked in `decisions-pending.md` against the VAX-11 Architecture Reference Manual). Both lock; a lock is simple and a bottleneck as cores multiply. RISC-V `LR`/`SC` and AArch64 exclusive loads and stores use a monitor, which maps onto AXI exclusive access, at the cost of forward-progress rules (*unverified* here). The pdp64 chose the monitor (errata 45). **Impact.** Lock words and lock-free structures use the atomics of chapter 7; C11 atomics lower to them; the hardware needs a reservation monitor and an exclusive access, not a bus lock.

2.11 The IOMMU: a page table for each device

A device that is a bus master (section 2.5) can write wherever its packets say, and a descriptor is only an address the driver gave it. If the driver is wrong, or the device is, or the device has been modified by an attacker, that address can be the kernel's. The chain: on the PDP-11 the map registers of 2.1 (`UBMAP` at `0170200`) existed so that an 18-bit address could reach more memory, and as a side effect limited what a device could reach; the VAX Unibus adapter kept them (`ubareg.h`). The **IOMMU** (input-output memory management unit: a translator between the device's addresses and memory's addresses, with a page table of its own for each device, as the processor's MMU has for each program) makes the limit the purpose. A device is given **device addresses** (also called I/O virtual addresses) in its descriptors; the IOMMU walks that device's table to turn each into a physical address, and refuses the access if the table has no entry or the entry forbids that kind of access. The table is per device (the unit is a **domain**: a set of mappings that one or more devices share), so a network card can reach its buffers and nothing else.

Decided. An IOMMU is part of the design (errata 75). The five recommendations of the synthesis in `decisions-pending.md` (F25) are accepted (errata 85): translation is on by default; each device is its own domain; descriptors contain no kernel pointers; the mappings of the rings, which stay put for the life of the queue, are permanent; and a small buffer is **bounced** (copied into a buffer mapped for the device, so the device cannot reach the page that holds other data). The IOMMU's leaf entry shares bits 0 to 39 with the processor's page-table entry, and bits 40 to 63 are free (errata 85). *Open.* The format of the device table, where the unit sits in the machine, how a fault is reported and virtualization (section 2.13). Until the unit exists, a device addresses all of memory and a user-space driver can direct its device to write anywhere (5.10.2, 5.13.2).

With no address bit that says "device" (errata 97), another device's window is an ordinary address, so the IOMMU also refuses a device's DMA into another device's window (2.3.6). In virtio the feature bit `VIRTIO_F_ACCESS_PLATFORM` (33) states that the addresses in a device's descriptors are subject to the platform's translation; a driver on a machine with an IOMMU must have agreed it (2.6.3, 2.13).

2.12 What was checked, and what was not

The specifications of PCI Express and virtio are not on this machine. What the facts rest on:

- **Linux headers** (`/usr/include/linux/pci_regs.h`, `virtio_pci.h`, `virtio_config.h`, `virtio_ring.h`, `virtio_blk.h`, `virtio_ids.h`): configuration-space header offsets and the command, status and header-type bits; base-address register fields and the all-ones

sizing rule; capability-list fields; the MSI-X record, table entry, mask and size fields; link speed and width codes; the virtio vendor-specific capability layout and `cfg_type` values; the common configuration field order (offsets computed from it); status bits; feature bits 28, 29, 32, 33 and 36; the descriptor, available ring and used ring, their flags and alignments; the virtio-blk header, request types and status values; the device types.

- **QEMU sources** (`/home/david/claude/qemu-src`): vendor ID 0x1AF4 and device-ID base 0x1040; the ECAM shifts (`pcie_host.h`); the doorbell decoding (`virtio_pci_notify_write`); MSI-X entry layout and mask handling; the BAR sizing mask; the tree vocabulary of `docs/pcie.txt`.
- **2.11BSD** (`/home/david/claude/facetlang/unixtree/2.11BSD/sys`): the RK11 register structure and bits (`pdpuba/rkreg.h`), `rkstart` (`pdpuba/rk.c`), `rkprobe` (`autoconfig/rkauto.c`), the RK11 at `0177400` (`pdpstand/rk.c`), its vector `0220` at level 5 and vector 4 as the bus error (`pdp/scb.s`), `br4` to `br7`, the UNIBUS map and `mapalloc` (`h/uba.h`, `pdp/machdep.c`), and the console at `0177560` (`pdp/cons.c`).
- **4.3BSD** (`unixtree/4.3BSD/usr/src/sys`): `nexus.h` (`NEX780`, `NEXSIZE`, the nexus types), `autoconf.c` (`probenexi`, `unifind`, `badaddr`), `ubareg.h` (`UMEM780`, `UBA_PURGE780`), `if_de.c` (the DEUNA ring ownership flags). V7 `m40.s` for `nofault`.
- **Unverified** (general knowledge): the 18-bit width and the 8 KB extent of the I/O page (consistent with the addresses above, not stated in a source); `MSYN`/`SSYN`, NPR priority above interrupts and the grant chain; the locked `DATIP`/`DATO` as hardware; lane counts beyond x8; the kinds of TLP, posting and completions; the negotiation of width and speed; the dates and lineage of PCI and PCI Express; that an empty configuration position reads all ones on real hardware; PCI Express emulation of the interrupt pins; the way MSI varies its data; that writing 0 to `device_status` resets; the value the specification asks to be written to a doorbell (QEMU ignores it); that the specification asks for a barrier between publishing the available index and reading the used flags; the older virtio numbering; the Q-bus; PCI Express hot-plug signalling; Amiga AutoConfig, NuBus, Thunderbolt; the cache behaviour of PDP-11 models; the architectures named in the commentaries as "modern comparables".
- **Decided** by the author and recorded in `errata.md`: every statement tagged *(D)*; nothing else in this chapter is a decision.

2.13 Still open

The bus chapter's open items, each with options in the decisions document: the interrupt controller and routing, and so how the address and data of an MSI-X entry are made (R1, 2.7.3); starting the other cores and inter-processor interrupts (R2, B2); coherence beyond four cores (R3); the detail of the IOMMU (its five recommendations are accepted, errata 85; the format of its table, where it sits and how it reports a fault are open); errors raised by devices (R7); virtualization (R8); where the configuration space and the windows sit in the physical address space and how wide that address is (how software finds the width: no register is defined); how many pages "the first few" are; the exact feature subset of each virtio device, and whether the pdp64 uses the `EVENT_IDX` feature (2.6.9) and declares `ACCESS_PLATFORM` and `ORDER_PLATFORM` (2.6.3); and where the root complex's status register that records such a miss sits (2.4.10).

Chapter 3 — Graphics: the terminal and its devices

> ***Iteration two.*** *The devices of this chapter (`vic-64x` with its 48-bit RGBA pixel, `sid-64x` with 48-bit samples, `blt64`, and the eight-register face) are planned for the future, with the author's 12-register network, sound and graphics cards (errata 75). The first iteration uses virtio-gpu and virtio-snd over PCI Express (errata 79 and 95); this chapter describes what follows them. Statements keep their tags; the decisions of errata 73 and 74 stand. Errata 105 and 106 record the author's requests for the chapter and what is still open in it.*

The pdp64's display is meant to bring back what the Blit terminal and the Commodore 64 had, text and graphics on the screen at once, set by simple stores to memory, at a modern colour depth and screen size; its output is HDMI or another standard graphics output; its form is not yet fixed, and the standard device of the first iteration is virtio-gpu. The chapter is written for a reader who knows the PDP-11 and its teletype, or who is learning computing from the start, and who has met nothing invented after the 1970s. It follows the order in which the ideas arrived, because each one answers a complaint about the one before:

Stage	What it contributed	Section
PDP-11 teletype (KL11)	a stream of characters, one line at a time	3.1
VT52, VT100 (the author's "vt55")	a screen the program can address by position, through escape codes	3.2
Blit (Bell Labs, 1980s)	a bitmap in the address space, the bit-block-transfer, a terminal that runs downloaded programs	3.3
Commodore 64 (1982)	text, bitmap, sprites and sound together, all set by pokes	3.4
VGA, SVGA, VESA	memory-mapped text and pixels again, but planes, banks and no sprites	3.5
GPU	vertices, shaders and command buffers; the text path of every terminal emulator	3.6, 3.7
pdp64 terminal	the Blit and the C64 at a modern depth, with glyph slots	3.8 to 3.15

After the terminal come the problems that made graphics programming annoying (3.16), tearing (3.17), the author's idea of a C64-mode core (3.18), windows and compositors (3.19), audio (3.20) and the open mashup that ends the chapter (3.21). The PDP-11 had a teletype and nothing else of this chapter; where a later topic has no PDP-11 antecedent the text says so. Tags: *(D)* decided; *(P)* proposed; *(S)* stub (not specified). A fact that could not be checked on this machine is marked *unverified* and listed in 3.22.

How to read this chapter. A term is defined where it first appears, as the technical word and a plain restatement. In the boxes-and-arrows figures a box is a piece of memory and an arrow an address or index stored in it. Code blocks are pseudocode (C-like; `poke(address, value)` and `peek(address)` are an ordinary store and load, as in chapter 2) unless marked PDP-11 assembly. The numbered statements are the rules; the history and explanation are unnumbered prose, as in chapter 2.

3.1 The teletype: one line at a time

A PDP-11 in 1975 talked to a person through a **teletype** (a keyboard and a printer on one machine, joined to the computer by a serial line: characters go one after another along a single wire pair, each as a short burst of bits). The machine knew nothing about the page. A character went out and the printer put it to the right of the last one; a carriage-return character moved the print head back to the left margin and a line-feed character moved the paper up one line. Nothing could be erased, because the ink was on paper. This is **line-at-a-time output**: the program's only notion of position is "the end of what I have printed".

The hardware was a Unibus device like those of chapter 2: a few registers. The console of 2.11BSD is a KL11/DL11, declared in `sys/pdp/cons.h` as four words (receive status, receive buffer, transmit status, transmit buffer) at address 0177560 (`cnaddr` in `cons.c`); the transmitter-ready bit of the transmit status word is `DLXCSR_TRDY`, 0200 (both checked in the 2.11BSD tree on this machine, where the files are stored gzipped). Printing a line was a loop that waits for ready and stores a byte:

```
print_line(string):
    for each byte c in string:
        while (peek(XCSR) & TRDY) == 0:     # the printer is slow: ten characters a second or so
(unverified)
            wait
        poke(XBUF, c)
    poke(XBUF, CR); poke(XBUF, LF)          # carriage return, line feed
```

and in PDP-11 assembly, with the console's register addresses (transmit status 0177564, transmit buffer 0177566, the third and fourth words of the structure; the loop is in the style of the `rk` driver of chapter 2, not copied from a driver):

```
        MOV  #msg, R0
1$:     MOVB (R0)+, R1        ; next character; R0 now points at the one after
        BEQ  3$               ; a zero byte ends the string
2$:     TSTB @#177564         ; XCSR: bit 7 is READY
        BPL  2$               ; plus: not ready, look again
        MOVB R1, @#177566     ; XBUF: this sends it
        BR   1$
3$:
```

Everything a program can say to such a device is a stream of characters. The Unix **tty** (short for teletype: the device file that a program reads and writes characters from and to) is therefore a stream, and the programs written for it, the shell, the editor `ed` and the compiler's messages, think in lines. The stream has no way to say "put this here", which matters as soon as the printer is replaced by a screen.

3.2 The glass teletype and its escape codes

A **video terminal** is a keyboard and a screen on the end of the same serial line. At first it imitated the teletype (the "glass teletype": characters appear at the bottom and the page scrolls up). Then it did what paper could not: move the cursor to any place and change what was there. The program asked for this with **escape sequences** (characters that the terminal obeys instead of displaying, introduced by the escape character, code 27, written ESC), so the stream carries both text and commands.

Two generations matter here. The DEC VT52 is the textbook example of the problem, and the author's chat of 2026-06-18 (`c64stuff.txt`, line 4888, the assistant's words) records its cursor-to-position code: ESC Y, then a row character and a column character, each with 32 added so that the numbers arrive as printable characters. In pseudocode:

```
goto(row, col):
    send(ESC); send('Y'); send(row + 32); send(col + 32)   # the VT52 form, as recorded in the chat
send_string("Hello")                                       # the text appears at the cursor
```

The later DEC VT100 and the ANSI standard that followed it use ESC, an opening square bracket, numbers and a letter: `ESC [ 12 ; 40 H` moves the cursor to row 12, column 40, and `ESC [ 31 m` makes what follows red (these two sequences are general knowledge, *unverified* here). The chat records only that "VT100/ANSI" and the "xterm-256color" subset are what ordinary programs speak (`c64stuff.txt`, lines 218 and 4875).

The author's request names a "vt55" between the teletype and the Blit. No text in the repository mentions a VT55; the records name the VT52 and the VT100, so the chapter describes those. (The DEC model of that number was a graphics terminal, which would fit the author's order; that is general knowledge and *unverified*.)

The escape-code terminal gave a **character-cell display** (a screen that is a grid of cells, 80 columns by 24 rows being the usual size, each holding one character) that a program could address by position. It gave no control over the shape of a character, no drawing, no mix of fonts, and it kept a slow serial line between the program and the screen, speaking escape codes that differed from one make to the next. Unix answered the variety with a database of terminal descriptions (**termcap**, then **terminfo**: a file saying, for each make of terminal, which bytes mean "move the cursor") and a library (**curses**: a program that works out the fewest bytes to send to turn the screen as it was into the screen as wanted). *The UNIX-HATERS Handbook* complains of this (chapter 6, "Original Sin", recorded in `docs/kernel-pain-points.md`, section 14G: "Unfortunately for us, Unix was designed in the days of teletypes"). Each change to a cell cost several bytes of command over a slow line; the Blit answered that.

3.3 The Blit: a bitmap, and the blit

The Bell Labs terminal called the **Blit** (Rob Pike, Bart Locanthi and John Reiser; the repository records their papers as *Blit 1983* and *Tradeoffs 1985* in `docs/kernel-pain-points.md`, section 14I) took the opposite course. Instead of obeying commands about a grid of characters it had a **bitmap display** (a screen in which every dot, every pixel, is one or more bits in memory, so a program draws anything by changing bits) and a Motorola 68000 processor at 8 MHz to do the drawing: "256K bytes of memory dual-ported between an 800×1024×1 bit display and a Motorola MC68000 microprocessor". The screen memory was in the processor's address space like any other memory, and a program changed the picture by storing into it.

A bitmap is a picture stored row after row (the figure in 3.5 shows it). The operation that makes it usable is the **bit-block-transfer**, written **bitblt** and said "bit blit": copy a rectangle of bits from one place to another, combining each source bit with the destination bit by a chosen rule, the **raster operation** (RasterOp: the bit-by-bit rule that gives the result, such as "replace", "OR" or "exclusive-OR"). A rule of two inputs has sixteen possible forms; the Blit authors found that four sufficed (store, OR, clear, XOR), and XOR dominated its use, because drawing a shape twice with it erases it again, so a cursor moves without a saved copy of what was beneath it. With bitblt a program scrolls a window (copy the rectangle up by one line of text), moves a window (copy it), draws a letter (copy the letter's rectangle from a stored font to the screen) and fills an area. In pseudocode in the style of the Blit's library:

```
bitblt(source_bitmap, source_rect, destination_bitmap, destination_point, operation)
bitblt(font, rect_of('A'), screen, (x, y), OR)       # draws an A with its top left at (x, y)
bitblt(screen, window_rect, screen, window_rect + (0, -line_height), STORE)   # scroll one line
```


The Blit was a small computer, not a protocol. Its authors give the reason: "To draw graphics in the windows, sending escape sequences is traditional but makes poor use of the processing power of the terminal"; an earlier terminal that interpreted escape sequences failed because "too much state information was maintained by the terminal and guessed at by the Unix program". The host sent it programs over an RS-232 serial line, and the authors name that line as the weak point: "The greatest problem, though, is certainly the low bandwidth." The pdp64 keeps two lessons from it: the framebuffer is in the address space, and the blit is an assist that can be bypassed (3.8.6).

On the author's account the Blit inspired rio (Plan 9) and NeWS (Sun's); the sources confirm the line from the Blit's `mux` through 8½ to rio. Section 3.19 says what they were and what the pdp64 could carry over.

The Blit also raises a question the pdp64 inherits. It drew its cursor in software, in XOR, redrawing it at 60 Hz (`kernel-pain-points.md`, section 14I); other machines had **sprites** (small pictures that the display hardware overlays on the screen at a position the program gives, without touching the screen memory beneath). The next machine had eight of them.

3.4 The Commodore 64: text, graphics, sprites and sound together

The Commodore 64 (1982) was a home computer with a 6510 processor (a 6502 with a few input and output lines added) and two custom chips, the **VIC-II** (video interface chip) and the **SID** (sound interface device); every figure in this section is general knowledge, *unverified* here. It was built for games, and a game needs a scrolling background, characters moving over it, colour, music and noise at once. The chips read their data from memory by themselves, and every control is a memory location that the programmer can **peek** (read a byte) or **poke** (write a byte): the names are the C64 BASIC commands for a load and a store, and the source of the author's phrase "peek poke style".



Text mode. The standard screen is 40 columns by 25 rows, 1000 cells. The picture is *two* arrays in memory: screen memory, 1000 bytes, normally at $0400 (the number of the glyph for each cell), and **colour RAM**, 1000 four-bit entries at $D800 (the colour of each cell, one of 16). The shape of each glyph is not in these arrays; it is in the **character ROM** (a read-only memory of 8 bytes a glyph, one byte a row of eight dots, 256 glyphs: 2 KB for one set), which the video chip reads, and which a program can also replace by pointing the chip at glyphs it has made in RAM. To put an A at the top left, in red, the BASIC programmer writes two pokes, and the video chip, which reads screen memory sixty times a second by itself, shows it (screen codes, colour numbers and addresses *unverified*):

```
poke(1024, 1)          # $0400: screen code 1 is the letter A
poke(55296, 2)         # $D800: colour 2 is red
poke(53280, 0)         # $D020: the border colour, black
poke(53281, 6)         # $D021: the background colour, blue
```

This is the "peek poke" model: the screen is memory, a cell is an address, and the chip does the display. There are no escape codes and no stream; a program that pokes address 1024 + 40 * row + column has put a character there, at any time, in any order.

Bitmap mode. The same chip could show a bitmap of 320 by 200 dots in memory, with colour attributes per 8 by 8 block, and **multicolour** modes that trade width for colour. These were modes of one chip, and a program could mix them, text in one band of the screen and graphics in another, by changing mode at a chosen line (the raster interrupt below).

Sprites. The VIC-II had eight **sprites**: movable objects of 24 by 21 dots, each described by 63 bytes of data in memory, a pointer byte (the last eight bytes of screen memory, $07F8 to $07FF, say which 64-byte block holds each sprite's shape) and a few registers (x position, y position, colour, enable, size, priority; collision registers that say which sprites touched). The chip draws the sprites over the background as the picture is read out; to move a sprite, the program changes two registers, and the picture underneath is never disturbed. A ship, a bullet and an enemy are each a sprite, and a game's movement is a handful of pokes per frame.

The raster and the raster interrupt. The VIC-II draws the screen by reading it in order, row by row, while an electron beam sweeps the tube (the **raster**; the whole sweep is a **frame**, 50 or 60 times a second depending on the television standard). A register holds the number of the line being drawn, and another can be set to a line number so that the chip interrupts the processor when the beam reaches it: the **raster interrupt**. Programs used it to change a register mid-screen, such as the background colour or a sprite position, and to make changes while the beam was elsewhere (3.17).

Sound. The SID is a three-voice synthesiser with filters, again with registers that the programmer pokes: a voice has a frequency, a waveform (triangle, sawtooth, pulse, noise), and an attack, decay, sustain and release envelope. A note is a

handful of pokes. Sound came from the same few chips, controlled the same way: **one machine, one address space, a few chips whose registers are memory, and a program that sets them directly**.


The C64's limits are those of 1982: 16 colours, 40 columns, 8 by 8 cells, 8 sprites, three voices. The author asks for the same ease without them (3.8).

3.5 The PC years: VGA, SVGA, VESA

The IBM PC took a different road: its video adapters were separate cards with their own memory and registers, and the software model mixed memory with input/output ports (separate I/O instructions, which neither the PDP-11 nor the C64 had). The **VGA** (Video Graphics Array, IBM, 1987) became the baseline that later adapters imitated. Everything in this section about the PC adapters is general knowledge, *unverified* here.

VGA text mode. The text mode is the C64's idea with the colour folded into the cell: 80 columns by 25 rows, 2000 cells, in memory at 0xB8000, two bytes a cell: the character code and an **attribute byte** (four bits of foreground, three of background and one bit for blink, or for a bright background). The shapes come from a font in the adapter's own memory, which a program can replace. To put a red A at the top left:

```
poke(0xB8000, 'A')          # the character
poke(0xB8001, 0x04)         # attribute: black background, red foreground
```




The glyph shapes are in the display adapter, not in this memory; the cell says which, and in what colours.

Layout as in general knowledge of the IBM PC adapters (unverified here, 3.22).

VGA graphics. The same card had graphics modes, and here the trouble began. Mode 13h (320 by 200, 256 colours, one byte a pixel, at 0xA0000) was the easy one: the framebuffer is a single array and a pixel is the byte at y * 320 + x. A byte names one of 256 palette entries, and the palette (a table of 256 colours that the program loads through I/O ports) is in the card. Modes with 16 colours and higher resolutions were **planar**: the four bits of a pixel's colour were stored in four separate **planes** (four arrays, the same pixel position in each), and a write reached whichever planes the registers selected. That was fast for some operations and a puzzle for the rest. The adapter's window onto its memory was 64 KB at 0xA0000, so any picture larger than 64 KB needed **bank switching** (the card has more memory than the window shows; a register chooses which 64 KB slice appears in the window, and the program must change the register whenever its drawing crosses a slice boundary).

SVGA and VESA. Every manufacturer's Super VGA added modes (800 by 600, 1024 by 768, more colours) and, since there was no standard, each used its own registers to switch to them and to select a bank. **VESA** (a standards body of display makers) wrote the **VBE** (VESA BIOS Extensions: calls into the adapter's ROM that list the modes, set one, and switch banks), and a later version let the card present its whole memory as one **linear framebuffer** at a high address, ending the banks. The result is a block of memory, a **width** and **height** in pixels, a number of bits per pixel, and a **stride** (also called pitch: the number of bytes from the start of one row to the start of the next, which can be more than the width times the bytes per pixel, because rows are padded to a convenient boundary).



Padding makes every row start on an aligned address; software must use the stride, not width x bytes.

What the programmer had to know. A graphics programmer of the late 1980s and the 1990s carried all of this: the VGA registers, set through ports, that choose which planes a write reaches and how its bits combine with what is already there; the planar layout, with one pixel's colour spread over four arrays; **Mode X** (the games community's name for an unofficial VGA mode of 320 by 240 that used the planar memory for more than one screen of pixels and faster fills); the bank register of each Super VGA chip, which differed from chip to chip, with quirks that the VESA calls hid only in part; the palette, whose entries could be rewritten to cycle or fade colours without touching the picture; the **retrace**, because a change made at the wrong moment tore the picture; and hand-written assembly **inner loops** for the fill, the copy and the line, because a few cycles a pixel decided whether a game ran. The author's referent is the books of Michael Abrash on PC graphics programming: "still, is ok to mention the problems graphics coders faced, which is why we had 800 page michael abrash books" (errata 105). The titles, dates and page counts are *unverified*; no copy is on this machine and no record in the repository names a title. The depth of those books measures what the hardware pushed onto the programmer. The pdp64's aim (3.16) is that the program needs none of it.


The uncomfortable split. The PC now had two worlds. In **text mode** the hardware drew the characters, so text was fast, small (4000 bytes) and easy, and nothing else could be on the screen. In **graphics mode** a program could show anything but drew every dot: even a letter was the program's job (copy its rectangle from a font, the Blit's bitblt in software), and text became slow and ugly. Changing between the two meant switching modes, blanking the screen and losing the conveniences of the other world. The C64 had mixed text, bitmap and sprites in one frame; the PC made the programmer choose. Windowing systems, which need both together, chose graphics and drew everything.

Why sprites vanished. The VGA had no sprites, so games of its era drew every moving object into the framebuffer in software, while a second copy of the screen was being prepared (3.17). The processor was by then fast enough to move a screenful of dots in a frame time, the framebuffer was ordinary memory that any program could write, and windowing systems composed overlapping windows in software, which left no use for a hardware plane or sprite. The cost was real: moving a mouse cursor, a ship or a window meant writing and restoring pixels while the display was reading the same pixels (3.17).

3.6 The GPU: pipelines, vertices, shaders

In the 1990s a new kind of chip took the drawing from the processor: the **GPU** (graphics processing unit), first for three-dimensional games and now for every screen (general knowledge, *unverified* here, as is the rest of this section). Its design follows from what a three-dimensional scene is: a list of **vertices** (points in space with a position, and perhaps a colour, a direction the surface faces and a place in a picture), joined into **triangles** (three vertices: the one shape that is always flat, so any surface can be built from them), seen by a camera. To draw it, the machine must (a) work out where on the screen each vertex lands, (b) find which pixels each triangle covers (**rasterization**: turning a shape into the set of pixels it covers), and (c) decide each pixel's colour, which is usually where a **texture** (a picture stored in memory, which is looked up at a position given by the vertex, to paint a surface with, say, brick) comes in. The three steps are the **graphics pipeline**.

the graphics pipeline: data goes in at the left, pixels come out at the right



Every vertex goes through the same program at the same time on different lanes; so does every pixel.
The programmer writes the two shaders (pink); the rasterizer between them is fixed.

This is the model of general knowledge of current GPUs (unverified here, 3.22); stages such as geometry and tessellation are left out.

The early GPUs did each step in fixed hardware. The change that made the current GPU is that two of the steps became **programmable**: the programmer supplies a **shader** (a small program, in a special language, that the GPU runs; the name is historical, because shaders began as programs that computed the shading of a surface). A **vertex shader** runs once for every vertex and says where it goes; a **pixel shader** (also called a fragment shader) runs once for every pixel a triangle covers and says what colour it is. The rasterizer between them stays fixed, because it is the same arithmetic for every program.


Why a GPU is fast. A processor core runs one thread of arbitrary code as fast as it can, with a deep pipeline, large caches and logic to guess and reorder. A GPU is built for *the same small program run on a very large number of independent items*: a million pixels each need the same few dozen instructions. So it has thousands of simple **lanes** (units that each do arithmetic on one item), grouped so that 32 or 64 lanes (the size varies by maker) execute one instruction at the same time on different data (**SIMD**: single instruction, multiple data), and memory of very high **bandwidth** (bytes per second) feeds them. When one group waits for memory the hardware switches to another. Three more things matter in practice. The CPU does not touch pixels: it writes a **command buffer** (a list of commands in memory, such as "bind this texture, use these shaders, draw these 3,000 vertices as triangles") that the GPU reads and carries out by itself, like the descriptor rings of chapter 2. Work is **batched**: one command draws thousands of things, so its cost is paid once. And textures are stored in a layout that keeps neighbouring pixels close together, with the filtering done in hardware.

The GPU is poor at code with many decisions or with items that depend on each other, and the programmer must describe the whole job as a pipeline, write shaders and feed it in large batches. Section 3.16 shows how much graphics boilerplate comes from that model.

3.7 Why a terminal emulator uses the GPU, and why a font needs three dimensions

A **terminal emulator** (a program that shows a grid of text in a window of a graphical desktop and acts like the VT-series terminal of 3.2) has a small job: a grid of cells, each a glyph with a foreground and a background colour. Alacritty, kitty and WezTerm draw that grid on the GPU (general knowledge, *unverified* here; the author's chat names kitty). Why would a program that shows only text use machinery built for three-dimensional games?

How a GPU draws text. A screen of text is the same glyphs over and over. The program draws each glyph once, with a font rasteriser, into a **glyph atlas** (one texture holding every glyph the screen uses, side by side), then describes the screen as a list with one entry per cell: its position, the part of the atlas to show, and the two colours. The GPU draws each cell as a **quad** (a rectangle of two triangles) textured with that part of the atlas, and the pixel shader mixes foreground and background by the glyph's value at each pixel. The whole screen is **one draw call** (one command that draws a whole list).



To draw the screen: send the GPU a list with one entry per cell, and run one draw call.

entry = (cell column, cell row, atlas rectangle of the glyph, foreground, background)

vertex shader: turn the cell position into screen corners; pixel shader: look the glyph up, mix fg and bg

a change of one cell, or a scroll by a row, is a change to the list or to a number, not to 2 million pixels

The atlas is made by a font rasteriser (CPU) and uploaded once; new glyphs are added as they first appear.

The processor never touches a pixel. It changes a cell in the list when the text changes, and scrolling a line is a change of one number (where the list starts) or a shift of the list, not a copy of two million pixels. The glyph is stored as coverage values, so the shader can place it at a fraction of a pixel and blend it: **antialiasing** (smoothing an edge by giving the pixels it crosses an in-between colour) and **subpixel positioning** (placing a glyph more finely than the pixel grid). The GPU does this from its own memory, and the processor stays free to run the program whose output is shown.

Why a font needs the three-dimensional machinery. There are two parts to the answer. First, a glyph in a TrueType font is not a bitmap but an **outline** (curves in a coordinate system independent of size), and turning it into pixels is **rasterization** again, the job the GPU's rasterizer does for triangles. A font rasteriser on the processor produces the atlas once; the GPU can also do the curves itself, by tessellating the outline into triangles, by testing in the pixel shader whether each pixel is inside the curve, or by storing a **signed distance field** (a texture in which each pixel holds its distance to the nearest edge of the glyph, positive outside and negative inside, so a pixel shader draws the glyph sharply at any size from a small texture; credited to a Valve paper of 2007, *unverified*). Each is the 3D pipeline used on a flat shape.

Second, the pipeline is three-dimensional only by convention. A current GPU has **no 2D mode**: the 2D accelerator of the 1990s, with its blits, line draws and rectangle fills, is gone from the hardware, and drivers draw a rectangle as two triangles with a shader (general knowledge, *unverified*). A flat picture is the case of the 3D machinery in which every z value is the same and the camera looks straight on. A flat-rectangle engine would be smaller and would do the terminal's job; it is not built because the GPU has to handle the harder case anyway. That is how the terminal ends up on the 3D chip, and why the pdp64, which need not have a 3D chip, must decide what to put in its place (3.21).

3.8 The pdp64 terminal: the C64's chips and the Blit's bitmap

The chain so far: the PDP-11 sent characters down a wire (3.1); the VT52 and VT100 let the program address a screen by position (3.2); the Blit put the bitmap in the address space and the C64 put text, sprites and sound behind pokes (3.3, 3.4); the PC split text from pixels (3.5); the GPU made drawing a pipeline of shaders (3.6). The pdp64 terminal takes the Blit's and the C64's side of that history. The graphics half of this section is a repository specification from before errata 78 and 95; the statements below keep their tags, and 3.9 gives the author's newer description.

3.8.1 The graphics terminal is based on two machines, not one: the **Commodore 64**, for its video and sound as chips with registers that a program writes, and the **Blit terminal** (Rob Pike's bit-mapped windowing terminal), for its framebuffer in the address space and the bit-block-transfer operation that moves rectangles of pixels. The pdp64 modernises and extends both. *(D)*

3.8.2 The video device `VIC-64X` is the Commodore 64's video chip (the VIC-II) extended: a framebuffer in the address space with 48-bit pixels, scanned out through a line buffer. A pixel is RGBA with 12 bits per channel (errata 73, the author's decision of 2026-10-24). The register formats and the other pixel formats are unspecified (3.11). *(D)*

3.8.3 The sound device `SID-64X` is the C64's sound chip (the SID) extended: voices with filters, and also a general sound path that is not limited to the SID's voices; audio samples are 48 bits (errata 74, the author's decision of 2026-10-24). The register formats and the layout of a 48-bit sample are unspecified (3.11). *(D)*

3.8.4 The blitter `BLT64`, the Blit's bit-block-transfer operation as a device, copies and combines rectangles of pixels with raster operations: registers for the source and destination base addresses, the strides, the width and height, a raster operation (the sixteen binary operations of source against destination and the common ternary ones), a mask or transparent colour, and a control register with direction, go, busy and interrupt on done. The device chat chose a three-operand `draw` instead (`decisions-pending.md` E3). *(P)*

3.8.5 Each of the three is a device in a slot: it is enumerated by the bus, mapped into its own 4 KB page, and found by its identification register like any other (chapters 2 and 5). The device chat put the C64 devices in one 8 KB window per process (`decisions-pending.md` E5). *(P)*

3.8.6 The framebuffer stays plain memory, so that software can draw without `BLT64`; the blitter is an assist that can be bypassed, not the only way to draw (the Blit authors' advice in 1985 was "transparent, so it can be bypassed"). *(P)*

3.8.7 Four raster operations are required of `BLT64`: store, OR, clear and exclusive-OR (these four sufficed on the Blit, and exclusive-OR dominated its use); the other twelve binary operations and the ternary ones are optional. *(P)*

3.8.8 Whether the video device has a hardware cursor or sprite is unspecified (the vertical-blank interrupt is 3.8.9); the Blit read the mouse position at the retrace interrupt and drew its cursor in software, in exclusive-OR. *(S)*

3.8.9 Every register of the video device that takes effect at a frame boundary is shadowed: one write to its `ARM` register latches them all together at the start of the next vertical blank, and a status bit says whether the arm was taken in this frame or missed it. A sticky underrun bit and an underrun counter report a scan-out that ran dry. The vertical-blank interrupt occurs at a fixed line of the frame, whose number a register holds. The sound path's audio clock relation (3.12.4) is part of the same mode setting. *(D)*

Commentary. **Chain.** The PDP-11 reached its terminal through a serial register pair (3.1). The Blit (1980s) put the bitmap in the address space and had a framebuffer in the address space and did the bit-block-transfer in software ("no pixel-moving hardware", Pike, Locanthi and Reiser, 1985); hardware blitters came later, on the Amiga and other machines of the 1980s (general knowledge, *unverified*). The Blit received downloaded code, characters and editing messages over a serial line and drew every pixel itself. The C64 (1982) put video and sound in chips whose registers a program pokes and whose screen memory the video chip reads by itself. No source read says that it preceded the X11 protocol; the lineage the sources confirm runs from the Blit's `mux` through 8½ to `rio` (`docs/kernel-pain-points.md`, section 14I). The pdp64 needs no display protocol between host and terminal, because the display is a set of devices on the bus; the nearest thing is the descriptor ring of chapter 5. The pdp64 takes the framebuffer and the operation from the Blit, adds the hardware engine `BLT64`, and takes the video and sound chips from the C64. Plan 9 moved its window system into files (`/dev/bitblt`, later `/dev/draw`), a stream of small commands written to a device; that has the shape of a descriptor-ring entry (the comparison is an inference, not a source's statement).

Trade-offs. The blitter covers scrolling a terminal, moving a window, drawing a glyph, filling a rectangle and exclusive-oring a cursor; it does no three-dimensional graphics. `MCPY` is no substitute: it is one-dimensional and occupies the processor, where a blit has a stride and a raster operation and runs concurrently. The 48-bit pixel (four 12-bit channels, errata 73) probably exceeds what a display connector carries (unverified), so the display device converts to the connector's depth on the way out; likewise the 48-bit audio sample exceeds what a converter takes, so the sound device keeps the precision for mixing and filtering and reduces it at the output.

Improvements. The C64's video and sound registers were scattered and irregular; the pdp64 versions use the uniform register face, so one driver skeleton serves them (errata 95 removed that face for the standard devices, 3.9). **Benefits.** The blitter is about 1,500 lookup tables and a line buffer, nearly all address arithmetic (`docs/pdp64-fpga-plan.md`, line 316). **Modern comparables.** Display controllers in embedded systems commonly pair a scan-out engine with a blitter, and sound chips sit behind an I2S interface (general knowledge, *unverified*). **Impact.** *Kernel:* a framebuffer, a sound and a blit driver are each a mapped page and a few register writes; the uncached framebuffer needs no cache maintenance. *Compiler:* none. *Hardware:* a scan-out engine, a line buffer, an address-arithmetic unit for the blitter and a mixer for the sound device, each independent of the processor.

3.9 The terminal as the author describes it: peek/poke text and graphics, and glyph slots


The author, 2026-11-10: “our virtio-console device is an attempt to bring the nice properties of the blit terminal and c64 for doing simple and easy peek poke style display of text and also doing graphics, but with modern color depths and screen sizes, and with glyph maps we can even have a ttf engine generate glyphs and they will go into their memory slots for use.”

3.9.1 The pdp64’s terminal is meant to bring the properties of the Blit terminal and the C64 that the earlier sections describe: a display that a program drives by simple peeks and pokes, for text and for graphics together, at modern colour depths and screen sizes; and a **glyph map** (a table of slots, each a place in memory for the picture of one glyph) that a TrueType engine fills, so that the shapes of the characters are made by software and used by the display through their slots. *(P)*

3.9.2 What the author calls “our virtio-console device” is not specified in this repository: no document defines a device of that name, its identification, its queues or its registers, and the form of the terminal device (a new virtio device, an extension of virtio-gpu, or the native `VIC-64X` family of 3.8) is **open**. *(S)*

Why the name does not settle the form. Errata 78 (2026-11-03) deferred the native devices `VIC-64X`, `SID-64X` and `BLT64`, and errata 95 (2026-11-09) dropped their model: “forget the native 8 register devices. gone. virtio across the board.” The standard video and audio devices are virtio-gpu in 2D mode and virtio-snd (errata 79). The real **virtio-console** is a serial text device. The Linux header `virtio_console.h` on this machine shows device type 3 (`VIRTIO_ID_CONSOLE`), a configuration structure of `cols`, `rows`, `max_nr_ports` and `emerg_wr`, the feature bits `SIZE`, `MULTIPORT` and `EMERG_WRITE`, and control messages for ports (`PORT_ADD`, `PORT_REMOVE`, `RESIZE`); its data are byte streams, one receive and one transmit queue for each port (the queue layout is from the virtio specification, not the header, *unverified*), with no cells, colours, glyphs or pixels. The repository mentions it only as a candidate console for the boot ROM and kernel (5.7.1), a text stream like the teletype of 3.1. The author’s “virtio-console” therefore names a device with cells, colours, glyph slots and graphics, which neither the real virtio-console nor virtio-gpu 2D has and which the native devices were to have. Four readings are possible, and the chapter chooses none: (1) a new virtio device type of the pdp64’s own, with the cell array and glyph slots as the device’s memory; (2) virtio-gpu extended by a text layer and glyph slots; (3) virtio-console as the text *stream* for existing tty programs (3.2) beside a separate display device; (4) the native device family renamed. This is the first question of 3.23.

What the author’s earlier terminal chat adds (2026-06-18, `docs/c64-devices-from-chat.md` section 6; a separate project, not a pdp64 decision): a cell holds a 32-bit foreground colour, a 32-bit background colour, a UTF-8 character and about eight bits of attributes (bold, italic, underline, blink); “the number of cells take up so little memory, the 64 bits devoted to color is trivial”; “each cell holds its actual data, not a reference to the data”; sprites are a separate plane that composites over the cells; existing tty programs must run through a shim and native programs use the terminal fully, “peek and poke is the internal interface”. That design fits the cell array of the figure below and differs from the author’s new words in one place: **the chat-era cell holds the character code itself, while the glyph map of the new words implies a slot** (3.16, pair 3, candidate (a) against (b)).



a cell is a few bytes at base + (row * columns + column) * cell size; cells 0 to 4 of row 0 are shown

The same slot 4 serves both letters l: a glyph is drawn once and used by every cell that names it.

A TrueType engine rasterises each glyph into its slot (3.9.3). Field names and sizes are placeholders, not a specification.
Slot 6 shows an empty slot, to be filled when a cell first needs it.

3.9.3 A glyph map is a table of **slots**; a slot holds the picture of one glyph (for example, a rectangle of coverage values, one byte for each pixel, which tells how much of the pixel the glyph covers, so that the display can antialias), and the screen is an array of cells each of which names a glyph (by slot, or by a character code that is looked up to a slot) and gives its colours and attributes. A TrueType engine, which is software, rasterises a glyph from the font's outline at the pixel size of the display and writes the result into a slot; a glyph is made once and used by every cell that names it. The layout of the slot (its width, height, pixel format, and whether a slot may hold several cells' width, for a wide glyph) and the number of slots are unspecified. *(S)*

As an arithmetic example, with the chat-era cell (about 13 bytes: 4 + 4 + 4 for a character + 1 for attributes) and a 1920 by 1080 screen of 8 by 16 pixel cells, there are 240 columns and 67 rows, 16,080 cells and about 209 KB of cells; with slots of 16 by 32 coverage bytes (512 bytes) and 4,096 slots, the glyph map is 2 MB. Both are small against a 12.4 MB frame at 48 bits (3.13.2), which is the author's observation of 2026-06-18: the cells are small, and text is cheap to store. These are examples, not decisions.

3.9.4 Whether the terminal has sprites is not stated in the author's description of 2026-11-10; the C64 had them and the earlier terminal chat gave sprites a separate plane, and statement 3.8.8 leaves the pdp64's hardware cursor and sprites unspecified. *(S)*

3.10 A peek/poke program for the terminal

This is what the author's description would let a program do. **No register of the terminal is specified** (3.11), so the capitalised names are placeholders and any number is an example.

```
# placeholders: SCREEN is the base of the cell array, COLS its width in cells,
#               GLYPHS the base of the glyph map, GLYPH_SIZE the size of one slot

put_glyph(row, col, slot, fg, bg):                # one cell: four stores
    cell = SCREEN + (row * COLS + col) * CELL_SIZE
    poke32(cell + GLYPH, slot)                    # which glyph (or the character code, 3.9)
    poke32(cell + FG, fg)                         # colours, modern depth: the pixel format of 3.8.2
    poke32(cell + BG, bg)
    poke8 (cell + ATTR, 0)

define_glyph(slot, font, codepoint):              # a glyph the program has just thought of
    bitmap = ttf_rasterise(font, codepoint, CELL_W, CELL_H)   # software: the TrueType engine
    copy(GLYPHS + slot * GLYPH_SIZE, bitmap, GLYPH_SIZE)      # an ordinary memory copy

put_glyph(0, 0, slot_of('A'), RED, BLACK)         # an A, red on black, top left
```

```
define_glyph(200, my_font, 0x03BB)                # a lambda goes into slot 200
put_glyph(0, 1, 200, WHITE, BLACK)                # and is used by naming slot 200
```

Graphics beside text, in the C64 manner, are another array and one more register set:

```
# the graphics plane: a framebuffer of FB_W by FB_H pixels; this sketch uses 32-bit pixels, as the standard
device does
# (the 48-bit pixel of 3.8.2 would be 6 bytes: a different multiplier and three 16-bit stores)
put_pixel(x, y, colour):
    poke32(FB_BASE + y * FB_STRIDE + x * 4, colour)         # FB_STRIDE counts bytes, as in 3.5
# sprites, if the design has them (3.9.4: not decided):
poke(SPRITE_N + X, 100); poke(SPRITE_N + Y, 80); poke(SPRITE_N + SHAPE, shape_slot)
```

Each line is one store, so the program is as small as the C64's was. Everything is memory, so `memcpy` fills a glyph slot as it fills any buffer. Compared with the list of 3.16 there is no mode setting, no format conversion, no flush (the memory type of 3.13.1 takes its place), no atlas to pack, no shader and no command buffer. The terminal does no three-dimensional graphics; for that the standard device, virtio-gpu, remains (3.14, 3.15).

3.11 The stub: the C64 and Blit documentation

3.11.1 The register-level definitions of `VIC-64X`, `SID-64X` and `BLT64` (register names, offsets, bit fields, the 48-bit pixel and sample formats, the sprite, raster-interrupt and voice models inherited from the C64, and the bit-block-transfer operations and windowing model inherited from the Blit) are a stub: only the `BLT64` registers listed in 3.8.4 are specified. The author's earlier device chat decided much of the rest (register conventions, the 8502 island, the display rules); it is extracted in `docs/c64-devices-from-chat.md` and awaits adoption (`decisions-pending.md` E1 to E11). *(S)*

3.11.2 What is fixed: the devices exist, they follow the eight-register convention in the terminal's slots (errata 95 later withdrew that convention for the standard devices), and the interrupt, `FENCE` and uncached-framebuffer rules of section 3.13 apply. *(S)*

Commentary. This section is the placeholder for the C64- and Blit-derived specification. The Blit side can draw on the papers recorded in section 14I of `docs/kernel-pain-points.md`: the four primitives `bitblt`, `texture`, `segment` and `point`, the `Bitmap`, `Rectangle`, `Point` and `Texture` types, half-open rectangles, and overlapping windows with obscured parts kept off screen. **Impact.** *Kernel:* none until defined. *Compiler:* none. *Hardware:* the block RAM budget (3.13.3) is settled before the video device is built.

3.12 How the terminal drives HDMI and the other ports

3.12.1 The display connector is standard kit: HDMI (and DVI and DisplayPort) is a transmitter chip that takes pixels and sync signals in parallel and does the link protocol, the encoding and the electrical signalling itself; on the first board it is the DE10-Nano's ADV7513, set up once over an I2C-style control bus. *(D)*

3.12.2 The video device's output side is therefore a pixel stream with horizontal and vertical sync, a clock and a data-enable, which is what every such transmitter accepts; the device's registers set the mode (width, height, blanking, pixel clock, the pixel format), the base address of the framebuffer and the display on and off. *(P)*

3.12.3 Other ports are the same shape: a different transmitter (VGA digital-to-analogue converter, DisplayPort, an LVDS panel) takes the same pixel stream, so the pdp64's side does not change, and each port is one more slot or one more output of the video device. *(P)*

3.12.4 The sound device's output is likewise a standard digital audio stream (I2S or the HDMI audio channel) into a converter or the transmitter. The processor never sees the HDMI packets, but whoever sets the mode must also program the audio clock relation: the transmitter needs N (and CTS, or a hardware CTS calculation) for each pixel clock and sample rate (an ADV7511 driver computes both; general knowledge, *unverified*). *(P)*

3.12.5 The ports that carry data, SATA for storage and USB for peripherals, follow the same pattern: the protocol is in the chip or controller block, and the processor's side is a slot with the common registers and a ring (chapter 5). *(D)*

Commentary. **Chain.** The PDP-11's output was the serial line of 3.1, with no display connector. The MiSTer framework on the DE10-Nano already works this way: the retro cores produce a pixel stream, and the framework's scaler and the HDMI transmitter do the rest, which is why the plan buys HDMI there. **Trade-offs.** The transmitter's control bus needs one-time setup, which a boot routine does with a few register writes; the pixel clock must be generated to the mode, with a phase-locked loop on an FPGA and the same block in silicon. **Improvements.** Replacing the transmitter or the connector changes

nothing above the video device, as a SATA controller behind its ring can be replaced without changing the disk driver. **Benefits.** No part of the operating system carries an HDMI, SATA or USB protocol stack. **Modern comparables.** Single-board ARM computers with a display controller and an HDMI transmitter (general knowledge, *unverified*). **Impact.** *Kernel:* a display driver sets a mode and a base address; hot-plug of a monitor is a bus event if the transmitter reports one. *Compiler:* none. *Hardware:* a pixel generator, a clock and an off-chip transmitter, with no protocol logic in the pdp64's own gates.

3.13 The framebuffer, the memory type and the memory budget

3.13.1 The framebuffer is mapped with the uncached memory type, or the processor's writes sit in the data cache while the video device scans out stale memory; a `FENCE` separates writing a device's registers from setting its go bit. *(D)*

3.13.2 On the first board the block RAM (about 5.5 megabits on the DE10-Nano) cannot hold a modern frame (a 1920 by 1080 frame at 32 bits is 8.3 MB, and at the 48-bit pixel of 3.8.2 it is 12.4 MB), so the framebuffer lives in main memory and the block RAM holds the scan-out line buffer of a few kilobytes. *(D)*

3.13.3 The block RAM budget (caches, translation buffer, the blitter's scratch and the sound voices' state) is settled before the video device is built. *(D)*


3.13.4 The framebuffer is ordinary memory and the devices' registers are device windows (section 2.3.6), so a page-table entry that maps the framebuffer as a device, or a register page as cached memory, is a mistake that the memory type of the page makes visible to the kernel. *(P)*

Commentary. **Chain.** The PDP-11 had no framebuffer; whether the 11/70's cache watched Unibus writes so that DMA looked coherent is *unverified* (2.5, commentary). The VAX Unibus adapter's buffered data paths needed purging (2.5), and ARM and MIPS systems with non-coherent DMA place cache maintenance in the kernel (*unverified*). The pdp64 chooses the memory type instead (2.5.2). **Trade-offs.** An uncached framebuffer makes a single pixel write slow and a long run of writes no slower per byte. That suits the blitter, which writes the bus directly, and punishes pixel-by-pixel drawing from the processor. **Modern comparables.** Write-combining memory types on x86 and ARM serve the same purpose (general knowledge, *unverified*). **Impact.** *Kernel:* the mapping rule is one memory-type value in the page-table entry. *Compiler:* none. *Hardware:* the scan-out reads main memory by bus mastering and competes with the processor for bandwidth.

3.14 virtio-gpu: the standard graphics device

The first iteration's display (errata 79: "virtio is fine"; virtio-gpu in its 2D mode) is a virtio device like the disk of chapter 2, so 2.6 applies: it is found by enumeration, its queues are rings of descriptors in memory, and the work is commands in a queue. The commands below are from the Linux header `virtio_gpu.h` and from QEMU's `hw/display/virtio-gpu.c`.

The vocabulary. A **resource** is a picture that the device owns, named by a number the driver chooses (`resource_id`), with a pixel format, a width and a height. Its **backing** is the driver's own memory that holds the pixels: a list of `{addr, length}` entries (`struct virtio_gpu_mem_entry`) naming the pages. A **scanout** is one output of the device (up to `VIRTIO_GPU_MAX_SCANOUTS`, 16, in the header); `SET_SCANOUT` says which resource, and which rectangle of it, an output shows. Two commands move and show the pixels: `TRANSFER_TO_HOST_2D` copies a rectangle of the backing memory into the device's picture, and `RESOURCE_FLUSH` tells the device that a rectangle changed and should be shown. The pixel formats are 32 bits with 8 bits a channel (eight in the header): `B8G8R8A8_UNORM`, `B8G8R8X8_UNORM`, `A8R8G8B8_UNORM`, `X8R8G8B8_UNORM`, `R8G8B8A8_UNORM`, `X8B8G8R8_UNORM`, `A8B8G8R8_UNORM`, `R8G8B8X8_UNORM` (values 1 to 4, 67, 68, 121 and 134; the names give the channel order, the *colour order* annoyance of 3.16). Every command starts with a `virtio_gpu_ctrl_hdr`: a type, flags, a 64-bit fence id, a context id and a ring index; the flag `VIRTIO_GPU_FLAG_FENCE` asks that the response carry the fence id once the work is done, which is the device's only completion-ordering tool. The rectangle is `struct virtio_gpu_rect`: x, y, width, height, four 32-bit numbers.



Each line is one command in the control queue, answered by a response; the header of every command is a type, flags, a fence id, a context id.

```
# the whole of a virtio-gpu 2D start-up and one update, as pseudocode over the queue of chapter 2.6
send(RESOURCE_CREATE_2D,     resource_id=1, format=X8R8G8B8, width=1024, height=768)
send(RESOURCE_ATTACH_BACKING, resource_id=1, entries=[{addr=PAGES, length=1024*768*4}])
send(SET_SCANOUT,            scanout_id=0, resource_id=1, rect={0,0,1024,768})

draw_into(PAGES)                                    # the driver writes pixels: ordinary stores
send(TRANSFER_TO_HOST_2D,    resource_id=1, rect={0,0,1024,768}, offset=0)
send(RESOURCE_FLUSH,         resource_id=1, rect={0,0,1024,768})
```

In QEMU's `virtio-gpu.c`, `transfer_to_host_2d` rejects a rectangle that is not inside the resource with `VIRTIO_GPU_RESP_ERR_INVALID_PARAMETER`, then copies it **row by row** from the backing into the resource using the resource's stride, or in one copy if the rectangle spans whole rows. `resource_flush` rejects a rectangle outside the resource the same way, then asks each scanout showing the resource to update the part of its display that the rectangle covers. The transfer is the **upload** and the flush is the **present**, and the program does both after drawing.

What it does not define. Neither the header nor the QEMU function mentions the vertical blank, a page flip, a refresh rate or tearing: the flush says "show this rectangle now" and the host decides when its display next reads it. The only timing handle is the fence of the header. QEMU's configuration has a `refresh_rate` field for each output (`include/hw/virtio/virtio-gpu.h`), and the device can report an EDID with the optional feature `VIRTIO_GPU_F_EDID`; the header does not say that either changes how a flush is timed. The standard device therefore gives a program a damage rectangle (the flush rectangle), a cursor (the cursor queue, `UPDATE_CURSOR` and `MOVE_CURSOR`), a fence and display information (`GET_DISPLAY_INFO`: size and enabled flag of each output), and no anti-tearing sugar (3.17) beyond that.

3.14.1 The standard graphics device of the first iteration is virtio-gpu in 2D mode over the virtio PCI Express transport (errata 79); its commands are the five of the figure, plus the cursor queue and the display-information query. *(D)*

3.14.2 The feature subset of virtio-gpu that the pdp64 requires (the EDID feature, the fence flag, the cursor queue, the blob and 3D features of the header, which are not used for 2D) is not specified. *(S)*

3.14.3 The framebuffer of virtio-gpu is the backing memory that the driver allocates; on the pdp64 it is ordinary memory mapped uncached (3.13.1), and the transfer command is the hand-off that tells the device to read it (the five steps of 2.5.3). *(P)*

3.14.4 The standard device has no 48-bit pixel and no text layer: the 48-bit pixel of 3.8.2 belongs to the native device that is deferred, and a text terminal over virtio-gpu is a program that draws glyphs into the backing memory with the processor (the way 3.5 ends) or with a library. *(S)*

Commentary. **Chain.** The PDP-11 has no antecedent: its devices had registers, not queues (2.1). QEMU offers virtio-gpu as a virtual machine's display (`hw/display`): the guest draws into its own memory and tells the host which rectangle to show. **Trade-offs.** It is the most standard route (one tested driver, the same in QEMU, `sim64` and the FPGA, as errata 79 says) and does everything in software: the processor writes every pixel and the host copies them, which is cheap for a terminal with little damage and costs a game what 3.5 described. **Improvements.** The sugar of 3.16 can be a library over it: set up the five commands, allocate the picture, draw text from a glyph cache and flush only the damage (sketch 4 of 3.21). **Benefits.** No special hardware, and the display of the first iteration works in the emulator now. **Modern comparables.** Linux's `virtio_gpu` driver, which sits on the DRM interface of 3.16. **Impact.** *Kernel:* a driver for the five commands, one queue of 2.6 and a cursor queue. *Compiler:* none. *Hardware:* none beyond the virtio device and the bus.

3.15 A standard graphics card

3.15.1 A PCI Express graphics card is not excluded by the architecture: a bridge could present PCI Express functions as slots on the bus, enumerated like any other device. *(P)*

3.15.2 Against a standard card: PCI Express configuration space, base-address mapping and message-signalled interrupts, a driver stack for a programming model that for some vendors must be reverse-engineered, the card's firmware and the initialisation a PC's firmware performs, and no hard PCI Express block on the first board (the Cyclone V and the Zynq 7020 are recorded as lacking one, *unverified* here; a Zynq UltraScale+ has a hard root complex, `docs/pdp64-fpga-plan.md`). *(D)*

3.15.3 On the other side PCI Express is a standard enumerated bus, which suits the bus-as-a-device design (each function a slot, as each USB device is), and OpenBSD carries graphics drivers for several vendors' cards ported from Linux (*unverified*). *(P)*

Commentary. **Trade-offs.** The terminal described here works on the first board; a standard card needs a PCI Express root complex, a large block where the chip has none, and a graphics driver ported to the pdp64, which is a larger task than the architecture (`docs/pdp64-fpga-plan.md` says the same and answers no to a discrete GPU). **Modern comparables.** PowerPC and RISC-V workstations take PCI Express graphics cards with open drivers (general knowledge, *unverified*). **Impact.** *Kernel:* a large graphics driver ported. *Compiler:* none. *Hardware:* a PCI Express root complex and a bridge to the bus.

3.16 What made graphics programming annoying

The author, 2026-11-10: "basically, anything that made graphics programming annoying or cumbersome or boiler platey, we want to sugar away to almost nothing." This is a goal; the means are open. **Boilerplate** is code written the same way in every program before the program can do anything of its own. This section lists the boilerplate that exists, shows three pieces of it, and asks of each what the architecture could do so that the program does not have to. The PDP-11 has no antecedent: its console needed none (3.1). The chain runs from the VGA programmer's register lore (3.5) to the Linux and Vulkan setup lists below.

3.16.1 The aim is that what made graphics programming annoying, cumbersome or boilerplate is reduced by the architecture to almost nothing; the means are open and each is a candidate (section 3.16 and its table). *(P)* (The author, 2026-11-10, errata 105.)

3.16.2 The standard first-iteration device, virtio-gpu, keeps its own protocol (3.14); where this section says that a sugar "would" appear, it appears in a device of the second iteration (3.8) or as a library over virtio-gpu, and no sugar is specified. *(S)*

3.16.3 The measure that every design in this chapter is held to is the author's: "graphics programming should be as simple and pleasurable as the c64 was." *(P)* (2026-11-10, errata 105; a goal, not a design.)

The books of Michael Abrash on VGA and PC graphics programming (the author's "800 page michael abrash books"; titles and page counts *unverified*, 3.5) exist because a programmer could not get a fast picture without knowing the VGA's registers, its planar memory, its retrace, the banking of each chip and how to hand-tune the inner loops. Each row of the table below is a piece of that knowledge, or of its successor (the long setup lists of the Linux display interface and of Vulkan), that the author would like the architecture to make unnecessary. The knowledge was real and was needed.

Three worked pairs follow. Each shows the boilerplate as the real systems have it (names are those of the real interfaces, checked in the headers on this machine where marked, otherwise general knowledge, *unverified*) and then what the pdp64 could offer. The pdp64 versions are sketches with placeholder names, not registers.

Pair 1: getting a picture on the screen at all. On a VGA/VESA PC the program asked the BIOS for the list of modes, picked one, set it, and found the framebuffer:

```
# VESA (VBE), 1990s: about 15 lines in a real program (illustrative, not measured)
info = vbe_get_controller_info()
for m in info.mode_list:
    mi = vbe_get_mode_info(m)
    if mi.width == 1024 and mi.height == 768 and mi.bits_per_pixel == 32 and mi.has_linear_framebuffer:
        mode = m
vbe_set_mode(mode | LINEAR_FRAMEBUFFER_BIT)
fb = map_physical(mi.physical_base, mi.pitch * mi.height)
```

On Linux (DRM/KMS, the kernel's display interface) the same job is longer. The program opens the device, lists **connectors** (the outputs), reads the monitor's modes (**EDID**, the data block in which a monitor describes the modes it supports; general knowledge), chooses one (`struct drm_mode_modeinfo` in `drm_mode.h`: pixel clock, horizontal and vertical totals and sync positions, refresh rate), allocates a **dumb buffer** (a plain pixel buffer), registers it as a framebuffer (`DRM_IOCTL_MODE_ADDFB2`, with a format code and a pitch), maps it, and sets the mode on a **CRTC** (the unit that does scanout; the name comes from cathode-ray tube controller):

```
# Linux DRM/KMS, one output, no atomic: about 40 lines in a real program (illustrative, not measured)
fd = open("/dev/dri/card0")
res = drmModeGetResources(fd)
conn = first connected connector in res
mode = conn.modes[0]                          # the monitor's preferred mode, by convention first
crtc = a crtc the encoder of conn can use
buf = create_dumb(fd, mode.hdisplay, mode.vdisplay, 32)    # returns handle, pitch, size
fb_id = drmModeAddFB2(fd, w, h, XRGB8888, handle, pitch)
ptr = mmap(fd, map_dumb(buf).offset, size)
drmModeSetCrtc(fd, crtc, fb_id, 0, 0, conn, mode)
```

A program on Vulkan or OpenGL meets another list: create an instance, enumerate physical devices, choose a queue family, create a logical device, a window surface, a swap chain and its images, image views, a render pass, framebuffers, command pools and buffers and synchronisation objects (the names `vkCreateInstance` and `vkCreateSwapchainKHR` are Vulkan's, whose headers are not on this machine, *unverified*; OpenGL's `glGenBuffers`, `glCompileShader` and `glLinkProgram` are in `glext.h` here). A "hello triangle" in Vulkan is commonly several hundred lines (general knowledge, illustrative). In virtio-gpu the equivalent is five commands (3.14): create resource, attach backing, set scanout, transfer, flush, with the drawing between them.

The pdp64 could offer **a device that already shows something**:

```
# the pdp64 way, open (a sketch)
# the device powers up with a sane default mode, in the monitor's preferred mode, with a canonical pixel
format:
fb = peek(DISPLAY_BASE)            # where the picture is, always mapped
w  = peek(DISPLAY_WIDTH); h = peek(DISPLAY_HEIGHT)
poke(fb + (y * w + x) * 4, 0xFFFFFFFF)     # a white pixel: done
```

Options, with trade-offs. (a) The device **reports its mode** (a register holds the width, height and refresh rate of the mode chosen at start-up from the monitor's data; virtio-gpu's `GET_DISPLAY_INFO` already returns the width and height of each output in a `virtio_gpu_resp_display_info`); nothing to set. *Cost:* the device reads the EDID itself (a small I2C engine, which 3.12.1 already puts at the transmitter chip) and applies a policy; a program that wants another mode still has the registers. (b) A **fixed canonical pixel format** with the device converting at scanout (the repository's 48-bit RGBA pixel, errata 73, would be that format on the native device; virtio-gpu offers only 32-bit formats with eight bits per channel: `VIRTIO_GPU_FORMAT_B8G8R8A8_UNORM` and its siblings, in `virtio_gpu.h`, so the 48-bit pixel does not exist on the standard device; 3.23 lists the inconsistency). *Cost:* a conversion stage in the scanout, and memory a program wastes if it wants fewer bits. (c) **Stride equal to width** unless the program asks for padding, and the framebuffer window **always mapped**: the program has no `mmap`, no bank register, no

`map_physical`; the window is in its address space from the start, a decision of the page tables and the bus (2.3.3 and 3.13.4). *Cost:* a fixed place in the address space, and a rule for what a program does that wants two framebuffers.

Pair 2: the cache and the flush. A processor has a **cache** (a small fast memory that keeps recently used data close to the core). Pixels the program has written may still be in the cache and not in memory, and a device that reads memory by DMA then sees the old data. Where the device does not snoop the cache, the program must flush:

```
# a display that does not snoop the cache: about 3 lines per update, in every program (illustrative)
draw(framebuffer)
cache_clean_range(framebuffer, size)       # push the dirty lines to memory
memory_barrier()                           # and make sure the writes are ordered before the notification
poke(DOORBELL, 1)
```

The pdp64 already removes this, and chapter 2 says how: processor caches are coherent with each other, a device and the processor are not, and the answer is a memory type, **uncached**, instead of a flush instruction: "buffers are mapped uncached and the hand-off is explicit" (2.5.2), and "No driver can forget a cache clean or invalidate, because there is none" (2.5, commentary). The framebuffer is mapped uncached too (3.13.1). The cost, stated in 3.13, is that a long run of writes is no slower per byte but a single write is slow; a write-combining memory type for the framebuffer is a candidate improvement (3.13) that the four memory types of 2.3.4 do not name. So the sugar is decided for correctness *(D)* and open for speed *(P)*.

Pair 3: drawing text. On a GL or Vulkan system text is the longest boilerplate, because the GPU has no text:

```
# a GPU text path (illustrative; about 150 lines in a real small program, not measured)
font = ft_load("DejaVuSansMono.ttf"); ft_set_size(font, 16)
atlas = new_texture(1024, 1024)
for each character c needed:
    bitmap = ft_render_glyph(font, c)          # the font rasteriser (CPU)
    rect = pack_into_atlas(atlas, bitmap)      # find room: a bin-packing problem
    upload(atlas, rect, bitmap)
    remember(c, rect, advance, bearing)        # metrics: how far to move on, where the glyph sits
for each cell on screen:
    append_quad(vertex_list, x, y, rect_of(char), fg, bg)
upload(vertex_list); bind(atlas, shader); draw(vertex_list)
# plus kerning, ligatures, right-to-left runs, combining marks, fallback fonts, scaling for HiDPI
```

The pdp64's terminal would do it as the C64 did, with one store:

```
# the pdp64 way, open (a sketch; names are placeholders)
poke(CELL(row, col).glyph, SLOT_OF('A'))     # or: poke(CELL(row, col).char, 'A')
poke(CELL(row, col).fg, RED)
# a new glyph: one library call fills a slot from the TrueType engine
font_render_into_slot(font, 'λ', slot)       # rasterises the outline and writes the bitmap into the slot
```

The author's glyph slots do the work of the atlas, and one library call replaces the first half of the boilerplate (3.9). Two candidates: (a) the cell holds the **character code**, and the device or a table maps the code to a slot, so the program never names slots (the author's c64x terminal of 2026-06-18, `c64stuff.txt`, line 5015: "each cell holds its actual data, not a reference to the data"); or (b) the cell holds the **slot number** directly, which is the simplest hardware and makes the program responsible for assigning slots. The choice is open (3.23): (a) is easier for the program and costs a lookup table in the scanout; (b) is nearly free and puts a small allocator in a library.

The pain points, in a table

Each row names something that has annoyed graphics programmers, the size of its boilerplate (line counts are *illustrative* and **not measured**), the sugar the architecture could offer, and where it appears in the sketches of 3.21 (S1 layers, S2 layers plus blitter, S3 command queue, S4 plain virtio-gpu with a library). "Decided" means the repository already decides it.

Pain point	Typical boilerplate (illustrative)	The sugar that would remove it	Where (3.21)
Mode setting and discovering what the display supports (EDID, modes)	15 lines (VESA) to 40 (DRM)	the device reads the monitor and starts in its preferred mode; a register reports it	S1 S2 S3 native; S4: `GET_DISPLAY_INFO` gives the size, a library the rest
Pixel formats	one format code to get right, and conversion code when it is not	one canonical format, the device converts at scanout	S1 S2 S3; S4 has 32-bit formats only

Pain point	Typical boilerplate (illustrative)	The sugar that would remove it	Where (3.21)
Stride and pitch	one multiply in every pixel address	stride equal to width unless asked; the address of pixel (x, y) is a register-reported formula	S1 S2 S3
Endianness and colour order (RGB or BGR, alpha first or last)	a swap or a table, in every program	one defined order, little-endian (decided for the machine, errata 72); the colour field order named once	all
Bank switching and mapping the framebuffer	5 to 20 lines	a window always mapped, no banks	all (3.13.4 is the rule for the type)
Double buffering and tearing	10 to 30 lines, plus a frame loop	a latching base register, a fence, per-layer flip, versioned buffers (3.17)	S1 S2 per layer; S3 queue; S4 flush
Synchronising with the display	polling or a vblank interrupt handler	raster interrupt and a fence (3.17); decided: vblank interrupt at a fixed line (3.8.9)	all
Cache coherence between CPU writes and the device	3 lines per update, forgotten once per project	decided: uncached memory type, no flush exists (2.5.2, 3.13.1); open: write-combining for speed	all
Device initialisation and context creation	50 to 200 lines (Vulkan), 25 (virtio-gpu)	the device works at power-up; a single `enable` bit, a default	S1 S2 S3; S4 via a library
Buffer and memory management (allocate, map, upload, barriers, fences)	20 to 100 lines	all video memory is a plain array in a window (S1 S2); no upload, nothing to map; or the device allocates (S3)	S1 S2 plain; S3 managed
Shader compilation and pipeline state	50 to 300 lines	no shaders at all in S1 S2; a few fixed programs in S3, chosen by a field	S1 S2 none; S3 fixed
Drawing text (glyph atlases, kerning, layout)	100 to 300 lines	a one-store put-character; glyph slots filled by a library call (3.9)	all native; S4 in a library
Clipping and windows	10 to 30 lines per drawing call	a clip rectangle register per layer; a window is a layer	S2 S3
Sprites and cursors	20 lines to save, draw and restore	hardware sprites and a hardware cursor, two registers each	S1 S2 S3; S4 has the cursor queue only
Colour spaces and gamma	a table and a conversion, or wrong colours	one defined space (linear or sRGB, to be decided) with the device applying the transfer curve	open: S1 S2 S3
Resolution changes and hot-plug	20 to 60 lines of event handling	the bus reports a plug as an event (decided in chapter 2, 2.4); the device re-reads the monitor and signals “mode changed”	all
Fonts and scaling (HiDPI: screens with several pixels to a logical dot)	a scale factor threaded through every program	cells and glyph sizes defined in physical units by the device; the TrueType engine renders for the real pixel size	S1 S2 S3
Input of palettes	256 writes through ports (VGA)	a palette is an array in memory, loaded by `copy`; or none (true colour)	optional
Sound and video sync	a timestamp and a resampler	one clock for both devices (the audio clock relation of 3.12.4, decided as a duty of the mode setting) and a frame counter that audio can read	all


Every item costs gates or flexibility, and the sugar column is a list of things to decide, not a recommendation. The repository has already decided the coherence rule *(D)*, the vertical-blank latch *(D)*, the uncached framebuffer *(D)* and little-endian *(D)*; every other cell in the sugar column is a candidate.

3.17 Scanout, tearing and double buffering

The chain: the C64’s raster register and interrupt (3.4) let a program time its changes to the beam; the VGA’s retrace (3.5) asked the same of PC programmers; double buffering and compositors moved the timing into the operating system; the pdp64 puts a latch in the device (3.8.9). The PDP-11’s teletype had nothing to tear.

Scanout. A display does not hold a picture; it is **refreshed**. The adapter reads the framebuffer from the first row to the last, in order, at a fixed rate, and sends each pixel to the monitor as it is read: this is **scanout**. The rate is the **refresh rate**, 60 times a second on most monitors (the C64's was 50 or 60, by television standard). Between frames, and between rows, there are **blanking intervals** when the monitor is sent no pixels (the beam of a tube had to fly back); the gap between the last row of a frame and the first of the next is the **vertical blank**, which VGA called the vertical **retrace**. The C64's raster register and interrupt (3.4) are the program's view of it: the number of the row being read now, and a way to be told when the beam reaches a chosen row.

Tearing. If the program changes the picture while the scanout is reading it, the part of the screen above the row being read shows the old picture and the part below shows the new one. The seam is a **tear**: a horizontal line where a moved object appears cut in two. **Flicker** is the related fault: a program that clears the screen and then draws lets the scanout catch it empty or half drawn. In the figure time runs to the right and the row being read rises from the first row to the last once a frame.



Time runs to the right; a frame is about 16.7 ms at 60 Hz (an example rate). The slanted line is the display reading one row after another.

Double buffering. The standard fix is two pictures. The **front buffer** is being shown; the program draws the next frame in the **back buffer**, and when it is complete the two exchange roles while the scanout is in the vertical blank and no row is being read. The exchange is a **swap** or a **page flip**. It can *change the base address* the scanout reads from (a register write; nothing is copied) or *copy* the back buffer into the front buffer (a **blit**, cheap with a blitter and slow without, and the copy itself tears if it outlasts the blank). In peek/poke pseudocode, single buffer first:

```
# 1. single buffer: tears and flickers
loop:
    clear(FRAME)                        # the scanout can see an empty screen here
    draw_scene(FRAME)                   # and half a scene here
```

```
# 2. double buffer, swap by changing the base address (a page flip), done by polling
front = BUF_A; back = BUF_B
poke(SCANOUT_BASE, front)
loop:
    draw_scene(back)                    # nobody is reading `back`
    while peek(RASTER_LINE) != 0:       # wait for the start of the blank: busy-waiting
        wait                            # (or wait for a vertical-blank interrupt)
```

```
    poke(SCANOUT_BASE, back)             # the flip: takes effect now
    swap(front, back)                    # draw next into the picture just retired
```

Double buffering has four costs. It **needs twice the memory**: at 1920 by 1080 and 4 bytes a pixel, 8.3 MB twice (3.13.2). It **needs a deadline**: if the next frame takes longer than a frame time the flip misses the blank, and the program either waits for the next one (the rate falls from 60 to 30 and then to 20, the "half frame rate" cost of `kernel-pain-points.md` 0.6 #3) or flips at once and tears. **Triple buffering** (three pictures, so the program can start the next frame while the finished one waits for the blank) removes the wait and adds a frame of memory and of **latency** (the delay between the program's input and what the screen shows). Polling the blank occupies the processor, and the interrupt version needs a driver. Finally, a base-address register must change *in the blank*, which a program that is itself interrupted cannot always manage: the Linux driver for one common graphics chip disables interrupts and busy-waits for the row to pass before it updates registers ("vblank evasion", `kernel-pain-points.md` 0.6 #13, from `intel_pipe_update_start`).

Is this still a problem with HDMI? The author asked (2026-11-10): "with modern hdmi is tearing even a concern?" Tearing is not a property of HDMI. HDMI (like DVI and DisplayPort, 3.12) carries a pixel stream at a steady rate and cannot know whether the picture was complete when it was read. A tear happens one step earlier, in the display controller that reads the framebuffer while a program changes it. On a phone or desktop the **compositor** (the system program that gathers the pictures of all windows and builds the one that is shown) and the driver hide it: they draw the next frame in a spare buffer and flip it at the vertical blank. That machinery is the boilerplate of 3.16, which the author wants the architecture to sugar away. A program on the pdp64 that writes straight into the framebuffer with no operating system between (a boot program, a game written to the metal, a C64-style program) can still tear, so the tear-free flip must come from the architecture or the device, not the cable.

Variable refresh (HDMI VRR, adaptive sync) turns a late frame into a short delay, which reduces the need for a blank-time flip but does not remove it: the frame still must not change *while* it is read. A television may hold a whole frame before showing it (latency), and a laptop panel may refresh itself from its own memory when nothing changes (panel self-refresh). Checked on this machine: HDMI is a pixel-stream transmitter (3.12.1), and the DRM header `drm_mode.h` has a page-flip call with a completion event (`DRM_MODE_PAGE_FLIP_EVENT`) and an asynchronous flag that allows a flip with tearing (`DRM_MODE_PAGE_FLIP_ASYNC`). *Unverified* general knowledge: the VRR and adaptive-sync standards and what a sink does with a late frame, television latency, panel self-refresh, and what phone and desktop compositors do. Whether a tear-free flip is worth hardware when the display is variable-refresh is a question for the author (3.23).

What the repository already decides. The video device (3.8) shadows every register that takes effect at a frame boundary: one write to `ARM` latches them all at the start of the next vertical blank, a status bit says whether the arm was taken or missed, a sticky underrun bit reports a scan-out that ran dry, and the vertical-blank interrupt occurs at a fixed line (3.8.9, errata 71, from `kernel-pain-points.md`). A base address in that register set therefore flips at the blank without the program arranging anything. The author's device chat of 2026-08 said the same ("multi-register updates are atomic at a named raster line or vblank", `docs/c64-devices-from-chat.md` section 2) and, for the eight-way machine, the assistant's proposal that the author accepted: "Flip on vsync unconditionally with an overrun interrupt instead of a barrier" (`c64stuff.txt` line 5647; the capitalisation is mine). No text decides anything beyond one shadowed register set: independent layers, damage, variable rate, fences, or a default that needs no program setup.

3.17.1 The architecture is to offer conveniences that avoid tearing, flicker and the other faults that forced programmers to double-buffer, and to do it so that the common program needs no more than a store; the form of those conveniences is open. *(P)* (The author, 2026-11-10: "we want to put in nice architectural sugar to avoid 'tearing' and all those other issues graphics programmers had to use double buffering to fix", errata 105.)

3.17.2 The mechanism that is decided is the shadowed registers and the one `ARM` write of 3.8.9; everything else in this section is a candidate. *(D)*

The candidates, each with what it costs, and none decided:

- **A scanout base register that latches at the vertical blank** (a page flip: the register holds the address of the picture to show and takes the new value only in the blank), with a completion **interrupt** or a **fence** (a counter that the device advances when the flip has happened, which the program can read or wait on, so it knows that the old picture is free). *Gives:* no tearing, no polling of the raster; the program writes one register and goes on. *Costs:* two pictures of memory

for the program that uses it, and a rule for what the register shows if it is written twice in one frame (the first is dropped, or the second waits). *Already in 3.8.9, except the fence.*

- **Per-layer latching**, in a design with layers (3.21, sketches 1 and 2): each layer has its own base register and flips independently, so a cursor or a sprite layer can move every frame while the text layer flips only when its text changes. *Gives:* the cheapest case for text, a moving cursor with no redraw. *Costs:* one set of registers per layer.
- **An atomic commit of several registers**: several registers are staged and applied together at the blank (this is what `ARM` of 3.8.9 is for the single set; Linux calls the same idea "atomic modesetting" and offers `DRM_MODE_ATOMIC_TEST_ONLY` to ask "would this work?" and `DRM_MODE_ATOMIC_NONBLOCK` to ask for it without waiting, both in `drm_mode.h` on this machine). *Gives:* a change of mode, picture and cursor that cannot be seen half-done. *Costs:* the shadow copies of the registers, which a small device pays in flip-flops; an optional test-before-commit is more.
- **A raster-position register and a raster interrupt** (the C64 way): the program can know the row being read and be interrupted at a chosen row. *Gives:* mid-frame changes (the C64's trick of a different colour or sprite position per band) and a way to time drawing behind the beam. *Costs:* one register and an interrupt source; encourages programs that are tied to the display's timing.
- **Variable refresh** (the monitor waits for the frame instead of reading at a fixed rate: so a frame that is late is not a missed blank but a short wait; the standards are called adaptive sync, FreeSync, G-Sync and, for HDMI, VRR, variable refresh rate; unverified general knowledge). *Gives:* a late frame costs only its own delay, not a halving of the rate. *Costs:* the output must support it (the HDMI transmitter chip of 3.12.1 and the monitor), and the device's mode registers must say so.
- **Damage rectangles** (the program says which part of the picture changed and only that part is sent on): this is what virtio-gpu's `TRANSFER_TO_HOST_2D` and `RESOURCE_FLUSH` take as a `virtio_gpu_rect` (3.14). *Gives:* less memory traffic when little changes (a terminal). *Costs:* the program must track what it changed.
- **A hardware cursor and sprites**: objects that the scanout overlays at a position without touching the picture under them, so moving one never needs a redraw and never tears. *Gives:* the cursor, and in a game its moving objects, for the price of two registers each. *Costs:* gates in the scanout path and a limit on how many. (virtio-gpu has a cursor in its protocol: a separate cursor queue, `UPDATE_CURSOR` and `MOVE_CURSOR`, `virtio_gpu.h`.)
- **Versioned or copy-on-write buffers**: the device keeps the picture the scanout is reading and the program writes to a fresh version that replaces it atomically when the program says it is done, so the program can never see or show a half-drawn frame and never has to name two buffers. *Gives:* the sugar nearest to "nothing to do": a program draws and says `commit`. *Costs:* the memory and copying are the device's; a page-granular copy-on-write needs the memory-management machinery of chapter 6 or a device-side equivalent; a whole-frame version is twice the memory with a rule of who allocates it.
- **A fence or sequence counter**: a register that the device increments when each commit has been applied, which the program can read (poll) or wait for on an interrupt, to know when a buffer is free. *Gives:* synchronisation with no guess. *Costs:* a counter and a rule for wraparound.

And the same loop, in the style the pdp64 could offer, written with three of the candidates (a latching base register, a fence, and the interrupt) in the form that the program meets:

```
# 3. the flip at the blank, with the sugar: no polling of the raster, no waiting for the flip to be safe
poke(SCANOUT_BASE, front)
loop:
    draw_scene(back)
    poke(SCANOUT_BASE, back); poke(ARM, 1)    # staged now, latched by the device at the next blank (3.8.9)
    wait_until(peek(FLIP_COUNT) >= expected)  # a fence: the old picture is free (a candidate, not defined)
    swap(front, back)
```

Section 3.21 says which sketch gives which of these cheaply: the layered sketches give per-layer latching and a hardware cursor almost for free, the command-queue sketch gives the fence and the atomic commit, and the virtio-gpu route gives damage rectangles and fences and nothing about the raster. `FLIP_COUNT` and `ARM` above are placeholders; the repository defines `ARM` only as a name in 3.8.9.

3.18 A c64 mode: a small computer on the die that acts as the terminal

The author, 2026-11-10: “we will have a c64 mode, where a c128 is built onto the die with sid etc, so a bit of code loaded into its address space by pcie dma will let it act as a terminal the way the blit and vt55 did.” This is a **proposed idea**, not a design. This section explains it for the two readers and states the questions it leaves open.


What the Blit did. The Blit (3.3) was a terminal with a computer of its own, and the host sent it **programs** instead of escape codes to interpret. The records in `docs/kernel-pain-points.md` (section 14I, from the Blit papers) say that the terminal received downloaded code over its serial line, that `mpxterm`, the terminal’s program, “is 1627 lines of C” plus “204 lines of assembler” and multiplexed several host programs over the one line, and that the authors held that “an intelligent terminal is not an idiot savant, it is one that can be educated”. A **terminal with its own small computer** is therefore a display, keyboard and mouse driven by a processor on the terminal’s side of the cable, running a program the host loaded; the host sends it messages and the program draws. How the download worked (the protocol, the program format) is not in the records and is *unverified*. The VT52 and VT100 were the opposite: a fixed circuit obeying a fixed set of codes (3.2).

A small core with the C64’s chips is a terminal on a chip. Take a small computer, give it the C64 family’s circuits (the **VIC**, the video chip; the **SID**, the sound chip), **screen memory**, **colour RAM**, **glyph memory** (3.9) and a window towards the host, and let the host load its program. The program is the terminal’s firmware: it receives bytes or messages from the host (by a mailbox), puts characters into screen memory, plays a sound, moves a sprite. The host sees a device that takes characters, as it saw a teletype, and the cleverness sits in a program the host can replace, as in the Blit.

What “loaded by PCI Express DMA” means, mechanically. The host puts the program image (the terminal’s code and initial data) in its own memory and tells the device’s **DMA engine** (the part that copies memory without the processor’s help, chapter 2) the image’s address, its length and the address in the small core’s memory where it goes. The engine reads host memory over the PCI Express link (the bus-master read of 2.5) and writes the bytes into the core’s memory. The core has been held in **reset** (a line that keeps a processor from running until it is released) since power-on, so it never executes incomplete memory; when the copy is done the host releases the reset and the core starts at its fixed start address. With placeholder names (no register of any such device exists):

```
load_terminal(image, length):                    # on the host, as a driver would
    poke(CORE_CTRL, HOLD_RESET)                  # the core is stopped
    poke(DMA_SRC,  physical_address_of(image))   # where the image is, in host memory
    poke(DMA_DST,  CORE_LOAD_ADDRESS)            # where it must go, in the core's address space
    poke(DMA_LEN,  length)
    poke(DMA_GO,   1)
    wait_until(peek(DMA_DONE) == 1)              # or an interrupt
    poke(CORE_CTRL, RELEASE_RESET)               # the core starts executing the loaded code
    # the host now talks to it through the mailbox:
    mailbox_send(PUT_TEXT, row, col, "hello")    # a message the loaded program understands
```

c64 mode: the host loads a program into a small core on the die, and the core is the terminal



1 the host places the image in its own memory; the device copies it into the core by DMA (over PCI Express).
2 the program lands at the core's load address; 3 the core is let out of reset and runs it as the terminal.

Which core, what the mailbox is, and how the image is checked are open (3.18); sizes and order are an example.

The core's address space is the C64's (3.4) with a mailbox added. Everything the loaded program needs is in one flat space, as in the 1982 machine: its own code, screen and colour memory, glyph slots, the video and sound registers, and a window the host also sees. Video goes to the display connector and audio to its audio channel (3.12); audio over HDMI brings the audio clock relation of 3.12.4 with it, which the core's program must honour or the transmitter's own calculation must supply.

3.18.1 A **c64 mode** may be offered: a small core on the die, with the C64 family's circuits (SID and others), into whose address space a program is loaded by DMA over PCI Express so that it acts as a terminal, as the Blit's terminal program did. *(P)* (The author, 2026-11-10, errata 105.)

3.18.2 C64 mode is the enabling or disabling of the on-die c128 as a PCI Express device: when it is enabled it takes over the graphics and audio output, or sends them to a compositor; the form of the compositor path is open. *(P)* (The author, 2026-11-10: "the mode is just enabling/disabling the c128 as a pcie device so it takes over the graphics and audio output... or sends them to a compositor. not sure what that would look like. is there virtio-compositor?")

3.18.3 Everything about this idea other than the two sentences above is open and unspecified: which core; whether "c64 mode" also means running unmodified C64 software; how video memory is shared; the form of the compositor path; how the core and the host talk; how the loaded image is authenticated and contained; and how the idea relates to the native devices and to virtio. *(S)*

The questions the author's words leave open, stated and not answered:

1. **Which core?** He wrote "a c128". The C128 (general knowledge, *unverified*) combined an 8502 (a faster member of the 6502 family, like the C64's 6510), a Z80 for CP/M, the VIC-IIe video chip, the 8563 **VDC** (a separate 80-column video chip with its own memory) and a SID, with a memory-management chip for banking. The repository mentions the 8502 only: the author's earlier device chat (`docs/c64-devices-from-chat.md` section 4, nothing decided) put an **"8502 compatibility island"** in the design, a soft 8502 held in reset at power-on, readable and writable by the host, running at the C64's clock so that Commodore software could run. Is the core (a) a real 6502-family core, hard or soft; (b) an emulation of one, in software or hardware; or (c) a core of the pdp64's own instruction set with the C64's registers? Does "c128" mean the 8502 only, or the Z80, the VDC and the memory-management chip too?
2. **What does "c64 mode" mean beyond the author's clarification?** He says the mode is "just" the on-die c128 appearing as a PCI Express device that takes over graphics and audio or sends them to a compositor (3.18.2). Open: does the loaded program run **unmodified C64 software** (the Kernal, BASIC and games, which need the exact chips and timing) or only **terminal firmware** written for the small core?

3. **How is video memory shared** with the host and with virtio-gpu (3.14)? Is the core's screen memory its own, behind a window, or in host memory that the video chip reads by DMA (3.13.2)? Who owns the scanout when the standard device is virtio-gpu, which has a resource of its own?
4. **How do the core and the host talk?** A mailbox and a doorbell, a virtio device with queues (2.6), or a shared window of memory? The figure draws a mailbox only as a placeholder.
5. **How is the host's program image authenticated and contained?** A program loaded from the host runs on the die with access to the core's whole address space and, depending on the design, to the bus. The IOMMU of errata 75 and 85 (the table of which memory a device may touch) answers this for devices that master the bus; whether the core's DMA goes through it, whether the image must be signed and who holds the key are the author's to decide.
6. **How does it relate to the deferred native devices (errata 78) and to virtio across the board (errata 95)?** The author said "forget the native 8 register devices. gone. virtio across the board." (errata 95) and earlier "iommu will allow us to map in c64/c128 and i think we should, but that is extraneous" (errata 75, 2026-11-03). A core with the C64 family's chips is a native, register-level device by definition. It is either (i) the surviving form of the native devices, serving as a terminal, with VIC and SID as its private chips; (ii) a device that speaks virtio to the host on its outside and the C64's registers only inside, which honours errata 95 on the bus; or (iii) an optional extra outside the standard that errata 95 did not have in view.
7. **What does it cost in gates and die area?** A 6502-class core is a few thousand gates (general knowledge, *unverified*). My own estimate, unmeasured: the core is small beside the display memory, which makes the idea attractive. A hard block costs area for everyone; a soft core exists only in the FPGA phase.
8. **How does its sound reach HDMI audio?** Through the 48-bit-sample sound path (errata 74, 3.8.3) or the SID's own output converted to the stream of 3.12.4.

The options, none decided. (a) **A hard core on the die** (a real 6502-family core plus the chips): fastest and smallest per core, permanent die area, and it fixes the idea in silicon before the author has answered the questions above. (b) **A soft core in the FPGA phase only**: no silicon cost, and the idea can be tried on the first board (the programmable logic can hold a small core and the chips, as the MiSTer framework does, 3.12); gone from a later chip unless made hard. (c) **Software emulation of the C64 machine on a pdp64 core**: no hardware and easiest to change, but it uses a core and loses the C64's exact timing; it is the Blit's idea turned around, with the emulator as the "terminal program". (d) **None: the terminal is a virtio device served by a host process**, the standard route of errata 95, with firmware that is a program on the host as a terminal emulator is (3.7); nothing on the die, and the terminal is no longer a computer of its own, which the author values in the Blit. Options (c) and (d) differ in where the C64 machine runs, not in whether it exists.


The compositor question

The author, 2026-11-10: "the mode is just enabling/disabling the c128 as a pcie device so it takes over the graphics and audio output... or sends them to a compositor. not sure what that would look like. is there virtio-compositor?"

What a compositor is. A **compositor** is the program (or hardware) that combines the pictures of several windows or sources into the one picture sent to the display, which is then scanned out as in 3.17. In a desktop window system each program draws into its own picture (its **surface**) and the compositor places the surfaces, one over another, into the frame the scanout reads. The PC's windowing systems did this in software (3.5); in the layered sketches of 3.21 the scanout hardware does it, as the C64's chip did with sprites. The PDP-11 has no antecedent; its terminal was a single stream.

Why "takes over" is the simple case. If the c128 owns the output outright when enabled, there is nothing to compose: the machine has one scanout and one audio path, and the only question is who drives them. The multiplexer is a single enable bit (path (a) below). The compositor case differs in one way: the core is one client among others, so its picture and sound must be handed over in a form that the host's compositor, or the display controller's layers, can place.

five ways the c64-mode core and the host could share the display and the audio



Green: the on-die core. Blue: output. Grey: the arbiter. Dashed: a thing that would have to be invented.
In (a) the multiplexer is one enable bit; in (b) to (e) the core becomes a client of something else.

The hand-over of any of these should happen in a vertical blank, with the audio muted by a short ramp (3.18).

What exists, checked. No virtio device is called a compositor: no entry of `virtio_ids.h` on this machine names one. The display-related types are GPU (16), input (18), sound (25), video encoder and decoder (30, 31), DMA buffer (37) and audio policy (39). The nearest parts in `virtio_gpu.h` are up to 16 scanouts (`VIRTIO_GPU_MAX_SCANOUTS`); `SET_SCANOUT_BLOB`, which sets a scanout from a blob resource (a memory object shared with the host without copying); a **cursor queue** separate from the control queue (`UPDATE_CURSOR`, `MOVE_CURSOR`); and capability sets (`VIRTIO_GPU_CAPSET_VIRGL`, `VIRGL2`, `GFXSTREAM_VULKAN`, `VENUS`, `CROSS_DOMAIN`, `DRM`) selected with `context_init`, so that several rendering contexts, each with its own ordering (the "timelines" of the header comment), share the device. QEMU's `docs/system/devices/virtio/virtio-gpu.rst` describes `virtio-gpu-rutabaga`, which provides "gfxstream rendering and Wayland display passthrough", with a `cross-domain` capset for Linux guests and experimental `x-gfxstream-composer` for Android guests; it says no more about what the cross-domain path carries. That the crosvm project uses the same mechanism to show a guest's windows as windows of the host's Wayland compositor (Wayland is the Linux display protocol in which clients hand surfaces to a compositor) is general knowledge and *unverified*. **virtio-snd** and **virtio-input** exist for audio and for keyboard and mouse. Paths (b) and (c) can therefore be built from parts that exist, and path (e) is a new device type; how a type gets its number is *unverified* here.

The options, none decided.

- **(a) Exclusive takeover.** When the c128 is enabled it owns scanout 0 and the audio path; the host's picture and sound stop. *Gives:* the simplest hardware (an enable bit and a mute); the C64's one-screen model. *Costs:* the host cannot show anything while the core runs; a text terminal that wants to coexist with a window system cannot. Right for a console in the Blit's sense, wrong for a window.
- **(b) The core is one more virtio-gpu scanout and one virtio-snd stream.** It is a second head of the display device (or a window on the host's, if the host maps heads to windows) and one more stream of the sound device. *Gives:* nothing new to invent; the host's existing drivers and compositor handle it; it is the shape of errata 95. *Costs:* the core must speak the virtio-gpu and virtio-snd protocols, so a small core would need those in firmware or hardware, which is the larger part of a driver.
- **(c) A surface for the host's compositor (the author's stated preference, below).** The core renders into a resource (or a blob) that the host's compositor treats as a window's surface, as any client's. *Gives:* the core appears as a window, with the host's window management, overlap and flipping; the path that Wayland passthrough takes (general knowledge, unverified). *Costs:* the compositor must know that the surface is the core's; a copy or a shared blob; the core's frame timing becomes the compositor's.

- **(d) Layers at scanout** (sketch 1 of 3.21). The display controller has a layer for the core and a layer for the host's picture and composes them as it reads them out. *Gives:* the cheapest path and no copy; the core's picture is a plane in video memory; a vertical-blank latch per layer (3.17) switches it without a tear. *Costs:* the display controller must be the layered one of sketch 1, which is not the first-iteration device.
- **(e) A new virtio device type for compositing.** It does not exist. What it would need to be useful: a way for a client to give the device a surface (a resource or blob), to say where it goes and how it overlaps, to swap it atomically at a blank, to ask for the frame's timing and to hand over the matching audio. Most of those are what virtio-gpu's resources, scanouts and fences already say; *a new device type would repeat them*, and it is the author's call whether a compositor is a device or a protocol of existing ones. *Gives:* one model for every client of the display, the core included. *Costs:* a specification to write and have accepted (unverified: the virtio process), and a driver for every host.

3.18.4 Of the five compositor paths the author prefers (c), that the c128 renders into a buffer that the host's compositor treats as a surface: "c128 drawing into a buffer makes most sense" (2026-11-10, errata 106). This is a stated preference, not a decision. *(P)*

It makes the core a client like any other, the way rio treats every window (3.19: a window is a buffer and a rectangle), and its parts exist (a virtio-gpu resource or blob as the surface, 3.14). Still open under it: how the compositor learns that the buffer is the core's, who owns the copy or shared memory, and how the core's frame timing meets the compositor's. The audio form of the same choice is in 3.20.

How the switch avoids tearing and pops. Enabling or disabling the mode changes who feeds the scanout and the audio path. A change in mid-frame tears the picture (3.17), and a sudden change of the waveform's value is heard as a pop. The remedy has the shape of 3.17: hand over at a **vertical blank**, as the latch of 3.8.9 does for registers (the enable bit is one more shadowed register that `ARM` latches), and **mute with a short ramp** (a fade of a few milliseconds down before and up after, not a cut). In path (a) the enable bit is the shadowed register and the mute belongs to the audio path; in (b) to (e) the compositor does the hand-over and the core only stops or starts its stream. The audio clock relation of 3.12.4 must stay unchanged across the switch, or the transmitter loses its lock and the sound drops.

Commentary. **Chain.** The PDP-11 had only the fixed terminals of 3.2. The Blit loaded its terminal program from the host. The C128 put several complete computers in one box (general knowledge, *unverified*), and the MiSTer framework runs C64 and C128 cores in programmable logic. The pdp64 proposal puts a small core on the die and loads it by DMA. **Trade-offs.** A computer of its own makes the terminal programmable and independent of the host's drawing, and makes it a second machine to load, secure and keep consistent with the first. **Impact.** *Kernel:* a driver for the loader and the mailbox. *Compiler:* none. *Hardware:* a core, memory, DMA and the C64 family's circuits, or nothing in option (d).

3.19 Windows: from the Blit to rio and NeWS

The author, 2026-11-10: "it should mention blit terminal was inspiration for the rio and NeWS windowing systems, and we'd like to bring over what we can of that simplicity also."

What the sources confirm and what they do not. The Blit's `mux` was a window system in the terminal; its successor on Plan 9 was **8½**, whose paper says "Primarily for reasons of history and familiarity, the general model and appearance of 8½ are similar to those of mux"; and **rio** replaced 8½ ("Note that 8½ has been replaced by rio (see rio(1))"; rio(1): "Rio manages asynchronous layers of text, or windows, on a raster display"; *layers* is the Blit's word). All of this is recorded in `docs/kernel-pain-points.md` section 14I. That the Blit inspired **NeWS** is the author's statement; no source read for the repository makes the claim, and the glossary says so. From *The UNIX-HATERS Handbook* (section 14G of the same file) the repository records that NeWS was an extensible window server in which "the client can download programs and data structures to draw the whole schematic", and that "Ultimately, NeWS was not economically or politically viable" (the reasons given are about licensing). That NeWS was Sun's, written in PostScript (a page-description language that is also a programming language) and designed by James Gosling is general knowledge, *unverified*.

What rio is. rio is the window system of Plan 9 (the research operating system that followed Unix at Bell Labs; Rob Pike wrote 8½ and rio descends from it). Its central idea, in the 8½ paper, is that the window system is a **file server**: "The most important contributor to its small size, though, is its overall design as a file server." A program uses a window by opening files (`/dev/cons` for text, `/dev/mouse`, `/dev/bitblt` or later `/dev/draw` for graphics); each window is a private screen, and the server keeps its bitmap and does the drawing ("no bitmap graphics operations are executed in the client at all"). It is one small

server with no **toolkit** (a library of buttons, menus and other widgets that every program of a window system links in; that X has several and rio's base system none is general knowledge, *unverified*).

What NeWS was. In a conventional window system a program on the host sends the display server drawing commands one at a time over a slow link, and each round trip costs time (the latency complaint of 3.2). NeWS made the server programmable: the host *downloaded a program* into the display server, which ran it locally for every mouse movement, so dragging a shape never crossed the link. This is the Blit's idea one step on: the Blit downloaded a program into a *terminal*, NeWS into a *window server*. The repository's note in section 14G of `kernel-pain-points.md` says the NeWS argument "is the same shape as the Blit lineage" and records that the text read does not mention the Blit.

The chain for windows: the PDP-11's teletype had none; the Blit's `mux` (terminal-side windows over a serial line), 8½ and rio (windows as files, on a local bus), NeWS (windows as downloaded code); the pdp64 asks which of these simplicities survive.

3.19.1 The pdp64 is to bring over what it can of the simplicity of the Blit's descendants rio and NeWS (the author: "we'd like to bring over what we can of that simplicity also"); a goal, and the means are open. *(P)*

3.19.2 Which of the options below the pdp64 takes, if any, is open. *(S)*

What simplicity could be carried over, as options with their trade-offs, none decided.

- **A window is a plain buffer and a rectangle.** The program owns a pixel buffer (or a cell array, 3.9) and the system knows only where to place it. *Gives:* the model of 3.16's goal; drawing is writes to memory with nothing to ask for. *Costs:* a buffer per window (memory), and a rule for who may write whose (the memory protection of chapter 6). *Ties to:* path (c) of the compositor question (3.18), where the c128 draws into a buffer that the compositor places.
- **Drawing is writes to that buffer.** No drawing protocol in the base system: the program uses `memcpy`, a library, or the blitter (3.21 sketch 2). *Gives:* no round trips, no server-side drawing language. *Costs:* every program draws for itself (the opposite of rio's "the server carries out the drawing"); a library must exist for text and shapes.
- **The server composes the buffers.** A small program (or the display hardware, sketch 1) places the buffers into the one picture. *Gives:* one place that handles overlap, flip and tear (3.17). *Costs:* a copy or a layer per window; the server must be trusted with every buffer.
- **Downloadable server-side code.** A program is loaded into the display server, as the Blit's terminal program and NeWS's PostScript were: here, into the c128 core of 3.18, which would be the display server. *Gives:* the display can be given new abilities without changing the host; interaction stays local. *Costs:* a second program to secure (3.18 question 5), and the two-halves problem of the Blit ("writing one program in two pieces is much harder than writing two programs", `kernel-pain-points.md` row 12).
- **No toolkit in the base system.** The system provides windows, text and pixels; widgets, if any, are a library the program chooses. *Gives:* the size rio had; nothing to keep consistent. *Costs:* every program draws its own look, and users see the inconsistency.
- **Windows as files, or as virtio queues.** rio exposes a window as files; the pdp64's devices are virtio queues (chapter 2). A window could be a queue of drawing messages (one more virtio shape), or a file the kernel maps, or both. *Gives:* the uniformity rio and 8½ had (`kernel-pain-points.md` records "the same device interface at every level"). *Costs:* a naming and permission model for files (a chapter 6 matter) or a queue per window.

3.20 The audio path: samples, mixers and the pdp64

The author asked, 2026-11-10: "what is the audio equivalent, what do those mixers do to combine multiple programs audio?" Audio has the same structure as video, with a **mixer** where video has a compositor, and this section follows the order of 3.17 and 3.18. The chain: the PDP-11 had no sound hardware in this repository's records, so there is no antecedent there; the C64's SID synthesised sound from registers (3.4); PC sound cards stored samples and read them out; a sound server mixes several programs; the pdp64 has to decide where that mixing lives.

What a sound card does. A sound is a pressure wave, stored as a list of **samples** (numbers, each the height of the wave at one instant) taken at a fixed rate, commonly 44,100 or 48,000 a second (both appear in the virtio-snd rate list below), each sample a 16-bit integer, 24 bits or a floating-point number. A **DAC** (digital-to-analogue converter: the chip that turns a number into a voltage) takes one sample on each tick of a clock, and the speaker moves. The device is fed from a **ring buffer** (a block of memory treated as a circle, which the program fills and the device empties, the device reading the next sample at each tick and the program writing ahead of it). This is the scanout of 3.17 again: the display reads the framebuffer at a fixed rate and the DAC reads the ring buffer at a fixed rate. A **buffer underrun** (the device reaches samples the program

has not yet written) is **audio's tearing**, heard as a click or a gap, and as certain when the program is late as a tear is when it draws late.

```
# fill the ring buffer: the program writes ahead of the read pointer, and notices an underrun
fill_ring(ring, next_frame):                # called by an interrupt each period, or in a loop
    while free_space(ring) >= PERIOD:
        samples = generate_or_read(PERIOD)   # this period's samples
        write_to_ring(ring, samples)
    if device_read_pointer_passed_write_pointer(ring):    # underrun
        count_underrun(); write_silence_up_to(...)        # a click is unavoidable; at least not noise
```

The SID's way. The C64 stored no samples (3.4). The SID has three **voices**, each an oscillator with a waveform, an envelope and a filter, in hardware: a program says "this frequency, this waveform, this attack and release" and the chip *synthesises* the sound. The sound is never in memory as numbers, so nothing underruns and nothing is mixed in software; the chip mixes its three voices inside itself. This is the difference between the C64's text mode (the chip draws from a description) and a framebuffer (the program draws every dot).

What a mixer does. When several programs play sound the card has one ring buffer and one DAC, so something must combine the sounds into one stream: the **mixer**, the audio compositor. Its job, per **period** (a short block of samples, a few milliseconds):

```
mix_period(streams, out):                   # one block of the output; runs once per period
    for each frame i in 0 .. PERIOD-1:
        sum = 0
        for s in streams:
            x = s.next_sample()             # after converting s to the output's rate and format
            sum += x * s.volume             # per-stream volume
        out[i] = clip(sum)                  # or a limiter: a gentle gain reduction instead of a hard cut
    write_to_ring(out)
```

A mixer also has four other jobs. It **converts each stream to a common rate and format**, because one program plays 44.1 kHz music, another 48 kHz speech and a third floating-point effects; this **sample-rate conversion** (resampling: computing the samples of a wave at the new rate) is a filtering job, so a mixer is more than an adder. It **applies per-stream volume** and **clips or limits** the sum, because two loud samples added exceed what the output can hold (**clipping**: a hard cut of the top of the wave, heard as distortion; a **limiter** lowers the gain smoothly instead). It balances **latency against underrun**: a small buffer follows the program quickly and leaves little margin for the program being late; a large one is safe and late. And it handles **clock drift**: the program's timer and the DAC's clock are different crystals, so over minutes one runs ahead of the other. The remedy is to drive the mixer from the *device's* clock (write when the ring buffer has room) and to resample by a fraction of a percent to absorb the difference.

Who the mixer is in real systems (general knowledge, *unverified* except where noted): on Linux a **sound server** (PulseAudio and, more recently, PipeWire) or ALSA's software mixing plug-in (`dmix`); on macOS CoreAudio; on Windows WASAPI's shared mode. This machine has the `pulseaudio` program and the ALSA library `libasound`; it has PipeWire's client library but no PipeWire program. QEMU has a mixing engine (`audio/mixeng.c`, `audio-mixeng-be.c`) and backends for ALSA, PulseAudio, PipeWire, CoreAudio, DirectSound, JACK, SDL and others (`qemu-src/audio`): a virtual machine's sound is mixed by the **host**, like any other program's.

What virtio-snd defines (checked in `/usr/include/linux/virtio_snd.h`). Four queues: control, event, transmit (`TX`) and receive (`RX`). Streams are **PCM streams** (pulse-code modulation: plain samples) with a direction (output or input), described by `virtio_snd_pcm_info`: a bitmap of formats (from 4-bit ADPCM and 8-bit mu-law through `S16`, `S24`, `S32`, `FLOAT` and `FLOAT64` to DSD and IEC958), a bitmap of rates (5,512 Hz to 384,000 Hz, including 44,100 and 48,000), and a range of channels. The driver sets a stream's parameters (`PCM_SET_PARAMS`: `buffer_bytes`, `period_bytes`, channels, format, rate), prepares, starts and stops it, then sends audio as buffers on the TX queue, each tagged with a `stream_id` and answered with a `virtio_snd_pcm_status` that carries a `status` and the **current device latency** in bytes. The event queue reports `PCM_PERIOD_ELAPSED` and `PCM_XRUN` (an underrun or overrun: the same word as the ring buffer's), and jack events; each stream has feature bits for shared memory, polling, and period and xrun events (`VIRTIO_SND_PCM_F_*`). Controls such as volume are optional (`VIRTIO_SND_F_CTLS`). The header says nothing about **who mixes**: it defines one stream at a time, as one card. Mixing several programs happens on the host side of the

device (QEMU's engine above) or, on a machine with no host, in the pdp64's own kernel or library before the stream is sent. The pdp64 is that machine, so who mixes is open.


3.20.1 The standard audio device is virtio-snd (errata 79); the device carries one stream at a time as a PCM stream of the formats and rates the device lists. *(D)*

3.20.2 The pdp64's mixer (the program or device that combines the audio of several programs into one stream, converts rates and formats and applies volume), where it lives (the kernel, a library or the device) and who drives it, are unspecified. *(S)*

The audio of the c128 core, the options parallel to the pixel options of 3.18, none decided. The author's preference for the pixel path (the c128 draws into a buffer, 3.18.4) has an audio form, but he has stated no preference for audio.

- **Exclusive takeover of the audio path** (parallel to 3.18 (a)): when the core is enabled it owns the audio output and the host's sound stops. *Gives:* nothing to mix; the SID's output goes to the converter or the HDMI audio channel. *Costs:* no music while the terminal bells.
- **The SID's output as a virtio-snd stream** that the host mixes with the others (parallel to 3.18 (c)): the core renders its voices to samples (or the SID model does), and the samples go into a stream as any program's would. *Gives:* the core is a client of the mixer; the host's volume, rate conversion and routing apply. *Costs:* the SID must produce samples at a rate (a design choice: the 48-bit sample path of errata 74 is exactly that), and its latency is the stream's.
- **A mix inside the device with a fixed gain:** the core's voices and the host's stream are summed by a small mixer in the device, at a fixed or registered gain. *Gives:* nothing for the host to know; cheap (an adder and a clamp). *Costs:* a fixed policy; the device has its own clock and a rate converter, or both streams must already be at one rate.
- **Hand-over with a fade:** whichever is chosen, switching the core on or off ramps the volume over a few milliseconds and changes at a period boundary (3.18) so that no pop is heard.

pixels and sound: several sources, one combiner, one buffer read at a fixed rate



A late frame tears; a late buffer underruns: a click. Both are cured by writing ahead of the reader and by letting the device clock, not the program clock, decide when the combiner runs.

The SID is the C64's exception: it makes the sound itself from three voices, so it has no buffer and no mixer in memory.

Stages after the model of general knowledge of sound servers (unverified, 3.22); virtio-snd streams as in virtio_snd.h.

3.21 A design still being worked out: what a mashup of GPU, video memory, C64 and Blit could look like


The author, 2026-11-10: "conclude the graphics chapter: we're still figuring it out, what would a mashup of gpu, vram, c64 and blit look like." **Nothing in this section is decided.** Every statement is tagged *(P)* or *(S)*; the sketches are shapes of ideas put side by side so that the questions at the end can be answered, and the repository recommends none. The chain behind them: the PDP-11 terminal was a character stream (3.1), the Blit and the C64 put memory-mapped bitmaps, text, sprites and sound behind a processor or a few chips (3.3, 3.4), the PC split them (3.5), and the GPU turned drawing into queued commands and shaders (3.6); the sketches mix those inheritances.

Two terms first. VRAM (video memory) is memory that belongs to the display device: it sits on the device, behind a window on the bus, and the scanout reads it without crossing the bus; the processor reaches it through the window (slowly: every access is a bus transaction). The alternative is **system memory** that the device reads by DMA as a bus master, as the video device of 3.13.2 does; the framebuffer is then ordinary memory and the scanout competes with the processor for it. A GPU card has VRAM; the first board of the pdp64 has none to speak of (the block RAM is 5.5 megabits and a frame

is 8.3 MB, 3.13.2), so on it every layer lives in system memory, and "VRAM" in the sketches below means "memory the device owns the use of", whichever kind it is. **Compositing** is combining several pictures into the one that is shown; the C64's sprites over text over a background were compositing in hardware, as the scanout read them out.

The properties the author has asked for, which each sketch is measured against: **(T)** simple peek/poke text and graphics at once; **(C)** modern colour depth and screen size; **(G)** glyph slots filled by a TrueType engine; **(S)** sprites, colour and sound in the C64's spirit; **(B)** the Blit's bit-blit and windows; **(U)** the GPU's command queue, parallel lanes and shaders. And the other two wishes of the day: anti-tearing sugar (3.17) and the boilerplate goal (3.16).

sketches 1 and 2: layers in video memory, composed by the display hardware as it reads them out



Sketch 1: the CPU writes the arrays; the display hardware does the composing; there is no command queue.
Sketch 2: the same, plus a few registers that move rectangles inside video memory (scrolling, window moves, glyph copies).
Nothing here is decided (3.21); the boxes are the shape of the idea.

Sketch 1: layered scanout, no command queue

3.21.1 Three **layers** (a text-cell layer, a pixel layer and a sprite layer) are plain arrays in video memory that the processor pokes; the display hardware composes them as it reads them out, one pixel at a time, and there is no command queue. *(P) What the programmer sees.* Three arrays, each at a fixed place, each with a small set of registers (base, size, stride, enable). The text array is the cell array of 3.9, with its glyph slots in another array; the pixel array is a framebuffer; the sprite layer is a table of entries (x, y, shape, colour, enable). A program pokes whichever it wants, in any order. *What is in video memory:* the cells, the glyph slots, the pixels, the sprite table and the sprite shapes. *At scanout:* for each pixel the hardware asks the layers from the top down (sprites, then text, then pixels), looks the cell up to its glyph, takes the glyph's coverage and the colours, and gives the first layer that is not transparent; the sprite layer needs to know only a few entries per row. The composing is done in a **line buffer** (a small memory that holds one row), as 3.13.2 already provides for. *Costs:* a compositor of the order of the 1,500 lookup tables the repository estimates for BLT64, plus a line buffer per layer (an estimate of mine, unmeasured); scanout traffic is the pixel layer's 498 MB/s at 1920 by 1080, 4 bytes, 60 Hz (746 MB/s at 6 bytes), plus about 13 MB/s for the cells and the glyph reads (arithmetic from the examples of 3.9). *Gives up:* anything beyond what the layers can say: no scaling or rotation, no effect that is not in the compositor; every change a program wants to make to the pixel layer is the processor writing pixels. *Properties kept:* T yes (this is the C64 and the Blit's memory-mapped screen); C yes; G yes (the text layer's glyphs); S yes (sprites, and colour per cell; sound is a separate device, 3.8.3); B no (no blitter, windows are the program's job); U no. *Text and graphics split:* healed, the C64's way: a program has text and pixels at once in one frame, with no mode switch. *A game:* sprites and a scrolling text or pixel layer, moved with a few pokes a frame; the C64 game, with a modern screen. *A terminal emulator:* pokes cells (a scroll is a few stores, or, with a base register for the layer, one store); the glyph slots are filled by the TrueType engine. *Sugar:* per-layer flip and a hardware cursor for free (3.17); the fence is the vertical-blank counter. *With virtio across the board:* needs a virtio device type of its own (reading 1 of 3.9); the layers are a device's contents, not the virtio-gpu protocol.

Sketch 2: the same, plus a small blitter and a glyph atlas

3.21.2 Sketch 1 plus a **blitter**, a few registers that copy and combine rectangles inside video memory (the Blit's RasterOp, the Amiga's blitter, BLT64 of 3.8.4), and a glyph atlas that the TrueType engine fills and the text layer indexes. *(P)*


What the programmer sees. Sketch 1, and a handful of blitter registers: source, destination, strides, width, height, raster operation, go. The atlas is the glyph map seen as one picture (3.7): a glyph is drawn from it by the blitter into the pixel layer when a program wants a glyph on the pixel layer at an arbitrary position, and the text layer's cells point at it directly. *In video memory:* sketch 1's contents and the atlas. *At scanout:* as sketch 1. The blitter runs beside it, in the blanking time or contending for the memory. *Costs:* the blitter and its arbitration with scanout; the repository's own estimate is about 1,500 lookup tables and a line buffer, "nearly all address arithmetic" (3.8 commentary), and a bus-master port on video memory. *Gives up:* the same as sketch 1, except that drawing, scrolling and window moves in the pixel layer no longer cost the processor the pixels. *Properties kept:* T, C, G, S as sketch 1; **B yes** (bit-blit with the raster operations of 3.8.7, and windows as layers or as rectangles in the pixel layer); U no. *Split:* healed as sketch 1, and the pixel layer gains the Blit's operations, so that text on it (a window of a program that draws its own glyphs) is cheap. *A game:* sprites for the actors and the blitter for the background tiles. *A terminal emulator:* the text layer as in sketch 1; the blitter scrolls and moves windows drawn on the pixel layer. *Sugar:* as sketch 1, plus a blit that starts at the vertical blank (the "start-at-vblank" of `architecture-recommendations.md` R-9), which stops a copy from tearing. *With virtio:* as sketch 1, the blitter a feature of the device; it would be a feature bit and a queue if its commands are descriptors rather than registers (the chat chose a three-operand `draw` command, `decisions-pending.md` E3).

```
# sketch 2: scroll the pixel layer up by one text line, then draw a glyph from the atlas (placeholders)
poke(BLT_SRC, FB + LINE_H * STRIDE);  poke(BLT_DST, FB)
poke(BLT_STRIDE, STRIDE);  poke(BLT_W, W);  poke(BLT_H, H - LINE_H)
poke(BLT_OP, STORE);  poke(BLT_GO, 1);  wait_until(peek(BLT_BUSY) == 0)
```

Sketch 3: a command-queue device with a peek/poke window

3.21.3 A device whose main interface is a **ring of commands** in the manner of virtio-gpu, with a tiny shader-like fixed program for drawing glyphs and sprites and video memory managed by the device, and a peek/poke compatibility window on top for the programs that want to poke cells and pixels. *(P)*

sketch 3: commands in a ring, a small drawing engine, and a peek/poke window on top



The program mostly writes commands (put this text, move this sprite); the window is for the cases where a poke is simpler.
The window and the engine both reach video memory, so the device must say which one wins when they touch the same cell.

Nothing here is decided (3.21).

What the programmer sees. Mostly commands: "put this text at this cell", "move this sprite", "fill this rectangle", "present"; and, as a convenience, the window: cells and pixels as plain memory that mirrors the device's. The device allocates its own video memory, so a program does not choose addresses. *In video memory:* what the device decides; the program sees handles. *At scanout:* the device renders the commands into whatever it scans out, at its own pace, and flips at the blank by itself (the sugar is free: a commit is a command). *Costs:* a command processor (a queue engine, as the virtio devices of chapter 2 already are), a drawing engine of fixed programs (the small piece of the GPU that the terminal needs: a textured quad with a glyph and two colours, a sprite), a memory manager for video memory and a consistency rule between the window and the queue;

more gates than sketches 1 and 2 by a clear margin (a judgement of mine, unmeasured), and more software in the driver. *Gives up:* the plainness of sketch 1; the program must know the device's model, and two ways to reach one cell must be reconciled. *Properties kept:* T only through the window (and only as well as the window is made); C yes; G yes (the engine reads glyph slots); S yes; B no blit, but "fill" and "copy" commands do its job; **U yes**, a command queue and parallel work, but a *fixed* program, not the general shaders of 3.6. *Split:* healed by the engine, which draws text and pixels from one queue. *A game:* a command per sprite or per tile, one "present" per frame, with little processor work. *A terminal emulator:* one command per changed run of cells; the glyph atlas as in 3.7, but made by the device. *Sugar:* the fence and atomic commit are the natural form (each command completes in order; a commit is a command); versioned buffers are the device's business. *With virtio:* the natural fit, a device with queues as in 2.6, and the closest in spirit to virtio-gpu, of which it could be a profile (reading 2 of 3.9).

Sketch 4: virtio-gpu 2D, the sugar in a library

3.21.4 The standard virtio-gpu 2D route of 3.14, with the C64 and Blit conveniences done in software by a library (cells, glyphs, sprites and cursor, blits, flips), and no special hardware. *(P)*

What the programmer sees. A library that offers the peek/poke look: a cell array in memory, `put_char`, sprites as library objects, and a `present` call that does the transfer and the flush for the damaged rectangles. *In video memory:* the host's resources; on the pdp64 the program's memory is the backing (3.14.3). *At scanout:* the host reads its resource when it likes; the library cannot flip at a blank because virtio-gpu has none (3.14); tearing is the host's concern and, on an emulator, usually invisible. *Costs:* nothing in gates; the processor draws everything and a flush copies; bus traffic is the damage rectangles. The glyph slots are a library table, filled from the TrueType engine on the processor. *Gives up:* everything hardware: the hardware cursor is the cursor queue only, there are no sprites except the cursor, no blits, no layers; the C64's "the chip draws it while you do other things" is the library's loop. *Properties kept:* T only through the library (the program pokes memory the library owns, and the library presents it); C only to 32 bits (3.14.4); G yes, in software; S no (the cursor excepted); B in software; U no. *Split:* healed in the library's picture, but each screen is still one pixel framebuffer. *A game:* draws into a back buffer and flushes it, in the PC way of 3.5 (slow, but running now). *A terminal emulator:* the library draws glyphs from a cache and flushes the damaged rows. *Sugar:* damage rectangles and the fence only (3.17, 3.14). *With virtio:* it is the standard (errata 79, 95); sketches 1 to 3 would be added to it as another device or as a profile.

Sketch 5: a c64-mode core as the terminal (a variant)

3.21.5 A small core with the C64 family's chips, into which the host loads the terminal program by DMA (3.18), as a variant or addition to any of the sketches above: it is the terminal, and the other sketches say what the display behind it does. *(P)*

What the programmer sees. The host programmer sees a device that takes messages (the mailbox); the programmer of the small core sees the C64: peek, poke, a screen at a fixed place, colour RAM, glyph slots, sprites and the SID, which is the author's "as simple and pleasurable as the c64 was" at its most literal. *In video memory:* the core's screen memory, colour RAM, glyph slots, sprite shapes. *At scanout:* the VIC (or its extension) composes text, bitmap and sprites as sketch 1 does; the flip is a register of the core's own. *Costs:* a core, its memory, a DMA loader and the chips (3.18, question 7); a second program to write, load and keep secure. *Gives up:* a single, standard programming model on the host's side; the host cannot poke a cell, only send a message. *Properties kept:* T yes, for the core's programmer; C if the chips are widened as the native devices were (3.8); G yes; S yes, with sound; B only if the chip family has a blitter; U no. *Split:* healed, in the core. *A game:* a C64 game, or one written for the core. *A terminal emulator:* the core *is* the terminal; the host sends text. *Sugar:* the VIC's latches and raster interrupt, which the core's program uses; nothing is hidden from it. *With virtio:* the open tension of 3.18, question 6.

The four main sketches side by side (sketch 5 is a variant of any of them)

	S1 layers	S2 layers + blitter	S3 command queue + window	S4 virtio-gpu + library
What the program does	pokes arrays	pokes arrays, starts blits	writes commands (or pokes the window)	calls a library, which sends the commands of 3.14
Who composes	display hardware, at scanout	display hardware, at scanout	the device's engine	the host, or the program

	S1 layers	S2 layers + blitter	S3 command queue + window	S4 virtio-gpu + library
Where glyphs live	slot array in video memory	atlas in video memory	the device's cache of slots	the library's table, in the program's memory
Sprites	hardware layer	hardware layer	engine primitive	no (cursor only)
Blitter	no	yes	fill/copy commands	in software
Commands or pokes	pokes	pokes and a few registers	commands, pokes as a window	commands under a library
Anti-tearing sugar	per-layer latch, cursor, raster	the same plus blit at blank	commit, fence, atomic	damage and fence only
Cost in gates (my estimate, unmeasured)	small: a compositor and line buffers	small to medium: add a blitter	larger: a queue engine, a drawing engine, a memory manager	none
Bus traffic	scanout, plus the pokes	the same, less processor traffic for blits	scanout, plus commands (small)	scanout is the host's; the program writes every pixel
Fits virtio everywhere (errata 95)	needs its own device type	needs its own device type	a profile of virtio-gpu, or its own	is virtio-gpu
Properties T C G S B U	T C G S, no B U	T C G S B, no U	C G S U; T by the window; B by commands	T by library; C only 32-bit; G in software

3.21.6 The five sketches (the four layers-and-queues shapes, and the c64-mode core as a variant) are the author's open design question, and none is decided; a combination (for example, sketch 4 now and sketch 2 or 3 as a second device later) is as open as a choice among them. *(S)*

A leaning, mine and not the repository's. Sketch 4 is what the first iteration already is; the author's question is what the second should be. Sketch 2 matches his words most closely (the Blit's bit-blit and the C64's text, graphics and sprites at once) and is the smallest hardware that makes peek and poke the main interface. Sketch 1 is sketch 2 without the blitter, which can be added later because it only reads and writes video memory. Sketch 3 fits better if he wants one family with virtio-gpu and a command queue as the main interface. The leaning assumes poke is the main interface; if he wants commands, sketch 3 is nearer.

The questions the author must answer to choose (each is repeated in 3.23): (1) **Who composes the layers**: the display hardware at scanout (1, 2), the device's engine (3), or software (4)? (2) **Where glyphs live**: a slot array the text layer indexes (1, 2), the device's own cache (3), or a library table (4); and does a cell hold a code or a slot number (3.16, pair 3)? (3) **Do sprites exist**, as a hardware layer, as an engine primitive, or only as the cursor? (4) **Is there a blitter**, and if so as registers or as commands? (5) **Are commands or pokes the main interface**, and what does the other do? (6) **Which virtio shape**: a device type of its own, a profile of virtio-gpu, or the standard device with a library, and so what the "virtio-console" of the author's words is (3.9)? (7) **VRAM or system memory** on the first board and later? (8) **What pixel format**: 48-bit native, with the standard device at 32 bits (3.14.4)?

3.22 What was checked, and what was not

- **Checked against the Linux headers on this machine:** `virtio_gpu.h` (command names and structures, formats and their values, the fence flag, cursor commands, `VIRTIO_GPU_MAX_SCANOUTS`, feature bits, capset ids; no vertical-blank or flip command), `virtio_console.h` and `virtio_ids.h` (the console's type 3, configuration and features; the list of device types, which has no compositor), `virtio_snd.h` (queues, formats, rates, `PCM_SET_PARAMS`, events, features), `/usr/include/drm/drm.h` and `drm_mode.h` (the page-flip, atomic and add-framebuffer ioctls and their flags, the mode structure) and `GL/glext.h` (the OpenGL entry points named).
- **Checked against QEMU sources** (`/home/david/claude/qemu-src`): `transfer_to_host_2d` and `resource_flush` and what they reject (`hw/display/virtio-gpu.c`); the `refresh_rate` field (`include/hw/virtio/virtio-gpu.h`); the rutabaga text (`docs/system/devices/virtio/virtio-gpu.rst`); the audio backends (`audio/`).
- **Checked against 2.11BSD** (`/home/david/claude/facetlang/unixtree/2.11BSD/sys/pdp/cons.h.gz` and `cons.c.gz`): the KL11/DL11 register structure, address 0177560 and `DLXCSR_TRDY`.
- **Checked against the repository's records:** the Blit's statements and numbers (the Blit and Tradeoffs papers as recorded in `docs/kernel-pain-points.md` section 14I; the Handbook quotations in section 14G); the VT52 `ESC Y` code and the "VT100/ANSI" and "xterm-256color" remarks (`c64stuff.txt`, lines 218, 4875, 4888, the assistant's words); the author's

terminal chat (`docs/c64-devices-from-chat.md` section 6); the vertical-blank rules (3.8.9, errata 71); the blitter's 1,500 lookup tables (`docs/pdp64-fpga-plan.md`).

- **Unverified** (general knowledge; no manual of these machines is on this computer): everything about the C64 chips (addresses, sizes, sprite size and count, colours, the SID's voices, the processor) and the IBM PC adapters (VGA text addresses and attributes, mode 13h and the planar modes, the 64 KB window, VBE, the palette, Mode X); the details of VT52 and VT100 sequences beyond the records; **what "vt55" refers to**; the speed of a teletype; which terminal emulators use the GPU; the Valve signed-distance-field paper; the titles, dates and page counts of Michael Abrash's books; GPU lane group sizes; variable refresh and its names; the Vulkan names; EDID as a data block; the Amiga's blitter; the C128's chips; NeWS as Sun's, in PostScript, by Gosling; the toolkit comparison; the real mixers on other systems; the Cyclone V and Zynq 7020 lacking a hard PCI Express block; the line counts of boilerplate (illustrative throughout); and all gate-count estimates of the sketches (mine).
- **Decided by the author and recorded in `errata.md`:** every statement tagged *(D)*; the author's words of 2026-11-10 are in errata 105 and 106 and tagged *(P)* or *(S)*.

3.23 Still open

1. **What "our virtio-console device" is**: a new virtio device type, virtio-gpu extended, the real virtio-console beside a display device, or the native family (3.9.2).
2. **The sketches of 3.21**: who composes the layers, where glyphs live, whether sprites exist, whether there is a blitter, whether commands or pokes are the main interface, VRAM or system memory.
3. **Whether a cell holds a character code or a slot number**, the glyph slot's layout and the number of slots (3.16 pair 3, 3.9.3).
4. **The anti-tearing sugar** (3.17): which candidates, whether a fence, per-layer latching, variable refresh or versioned buffers are specified, and whether a tear-free flip is worth hardware when the display is variable-refresh.
5. **The boilerplate sugar** (3.16): the default mode, the canonical pixel format, stride and mapping, colour space and gamma, the units of cells and fonts for HiDPI, a palette or none.
6. **The 48-bit pixel against virtio-gpu's 32-bit formats** (3.14.4), and a write-combining memory type for the framebuffer (3.13).
7. **The register-level definitions** of `VIC-64X`, `SID-64X` and `BLT64` (3.11, deferred); the feature subset of virtio-gpu and virtio-snd (3.14.2), and whether OpenBSD has a virtio-snd driver (errata 79).
8. **The block-RAM budget** and the underrun rule of the line buffer (3.13.3); the hot-plug scope (`decisions-pending.md` F23).
9. **The c64 mode** (3.18): which core, unmodified C64 software or terminal firmware only, how video memory is shared, how core and host talk, how the loaded image is authenticated and contained, how it relates to the native devices (errata 78) and to virtio across the board (errata 95), the cost, the sound path.
10. **The compositor path of the c64 mode** (3.18.4 and the five paths): the details under the author's preferred path (c), and the hand-over without tear or pop.
11. **The window model** (3.19): a plain buffer and a rectangle, drawing as writes, a composing server, downloadable server-side code, no toolkit, windows as files or as virtio queues, and whether the c128 core is the display server.
12. **The audio path** (3.20): where the mixer lives and who drives it, the form of the core's audio (takeover, a virtio-snd stream the host mixes, a fixed-gain mix in the device), the rate and format of the SID's output, the fade at hand-over.

Chapter 4 — Boot, the BIOS, the disk label and the GPT

The machine starts the way the PDP-11 did: a small ROM in the controller chip loads one block from the boot device and jumps to it, and every later stage is an ordinary program, open source, compiled by the project's own compiler. This chapter is written for a reader who has keyed a bootstrap in on a PDP-11 front panel, used a boot ROM, or typed `boot` at the : prompt of Unix Version 7 or 2.11BSD, or who is learning computing from the start, and who has not met anything invented after the 1970s: no BIOS, no UEFI, no partition table, no device tree, no start-up of a second processor, no firmware update. It follows the author's order (errata 110): the PDP-11 boot (4.1), then the systems that came between, the VAX, the Commodore 64, the PC's BIOS with the MBR, and the GPT with UEFI (4.2), each with the one thing it added; then the pdp64's boot, stage by stage (4.3 to 4.10), with the numbered decisions where the reader meets them; then the five boots and the pdp64 side by side (4.11). The wider review of how other systems boot is `../boot.md`. Tags: *(D)* decided; *(P)* proposed; *(S)* unspecified. A fact about an older or another machine that could not be checked on this computer is marked *unverified* and listed in 4.12.

How to read this chapter. A term is defined where it first appears, as the technical word followed by a plain restatement. Boxes-and-arrows pictures are the kind a textbook draws for a linked list: a box is a piece of memory, a register or a program, an arrow says what is handed on. Code blocks are pseudocode (C-like, `#` starts a comment) unless the text says they are PDP-11 assembly; the PDP-11 code is quoted from the V7M sources on this machine. Every pdp64 sketch is **an illustration written for this chapter**: no pdp64 boot ROM, first stage or second stage exists (the QEMU machine loads the kernel directly, 6.12.2), so none of it is tested. The decisions are the numbered statements; where the repository does not say, the text says *not specified*.

4.1 What you already know: starting a PDP-11

A processor that has just been powered on has a problem that no program can solve for it: the program that loads programs has to come from somewhere, and the memory holds nothing it can trust. This is the **bootstrap problem** (after the old joke of pulling yourself up by your own bootstraps, shortened to "boot"). A PDP-11 solved it in three ways, each a smaller job for the operator than the one before.

The front panel. The console had rows of switches. You set the address switches to a memory address and pressed LOAD ADDRESS, set the data switches to a word and pressed DEPOSIT (which stores the word and steps the address), repeated that for each word of a short **bootstrap loader** (a program of a few dozen words that reads a bigger program from a device), set the start address and pressed START. The V7M `boot(8)` page still says so: "load block 0 of the boot device by fiddling with the console keys as appropriate for your hardware. If you have no appropriate ROM, some programs suitable for manual use are given below". (The switch mechanics are general knowledge, unverified.)

The boot ROM. Later machines kept the loader in a **ROM** (read-only memory: storage that holds its contents without power) on the processor board. The V7M tape bootstrap names one such card in a comment (`sas/htboot.s`: "The M9312, which is the only boot for the TS11"). That a console switch or command chose the device and that each ROM held a program for one kind of device is general knowledge, unverified. What the ROM did is the subject of this chapter in one sentence: it read **block 0** (the first 512-byte **block**, the unit a disk is read in, numbered from 0) of the boot device into low memory and jumped to it.

Block 0, the primary bootstrap. The program in block 0 is the **primary bootstrap**, small enough to fit in one block. The V7M page says it in one paragraph: "A PDP11 UNIX system is started by a two-stage process. The first is a primary bootstrap which is able to read in relatively small stand-alone programs; the second (called *boot*) is used to read in the system itself. The primary bootstrap must reside in the otherwise unused block zero of the boot device. It can be read in and started by the standard ROM programs, or if necessary by keying in a small startup routine." Here is the head of the primary bootstrap for the RM02/3 and RP04/5/6 disks, `sys/mdec/hpuboot.s` (285 lines, counted), which shows what a block-0 program has to do for itself:

```
/ UNIX/v7m RM02/3 and RP04/5/6 block 0 bootstrap
/ Can only boot from unit zero.
/ Assumes disk at standard address (0176700).

core = 28.
.. = [core*2048.]-512.          / 28 K words = 56 KB, less 512 bytes: high in memory

start:
        mov     $..,sp          / the stack is just below the program's new home
        clr     r0
        mov     sp,r1
        cmp     pc,r1           / are we running below the intended origin?
        bhis    2f
1:      mov     (r0)+,(r1)+     / yes: copy this program up, out of the way
        cmp     r1,$end
        blo     1b
        jmp     (sp)
2:      clr     (r0)+           / clear core to make things clean
        cmp     r0,sp
        blo     2b
        mov     $drive,*$hpcs2  / initialize the disk hardware and select the drive type
        ...
        mov     $'\r,r0         / print CRLF and '#' as a prompt
        ...                     / read a pathname from the console, then walk the
                                / inodes from the root (inode 2) to find the file
        jsr     pc,*$0          / the loaded program is entered by a call
```

The ROM put this program at address 0. It copies itself to the top of the first 56 KB so that the kernel can be loaded at 0, clears the rest of memory, starts the disk, prints `#`, reads a file name, finds the file by reading the disk's **inodes** (the file system's table entries, one per file) from the root directory down, loads it and enters it. The file it loads is the second stage.

The second stage, `boot`. `boot` is an ordinary C program (`sys/sas/boot.c`, 272 lines, counted). The V7M page: "When read into location 0 and executed, *boot* sets up memory management, relocates itself into high memory, and types `Boot` and `:` on the console. Then it reads from the console a device specification followed immediately by a pathname", for example `hp(0,0)unix`: the device, the unit, and the block offset of the file system on it. "*Boot* finds the corresponding file on the given device, loads that file into memory location zero, sets up memory management as required, and calls the program by executing a `trap` instruction." So there were two prompts, `#` from the first stage (type `boot`) and `:` from the second (type `hp(0,0)unix`). There were two stages because block 0 holds 512 bytes of program, enough to find a file by name but not also a menu, a device table and an error message for every disk; and a bigger program with all of that can be an ordinary compiled file, replaced by copying a new one in. The page also provides `/boot.bu`, "a backup copy of the bootstrap", the PDP-11's first recovery measure (4.10).

2.11BSD, the same kernel grown up, is explicit about the limit and about what the stages hand on. Its `boot(8)` page: "a primary bootstrap (limited to 512 bytes) ... must reside in block zero of the boot device (the disklabel resides in block one) ... `disklabel(8)` is normally used to place a copy of the appropriate bootstrap in block zero of new file systems"; copies are kept in `/mdec`. The header of its `hpuboot.s` says "assembled size must be <= 512; if > 494, the 16-byte a.out header must be removed" and that features "had to be removed to make room". The next stage receives the machine **in registers**: the comment in `pdpstand/srt0.s` reads "the bootstrap passes the cputype through in r0", `r1` holds the controller's register address and `r3` the boot device's major and minor number; `pdpstand/boot.c` declares a `checkword` that is "one's complements of bootopts", and tests `checkword != ~bootopts` to tell a boot that passed its options from one that did not (the register that carries it, `r2`, is not named in the lines read). That is the PDP-11 form of what the pdp64 does with `r0`, `r1` and the boot-information block (4.4, 4.6).

`ODT` and the console. When nothing booted you were not stranded: the processor or the ROM carried a tiny monitor, **ODT** (Octal Debugging Technique, a console program that lets you type an address, see the word there, change it, and start a program at an address). A PDP-11 with a dead disk could still be inspected and a bootstrap keyed in. (`ODT` is not in the sources on this machine: general knowledge, unverified.)

What a PDP-11 did not have. It had no partition table on the disk: V7's `hp.c` compiled the disk's regions into the driver (`hp_sizes[8]`, eight pairs of a size and a first cylinder, with comments such as "cyl 44 thru 429"; the V7M version has 24 entries for three drive types), so changing the layout meant recompiling the kernel (4.5). It handed the kernel no description of the

machine: the devices and their addresses were compiled in (chapter 6's vector table is that table) and the bootstrap passed three or four registers (4.6). It had one processor, so no other processor to start (4.7); no device that needed a program of its own before it would work (4.8); no firmware, so no BIOS and no UEFI (4.2, 4.9); and a monitor but no watchdog, so nothing restarted a hung machine (4.10). What the pdp64 keeps is the chain: a ROM that reads block 0 and jumps; a first stage that fits in a block; a second stage that is an ordinary program and finds the kernel by name; registers that carry the boot device across; a console monitor when nothing boots.

4.2 What came between: the VAX, the Commodore 64, the PC with a BIOS, the GPT with UEFI

The author named four systems between the PDP-11 and the pdp64: "pdp11 boot, vax boot, c64 boot, the x86 bios boot with mbr, then finally the gpt/uefi" (errata 110). Each added or removed one thing from the PDP-11 chain, and each is told here as steps and with the one idea it contributed. The marks: **(read)** is read in the sources on this machine, **(repo)** is from the repository's documents, **(unverified)** is general knowledge, the handbooks and specifications not being here.

The VAX: a console computer starts the machine

What it added: a processor whose only job is to start the main one, and a boot block of 15 sectors (the PDP-11's 512-byte block 0 and ROM made larger). The 4.3BSD sources are on this machine; the console and DEC's own boot program are not.

1. A **console processor** (on the VAX-11/780 a separate small computer) powers up and runs a self-test; it also provides the console commands and starts the other processors on multiprocessor models. (repo: `boot.md`; unverified otherwise)
2. On a boot command the console, or a boot ROM on the smaller models, reads the boot block (block 0) of the device into memory and starts it with registers describing the device. (repo; read for the registers below)
3. That first-level program is `raboot.c` in 4.3BSD-Tahoe. Its header says it "loads next 7.5Kbytes from boot sector of file system" to `0x50000` (sectors 1 to 15 of an 8 KB boot area, `BOOTLAST` 15) and "should work with any disk using 750 boot rom". It takes the Unibus I/O page address from `r1` (the adapter number is cut from it), the controller address from `r2`, the unit from `r3`, and the boot flags and partition from `r5`. (read)
4. The second level is `vaxstand/boot.c`: it takes `r10` (the device) and `r11` (the options), prints `Boot` and then the `:` prompt, opens a file by name and enters it. The default name is `hd(6,0,0) /vmunix` (`saio.h`). (read)
5. The kernel runs. In 4.3BSD `rpb.h` holds the "restart parameter block, which is a page in (very) low core which runs after a crash", a record for a dump routine and not a boot hand-off; what DEC's own boot program (VMB, a name from general knowledge) passed is unverified.

The 8 KB boot area of step 3 is where the pdp64's 8 KB boot area comes from (4.5.3).

The Commodore 64: the ROM is the whole boot

What it added: nothing to load. All of this is general knowledge, unverified; nothing about the C64's boot is in the repository beyond the machine's description in chapter 3.

1. The 6510 processor, on reset, reads its start address from the two bytes at `0xFFFC`; they lie in the **KERNAL ROM**, the top 8 KB of memory, so the first code is in ROM and nothing is loaded.
2. The KERNAL's cold-start routine initialises the chips, tests the RAM, sets the vectors and the screen.
3. It looks at `0x8000` for the signature `CBM80`; if a cartridge carries it, the cartridge's start address is called (**cartridge autostart**).
4. Otherwise it enters the **BASIC ROM's** cold start, which prints its banner and `READY.`
5. The user types `LOAD` and `RUN`; the program comes from the datasette or from the 1541 disk drive, a separate machine with its own processor and ROM.

The C64 has no second stage: the ROM is the operating system, and a program on a cartridge or disk replaces it by hand. The pdp64 takes from it one point: the first code is in a ROM that storage cannot damage.

The PC with a BIOS and an MBR: services in firmware, and a table in block 0

What it added: a firmware library the first stage can call, so that 512 bytes can read a disk; and a partition table sharing block 0 with the code. The facts come from the OpenBSD sources on this machine where they can, and are otherwise general knowledge, marked unverified.

The BIOS. The IBM PC of 1981 (unverified) kept a ROM called the **BIOS** (Basic Input/Output System). The name has stuck to four jobs that are worth pulling apart: (1) **bring-up and self-test**, initialising the chipset, sizing the memory, checking the basics (the power-on self-test); (2) **the first code**: find a boot device, read its first sector (the PC's word for a block, 512 bytes) to a fixed address and jump to it; (3) **a library of services** called by **software interrupt** (an instruction that behaves like a trap through a vector: the PDP-11's `emt` or `sys` is the same kind of thing), one service each for the disk, the screen, the keyboard and the memory map; (4) **configuration**, a setup screen and a small battery-backed memory for the clock and the settings. The third job is why a 512-byte boot sector can read the rest of a disk: it carries no disk driver, it calls the BIOS's. OpenBSD's PC first stage does exactly that: `biosboot.S` and `mbr.S` call `INT 0x13`, the BIOS disk service (read). The PDP-11's bootstrap carried its own driver (the `hpcs1` and `hpcs2` writes above); the PC's borrowed the firmware's.

The steps (the OpenBSD loaders are read; the rest is unverified):

1. The processor starts at the **reset vector**, `0xFFFFFFF0`, at the top of the 4 GB space, where the firmware flash is mapped, in 16-bit real mode. (unverified)
2. The BIOS runs its self-test (POST), initialises the chipset and memory and runs the **option ROMs** of add-in cards. (unverified)
3. It goes through the **boot-device order**, reads the first 512-byte sector, the **MBR**, to `0x7C00`, and checks the signature `0x55AA`; the code in the first 446 bytes runs. (the 446, the table and the signature are read in OpenBSD's `disklabel.h`; the address and the order are unverified)
4. The MBR code finds the **active** partition in the four-entry table and loads its first sector, the **partition boot record** (OpenBSD: `mbr.S`, which "finds the first active partition", then `biosboot`, whose manual page says "roughly 512 bytes of code"). (read)
5. That program, using `INT 13h` for every disk read, loads the next stage, `/boot`, which loads the kernel. (read: `biosboot.S`)
6. The kernel gets the memory map and the machine's description from the loader and the BIOS. (unverified)

The boot sector and its 446 bytes. The MBR (master boot record) is one block with three parts: 446 bytes of first-stage program, a **partition table** of four 16-byte entries (a **partition** is a named region of the disk, so that several operating systems can share one disk), then the two-byte signature `0xAA55` (the bytes `0x55`, `0xAA`). OpenBSD's `sys/disklabel.h` has it in C: `dmbr_boot[446]`, four `dos_partition` entries, `dmbr_sign` at byte `0x1fe`; an entry holds a flag byte (`0x80`, active), a type byte, and a start and a size of 32 bits each (read). The code gets 446 bytes because that is what a table and a signature leave in a sector. The 32-bit size caps the scheme at 2 TiB of 512-byte sectors (2^{32} x 512, arithmetic), and four entries is why "extended" partitions with a chain of further tables exist. The OpenBSD chain is BIOS, `mbr.S`, `biosboot`, `/boot`, kernel: four programs before the kernel, against the PDP-11's three (ROM, block 0, `boot`) or V7's own count of two (block 0 and `boot`).

Real mode. The BIOS and the first stages run in **real mode**, the 16-bit mode of the 8086 of 1978 (unverified) that addresses one megabyte, the only mode the processor starts in. Getting out of it is the loader's job and one thing the pdp64 does not have to do (4.7).

The GPT and UEFI: a table that outgrew the sector, and firmware that reads files

What it added: a partition table with 64-bit sector numbers, and a firmware that understands a file system and runs a program from it, so there is no boot sector to jump to.

The GPT. The four 32-bit entries ran out, and UEFI brought the **GPT** (GUID partition table; a **GUID** is a 128-bit identifier, long enough that two made anywhere will not collide). OpenBSD's `gpt_header` and `gpt_partition` structures (read) show it: the header sits in the second block (`GPTSECTOR 1`) with "EFI PART" in its first eight bytes; it holds a **CRC32** (a 32-bit check value computed over the bytes) of itself, the location of an alternate header (the **backup copy** at the end of the disk, so a damaged table can be rebuilt), and a CRC32 of the entry array; OpenBSD's constants are 128 entries of at least 128 bytes (a type GUID, a unique GUID, a 64-bit first and last block, attribute bits, a 36-character UTF-16 name). All values are little-endian (low byte first, the PDP-11's and the pdp64's byte order). The UEFI specification itself was not opened. Block 0 of a GPT disk is a **protective MBR**: an MBR with one entry of type `0xEE` ("EFI Protective Partition") covering the disk, so that an old tool that reads only the MBR sees a full disk and does not offer to partition it.

UEFI. The BIOS's successor is a firmware standard, **UEFI** (Unified Extensible Firmware Interface). The steps (OpenBSD's `efiboot` is read; the rest is unverified):

1. The firmware starts, through phases of its own, and runs its **boot manager**, which reads **boot variables** from non-volatile memory (**NVRAM**) to learn which loader to run. (unverified; the loaders call `GetVariable` and `SetVariable`: read)

2. It reads the GPT, finds the **EFI system partition** (`GPT_UUID_EFI_SYSTEM`, read) and its **FAT** file system (the MS-DOS file system, kept as the common denominator), and opens the loader file by name.
3. The loader is a **PE/COFF** program, the executable format of Windows (portable executable, from the Common Object File Format), where the PDP-11 and the BSDs use `a.out` or ELF. OpenBSD's arm64 loader begins "We need to be a PE32+ file for EFI" (read: `start.S`). The firmware runs it with a table of **boot services** (function pointers: allocate memory, read the memory map, read a file, write to the console, draw on the screen) and a few **runtime services** (clock, reset, variables) that stay after boot.
4. The loader calls the boot services and picks up the **memory map** and the **configuration tables** that describe the machine to the kernel: **ACPI** (a standard of tables, with a byte-code interpreter the kernel must carry) or a **device tree** (a tree of nodes naming each device and its addresses, flattened into a blob). OpenBSD's loaders look for both (`EFI_ACPI_TABLE_GUID`, `FDT_TABLE_GUID`; read).
5. It loads the kernel and calls **exit boot services** with the memory map's key, retrying once because the call refuses a stale key (`efiboot.c`, read); the firmware's boot services are gone after that.
6. The kernel runs with the memory map and the tables. With **Secure Boot**, each image is signed and checked against keys held in the firmware. (unverified)

Beneath this the firmware is a large program with phases of its own. The QEMU tree here carries built images of the open-source implementation EDK II (`pc-bios/edk2-*.fd.bz2`); the x86-64 code image is 3,653,632 bytes uncompressed (measured).


The chain, and the six jobs side by side

From the PDP-11 to the pdp64 the first code moved from the operator's keys, to a ROM, to a console computer (VAX), to the processor's own ROM with nothing loaded (C64), to a BIOS with services (PC), to a firmware that runs files (UEFI); and the pdp64 returns to the ROM and block 0 of the PDP-11. The jobs, by system:

Job	PDP-11	PC with a BIOS	PC with UEFI	pdp64
Bring-up	the processor and its ROM	the BIOS	the firmware	the controller's sequencer; on the FPGA the vendor's memory block
First code	ROM or front panel reads block 0	BIOS reads the MBR	firmware runs a loader file	the boot ROM reads block 0
Services for the loader	none: the bootstrap has its own driver	software interrupts	boot services	none: the loader has its own drivers
Finding the kernel	a name typed at `:`	partition boot record, `/boot`	the loader on a FAT partition	the second stage reads the label and finds `/bsd`
Telling the kernel about the machine	registers	registers and the BIOS's memory map (unverified)	the memory map and ACPI or a device tree	the boot-information block
Starting other processors	none	INIT and START-UP signals	the same	a write to a start register

three ways to start a machine: the PC with a BIOS, the PC with UEFI, the pdp64

PC with a BIOS (since 1981)




the loader calls the BIOS for every disk read, in 16-bit real mode, and has no drivers of its own

PC with UEFI (since about 2005)



no boot sector: the firmware parses the GPT and the FAT file system, runs the loader file, which calls the services and then gives them up

the pdp64



no services layer to call and nothing to give up: every stage after the ROM is an ordinary program built by the project's compiler

The PDP-11 chain was the pdp64's: ROM or front panel, block 0, boot, unix (4.1).
Both PC chains are general knowledge, unverified (4.12), except where the OpenBSD loaders show it: the amd64 tree on this machine has both, biosboot (862 lines) with boot (189), and efiboot (4,593 lines), measured (4.12).
Years are general knowledge, unverified. Real UEFI firmware has more phases than drawn, and keeps some code resident that the operating system cannot see.


4.3 What takes the place of a BIOS

4.3.1 The pdp64's "BIOS" is the controller chip's boot ROM and its monitor. It brings up the machine, loads the first block, and offers a console monitor when nothing boots. It has no resident services and nothing is called after boot. *(P)*

4.3.2 The boot software is open source and part of the specification: the ROM and monitor, the first-block program, the second-stage loader and the boot tools. *(D)*

4.3.3 Everything in the project, the boot software included, is under the BSD 2-clause licence. *(D)*

Why there are stages. The chain is a ROM, a first block, a second stage and a kernel, and each exists because the one before it is too small to do the next one's job. The ROM sits in the controller chip, where every byte costs silicon: it reads one block from the boot devices and does nothing else. The first block is 512 bytes, and under a GPT only the 446 bytes of the protective MBR's code area are its own (4.5): it holds a short list of where the next program lies on the disk and the few instructions that read it. Only the second stage, an ordinary C program loaded from disk, can be as large as it needs to understand a file system, the partition table and the label. The PDP-11 had the same chain without the partition table (the `#` and `:` prompts of 4.1).



Stage sizes are the reason for the stages: the ROM and the first block are the smallest code that can be made to find the next, and only the second stage is big enough to read a file system. The ROM holds the monitor too (4.10), reached when no block 0 loads.

The kernel is OpenBSD (errata 41 and 47). Where block 0 lands (0x1000 in 4.4) is an address still to be chosen (4.13).

Why open source, and why it is in the specification. The author's words (errata 47, 2026-10-22): "we'll have an open source boot sector boot loader as part of the spec; that is part of the spec that the boot loader/bios is open source." The firmware that ships on a PC is typically a vendor's build whose source the owner does not have (unverified), runs before anything the owner can inspect, and stays resident afterwards (4.2). In the pdp64 every stage after the controller's own sequencer is a published source file built by the project's compiler, and the ROM and monitor are in the same position, so no closed program sits at the root of the chain. The licence is that of the whole project (errata 48: "bsd license for everything"; the 2-clause variant is the assistant's choice of the common default, noted there). The UEFI specification itself is published (4.9), so what is closed on a PC is the shipped firmware and not the specification.

Commentary. **Chain.** The PDP-11's ROM and `ODT` did jobs 1, 2 and (as a monitor) 4 of the BIOS list; the PC added job 3, the services, so that a 512-byte sector could read a disk; UEFI turned job 2 into a loader file and job 3 into boot and runtime services. **Trade-offs.** The pdp64 returns to the PDP-11 split and drops job 3: every device speaks virtio through one transport (chapter 2), so the loader and the kernel share one driver design and the loader needs no firmware to read a disk. The cost is a driver for the boot disk in the second stage, small because a virtio device is a handful of structures. **Benefits.** There is no firmware API to specify, no compatibility layer, no resident management code and no closed blob at the bottom of the trust chain; the failure cases reduce to one, the first block did not load, and the monitor is the recovery. **Impact.** *Kernel:* no firmware services to call or to fix. *Compiler:* builds the ROM, loader and tools. *Hardware:* a boot ROM of a few hundred bytes to a few kilobytes, with a driver per boot device (not specified more closely).

4.4 The reset state and the first block

What happens at power-on. The **controller chip** (the chip that holds the boot ROM, `boot.md`) brings up the memory and holds every core in **reset** (a state in which a core executes nothing and keeps no state). The ROM runs on core 0. On the PDP-11 the equivalent was the processor's own power-up and the ROM or the front panel; here it is a small program in the controller that does five things in order: find a boot device, read block 0 into low memory, check that it looks like a boot block, set core 0's registers, and start core 0 at the block. If it finds no device or no boot block, it runs the monitor (4.10). In pseudocode:


```
rom_entry():                                # core 0; every other core is held in reset
    for dev in boot_order:                  # disk or flash, then SD card, then the serial line (4.4.1)
        if not bring_up(dev): continue      # enumerate the bus, find the function, handshake (4.8)
        if not read_block(dev, 0, LOAD):    # LOAD = 0x1000 in this chapter's example (4.4.2)
            continue
        if byte[LOAD + 510] != 0x55 or byte[LOAD + 511] != 0xAA:
            continue                        # not a boot block: try the next device
        info = fill_boot_info(dev)          # memory ranges, cores, root complex, device, console (4.6)
        core0.mode = KERNEL; core0.priority = 7; core0.translation = off; core0.VBR = 0
        core0.guard = clear                 # the user-memory guard
```

```
        core0.r0 = number_of(dev)            # which device it came from
        core0.r1 = info                      # the boot-information block
        core0.r14 = 0x10000                  # the top of the first 64 KB of memory
        core0.all_other_registers = 0
        core0.pc = LOAD                      # the first instruction of block 0
        return                               # core 0 now runs the block; the ROM is done
    monitor()                                # nothing booted: the console monitor (4.10)

read_block(dev, n, address):                 # the standard disk: one virtio-blk request (5.6.2)
    build a three-descriptor chain: request header (type = read, sector = n),
                                    a 512-byte buffer at `address`, a one-byte status
    FENCE; write the queue's doorbell; poll the used ring until the chain returns
    return status == OK
```

The ROM polls (checks in a loop) rather than using interrupts because no interrupt controller is set up yet (the reason is the assistant's; the repository does not say). It needs a driver for each kind of boot device; for the standard disk that is the virtio-blk reader of chapter 5: find the function in the bus's configuration space, set up one queue, read one block. Which device comes first, and how the ROM names a device in `r0`, are not specified (F10 of `decisions-pending.md` leaves the order after the disk open).

The first few pages of memory. The **vector table** (the table of handlers that an exception or an interrupt jumps through, chapter 6) is **one whole page**, 512 entries of 8 bytes, at address 0, because the system register `VBR` (vector base register) is zero at reset (6.12). The PDP-11's was a fixed table of a few hundred bytes at 0 to 0377, and its boot programs lived elsewhere. The author summarised the PDP-11 way (2026-10-22) as "load 512 byte block 0 then jmp 0", "not precisely true, but directionally true"; here the "jmp 0" becomes a jump to the address block 0 was loaded to, because the first page holds the vectors. Block 0 is loaded **above** the table, at 0x1000 in this chapter's example (the address is "to be chosen"; `docs/boot.md`), so that the first stage runs without overwriting the vectors. The stack pointer `r14` starts at the top of the first 64 KB, so the first stage has a stack before it has run an instruction. `r1` points at the **boot-information block** (4.6). The author's rule of errata 102 is that no device window is mapped in **the first few pages**, where "the boot stuff is loaded"; how many pages that is, is not decided.



0x1000 and the 64 KB stack top follow the proposal of 4.4 and the figure of chapter 6; how many pages are reserved is not decided (errata 102).
Not to scale. The ROM itself is not in this memory: it sits in the controller chip, outside the address space the kernel uses.
On the PDP-11 the vectors sat at 0 to 0377 and the bootstrap was loaded elsewhere, often high in memory (4.1).

4.4.1 At reset the controller brings up memory, holds every core in reset, and looks for a boot device in a fixed order: disk or flash, then SD card, then the serial line. *(P)*

4.4.2 It reads block 0 of the first device that answers (for the standard disk, a virtio-blk read request) into low memory, checks the `0x55AA` signature in the last two bytes, and starts core 0 at that address. It does not parse a partition table. *(P)*

4.4.3 Core 0 starts in kernel mode at priority 7 with translation off (every address physical), `VBR` zero and the user-memory guard clear; `r0` holds the boot device number, `r1` the address of the boot-information block, `r14` the top of the first 64 KB of memory, and the other registers are zero. *(P)* The first few pages of the physical address space are reserved for the boot code and boot data, and no device window is mapped there (2.3.6, *(D)*); how many pages is not decided. *(P)*

4.4.4 If no boot device answers, or a key is held at power-up, the monitor runs on the serial console. *(P)*

Not specified here: where block 0 is loaded (0x1000 is an illustration); how the ROM finds the boot device's windows before any software has assigned them (2.4.1 says the processor assigns windows; the ROM is the first software to do it, and the repository does not say where it puts them or whether it leaves them for the kernel); which fields of the boot-information block the ROM fills and which the second stage adds (the natural reading, since the ROM knows the memory, the cores and the device, is that the ROM fills the block and the second stage adds the command line and the screen, 4.6; not stated); and the number of reserved pages.

Commentary. **Chain.** PDP-11: ROM or keys read block 0 and jump, the boot device in registers. VAX: a console or a boot ROM does the same with the boot block and registers `r1` to `r5` (4.2). PC: the BIOS reads one 512-byte sector to a fixed address (unverified: the address). UEFI: no block 0, a file run from a FAT partition. pdp64: the PDP-11 step again, with the reset state written down. **Trade-offs.** A boot ROM with a driver per boot device is more code in the controller than a "jump to a fixed flash address" scheme and much less than firmware; the first block must fit in one sector. **Benefits.** The first stage is the same on every board and the first kernel code makes no guesses about the reset state. **Impact.** *Compiler:* the first block is 446 bytes of assembler. *Hardware:* the ROM reads one block and starts one core.

4.5 The disk: a GPT around the BSD label

What a partition is, and why V7 had none on the disk. A disk is one long run of blocks, and a computer wants several regions of it: a root file system, a swap area, a place for the users' files. A **partition** is such a region, and something has to record where each begins and ends. There are three places for the record, and the chain from the PDP-11 visits each. V7 put it **in the kernel**: the disk driver compiles in a table (`hp_sizes[8]` in V7's `hp.c`), so changing the layout means a new kernel; 4.3BSD's `vaxmba/hp.c` also compiles in its size tables (`rp06_sizes[8]`, `rm03_sizes[8]` and others). The 4.3BSD-Tahoe `disklabel.h` (1988: its header is dated 6/27/88) put it **on the disk**: a **disk label**, a structure in one of the first blocks holding the disk's geometry and a table of its partitions, "in block 0 or 1, possibly offset from the beginning to leave room for a bootstrap", marked by the magic number `0x82564557`. 2.11BSD's block 0 holds the bootstrap and its block 1 the label, the same two places as here. OpenBSD's label is its descendant: the same magic number, **16 partitions** (`MAXPARTITIONS16`, against Tahoe's 8) and sector counts beyond 32 bits (`d_secperunith` holds the high part). The third place is the PC's, a **table in the first sector** (the MBR table of 4.2, then the GPT).

Why the pdp64 has both a GPT and a label. The author (errata 50, 2026-10-22, message 2631): "fine, we will have the gpt wrapper for the disk label." The disk carries a GPT with a protective MBR, so that other operating systems and partitioning tools recognise it, and the operating system's own partition (type `GPT_UUID_OPENBSD`) holds the BSD label, which says where the root file system, swap and the rest are. The label alone would be smaller and unreadable to everything else; the wrapper costs a GPT reader in the second stage and the kernel. The author added (errata 51, "follow the majority as far as boot block offset"): inside the OS partition the label is at **sector 1, offset 0**, the sector that most of OpenBSD's ports use, leaving sector 0 for a boot block.

The first stage lives in the protective MBR. Block 0 of a GPT disk is the protective MBR, 512 bytes: 446 bytes of code, the table (one entry, type `0xEE`), then `0xAA55` (the bytes `0x55`, `0xAA`: the `0x55AA` of 4.4.2). The first stage has 446 bytes. It cannot understand a GPT or a file system in that space and does not try: it carries a **block list**, three numbers per piece of the second stage (first block, number of blocks, load address), written into its code area by the **`installboot`** tool at installation; it reads those blocks and jumps to the first. The BSDs already do this. OpenBSD 4.6's `installboot(8)` page for the sparc says the first-stage program "loads the second stage program from a set of filesystem block numbers that have been hard-coded into it by the installboot program"; on the PC `installboot` patches `biosboot` with the location of `/boot`, and `biosboot(8)` says to re-run it whenever `boot(8)` is changed, "as its inode may change" (read). Because the boot-code bytes are the only place the pdp64 keeps block-list data, a damaged GPT cannot stop the machine reaching the second stage, which can repair it.

```
first_stage():                              # at LOAD (0x1000): 446 bytes of code plus the block list
    # entering state: kernel mode, priority 7, r0 = boot device, r1 = boot-information block, r14 = a stack
    for entry in block_list:                # entries written by installboot: (start, count, address)
```

```
        read_blocks(r0, entry.start, entry.count, entry.address)     # (see the open question below)
        if failed: goto monitor_or_halt       # what to do on failure is not specified
    jump to block_list[0].address             # the second stage, with r0 and r1 unchanged
```

The pseudocode hides a question the repository does not answer: **how the first stage reads blocks.** 4.3.1 says the ROM offers no services after boot, and a virtio-blk read needs a queue, three descriptors, a doorbell and a poll (4.4). Whether that fits in 446 bytes beside the list is unknown: nothing has been assembled. The PDP-11 primary bootstrap carried its own disk driver (the `hpcs1` and `hpcs2` writes of 4.1) and the PC's called the BIOS. Three ways out, none decided: the first stage holds a small polled virtio-blk reader of its own (the PDP-11 way, consistent with 4.3.1); or the ROM leaves a read routine and tells the first stage where it is (a firmware call in miniature, against 4.3.1); or the ROM loads more than block 0, the whole 8 KB boot area of 4.5.3 for example, so the first stage has room for the reader. The question is in 4.13.


4.5.1 The disk carries a GUID partition table with a protective MBR; the operating system's own partition holds the BSD disk label, which names the root, swap and other partitions. *(D)*

4.5.2 Block 0 is the protective MBR, so the first stage lives in its 446 boot-code bytes, carrying a short block list (start block, count, load address) to the second stage; neither the ROM nor the first stage parses the GPT. *(P)*

4.5.3 Inside the BSD partition, the label is at sector 1, offset 0; the boot area is 8192 bytes at the start of the partition; the file system begins after it, its superblock at offset 8192. *(D)*

Sector (512 bytes) of the BSD partition	Contents
0	the partition's own boot block
1	the disk label, at offset 0
2 to 15	the rest of the 8 KB boot area
16 on	the file system, superblock at offset 8192

4.5.4 Sector counts are 64-bit throughout; the label has 16 partitions and its sizes carry high fields beyond 32 bits. *(D)*



The label (offset 0 of sector 1) has the magic number 0x82564557 and names up to 16 partitions (root, swap, ...); its sizes carry high fields beyond 32 bits. The kernel is a file in the root file system, which the second stage finds.

On the PDP-11 there was no such table: V7 compiled eight (size, first cylinder) pairs into each disk driver (hp_sizes[8] in hp.c). In 2.11BSD block 0 held the 512-byte bootstrap and block 1 the disk label: the same two places as here.

The MBR and GPT layouts are as the OpenBSD header disklabel.h has them (4.12); the 8 KB area and sector 1 are decided (4.5.3). Whether a separate boot partition is needed at all is open: the block list can point into the root file system (4.13).

The **superblock** (the file system's first record: its size, its block size and where its tables are) sits at byte 8192 of the partition, after the 8 KB boot area that the BSD tradition reserves for the bootstraps (errata 51: sector 0 the primary bootstrap, sectors 1 to 15 the label and a secondary bootstrap; the VAX's `raboot` of 4.2 loads sectors 1 to 15). The second stage can live in the boot area, in a small boot partition, or as a file in the root file system; whether a dedicated boot partition is needed is open (4.13), since the block list can point at any of them.

Commentary. **Chain.** V7: sizes in the driver, nothing on the disk. 4.3BSD-Tahoe: the label on the disk. PC: an MBR table of four 32-bit entries, then the GPT with a protective MBR. pdp64: the GPT outside, the BSD label inside. OpenBSD's tree has seven architecture headers with the label at sector 1 offset 0 (amd64, i386, arm, arm64, riscv64, hppa, powerpc64) and Alpha and SPARC64 at sector 0 (offsets 64 and 128); the port adds one header of a dozen lines. **Trade-offs.** The label alone is the smallest design and unreadable to other systems' tools; the GPT wrapper costs a GPT reader in the second stage and the kernel (OpenBSD's kernel already has one) and gives a disk other systems recognise. **Benefits.** The first stage does not depend on a GPT that may be damaged. The label code, `disklabel`, `newfs` and `installboot` come with OpenBSD. **Impact.** *Kernel:* the label code and tools come with OpenBSD. *Compiler, hardware:* none.


4.6 The second stage and the hand-off

What the second stage is for. The first stage put a bigger program in memory. The second stage does what the PDP-11's `boot` did, with more to read: it finds the disk, reads the partition table, reads the label, finds the root file system, finds the kernel by name in it, loads the kernel and enters it. Because it is a C program loaded from disk it can be as large as it needs and be replaced by copying a file. It has its own drivers (the virtio-blk reader, now complete) and no firmware to call. As a sketch:

```
second_stage():                                 # loaded by the first stage; r0 and r1 as at reset
    dev = open_boot_device(r0)                  # the same virtio-blk driver the ROM used, now complete
    gpt = read_gpt(dev)                         # header at block 1: check "EFI PART" and the CRC32;
                                                # if it is bad, use the backup at the end of the disk
    part = first entry whose type GUID is the OpenBSD type
    label = read(dev, part.start + 1)           # sector 1 of the partition (4.5.3)
    check label.magic == 0x82564557 and the label's checksum
    root = the label's root partition ('a'); mount it read-only
    cmdline = prompt("boot> ") or the default   # as the V7 ':' prompt: which kernel, which options
    elf = root.open("/bsd")                     # an ELF file, the toolchain's own object format
    for seg in elf.loadable_segments:
        copy seg.file_bytes to physical address seg.address; zero the rest of seg
    info = r1                                   # the block the ROM began; add what only we know:
    info.cmdline = cmdline
    info.video = framebuffer if we set one up (4.6.4)
    info.checksum = checksum(info)
    jump elf.entry with r0 = boot device, r1 = info     # still kernel mode, priority 7, translation off
```

The hand-off: how the kernel learns about the machine. The PDP-11 had four registers and a kernel built for the machine. A kernel that is to run on any pdp64 has to be told: how much memory there is and where (ranges, since memory is not always one block), how many cores, where the bus's root complex is (so that it can **enumerate**, walk the bus and list what is attached, 2.4), which device it was loaded from, where the console is, and the command line. The way to tell it is a **boot-information block**, a structure in memory whose address is in `r1`. The chain: the PDP-11 passed registers, as did the VAX (`r10`, `r11` to `boot`, 4.2); UEFI passes a memory map and **ACPI tables** or a **device tree** through configuration tables (4.2), and an operating system for several architectures carries a parser for each. The VAX's restart parameter block is a crash-dump record, not a hand-off (4.2); the Alpha's hardware restart parameter block is unverified here. The pdp64's hand-off is small because the bus describes its own devices: the block names memory, cores, the root complex, the boot device, the console and the screen if one was set up, and the kernel finds everything else by enumeration.

the boot-information block: a struct the second stage fills in and r1 points at



Each row is one 64-bit word in this drawing (the offsets are bytes). The contents are statements 4.6.2 and 4.6.4; the offsets, the widths and the order drawn are an example, not specified.

Defined once in a grammar from which the headers are generated, so the loader and the kernel cannot disagree (4.6.3). The devices are found by enumerating the bus (2.4), so the block stays short.

The VAX and Alpha passed similar blocks, a restart parameter block each (from the boot review, unverified, 4.12).

4.6.1 The second stage is a program in C that understands the root file system, reads the GPT and the label, loads `/bsd` (an ELF file) and jumps to it with `r0` and `r1` as before and a command line in the boot-information block. *(P)*

4.6.2 The boot-information block names the memory ranges, the core count, the address of the root complex and the identity of the boot device and the console; the kernel enumerates every other device by PCI Express enumeration (section 2.4). *(P)*

4.6.3 The block's layout is defined once, in a grammar from which the headers are generated, and carries a checksum and a version. *(P)*

4.6.4 The boot-information block carries the video device's base address, size, pitch and pixel format when the boot loader has set it up, and nothing about the device's clock or power state is changed behind the kernel: its pixel clock stays up until the kernel's driver owns the device. *(D)*

Statement 4.6.4 exists so that the loader can set up a picture for the boot messages and the kernel can keep drawing on it until its own driver takes over, without the screen flickering or going blank: the **framebuffer** the loader set up is described in the block, and the device is left as it is. (That the PC learned this the hard way is the assistant's earlier wording and is unverified.)

Commentary. **Chain.** PDP-11: a kernel configured at build time, three or four registers. VAX: registers again (`r10`, `r11`). UEFI-era systems: ACPI tables or a device tree. pdp64: one block, because the bus is enumerable. **Trade-offs.** A fixed-layout block with a checksum has two failure cases (bad checksum, unknown version), against the parser a device tree or ACPI needs. OpenBSD's arm64 and riscv64 ports already parse a device tree and attach drivers from it, which could save kernel code if the port reuses many of their drivers (4.13). **Benefits.** The generated header cannot disagree with the loader. **Impact.** *Kernel:* reads a structure. *Compiler:* generates the header from one grammar. *Hardware:* none.

4.7 Starting the other cores

The problem the PDP-11 did not have. A PDP-11 had one processor, so "start the machine" was one thing. A pdp64 may have several **cores** (processors on one chip; chapter 7), and at reset only core 0 runs the boot code. The kernel has to start the others, each with its own stack and its own idea of who it is. The precedents, from the boot review (`boot.md`; counts measured there in Linux `7be4bc52` and re-counted for this chapter): on x86 the boot core sends INIT and START-UP signals through the interrupt controller (Linux's comment: "INIT, INIT, STARTUP sequence"), the START-UP carrying an address below one megabyte; the other core wakes in the 8086's **real mode** (4.2) and a hand-written **trampoline** (a short program that takes a processor from a limited mode to its full one, through two more modes) must walk it into 64-bit mode. Linux's `arch/x86/kernel/smpboot.c` is 1,528 lines and `arch/x86/realmode` another 1,258. arm64 asks firmware through a


call, PSCI, in 124 lines (`arch/arm64/kernel/psci.c`), or has the waiting cores **spin** (loop on a word in memory) on a **spin table** until the boot core writes an address there, in 127 (`smp_spin_table.c`); RISC-V asks the firmware to start a **hart** (its word for a core) in 108 lines (`cpu_ops_sbi.c`) or spins in 58 (`cpu_ops_spinwait.c`). That the VAX console processor started the VAX's other processors is unverified.

The pdp64's rule: one register write. A pdp64 core has no mode ladder, so it can start in its normal mode at any address. The controller holds every core but core 0 in reset; to start core *n*, the kernel writes, to a register block in the controller that belongs to core *n*, the address where the core should begin and one argument, and the controller releases the core into **kernel mode at priority 7** with its core number in `r0` and the argument in `r1`. By the kernel's convention the argument points to a structure that belongs to that core (its stack, its per-CPU data). A core that sticks is reset by a write to a core-reset register and started again.

```
start_secondary_cores():                    # core 0, in the kernel, after its tables are built
    for c in 1 .. core_count - 1:           # core_count comes from the boot-information block
        percpu[c] = allocate(percpu_size); percpu[c].stack = allocate(KSTACK)
        percpu[c].online = 0
        write(start[c].entry, secondary_entry)   # the exact registers are not specified (4.7.1)
        write(start[c].argument, percpu[c])
        write(start[c].go, 1)                    # the controller releases core c into kernel mode
        wait up to a timeout until percpu[c].online == 1
        if not online:
            write(core_reset[c], 1)              # 4.7.2: stop it, and try once more
            ... start it again, or mark core c failed and go on without it

secondary_entry():                          # core c: kernel mode, priority 7; r0 = c, r1 = percpu[c]
    set VBR and the page-table base to the kernel's, turn translation on, ISYNC    # chapter 6 (6.12)
    set the per-CPU pointer DP from r1; set R14 = percpu.stack top                  # chapter 7 (7.4.2)
    percpu.online = 1                       # core 0 is polling this word
    enable the clock; enter the scheduler's idle loop (WFE until there is work)    # chapter 6, 7.6
```

starting the other cores: one register write each, then the core is a core



time runs to the right (not to scale); priority 7 on entry. The entry address is where the kernel's per-core code starts; the argument is a pointer to that core's own structure. A core that sticks is reset by a write to a core-reset register of the controller and started again (4.7.2).

x86, for comparison (general knowledge and Linux smpboot.c, 4.7): the boot core sends INIT and START-UP signals through the interrupt controller; the other core wakes in 16-bit real mode at an address below 1 MB, and a trampoline must walk it through protected mode into 64-bit mode.

The pdp64 has no such ladder: a core starts in its normal mode at any address. What the start registers look like is proposed, not decided (4.7.1); the register block's address is open (4.13); the SMP chapter (7.8.1) names r0 only, where 4.7.1 loads r1 too.

The cost is one register block in the controller, with a start register and a reset hold per core. The started core has no translation or stack of its own; the kernel's entry code sets them up in its first instructions, as the first kernel does (6.12). Whether a started core begins with translation off, and what `MMUCTL` it sees, are not specified.

4.7.1 The controller holds every core except core 0 in reset; a write to a core's start register in the controller gives it an entry address and an argument and releases it into kernel mode at priority 7, with its core number in `r0` and the argument in `r1`. *(P)*

4.7.2 A stuck core is reset by a write to a core-reset register. *(P)*

Other chapters. This is option 1 of boot decision B2 and of R2 in `decisions-pending.md`, which recommend it and leave it proposed (the other options were the x86 signals, a firmware call, a spin table and a table that all cores start from). Chapter 7 states the same rule as 7.8.1 and loads `r0` only, where 4.7.1 loads `r1` too; the difference is to settle (4.13). Waiting uses `WFE` and `SEV` (7.6); an **inter-processor interrupt**, a signal from one core to another, is a write to a per-core register of the interrupt controller (7.8.2).

Commentary. **Chain.** PDP-11: one processor, nothing to start. VAX: the console processor started the others (unverified). x86: INIT and START-UP signals and a trampoline through three modes. arm64 and RISC-V: a firmware call or a spin loop. pdp64: a register write. **Trade-offs.** With no mode ladder the whole protocol is one write, at the cost of a small register block in the controller. **Benefits.** Fewer lines than any system counted, and one recovery path, a core reset. **Impact.** *Kernel:* starting a core is a register write. *Compiler:* none. *Hardware:* a start register and a reset hold per core.

4.8 Starting the devices

The INIT bit. On the Unibus every device had a **control and status register** (CSR) with a bit that told the device "initialise yourself" and a bit that said it was ready: you wrote `INIT`, waited for `READY`, and the device was in a known state (the RK11 of chapter 2 has `GO` and `RDY` in its CSR). All the work happened behind the register, in the device's own logic. The pdp64 keeps the idea and makes it a conversation: under virtio (2.6.3) the driver writes **zero** to the device's `device_status` byte, which resets it, then sets the bits `ACKNOWLEDGE`, `DRIVER`, `FEATURES_OK` and `DRIVER_OK` in order, each meaning "I have got this far", and the device answers by refusing or accepting the features the driver chose. That is the `INIT` and `READY` of the CSR spread over a few steps, and `init_device(fn)` of 2.6.3 is the pdp64's device start. At boot the ROM runs it for the boot disk (4.4), the second stage again for the devices it uses, and each kernel driver at attach.

Firmware for a device. Some devices contain a small processor and need a program, **firmware**, loaded into them before they work; a network or wireless card is the usual case, a graphics device another. The PDP-11 had no such device and no way to give it one. On a PC the driver loads the blob from a file at attach time (Linux's `request_firmware` and OpenBSD's `firmload(9)`: unverified, not looked up), and the files come in a separate package. The pdp64 proposal is that such a device is given its firmware through a descriptor operation (a request on the device's queue, or a descriptor giving the address and length of an image in memory, with a small header the device checks: identifier, version, length, checksum) **once the root file system is available**, and that a device the boot depends on needs none: the boot disk, the console and the interrupt controller work from their built-in logic alone, so that no device waits for firmware that is on the disk it controls.

```
start_device(dev):                          # at boot or at attach
    init_device(dev)                        # the handshake of 2.6.3; reset first
    if dev.needs_firmware:                  # a device the boot depends on never does
        image = read_file(root_fs, firmware_name(dev))      # the file system must be up (4.6)
        check image.header: device id, version, length, checksum
        submit a descriptor chain giving dev the address and length of image
        wait for the device to answer; if it refuses, mark the device failed
```

4.8.1 A device is initialised by writing its `INIT` bit and waiting for `READY`; a device that wants firmware is given it through a descriptor operation once the root file system is available, and a device the boot depends on needs no firmware. *(P)*

What the statement predates. 4.8.1 was written when devices were eight registers with an `INIT` and a `READY` bit (errata 29, withdrawn in favour of virtio by errata 95); the `device_status` handshake above is how it reads under virtio. How a virtio device is handed firmware is not specified: virtio has no firmware operation of its own, so a request type or a separate device would have to be defined (4.13).

Commentary. **Chain.** PDP-11: the CSR's `INIT` bit, nothing more. PC: PCI Express devices initialised through configuration space and per-device driver code, firmware blobs loaded from files. pdp64: the virtio handshake, firmware by descriptor. **Trade-offs.** A reset bit and a status register make the simplest device, with one failure case, a timeout. A firmware window lets a device be cheap (no flash) and makes an update a file replacement, at the cost of a header format and a device that rejects a wrong image safely; boot-critical devices are excluded because a device whose firmware is on a disk it must itself read cannot start. **Impact.** *Kernel:* a device start is the 2.6.3 handshake. *Compiler:* none. *Hardware:* a status register per device.

4.9 Why UEFI is not used

4.9.1 The pdp64 does not use UEFI: its boot is the block-0 route of sections 4.4 and 4.5, its hand-off is the boot-information block, and its devices describe themselves. UEFI firmware is not part of the specification and is not built. *(D)*

4.9.2 The hand-off and the second stage are kept simple enough that a UEFI shim could be written by someone who wanted one. *(D)*

Both statements are the author's decision of 2026-11-10 (errata 109). The record, in his words (the 2026-10-22 messages are in the decision log, thread 1889, messages 2614 and 2620; the 2026-11-10 ones are quoted from errata 109 and 110 and are not in that log). On 2026-10-22 he asked, of boot, "look into uefi; is it worth it at all? can't we do what pdp11 used to do, load 512 byte block 0 then jmp 0? (not precisely true, but directionally true)", and asked how UEFI plays into partitions and the GPT; the review (`boot.md`) answered that UEFI was not worth it as the machine's own boot, and the earlier text's 4.6.1 and 4.6.2 were the assistant's proposals, tagged *(P)*, never a decision. On 2026-11-10 he asked "i thought we did decide to allow uefi? check all the threads where we discussed it" (no decision to allow UEFI was found in any recorded message), then "or we kept the originnal simple pdp11 boot block method?", and, given three options, chose "option 2, block 0 with a shim possible".

Is UEFI an open specification, and what does an open-source system do with it? The author asked, after the decision (2026-11-10): "if uefi isn't an open spec how are all the open source os supporting it? it requires binary firmware blobs?" By what could be checked:

- **The specification** is published by the UEFI Forum, the industry body that maintains it, and can be read without charge (general knowledge, unverified: it is not on this machine, and whether implementing it needs a membership, a licence or a compliance test is not known here). The closed part is elsewhere.
- **An open-source implementation exists.** EDK II, the TianoCore project's reference implementation, is under BSD-2-Clause-Patent (read: `/home/david/claude/qemu-src/pc-bios/edk2-licenses.txt`, and `/usr/share/doc/ovmf/copyright`, "Upstream-Name: edk2"). Built images are on this machine (QEMU's `pc-bios/edk2-*.fd.bz2` and `/usr/share/OVMF`, including `OVMF_CODE_4M.secboot.fd`), so an emulated PC boots under open firmware. The source is not here (`roms/edk2` is empty), so nothing about its size or contents was read.
- **Open-source operating systems write the loader side.** OpenBSD's `efiboot` (read) runs on top of firmware already on the machine and calls its services; it ships no firmware. That Linux and NetBSD do the same is unverified here. A loader needs no blob.
- **The proprietary blobs are in the firmware shipped on real PCs:** the vendor's builds, and the CPU vendor's initialisation code that brings up memory and the chipset, which many boards include as a binary (unverified, not on this machine). That is a property of how PCs are made, not of the UEFI specification.
- **Secure Boot** adds a chain of signed loaders and keys kept in the firmware's variable store (unverified; the `secboot` image names above are all that was seen).

The author's conclusion (2026-11-10): "I guess leaving the door open to uefe support but having the classic mbr fallback, gpt wrapper is a good choice then." That **confirms option 2** of errata 109 and decides nothing new (errata 110). The two routes share one disk: block 0 of the pdp64 disk already has the protective MBR and GPT layout (errata 50, 4.5), so the classic route (the ROM reads block 0) and a future UEFI route (a firmware, or the shim, reads the GPT and a FAT system partition) read the same disk without repartitioning it.

What a shim is, and what it is not. The author asked, "not sure why firmware and coff are needed for uefi, with virtio native that shuld be minimal, no?" and then, "yes, state the shim's real scope." Virtio removes most of the driver mass that a full firmware carries (it ships drivers for every disk, network card and screen it might meet; the pdp64 has one device interface), and the shim needs only the drivers the second stage has. Two things stay, and they are the shim's real scope:

1. **PE/COFF.** The UEFI specification requires a UEFI application to be a PE32+ image (unverified: the specification is not here); that is a property of the **loader programs**, not of the firmware. To run an existing loader such as OpenBSD's `efiboot` it must be built as a PE/COFF image *for the pdp64*, so the toolchain has to produce one, and a **machine-type code** (a 16-bit number in the image's header that names the processor; OpenBSD's arm64 loader uses `IMAGE_FILE_MACHINE_ARM64 0xaa64`, read) would have to be assigned by the owners of the specification (unverified). It need not be a linker feature: OpenBSD's arm64 loader is linked as an ordinary ELF file and wrapped as PE32+ by a header written by hand in assembler (`start.S`, 176 lines) plus a self-relocator (`self_reloc.c`, 124 lines), with `objcopy` doing the rest (read, counted). The loader is itself a program that must be compiled for the pdp64.
2. **A small services layer.** The shim provides the few services loaders use: memory allocation and the **memory map**; reading a file from the boot partition; the console and the **graphics output protocol** (a framebuffer to draw on); **exit**

boot services; a runtime clock and reset; all over virtio. It also hands the kernel a device description in the form such a loader expects, a device tree or tables.

How many services, counted. The three UEFI loaders in `/home/david/claude/kernel-src/openbsd/sys/arch/*/stand/efiboot` call these (counted as `BS->`, `RS->` and console calls in the `.c` files; the number is the count of call sites in the amd64 loader):


Boot services (`BS->`)	Runtime services (`RS->`)	Console and file protocols (through a handle)
`HandleProtocol` 13, `AllocatePages` 7, `LocateHandle` 5, `LocateProtocol` 2, `LocateHandleBuffer` 2, `GetMemoryMap` 2, `FreePages` 2, `WaitForEvent`, `SetWatchdogTimer`, `FreePool`, `AllocatePool`, `Exit`, `ExitBootServices` (1 each); the arm64 and riscv64 loaders add `SetTimer`, `CreateEvent`, `CloseEvent` and lack the two pool calls	`ResetSystem` 3, `GetVariable` 3, `SetVariable` 2, `GetTime` 1 (called as `ST->RuntimeServices->GetTime`)	the text console (`OutputString`, `ReadKeyStroke`, `SetMode`, `QueryMode`, ...), the disk (`ReadBlocks`, `WriteBlocks`), files (`Open`, `Read`, `Write`, `Close`, `SetPosition`, `GetInfo`), the network (`Mtftp`, `Transmit`, `Receive`), the graphics output protocol, the random-number protocol

That is 17 distinct boot and runtime calls in the amd64 loader (13 and 4) and 18 in the arm64 and riscv64 ones (14 and 4); errata 109 and `boot.md` say “about fifteen to seventeen”, which this count corrects. It counts what **one** loader uses and is not a specification of what a shim must offer: another loader uses others, and whoever writes the shim reads the loader.

A sketch of the shim (an illustration; no such code exists). The shim is the second stage, loaded by block 0; it builds the services table, loads the loader’s PE image, calls it, and answers its calls.

```
shim_entry():                                # the second stage of a pdp64 that wants UEFI loaders
    info = r1; heap = free_ranges_from(info.memory_ranges)
    table = new system_table {
        boot_services = {
            allocate_pages = shim_allocate_pages,   # out of the heap; the loader asks for a page count
            free_pages     = shim_free_pages,
            get_memory_map = shim_get_memory_map,   # the ranges of `info`, plus what the heap handed out
            locate_protocol = shim_locate_protocol, # the console, the graphics output, a file volume
            exit_boot_services = shim_exit_boot_services,
            ... }                                    # the others a given loader uses; unused ones return
"unsupported"
        runtime_services = { get_time = clock_register, reset_system = reset_register, ... }
        configuration_tables = [ (DEVICE_TREE_GUID, make_device_tree(info)) ]   # made from the boot-
information block
    }
    image = read_file(boot_partition, loader_path)  # the path convention is not specified
    entry = pe_load(image)                          # headers, sections, relocations
    status = call entry(image_handle, &table)       # the loader runs, and calls back through the table

shim_exit_boot_services(handle, map_key):
    if map_key != current_map_key: return INVALID_PARAMETER    # the map changed since the loader read it
    stop the shim's console and timer; free the memory of the boot-services data
    keep only the runtime services: the clock and reset are register writes
    return SUCCESS                                 # the loader owns the memory and enters the kernel
```



The loader needs the services table, a PE/COFF image of its own and a machine-type number for the pdp64 that the owners of the UEFI specification would have to assign (unverified, 4.12). The shim is a few services over drivers that already exist; it is not a firmware stack: no PEI, DXE or driver model, no variable store, no setup screen. Nothing is built; this illustrates the size of the job (4.9).

The services named are those OpenBSD's efiboot loaders call (measured, 4.12): 17 (amd64) or 18 (arm64, riscv64) boot and runtime services, count Which of them a given loader needs is for the person who writes the shim to find by reading that loader.

The costs. A shim is not a UEFI firmware stack. The boot review's figure of "hundreds of thousands to millions of lines" for a UEFI firmware (`docs/boot.md`, "Is UEFI worth it?") was never confirmed against a source, describes a full stack such as EDK II, and is not used as the cost of a shim. **No count of the shim's lines is given, because none can be measured here:** no UEFI implementation source is present (the `edk2` and `u-boot` directories under the QEMU tree's `roms/` are empty). Measured are the loaders that would run on it (OpenBSD's `efiboot`: 4,593 lines for amd64, 7,195 for arm64, 4,513 for riscv64) and the 176 lines of header and 124 of relocator above. The costs that remain:

- **A PE/COFF build and a number.** The toolchain emits a PE/COFF image, and a machine-type number must be obtained (unverified).
- **A loader to port** to the pdp64 as any program is, the larger part of the work.
- **A services layer** written, tested and kept in step with the loaders it serves.
- **Code to trust before the kernel.** The shim is open source (4.3.2), runs only at boot and is not resident afterwards except for the clock and reset.
- **A platform description** (a device tree or tables) built from the boot-information block.

It does not cost a closed firmware, a variable store, a setup screen or a second boot path in the machine itself: the machine's own boot stays block 0.

Commentary. **Chain.** PDP-11 and VAX: no firmware services. PC: the BIOS, then UEFI to give one installer a way to boot on any machine offering it. OpenBSD's arm64 and riscv64 ports use UEFI and a device tree, with loaders of 7,195 and 4,513 lines; for amd64 the loaders total 15,440 lines, a BIOS boot block of 862 lines and a second stage of 189 beside the UEFI loader of 4,593 (counted; the total includes `libsa`, 6,319). pdp64: block 0, with the door left open. **Trade-offs.** UEFI firmware would let existing generic loaders run unchanged and offer a standard memory map and a secure-boot chain; it costs a large firmware, adds failure modes (variable storage, drivers, boot-order state), enlarges the attack surface, and still needs a device tree or ACPI to describe the devices. A shim gives the first benefit without the rest, at the price of a services layer and a PE/COFF build. **Benefits.** The pdp64 has one architecture and one platform description, the case UEFI was not built for. **Impact.** *Kernel:* no firmware interface, no memory-map translation in the machine itself; a shim would translate the boot-information block. *Compiler:* no PE/COFF unless a shim is built. *Hardware:* no firmware stack.

4.10 Recovery

What to do when nothing boots. A PDP-11 with a dead disk was not a dead machine: `ODT` let you examine memory and key a bootstrap in (4.1), and V7 shipped `/boot.bu`, a backup of the second stage. The pdp64 keeps the idea and gives it a place.

The ROM that reads block 0 (4.4) also contains a **monitor**, a small program that runs on the serial console when no boot device answers or when a key is held at power-up and offers a few commands: examine and deposit memory and registers, load a program over the serial line, start at an address or from a named device, reset a core, reset the machine. It needs a working serial port and nothing else, so it also brings up a new board before any boot device works.

```
monitor():                                  # the ROM's console program; no interrupts, no memory but the
first pages
    loop:
        print("pdp64> ")
        line = read_line(serial)
        case first word of line:
            "x" addr [n]    : print n words at addr                 # examine (the PDP-11's `addr/`)
            "d" addr value  : store value at addr                   # deposit
            "r" [name value]: print or set a register of the stopped core
            "l"             : read a program from the serial line into memory   # load
            "g" addr        : start core 0 at addr (r0, r1 as in 4.4.3)
            "b" device      : try to boot from this device
            "c" n           : write core n's reset register (4.7.2)
            "z"             : write the root complex's reset register (2.9.4; what else it resets is not
specified)
            otherwise       : print("?")
```

The command letters and the prompt are an illustration. A **watchdog** is a hardware timer that counts down and restarts the machine unless software writes to it ("kicks" it) in time; a hung kernel stops kicking and is restarted. The PDP-11 had none; whether PC firmware offers one is unverified. It needs about ten lines in the kernel. `decisions-pending.md` P7 asks for a bus-controller reset register and a watchdog **in place of** firmware calls, and the monitor's reset command writes that register.

4.10.1 The controller's ROM includes a monitor reached on the serial console when nothing boots: examine and deposit memory and registers, load a program over the serial line, start at an address or from a named device, reset a core, reset the machine. *(P)*


4.10.2 A hardware watchdog restarts the machine if the kernel hangs. *(P)*

Commentary. **Chain.** PDP-11: `ODT`, the front panel and `/boot.bu`. VAX: the console processor (unverified). PC and UEFI: a setup screen and rescue media (unverified). pdp64: a monitor in ROM and a watchdog. **Trade-offs.** A monitor is a few hundred bytes of ROM (an estimate; nothing has been assembled) and needs a serial port. **Benefits.** It is the recovery path that needs the least code. **Impact.** *Kernel:* the way in when nothing boots. *Compiler:* none. *Hardware:* a serial port and the ROM bytes.

4.11 Five boots side by side

The five referents in the author's order, and the pdp64 as the sixth, as the chains of 4.1 and 4.2 and 4.3 to 4.10 give them. A dagger marks a cell that rests on general knowledge, unverified; the last column says which of the five the pdp64 resembles.

five boots and the pdp64: who runs, in what order, and what each stage knows



Sources: a and b read in V7M, 2.11BSD and 4.3BSD-Tahoe; d and e partly read in OpenBSD; c, and the rest of b, d and e, are general knowledge, unverified (4.12).

The pdp64 (f), in one paragraph: the ROM in the controller chip runs on core 0, reads block 0 through a virtio-blk request, checks `0x55AA`, and starts core 0 at it with `r0`, `r1` and `r14` set (4.4); the first stage, in the protective MBR's 446 bytes, reads the blocks on its list (4.5); the second stage reads the GPT, the label and the root file system, fills in the boot-information block and loads `/bsd` (4.6); the kernel enumerates the bus and starts the other cores by register writes (4.7). A proposal and a decision, no code.

Property	(a) PDP-11	(b) VAX	(c) C64	(d) x86 BIOS, MBR	(e) GPT, UEFI	(f) pdp64, and which it resembles
Who runs first	the processor, then the operator's keys or a ROM†	the console processor†	the 6510 from its reset vector†	the processor at `0xFFFFFFF0`†	the same, then the firmware†	the ROM on core 0: like (a) and (b), without the operator
Where the first code lives	front panel or boot ROM	console ROM and storage†	the KERNAL ROM†	firmware flash†	firmware flash†	a ROM in the controller chip: like (a) and (c)
How big the first code may be	a few dozen words (keys)†, a ROM's size†; block 0 of 512 bytes (read)	the boot block; the 750 loaded 7.5 KB next (read)	the ROM's 8 KB†	446 bytes in the MBR (read)	the loader file, any size†	the ROM's size; 446 bytes in block 0: like (d)
How it finds the next stage	block 0 reads a name (`boot`) by walking inodes; `boot` reads `hp(0,0)unix` (read)	the boot block loads sectors 1 to 15; `boot` opens a name (read)	it does not: `LOAD` by the user†	the active flag in the table, then `INT 13h` reads (read)	the boot variables and the GPT's type, then a name on FAT†	a block list in block 0, then the GPT, the label and a name: like (b) and (a)
What the hand-off carries	registers (2.11BSD: `r0`, `r1`, `r3`, a check word) (read)	`r10`, `r11` to `boot` (read)	nothing: the program owns the machine†	registers and the BIOS's memory map†	the memory map and ACPI or a device tree (read)	`r0`, `r1` and the boot-information block: like (a) in registers, like (e) in a description
How it is repaired	keys, `ODT`†, the backup `/boot.bu` (read for the last)	the console†	the ROM cannot be damaged by storage; a cartridge†	re-write the MBR from another disk†	the firmware's setup and boot manager†	the monitor, a core reset, a watchdog (4.10): like (a); a damaged

Property	(a) PDP-11	(b) VAX	(c) C64	(d) x86 BIOS, MBR	(e) GPT, UEFI	(f) pdp64, and which it resembles
						GPT does not stop the first stage (4.5)
What is open source	the BSD and V7 stages (the sources here); ROMs†	the BSD stages (read); the console†	the ROMs are Commodore's†	the loaders, in OpenBSD (read); the BIOS is a vendor's†	the specification is published†; EDK II is BSD-2-Clause-Patent (read, 4.9); shipped firmware often not†	everything, by decision (4.3.2)
How many programs before the kernel	3 (ROM or keys, block 0, `boot`)	3 (console, boot block, `boot`)	1 (ROM) or 2 with a cartridge†	4 (BIOS, `mbr.s`, `biosboot`, `/boot`) (read)	3 or more, with firmware phases†	3 (ROM, block 0, second stage): like (a) and (b)
What recovery exists	`ODT` and the front panel†	the console†	reset, a cartridge†	the BIOS setup, a rescue disk†	the setup, rescue media, a fallback loader name†	the monitor and the watchdog (4.10), the same disk readable by a UEFI route (4.9)

Property by property, the pdp64's boot is the PDP-11's and the VAX's: a ROM, a first block, a second stage that finds a file by name, a hand-off in registers. It takes three things from the PC: the protective MBR and its 446 bytes (d), the GPT (e), and, in the boot-information block, a description of the machine (e) that the PDP-11 and the VAX did not pass. From the C64 it takes the ROM as the first code, undamaged by what is on storage; the C64 had no second stage. It differs from all five in that every stage is open source and no stage calls firmware after the ROM.

4.12 What was checked, and what was not

The rule of the project is: check, do not guess. The handbooks and specifications are not on this machine. What each fact rests on:

- **Unix sources** (`/home/david/claude/facetlang/unixtree`, files are gzipped): V7M `sys/mdec/hpuboot.s` (285 lines), `sys/sas/boot.c` (272 lines), the `boot(8)` page, `sas/htboot.s` (the M9312 comment), `dev/hp.c` (24 entries); V7 `usr/sys/dev/hp.c` (`hp_sizes[8]`, "cyl 44 thru 429"); 2.11BSD's `boot(8)` page, `sys/mdec/hpuboot.s` (the 512 and 494 bytes), `sys/pdpstand/srt0.s` (`r0`, `r1`, `r3`) and `boot.c` (`checkword`), `sys/h/disklabel.h`; 4.3BSD-Tahoe `h/disklabel.h` (the block 0 or 1 comment, `0x82564557`, 8 partitions), `mdec/raboot.c` (registers, 7.5 KB, `0x50000`, `BOOTLAST`), `vaxstand/boot.c` (`r10`, `r11`, `Boot, :`), `vaxstand/saio.h` (the default name), `vax/rpb.h`; 4.3BSD `vaxmba/hp.c` (size tables); OpenBSD 4.6 `sparc/stand/installboot/installboot.8`.
- **OpenBSD** (`/home/david/claude/kernel-src/openbsd`, commit `2114d7b7`): `sys/sys/disklabel.h` (`DOSPARTOFF` 446, the signature at `0x1fe`, type `0xee`, "EFI PART", `gpt_header`, `gpt_partition`, `NGPTPARTITIONS` 128, `GPTMINPARTSIZE` 128, `GPTPARTNAMESIZE` 36, `MAXPARTITIONS16`, `d_secperunith`, both GUIDs); the `arch/*/include/disklabel.h` label sectors; `arch/amd64/stand` (`mbr.S` 521 lines, `biosboot.S` 862 and `biosboot.8` ("roughly 512 bytes of code", the `installboot` patching, "its inode may change"), `boot/` 189, `libsa` 6,319, `efiboot` 4,593, 15,440 in all); `arch/arm64/stand/efiboot` (7,195 lines, `start.S` 176, `self_reloc.c` 124) and riscv64 (4,513); the service counts; the `ExitBootServices` retry.
- **Linux** (`/home/david/claude/kernel-src/linux`, `7be4bc52`), re-counted: `smpboot.c` 1,528 lines, `arch/x86/realmode` 1,258 (`.c`, `.h`, `.S`), PSCI 124, spin table 127, RISC-V SBI start 108 and spin 58.
- **EDK II:** the licence in `qemu-src/pc-bios/edk2-licenses.txt` and `/usr/share/doc/ovmf/copyright`; the x86-64 code image 3,653,632 bytes uncompressed; the `secboot` image names in `/usr/share/OVMF`; no source in `roms/edk2`.
- **The repository:** the statements of this chapter against `docs/errata.md` (47, 48, 50, 51, 95, 101, 102, 103, 109, 110), `docs/boot.md`, `docs/decisions-pending.md` (B2 and R2, P7, F10), chapters 2, 5, 6 and 7 (2.3.6, 2.4, 2.6.3, 2.9.4, 5.6.2, 6.12, 7.4.2, 7.6, 7.8), and the author's messages of 2026-10-22 in `docs/decision-log` (threads 1889, messages 2614, 2620, 2631).
- **Unverified** (general knowledge): the front panel's switches and keys and the bootstrap loader of a few words; that the M9312 held one ROM program per device; what `ODT` does and its name; the date of the IBM PC and the 8086; the BIOS's four jobs and its other services; real mode and the 1 MB limit; the reset vector `0xFFFFFFF0`, the load address `0x7C00` and the boot-device order; the whole Commodore 64 boot (`0xFFFC`, KERNAL, `CBM80` at `0x8000`, BASIC, datasette, 1541); the VAX console processor, VMB and that the console started other processors; the Alpha's hardware restart parameter block; the UEFI boot manager, NVRAM variables and Secure Boot; that the UEFI specification requires

PE32+ images and FAT on the system partition, and that a machine-type code would be assigned by its owners; the publication terms of the UEFI specification; `request_firmware` and `firmload(9)`; that Linux and NetBSD loaders do what OpenBSD's does; whether PC firmware has a watchdog; that the PC learned the video lesson of 4.6.4 "the hard way".

- **Decided by the author and recorded in `errata.md`:** everything stated as a decision with a tag *(D)*; the pseudocode of this chapter is an illustration, and nothing in it is a decision. The author's 2026-11-10 words are quoted from errata 109 and 110, which are not in the decision log.

4.13 Still open

Decisions the author has asked for, or that follow from the author's, and that are not made: (a) the address block 0 is loaded to (0x1000 is the example; errata 102(a)) and how many pages "the first few" are; (b) how the first stage reads blocks: a small reader of its own in 446 bytes, a routine the ROM leaves, or a larger first stage loaded by the ROM (4.5); (c) how the ROM finds and maps the boot device's windows before any software has (4.4); (d) who fills which fields of the boot-information block, the ROM, the second stage or both (4.4, 4.6), and its layout, order and widths (4.6.3); (e) the partition type of the boot partition, and whether a dedicated boot partition is needed, since the block list can point at the second-stage file in the root file system or at the 8 KB boot area (4.5); (f) the device-tree option: whether the boot-information block is replaced or accompanied by a device tree if the OpenBSD arm64 and riscv64 drivers are reused (4.6); (g) the registers of the core start block, whether a started core begins with translation off, and the difference between 4.7.1 (`r0` and `r1`) and 7.8.1 (`r0`) (4.7); (h) how a virtio device is given firmware, and whether the `INIT` and `READY` words of 4.8.1 are restated over virtio (4.8); (i) the order of the other boot media after the virtio-blk disk (F10); (j) the monitor's commands, the serial speed and what is kept in non-volatile memory (boot order, serial speed: `boot.md`); (k) the shim: the path of the loader it runs, the services it offers, the machine-type number (4.9), none to be settled until someone wants one.

Facts still to check against their own documents: the PDP-11 power-up behaviour, the M9312 boot ROMs and `ODT`; the VAX console, VMB and the Alpha boot protocols; the C64 boot; the x86 reset vector and START-UP rules; PSCI, the SBI hart calls and the spin table as specified; what the UEFI specification requires of a loader and of firmware, including the machine-type registry; the size of a UEFI services layer, which only an implementation could give.

Chapter 5 — The device driver model

A driver on the pdp64 is an ordinary program that finds a device by its identifiers, agrees features with it, gives it queues in memory, hands it requests as chains of descriptors and learns from the used ring that they are done, by an interrupt or by polling; because every standard device speaks virtio, one transport routine serves the disk, the network card, the display and the sound device, and each has a thin class driver on top. The form of the console, the timer and the entropy source is not specified (5.7).

This chapter is written for a reader who has written or read a driver for V6, V7 or 2.11BSD Unix (a `strategy` routine, a `struct buf`, the CSR of an RK11, an interrupt vector pair), or who is learning computing from the start, and who has not met virtio, PCI Express, MSI-X, a driver that attaches by matching identifiers, or a machine description that is not compiled into the kernel. It runs from what that reader knows to what the pdp64 does: the PDP-11 driver (5.1), the systems between (5.2), what a driver is now (5.3), the interface it programs (5.4), its life (5.5), the disk (5.6), the console, timer and entropy source (5.7), the network, display, sound and USB drivers (5.8), interrupts (5.9), the memory a device reaches (5.10), errors (5.11), firmware (5.12), where drivers run and how they are written in C (5.13) and how one is tested (5.14). The bus, the virtio structures and the MSI-X table are chapter 2; this chapter uses them and does not repeat them. Tags: *(D)* decided; *(P)* proposed; *(S)* unspecified. A fact about an older or another machine is marked **(read)** when it was read in a source on this computer, **(repo)** when it comes from the repository's documents, and *unverified* when it is general knowledge that could not be checked here; 5.15 lists what was checked.

How to read this chapter. A term is defined where it first appears, as the technical word followed by a plain restatement. Boxes-and-arrows pictures are the kind a textbook draws for a linked list: a box is a piece of memory or a program, an arrow says what is handed on. Code blocks are C-like pseudocode (`#` starts a comment, `mmio_read32(address)` and the like are ordinary loads and stores to a device register) unless the text says they are V7 or 2.11BSD C, quoted from the sources on this computer. **No pdp64 driver has been written**: every pdp64 listing in this chapter is an illustration, and so is untested, except where it names a test that exists (5.14). The decisions are the numbered statements; where the repository does not say, the text says *not specified*.

5.1 What you already know: a PDP-11 driver

A **driver** (the part of the kernel that knows how to operate one kind of device, and nothing else) in V7 or 2.11BSD has four parts: a structure laid over the device's registers, entry points listed in a table, an interrupt routine, and a way of being found and started. The disk driver `rk.c` has all four (135 lines in V7, 204 in 2.11BSD, counted), and the console driver is a second example.

The registers. V7's `rk.c` begins with `#define RKADDR ((struct device *)0177400)` and declares the structure `struct device { int rkds; int rker; int rkcs; int rkwc; caddr_t rkba; int rkda; }`: six words at a fixed address, which chapter 2 (2.1) explains and draws. The driver reads and writes the fields. In the control and status register (the **CSR**, one word whose bits both command the device and report on it) the bits it needs are GO (01), IDE (interrupt on done enable, 0100), RDY (0200) and ERR (0100000) (2.11BSD `rkreg.h`).

The device switch. The kernel does not know drivers by name. Two arrays, `bdevsw` for block devices and `cdevsw` for character devices, hold one row of function pointers per driver, and the **major device number** (one half of a device number; the other half, the **minor number**, selects a unit within the driver) picks the row. In 2.11BSD's `pdp/conf.c` the RK05 is row 6 of `bdevsw` and row 15 of `cdevsw`:

```
/* bdevsw: open, close, strategy, root, size, flags */
/* rk = 6 */    rkopen,  rkclose,  rkstrategy,  nulldev,  rksize,  0,
/* cdevsw: open, close, read, write, ioctl, stop, ttys, select, strategy */
/* rk = 15 */   rkopen, rkclose, rawrw, rawrw, nodev, nulldev, 0, seltrue, rkstrategy,
```

A disk has both rows. Through the block row the kernel reads and writes 512-byte blocks by way of its **buffer cache** (disk blocks kept in memory), and through the character row `rawrw` reaches the same `rkstrategy` for the **raw** interface, which moves data between the disk and a user's memory without the cache.

The strategy, start and interrupt routines. A block driver is three routines around a queue. This is V7's `rk.c` with the disk-statistics lines left out:

```
rkstrategy(bp)  register struct buf *bp;
{
        /* give the device an address it can use */
        if(bp->b_flags&B_PHYS)  mapalloc(bp);
        if (bp->b_blkno >= NRKBLK) { bp->b_flags |= B_ERROR; iodone(bp); return; }
        bp->av_forw = (struct buf *)NULL;
        /* keep rkintr out while the queue changes */
        spl5();
        if(rktab.b_actf == NULL) rktab.b_actf = bp; else rktab.b_actl->av_forw = bp;
        rktab.b_actl = bp;
        /* the device is idle: start it */
        if(rktab.b_active == NULL) rkstart();
        spl0();
}
rkstart()
{
        if ((bp = rktab.b_actf) == NULL) return;
        rktab.b_active++;
        bn = bp->b_blkno;  dn = minor(bp->b_dev);  cn = bn/12;  sn = bn%12;
        RKADDR->rkda = (dn<<13) | (cn<<4) | sn;          /* disk address     */
        RKADDR->rkba = bp->b_un.b_addr;                  /* memory address   */
        RKADDR->rkwc = -(bp->b_bcount>>1);               /* words, negative  */
        com = ((bp->b_xmem&3) << 4) | IENABLE | GO;
        if(bp->b_flags & B_READ) com |= RCOM; else com |= WCOM;
        /* go; the interrupt comes when done */
        RKADDR->rkcs = com;
}
rkintr()
{
        if (rktab.b_active == NULL) return;
        bp = rktab.b_actf;  rktab.b_active = NULL;
        if (RKADDR->rkcs < 0) {                          /* the error bit */
                deverror(bp, RKADDR->rker, RKADDR->rkds);
                RKADDR->rkcs = RESET|GO;
                while((RKADDR->rkcs&CTLRDY) == 0) ;
                /* retry up to ten times */
                if (++rktab.b_errcnt <= 10) { rkstart(); return; }
                bp->b_flags |= B_ERROR;
        }
        rktab.b_errcnt = 0;
        rktab.b_actf = bp->av_forw;
        /* wake whoever sleeps on this buffer */
        iodone(bp);
        rkstart();                                       /* the next request */
}
```

The **buffer header** `struct buf` is the kernel's record of one transfer: the device (`b_dev`), the block number (`b_blkno`), the byte count (`b_bcount`), the memory address (`b_un.b_addr`, with `b_xmem` for the bits above 16), flags such as `B_READ` and `B_ERROR`, and a link (`av_forw`) that chains it onto the driver's queue (`buf.h`). The strategy routine is called by the file system or by `physio`, one buffer at a time. Because the controller does one transfer at a time, the queue of waiting requests lives in the kernel's memory, and `rkstart` feeds the hardware from it. `spl5()` is one of the **spl** functions (set priority level: they write the priority bits of the processor status word); while the priority is 5, an interrupt of level 5 or lower waits, so `rkintr` cannot run between the test of the queue and its change. 2.11BSD writes `s = splbio(); ... splx(s)`, which restores the previous level and does not drop to 0, and `splx` writes the low byte of the status word at `0177776` (`rk.c`, `machparam.h`, read).

The interrupt vector. A device that finishes asserts a **bus request** line, BR4 to BR7 (the RK11 uses BR5); when the processor's priority is lower, it takes the interrupt, and the device supplies a **vector**, a number set by switches on the card

that is the address of two words in low memory: a new program counter and a new status word. The processor pushes the old pair on the stack and loads the new one (6.3 gives the pdp64's version). 2.11BSD's `pdp/scb.s` fills the pair for the RK11 with `DEVTRAP(220, rkintr, br5)`: at address 0220, the address of `rkintr` and priority 5. The routine ends with `RTI`, return from interrupt.

INIT and READY. A device is put in a known state by a command and a wait. `rkintr` above writes `RESET|GO` to the CSR and spins until `CTLRDY` (the RDY bit) comes back; `rkprobe` writes `DRESET|GO`; the RX02 floppy controller has a bit named `RX_INIT`, "initialize" (`rxreg.h`, read). All the work happens behind the register, in the device's own logic: the driver writes one bit and waits for another. Chapter 4 (4.8, statement 4.8.1) keeps this as the PDP-11 way of starting a device, and 5.5 shows what it becomes.

Character devices and the clist. A terminal is read and written a byte at a time, and the kernel shares the work with the **line discipline** (the kernel code that edits the input line and echoes it, so that no driver does). 2.11BSD's console driver for the KL11 serial line (`pdp/cons.c`, 196 lines) is five small routines: the receive interrupt `cnrint` reads the data buffer register and passes the byte up with `(*linesw[tp->t_line].l_rint)(c, tp)`; `cnstart` takes the next byte from the terminal's output queue with `getc(&tp->t_outq)`, writes it to the transmit buffer when the transmitter is ready (`DLXCSR_TRDY`) and marks the line busy; the transmit interrupt `cnxint` clears the busy mark and calls the line discipline's `l_start`, which calls `cnstart` again. The queues are **clists** (character lists: chains of small blocks of `CBSIZE` bytes taken from one free list; `getc` returns -1 when the list is empty). The console is at `0177560` and interrupts at vectors 060 and 064, both BR4; the line clock KW11-L is at vector 0100, BR6, and runs `hardclock` (`scb.s`).

Being found. In V7 nothing finds a device: `conf.c` and the vector table `l.s` are written by hand. 2.11BSD added `autoconfig(8)`, a user program that "needs the ucall() system call and special kernel to work" (`autoconfig/main.c`): it reads `/etc/dtab`, calls the driver's **probe** routine for each line (`rkprobe` writes the CSR to make the controller raise an interrupt and returns `ACP_IFINTR`, "exists if the interrupt arrives"), patches the interrupt vector, and calls the driver's **attach** routine (`rkattach(addr, unit)` stores the controller's address in `RKADDR`).

Moving data: `physio` and map registers. A raw read or write goes through `physio`, which builds a buffer header that points into the user's memory: it turns the user's virtual address into a physical one from the user's segment registers, locks the process in memory (`SLOCK`), calls the strategy routine and sleeps until `B_DONE` (`vm_swp.c`, read). It translates only the first address and passes the whole length, so it assumes that the buffer is one contiguous run of physical memory. The Unibus carries 18 address bits, so a device cannot name all of a larger memory; the **map registers** (table entries that translate a device's address to a memory address) at `0170200` do (`h/uba.h`), and `mapalloc(bp)` of `rkstrategy` allocates registers for a raw transfer and rewrites the buffer's address into one the device can use (`pdp/machdep.c`, read).

The Q-bus. The PDP-11's second bus, the Q-bus, carries the same programming model: registers in an I/O page, vectors, BR levels (that the Q-bus served the lower-cost PDP-11s such as the 11/23 is *unverified* here; no source on this computer describes it). What reaches a driver is the address width. 2.11BSD supports "22-bit q-bus systems" (`MAXCLICK_22`, "22 bit QBUS", `pdp/machdep2.c`), where memory is larger than an 18-bit controller can name. A controller built for the 18-bit Unibus, such as the RK11, then cannot reach a buffer above 256 KB, and `rkstrategy` calls `sofub_alloc(bp)`: a **soft Unibus map** that copies the data through a bounce buffer below 256 KB with `copyv`, and `sofub_relse` copies back (`pdp/machdep.c`, `rk.c`, read). `rl.c` notes that third-party 18-bit RL controllers work this way on a Q-bus and that the DEC RLV11 "does not properly monitor the I/O page signal", so it cannot (read). The drivers, the registers and the vectors were the same on both buses; the DMA address was the part that differed (5.10).

What the PDP-11 driver did not have. The driver is told what is there; the device is not asked. A device does one command at a time. The register set is the device's own, so a new kind of device is a new set of bits to learn. The interrupt vector and its level are set by hand. No device needed a program loaded into it before it worked (4.1). The pdp64's drivers change each of these, and 5.3 starts from this list.

5.2 What came between: the VAX, PCI, virtio and OpenBSD

The author's own statements about drivers name few referents. He said, of the eight-register devices, that drivers "should be trivially small" (errata 49, since withdrawn with the eight-register model by errata 95); he asked for "a standard audio/video interface so there is no bullshit with supporting a bunch of device drivers, although as a pcie bus any device MAY be attached and supported" (errata 78); and he chose virtio: "yeah, virtio is fine" (errata 79), "forget the native 8 register devices. gone. virtio across the board" (errata 95), "disk is virtio-blk" (errata 101). OpenBSD is the first operating system

(errata 41). On 2026-11-09 he also wrote that "we will support all the virtio devices in silicon (the ones it makes sense to support, that is)" and asked what "syntactic sugar" (not new opcodes) could make devices easier to use "like the 12 register + dma thing" (message 592:13); which virtio devices make sense, and the sugar, are not answered in the repository (5.16). No other system is named in his messages on drivers (the decision log was searched); `docs/decisions-and-status.md`, the ledger, agrees with this list: its subjects for devices are DONE for the virtio-net, virtio-gpu and virtio-snd standard and for USB and NVMe as the modern I/O hardware, and it still shows the virtio-only chapter rewrite as TO DO, which this chapter and chapter 2 now are. The VAX, PCI and the intermediate OpenBSD interfaces below are the assistant's steps, from the sources read.

step	what it contributed to drivers	basis
PDP-11, V6 to 2.11BSD	register structure, device switch, strategy/start/interrupt, `spl`, `INIT`/`READY`, probe and attach (2.11BSD), map registers	read (5.1)
PDP-11 on the Q-bus	the same drivers and registers; 22-bit memory, so an 18-bit controller needs a bounce buffer (the soft Unibus map)	read (5.1); which models *unverified*
VAX, 4.3BSD	`config(8)` turns a text file into the device tables (`ioconf.c`); a driver is one table of probe, slave, attach and start routines (`struct uba_driver`); the kernel scans the adapter and calls the probe where something answers; `ubalLoc` hands out map registers; `ubareset` calls every driver's reset routine	read
PCI	a function names itself by vendor and device number, so a driver's probe tests numbers and pokes no address; windows are placed by software	structure read in OpenBSD; history *unverified*
PCI Express, MSI-X	an interrupt is a memory write, so each queue can have its own vector; a bus-mastering device reads and writes memory by itself	chapter 2 (2.5, 2.7)
virtio	one transport and one queue structure for every class of device; a class driver is only the request format; features are agreed at start	`virtio_*.h`, QEMU, OpenBSD `vioblk.c` (read)
OpenBSD, the pdp64's first system	a softc and a `cfattach` of `match` and `attach`; DMA through `bus_dma` maps with explicit syncs; the interrupt priority survives as `IPL_BIO`; `bdevsw` and its strategy routine survive; a virtio disk appears as a SCSI adapter under `sd(4)`	read (5.13)
pdp64	virtio across the board; found by enumeration; MSI-X; uncached buffers and no cache syncs; an IOMMU when it exists	errata 79, 85, 95, 101

The VAX's `config(8)` and `uba_driver` are in `etc/config/mkioconf.c` and `sys/vaxuba/ubavar.h` of the 4.3BSD tree; the kernel's scan (`unifind` in `sys/vax/autoconf.c`) calls `(*udp->ud_probe)` where `badaddr` finds a device. `ubareset` (`vaxuba/uba.c`) "generate[s] a reset on uba number uban" and then calls `(*cdp->d_reset)(uban)` for every row of the character device table, so that each driver re-issues what was pending.

5.3 What a driver is on the pdp64

The pdp64 changes the four parts of 5.1 in turn. The register structure is a PCI Express function whose windows hold the virtio structures instead of the device's own registers (statements 5.3.2 to 5.3.5, and 5.4). The device switch row is the OpenBSD driver's own interface (5.13). The vector and the level are a message that the device writes (5.9). The probe and attach are an identifier match and a handshake (5.5). Figure 5.1 draws the two side by side.


5.3.1 Every standard device is a virtio device or a USB (xHCI) controller; the disk, network, graphics and audio devices are virtio-blk, virtio-net, virtio-gpu (2D) and virtio-snd, over the virtio PCI Express transport, so that one transport driver and a thin class driver per device serve the system and the same devices run in QEMU, `sim64` and the FPGA. *(D)* Any other PCI Express device, an NVMe controller for example, may be attached with its own driver; it is not a standard device. *(D)* (Neither QEMU's pdp64 machine nor `sim64` has a virtio device yet: 5.14.)

5.3.2 A device is a PCI Express function whose windows (the regions its base-address registers describe) a driver maps with the device memory type, strongly ordered. *(D for the memory types; P for windows that start on page boundaries and are whole pages)*

5.3.3 A driver reaches a register with an ordinary load or store; there are no input or output instructions and no port space. *(D)*

5.3.4 Registers are naturally aligned and accessed at their own width; the machine is little-endian throughout and the virtio structures are little-endian, so a driver has no byte-order or byte-lane cases. *(D)*

5.3.5 Accesses to a device page happen in program order; one `FENCE` separates the last write to memory the device will read from the write that notifies the device. *(D)*



What a driver was told on the PDP-11 (the address, the vector, the level) it asks or reads on the pdp64; what it knew (the register bits) it negotiates.
Sources: V7 rk.c, 2.11BSD rkreg.h, pdp/conf.c, pdp/scb.s (read); virtio_pci.h, OpenBSD vioblk.c (read); chapter 2.

Commentary. **Chain.** PDP-11: a structure laid over fixed addresses (`RKADDR` at `0177400`), so that the register is a field and the driver needs no accessor. VAX: the same structure at an address the kernel found by scanning the adapter, plus map registers and data paths to manage. PCI and PCI Express: the registers are in windows that software placed, so the address is a value the kernel hands the driver; Linux and BSD wrap every access in an accessor (`readl`, `bus_space_read_8`) to hide port-or-memory differences and byte order (*unverified* for the names; OpenBSD's `virtio_read_device_config_4` and `_8` are read in `vioblk.c`). pdp64: ordinary loads and stores through a pointer to a structure, because the machine has no port space and one byte order, so the accessor is a load or a store. The assistant's reasoning from this: the register's address is a virtual address the kernel maps, so the driver is position-independent, which `RKADDR` at `0177400` was not. **Trade-offs.** A window of whole pages wastes address space and no memory, and lets the kernel give one device to one protection domain. Taking virtio rather than a design of the pdp64's own gives up the freedom to shape the registers and gains every driver and every emulated device that already exists. **Impact.** *Kernel:* one transport driver and a thin driver per class; no accessor layer. *Compiler:* register access is a `volatile` load or store of the register's width through a pointer to a structure (5.13). *Hardware:* a device window is decoded by page address; the devices are standard PCI Express functions.

5.4 The interface a driver programs: structures, queues and features

Chapter 2 explains the structures (2.6.2 to 2.6.9) and gives pseudocode for the handshake (`init_device`), the queue set-up (`setup_queue`), posting and reaping (`post`, `reap`). This section keeps the decisions as the driver writer needs them.

5.4.1 The driver finds a virtio device's structures through the capabilities in its configuration space: the common configuration, the notification area, the interrupt status and the device-specific configuration, each at an offset in one of the device's windows. *(D)* The common configuration has these fields, as the virtio specification lays them out (the offsets are those of `struct virtio_pci_common_cfg` in the Linux header `virtio_pci.h`, read; the header spells the driver's feature fields `guest_feature_select` and `guest_feature`, the interrupt-vector field of the device `msix_config`, and each queue address as a `_lo` and a `_hi` word):

Offset	Field	Meaning
`0x00`	`device_feature_select`	which 32 bits of the device's features `device_feature` shows
`0x04`	`device_feature`	the device's feature bits (read-only)
`0x08`	`driver_feature_select`	which 32 bits of the driver's features `driver_feature` sets

Offset	Field	Meaning
0x0C	driver_feature	the features the driver accepts
0x10	msix_config	the interrupt vector for a change of configuration
0x12	num_queues	how many queues the device has (read-only)
0x14	device_status	the handshake bits; writing zero resets the device
0x15	config_generation	changes when the device-specific configuration changes
0x16	queue_select	which queue the next fields describe
0x18	queue_size	the number of entries of the selected queue
0x1A	queue_msix_vector	the interrupt vector of the selected queue
0x1C	queue_enable	the driver sets it to 1 to start the queue
0x1E	queue_notify_off	where, in the notification area, the driver notifies this queue
0x20	queue_desc	physical address of the descriptor table
0x28	queue_driver	physical address of the available ring
0x30	queue_device	physical address of the used ring

5.4.2 A transfer is a chain of descriptors in a queue (a virtqueue) in host memory. A descriptor is 16 bytes: a 64-bit buffer address, a 32-bit length, 16 bits of flags (NEXT: the chain continues; WRITE: the device writes the buffer; INDIRECT: the buffer is a table of descriptors) and a 16-bit index of the next descriptor. *(D)*

5.4.3 The driver puts the head of a chain in the available ring and advances its index, executes FENCE, and writes the queue's notification address; the device carries the chain out and writes the head and the byte count in the used ring, advances the used index, and may interrupt. Progress is therefore in memory, not in the device. *(D)*

5.4.4 The driver and device agree on features before any queue runs: the driver reads the device's features, writes the subset it accepts, and the device confirms it; the version-1 feature is required. *(D)* The feature subset that the pdp64 accepts for each device, and the platform-ordering feature that the pdp64 must declare, are not specified. *(S)*

5.4.5 A device that carries traffic in two directions (a network card) has one queue for each direction in the one device; a console-like device is the same pattern. *(D)*

Commentary. **Chain.** PDP-11: the command is the register values; one is in flight, and the completion is the interrupt or the RDY bit. VAX and PCI: the same, with the DEUNA Ethernet controller of 4.3BSD (four registers, `dereg.h`) as the exception, whose transmit and receive **rings** (circular arrays of entries in memory, each with an ownership bit) let the driver queue many frames; its `if_de.c` is where the ring appears in the sources read. virtio: the ring becomes the standard, with the done mark in a second ring (the used ring) and not in the descriptor, and the control registers shrink to a handshake. pdp64: the standard as it is, on a PCI Express function. **Modern comparables** (*unverified*, general knowledge): NVMe's submission and completion queues, the descriptor-done bit of Intel Ethernet controllers and the command lists of SATA controllers are all rings with a done mark, so a virtqueue is the common shape and not a novelty. **Trade-offs.** A queue per direction keeps each ring in order and simple; the used ring costs one write per chain. The pdp64 does not control the standard, and a feature or a field it dislikes stays. **Impact.** *Kernel:* one transport driver and a thin driver per class. *Compiler:* the descriptor is a 16-byte structure with natural alignment (no padding is needed: `8 + 4 + 2 + 2` bytes), and register offsets are named constants. *Hardware:* the interface is the specification's, so a standard device works.

5.5 The life of a driver: probe, attach, run, fail, detach

The five steps are the PDP-11's, in the order autoconfiguration calls them, with the bus doing the finding.

5.5.1 *Probe.* The kernel enumerates the bus (section 2.4), reads each function's identifiers, and matches the virtio device type (or the USB class) against the drivers it has. *(D)*

5.5.2 *Attach.* The driver resets the device (zero to `device_status`), sets the acknowledge and driver bits, negotiates features, sets the features-ok bit and reads it back, sets up each queue (its size and the three addresses, then `queue_enable`), and sets the driver-ok bit. *(D)*

5.5.3 *Run.* The driver puts the queue in uncached memory, fills descriptors, publishes the chain in the available ring, executes FENCE, and notifies the queue; a chain is complete when it appears in the used ring, which the driver sees by polling or by the interrupt. *(D)*

5.5.4 *Fail.* A device that sets its needs-reset bit, or that stops answering, is reset and its queues reprogrammed, and the driver resubmits the chains that are not in the used ring. *(P for the resubmission rule; D for the reset)*

5.5.5 *Detach.* A departure event, or a bus fault from an absent device, tells the driver to stop; it reads, saves, resends or fails the chains still queued. *(P)*

`INIT` and `READY`, and the status handshake. The PDP-11's start of a device (5.1) is one command and one wait: write `INIT` (or `RESET|GO`), spin until `READY`. Statement 4.8.1 *(P)* says the same for the pdp64 in the words of that time, "written when devices were eight registers". The virtio `device_status` byte is that idea spread over steps: writing zero resets the device (the `INIT`), and the driver then sets `ACKNOWLEDGE`, `DRIVER`, `FEATURES_OK` and `DRIVER_OK`, each meaning "I have got this far", reading `FEATURES_OK` back to learn whether the device accepts the features chosen (the `READY` answer, now with a refusal possible; 2.6.3). The assistant's reasoning: the step that is new is the negotiation, which the one-bit form could not carry because the PDP-11 device had nothing to negotiate. The ledger lists the device-initialisation protocol as IN THE AIR (no standing decision; PCI Express supplies its own reset and init, errata 80); the handshake follows from "virtio across the board" (errata 95) and is the form this chapter and 4.8 use.

Probe and attach for a virtio-blk driver, written over the helpers of chapter 2 (`find_virtio_structures`, `init_device`, `setup_queue`); the names are the assistant's, an illustration:

```
# 5.5.1: called for every function the bus walk found
vioblk_match(fn):
    # 0x1040 + device type 2 (2.6.2)
    return fn.vendor == 0x1AF4 and fn.device == 0x1042

vioblk_attach(fn):                              # 5.5.2
    # 2.6.2: where the common configuration, notify, status, device config are
    find_virtio_structures(fn)
    # 2.6.3: reset, ACKNOWLEDGE, DRIVER, features, FEATURES_OK, queue 0, DRIVER_OK
    init_device(fn)
    # virtio_blk_config.capacity, in 512-byte sectors (virtio_blk.h)
    capacity = mmio_read64(device_config + 0)
    # the block driver's row of bdevsw, 5.13
    register_disk(fn, capacity, vioblk_strategy)
```

OpenBSD's `vioblk_match` is the same test, on the device number alone (`va->va_devid == PCI_PRODUCT_VIRTIO_BLOCK`, with the vendor tested one level down in `virtio_pci_match`), and its `vioblk_attach` asks for the features `RO`, `NOTIFY_ON_EMPTY`, `SIZE_MAX`, `SEG_MAX` and `FLUSH`, reads the capacity, allocates the queue with `virtio_alloc_vq` and registers its completion routine in `vq_done` (read, `vioblk.c`). What differs from the PDP-11's `rkattach`: the driver is not told an address, there is a negotiation, and every step can fail with a defined status.


Commentary. **Chain.** PDP-11: V7 has no probe; 2.11BSD's `rkprobe` pokes an address and `rkattach` stores it. VAX: `ud_probe` and `ud_attach` in a table, called by the kernel's scan. PCI: the identifier match replaces the poke, and BSD's autoconfiguration calls `match` then `attach`; OpenBSD's `cfattach` for `vioblk` is `{ sizeof(softc), vioblk_match, vioblk_attach, NULL }`, so it has **no detach routine** (read). Linux's driver model has `probe` and `remove` (*unverified*). PCI returns all ones for a read of a removed device (*unverified*), which, as the assistant reasons, is why a pdp64 driver that finds all ones cannot tell a departed device from a register that holds them, and why the pdp64 faults instead (2.4.5). pdp64: probe by identifier, attach by the status handshake, and a defined detach path because the bus reports departures (2.4.4 to 2.4.6). The probe reads the bus and not a configuration file, so a new device needs no line in `dtab` or `ioconf.c`. **Trade-offs.** The five steps are the same for every device, so the work that differs is the personality: what the requests mean. A detach path that no BSD virtio driver has is new work. **Impact.** *Kernel:* the steps are the same for every driver, so only the requests differ. *Compiler:* none. *Hardware:* none beyond the device's own.

5.6 The block path: virtio-blk

5.6.1 Storage is virtio-blk: a virtqueue of requests, each a header (read, write or flush, and the sector), the data buffers and a status byte, the device marking the request done in the used ring. *(D)* An NVMe controller, which keeps a submission queue and a completion queue in host memory with a doorbell register for each (the shape of the virtqueue with a different command encoding), may be attached as any PCI Express device may; it is not the standard disk. *(D)*

5.6.2 The **disk** is virtio-blk (the author's decision of 2026-11-10, errata 101) with read, write and flush at 512-byte sectors. *(D)* The boot ROM reads block 0 with one read request on the device's queue (4.4). *(P)*

The request is the three-descriptor chain of chapter 2 (2.6.5, with its figure): a header the device reads (type 0 read, 1 write, 4 flush, the priority and the sector), the data buffer (device-writable for a read) and one status byte the device writes (0 OK, 1 I/O error, 2 unsupported; `virtio_blk.h`, read). Figure 5.2 follows one request through the driver, the rings and the device.



Sizes and flags as in chapter 2 (2.6.5 to 2.6.7) and virtio_blk.h; the numbers 12 and 513 are an example. The data is written before the used entry before the used idx

The strategy, start and interrupt routines of 5.1 become the following, a block driver written as an illustration over the `post` and `reap` of chapter 2 (2.6.7). The queue of waiting requests is still the kernel's, but the hardware now takes up to `queue_size` chains at once, so `start` fills the ring until it is full, not until the controller is busy:

```
# called one buf at a time, as rkstrategy is
vioblk_strategy(bp):
    s = splbio()                                # IPL_BIO in OpenBSD (5.9)
    append bp to queue
    vioblk_start()
    splx(s)


vioblk_start():
    while queue not empty and free_descriptors() >= 3:
        bp = take head of queue
        h = alloc_hdr();  h.type = (bp.flags & B_READ) ? 0 : 1
        h.ioprio = 0;  h.sector = bp.blkno
        s = alloc_status_byte()
        d0 = get_free(); d1 = get_free(); d2 = get_free()
        desc[d0] = { addr: h,         len: 16,         flags: NEXT,         next: d1 }
        wr = (bp.flags & B_READ) ? WRITE : 0       # the device writes the buffer on a read
        desc[d1] = { addr: bp.addr, len: bp.bcount, flags: NEXT | wr, next: d2 }
        desc[d2] = { addr: s,         len: 1,          flags: WRITE,        next: 0 }
        inflight[d0] = bp
        post(q, d0)                             # FENCE, then the doorbell (5.3.5)

vioblk_intr():                                  # the queue's vector, at IPL_BIO
    # reap(q), with the buf completed as rkintr completes it
    while last_used != used.idx:
        e = used.ring[last_used mod n];  bp = inflight[e.id]
        if status_byte(e.id) != 0: bp.flags |= B_ERROR
        free_chain(e.id);  last_used += 1
        iodone(bp)                              # wake the sleeper, as in 5.1
    vioblk_start()                              # slots are free again: send more
```

The routine that polls, which the boot ROM and a crash dump use because they run with no interrupt set up, differs only in who waits (chapter 2, 2.6.8, gives the polled loops side by side):

	RK11, interrupt style (5.1)	virtio-blk, interrupt style (above)	virtio-blk, polled (the boot ROM)
strategy	queue the buf; start if idle	queue the buf; fill the ring	`blk_read` (2.6.7): set `NO_INTERRUPT` in `avail.flags`
start	four register writes, GO	`post(q, d0)`: one doorbell write	`post(q, d0)`
completion	`rkintr`: ERR? retry up to 10 times; `iodone`; start the next	`vioblk_intr`: status byte, `B_ERROR`, `iodone`, start more	spin while `last_used == used.idx`; read the status byte of `d2`
in flight	one transfer	up to `queue_size` transfers	up to `queue_size` transfers

The raw interface changes with paging. `physio` of 5.1 translated one address and passed the whole length, because a PDP-11 process's memory was contiguous; with a page-table memory (chapter 6) a user's buffer is a list of pages scattered in physical memory, so the driver describes it with one descriptor per page (statement 5.10.3) and the pages must stay in place until the status byte is written. Figure 5.3 draws the layers a request crosses on the two machines.



The raw interface skips the cache: rawrw -> physio -> strategy; on the pdp64 physio pins the pages and gives one descriptor per page (5.6, 5.10.3).
Sources: V7 rk.c, 2.11BSD conf.c and vm_swp.c (read); OpenBSD vioblk.c, sd.c, conf.c (read). Each layer of the right column is OpenBSD code; none is built for the pdp

Commentary. **Chain.** PDP-11: one command at a time, a software queue per drive, one interrupt per transfer. VAX: the Unibus RK611 driver of 4.3BSD (`vaxuba/rk.c`) is a `uba_driver` whose start routine `rkdgo` loads the registers after `ubalLoc` has found map registers. PCI: the same registers, now with a controller that queues commands itself (SCSI, ATA, NVMe: the shape of the virtqueue, errata 61 and 75). virtio-blk: three descriptors and a status byte. OpenBSD: `vioblk.c` (747 lines, counted) is not a block driver with a strategy routine of its own but a SCSI adapter (`vioblk_scsi_cmd`) under the `sd(4)` disk driver, whose `sdstrategy` (`scsi/sd.c`) keeps the `bdevsw` row (read). pdp64: the same driver, with `bus_dmamap_sync` calls that do nothing (5.10). **Trade-offs.** A request with many commands outstanding replaces the one-at-a-time loop and its retry-ten-times error handling by a status byte and a reset (5.11). The cost is memory for the queue and the ordering rule between data and the used index (5.10.4). **Impact.** *Kernel:* a disk driver is a skeleton shared by all devices; OpenBSD's `vioblk.c` is the model. *Compiler:* none. *Hardware:* the device writes the data before the used entry before the used index.

5.7 The console, the timer and the entropy source

5.7.1 The form of the console, the timer and the entropy source under this interface is not specified: the candidates are a UART-style console, a small fixed timer and interrupt controller that need no enumeration, and virtio's console and entropy devices; the entropy pool is one device shared by all cores. *(S)*

This section is **open**: it states what the repository says and what the briefing offers, and decides nothing. The author's statements bear on it in two places only. Errata 85 (the ledger marks the entropy subject IN THE AIR, because its chain shows only potentials and errata 85 records them as decisions; the author's rationale there is "guys suffered from bad rng in the past", and optimising their algorithms "is ok", message 1882:69): the random-number pool "is one device shared by


all cores; no per-process pool; no version register and no updatable firmware", "an assistant to the operating system's own generator, which absorbs into it and squeezes from it". Errata 86: the secure core takes no periodic timer tick. No console, timer or entropy referent from another system is recorded in his messages.

What exists in the repository (read). `spec/pdp64-system.hbnf` defines, for the QEMU machine and `sim64`, a **timer**: a 64-bit free-running counter at 10,000,000 ticks a second of QEMU's virtual clock, a 64-bit compare register and a control register (enable, pending), interrupting at level 6 on vector 32 while the counter is at or above compare; and a **console** in the spirit of the KL11: four 64-bit registers (`RXCS`, `RXDB`, `TXCS`, `TXDB`), READY in bit 7 and interrupt-enable in bit 6, level 4, vectors 33 (receive) and 34 (transmit). They sit at fixed addresses (`0x8000000000`, `0x8000001000`) behind physical-address bit 39 of errata 60, which errata 97 withdrew; the specification and the QEMU machine have not been changed (5.14). Neither is virtio nor PCI Express. `decisions-pending.md` F11 leans to a 16550-style UART in place of the KL11-style console, and F12 to "a small device tree for these (timer, interrupt controller, UART), PCI Express enumeration for the rest". A **device tree** is a data structure, written by hand or by the boot loader, that lists each device the bus cannot enumerate with its type, address and interrupt, so that the kernel reads it instead of probing; no device tree exists in the repository yet.

What virtio has (read in `/usr/include/linux`, QEMU and OpenBSD). *Console:* device type 3. Port 0 has one receive queue and one transmit queue (queues 0 and 1 in QEMU's `virtio-serial-bus.c`; further control queues exist when `MULTIPORT` is negotiated); the configuration holds `cols`, `rows`, `max_nr_ports` and `emerg_wr`, and the feature `EMERG_WRITE` (bit 2) lets a driver print one character by writing it to `emerg_wr` (offset 8 of the configuration) with no queue and no buffer in memory; QEMU passes the low byte to the port. OpenBSD's `viocon.c` (617 lines) drives the queues through the tty layer and asks only for `SIZE`; it does not use `EMERG_WRITE`. *Entropy:* device type 4, one queue; the driver posts a device-writable buffer and the device fills it with random bytes (QEMU `virtio-rng.c`, queue of 8 entries). OpenBSD's `viornd.c` (201 lines) asks for 16 bytes at boot and again at an interval, and passes each word to `enqueue_randomness`, so the device is an input to the kernel's own generator, the shape of errata 85. *Timer:* no standard tick device. The ID list has `VIRTIO_ID_CLOCK` (17, "virtio clock/timer"), and `virtio_rtc.h` defines a clock-reading request, a cross-timestamp request and an alarm (`VIRTIO_RTC_F_ALARM`, `SET_ALARM`, a notification `VIRTIO_RTC_NOTIF_ALARM`); QEMU has a `vhost-user-rtc` device. A real-time clock with an alarm is a wall clock with one request and one notification through a queue; whether a periodic tick or a one-shot compare could be served so is not stated by any file read.

What the briefing offers (`docs/decision-log/data/shared/oq/B.md`, item Q6; open material, the assistant's proposals and not decisions). Five options for the three devices: (1) the fixed console and timer of the implementation and virtio-rng for entropy; (2) the timer inside the core (a shared counter and a one-shot compare register per core, read and written by system registers) with a minimal fixed UART for boot and panic and virtio-rng; (3) everything enumerated, virtio-console and virtio-rng and the timer in the core; (4) the author's absorb-and-squeeze pool of errata 85 as a fixed device; (5) no entropy hardware, only software gathering and a boot seed. The same document lists the costs the options carry: a fixed device is a second device model beside virtio; a virtio console cannot print before the bus works. `smp-decisions.md` section 4 leans to a global counter and a per-core one-shot compare. **The emergency write above bears on the second cost** and the briefing does not mention it: it needs the bus (the device's window mapped, its configuration structure found) but no queue, no descriptor, no DMA and no IOMMU entry, so a panic path through it is a store, though not a store at a fixed address. Whether the boot ROM may find the console by enumeration is part of what is open.

the console, timer and entropy source: the options (OPEN, 5.7.1; nothing decided)



A virtio-console needs the bus and a queue before it can print; its emergency write needs the bus and no queue. A fixed console needs neither.
Sources: spec/pdp64-system.hbnf, qemu/hw-pdp64, virtio_console.h, virtio_rtc.h, QEMU virtio-rng.c (read); the briefing B.md, Q6 (open material).

A complete tiny console driver, for the fixed console of the QEMU machine (the first and last lines of `tests/qemu/con-tx.S` and `con-rx.S` do in assembly what `con_putc_polled` and `con_rxint` do here); a virtio-console version would replace the three register writes with a transmit-queue post and keep the shape. An illustration:

```
# fixed address in the present machine (0x8000001000)
CON = MAP_CONSOLE
RXCS = 0;  RXDB = 8;  TXCS = 16;  TXDB = 24  # four 64-bit registers
READY = 1 << 7;  IE = 1 << 6                 # as the KL11's bits
ring txq, rxq                                # circular byte buffers: the clist's job

# vectors 33, 34: con_rxint, con_txint (6.3.3)
con_attach():
    # receive interrupts on; transmit off for now
    mmio_write64(CON + RXCS, IE)

# the boot code and a panic: no queue, no interrupt
con_putc_polled(c):
    while (mmio_read64(CON + TXCS) & READY) == 0: spin
    mmio_write64(CON + TXDB, c)

con_write(buf, n):                           # from the tty layer, as cnstart's caller
    s = spl4()                               # keep con_txint out while txq changes
    for c in buf[0..n): put(txq, c)
    # interrupts while IE is set: starts output
    mmio_write64(CON + TXCS, IE)
    splx(s)

con_txint():                                 # vector 34, level 4
    if empty(txq): mmio_write64(CON + TXCS, 0)       # nothing left: interrupt off
    else:          mmio_write64(CON + TXDB, get(txq))

con_rxint():                                 # vector 33, level 4
    tty_input(mmio_read64(CON + RXDB))       # reading RXDB clears READY
```

A timer tick handler, for the fixed timer: the interrupt stays asserted while the counter is at or above the compare register, so the handler moves the compare register forward by one period (`tests/qemu/mini-kernel.S` does this with `PERIOD` 200000, 20 ms at 10 MHz). An illustration:

```
timer_attach():
    mmio_write64(TIMER + COMPARE, mmio_read64(TIMER + COUNTER) + PERIOD)
```

```
    mmio_write64(TIMER + CONTROL, ENABLE)    # bit 0

timer_intr():                                # vector 32, level 6
    # drops the request
    mmio_write64(TIMER + COMPARE, mmio_read64(TIMER + COMPARE) + PERIOD)
    hardclock()                              # ticks++, due callouts, accounting
```

Commentary. **Chain.** PDP-11: the KL11 console has a receive and a transmit CSR with READY and IE bits and interrupts at BR4 on vectors 060 and 064; the KW11-L line clock interrupts at line frequency at BR6 on vector 0100 and `hardclock` runs on each tick; both are at fixed addresses and need no probe (`cons.c`, `scb.s`, read). VAX: an interval timer in processor registers and a console processor (`boot.md`, from memory in the repository, *unverified* here). The PC: a UART at a legacy port and a programmable timer, then per-core timers; the ARM and RISC-V systems of today describe their UART and timer to the kernel in a device tree (*unverified*; OpenBSD has the `sys/dev/fdt` bus, read, and a virtio-over-memory-mapped-registers transport `virtio_mmio.c` for machines that have a device tree and no PCI). pdp64: the console and timer exist today as the KL11 shape (5.7, read) and the form that will stay is open. **Trade-offs.** A fixed console works before the bus does and costs a second device model; a virtio console is one model and cannot print before the queue is set up, unless the emergency write serves; a timer in the core removes a device and a lock and adds system registers, a counter distribution and an architectural definition (`smp-decisions.md`, read). **Impact.** *Kernel:* the console must work before enumeration for the boot ROM and the panic path; the timer must work before any driver. *Compiler:* none for the console and entropy; a timer in system registers adds `MTSR` and `MFSR` numbers. *Hardware:* a fixed UART or timer is a few registers; a virtio console is a queue engine; an entropy source is a physical circuit whose quality the standard would promise.

5.8 The network, graphics, sound and USB drivers

Each class driver is a few request formats over the transport of 5.4. What the driver does is the part that differs.

5.8.1 The **network card** is virtio-net: a receive queue the host fills with buffers for the device and a transmit queue of frames to send; the device completes each receive buffer with the frame length. *(D)*

5.8.2 The **graphics device** is virtio-gpu in its 2D mode (create a surface, point it at memory, flush a rectangle) and the **audio device** is virtio-snd (streams in queues in shared memory). *(D)*

5.8.3 USB is an xHCI host controller, a PCI Express function, driven by the operating system's USB stack, which enumerates the attached devices. *(P)*

virtio-net (device type 1). The driver keeps the receive queue full: it posts empty buffers with `WRITE`, and the device fills one with a frame and reports its length in the used ring; to send, the driver posts the frame and the device reads it. Each frame starts with a 10-byte `struct virtio_net_hdr` (flags, GSO type, header length, GSO size, checksum start and offset; `virtio_net.h`, read), which tells the device which checksum to fill in and where. Queue 0 receives, queue 1 transmits, and a control queue exists with the feature `CTRL_VQ`; the MAC address is in the device configuration with the feature `MAC` (`virtio_net.h`, QEMU `virtio-net.c`, read). OpenBSD's `if_vio.c` is 2,184 lines (counted), the largest virtio driver of the tree. The PDP-11's counterpart is the DEUNA of 4.3BSD or the network driver of a Unix with a network (V7 has none).

virtio-gpu (type 16). Two queues: the control queue, 256 entries in QEMU, carries the commands of chapter 3 (3.14: create a resource, attach its backing memory, set the scanout, transfer a rectangle, flush it), and the cursor queue, 16 entries, carries cursor updates. The driver sends a command and waits for the response in the same chain. OpenBSD's `viogpu.c` (727 lines, read) has the functions `viogpu_create_2d`, `viogpu_attach_backing`, `viogpu_set_scanout`, `viogpu_transfer_to_host_2d` and `viogpu_flush_resource`, the five commands of the figure of 3.14. The PDP-11 had no counterpart; the nearest is the display register pair of a VT11 or the bitmap of a Blit, which chapter 3 tells.

virtio-snd (type 25). Four queues in the order control, event, transmit, receive (`virtio_snd.h`, read; QEMU adds them in that order); the control queue sets up the streams, and the transmit and receive queues carry the samples of an output or an input stream. Chapter 3 (3.20) says what a stream is and what a mixer does with it. **OpenBSD's tree on this computer has no virtio-snd driver:** `sys/dev/pv` holds `if_vio.c`, `vioblk.c`, `viocon.c`, `viogpu.c`, `viomb.c`, `viornd.c`, `vioscsi.c` and `virtio.c`, and no sound file, so the question of errata 79 ("whether OpenBSD has a virtio-snd driver (if not, one is written)") is answered for that tree: one is written. The PDP-11 had no audio device.

USB (an xHCI controller, a PCI Express function). The controller runs the protocol in hardware; the driver gives it lists of transfer descriptors in memory and reads an event ring, the same pattern as a virtqueue with its own formats. The operating

system's USB stack enumerates the devices behind the controller (2.4.3). The author's uses of USB are the keyboard, the mouse and a hard drive ("modern usb keyboard, mouse, and nvme hard drive", message 531:0; the ledger's modern I/O hardware subject, DONE); the class drivers that those need (human interface device, mass storage) are not described in the repository. That a USB-to-Ethernet adapter appears to the host as a network class device is *unverified*.

Commentary. **Chain.** PDP-11: one driver per controller, each with its own registers (`rk.c`, `cons.c`, `dz.c`, 579 lines for the multiplexer). VAX: the same, with the adapter handling the memory mapping. PCI: one driver per chip family, with firmware and quirk tables (`kernel-pain-points.md`, repo). virtio: one transport and a thin driver per class, so that a card of any vendor that speaks the standard works with the drivers already written. pdp64: that, for network, graphics and audio; xHCI for USB. **Trade-offs.** One transport means one driver to write, at the cost of feature negotiation and a queue format that the pdp64 does not control; an existing USB stack comes with xHCI at the price of that large stack. **Impact.** *Kernel:* one transport driver and a thin driver per class; a virtio-snd driver to write. *Compiler:* none. *Hardware:* standard PCI Express functions; the same virtio devices are the aim in QEMU, `sim64` and the FPGA.

5.9 Interrupts as a driver sees them


5.9.1 A device interrupts by a message-signalled write (MSI-X): the configuration change and each queue have a vector that the driver sets in the common configuration, and the interrupt status structure says why. *(P)*

5.9.2 A driver may mask a device's interrupts and poll the used ring instead. *(D)*

5.9.3 A changeable interrupt target is changed with its vector masked and then read back, or is a single atomic register write. *(D)*

5.9.4 The write that raises an interrupt cannot overtake the data writes that precede it (section 2.5.4). *(D)*

What changes for the driver is where the vector number and the level come from. On the PDP-11 the programmer chose them by switches and by the vector table: the RK11's pair at 0220, level 5. On the pdp64 the driver asks the interrupt controller for an address and a data word (`interrupt_controller_allocate` in 2.7), writes them into the device's MSI-X entry for the queue, tells the queue its entry (`queue_msix_vector`), and installs its handler in the vector table at `VBR + 8 × vector` (6.3.3). One queue, one vector, one core: the handler of `vioblk_intr` runs when the queue's vector arrives, and reads the used ring to learn what finished, where `rkintr` read the CSR. Figure 5.4 draws the two paths.



PDP-11: a wire and a level shared by every device on it; the vector was set by switches on the card; the handler asks the CSR what happened.
pdp64: a memory write that cannot pass the data written before it (5.9.4); one vector for each queue; the handler asks the used ring.
The dashed box is open: which unit receives the write, how a core is chosen and how the vector number is made are decision R1 (appendix B, 2.7.3)

Sources: 2.11BSD pdp/scb.s (DEVTRAP(220, rkintr, br5)); chapter 6 (6.3.1 to 6.3.6) for the entry; chapter 2 (2.7) for MSI-X.
The priority of 7 on entry is the PDP-11's own habit (errata 40); the handler lowers it with SPL.

An entry puts the processor at priority 7 with the interrupted program counter and status word in registers (6.3.1 and 6.3.2); the handler saves them with `PUSHX`, lowers the priority with `SPL` to its own level, does its work, restores the pair with `POPX` and returns with `RTI` (6.3.4). The level of a device is the level the interrupt controller gives its vector; the kernel's `splbio` is the status-word priority at which the block code runs. OpenBSD keeps the idea: `vioblk_attach` sets `vsc->sc_ipl = IPL_BIO` (read), and `virtio_pci.c` can give a device one MSI-X vector for configuration changes and one for each queue (`IRQ_MSIX_PER_VQ`), or one shared by all queues (`IRQ_MSIX_SHARED`), up to `MAX_MSIX_VECS`, 16 (read).

Not specified. The unit that receives the write, how a core is chosen, how the vector number is made and the level assigned are the interrupt-controller decision **R1** of appendix B and statement 2.7.3, which are **open**. The briefing (`B.md`, item Q7) lays out six options, none decided: a per-core interrupt file that messages write; that file plus a remapping table in the IOMMU (`smp-decisions.md` leans to this as the end state); an ARM-GIC-style distributor; wired lines to core 0 for the fixed devices; per-core event rings in memory; and polled devices on dedicated cores with interrupts only for the timer, interprocessor interrupts and errors. It also records that 256 vectors per core do not fit the 224 free entries (32 to 255) of the 512-entry vector table of 6.3.6; the numbering is part of what is open. The vectors of the QEMU machine (32 timer, 33 and 34 console) are fixed wires (5.7), and the `-i N:LEVEL:VECTOR` option of `sim64` injects an interrupt by instruction count (5.14).

Commentary. **Chain.** PDP-11: four bus-request lines and switch-set vectors; a level shared by several devices, so a handler may have to ask which spoke; `spl` raises the priority to keep a handler out (5.1). VAX: 31 priority levels and a **system control block**, a table of vectors in memory (the repository's `decisions-pending.md`, checked there against a VAX architecture manual; not on this computer); `spl` becomes `splbio`, `spltty`, `splclock`. PCI: four shared pins per slot, and a handler that asks each device whether it was the one. PCI Express: MSI-X, an interrupt as a write (2.7). virtio: a vector per queue. pdp64: MSI-X for the standard devices, vectors in the same table as exceptions, priority 7 on entry (errata 40, "a throwback to pdp-11 design"), and the controller open. **Trade-offs.** A message carries its own vector, so no switch and no assignment table are needed and there can be thousands; the controller is an address that many devices write, and a confused device that writes the wrong address causes an interrupt, which the IOMMU can refuse (2.11). **Impact.** *Kernel:* an interrupt routine reads the used ring and the status structure; a controller driver. *Compiler:* none. *Hardware:* an MSI-X target in the interrupt controller, and the eight-level priority encoder.

5.10 DMA and the buffer's memory

5.10.1 Buffers and queues are in memory mapped uncached, and the driver does no cache clean or invalidate. *(D)*

5.10.2 A device addresses physical memory directly and the driver gives it physical addresses; until an address-translation unit for devices exists, every device must be able to address all of memory. *(P)*

5.10.3 A buffer that crosses a page is described by several descriptors chained with the `NEXT` flag; the driver does not make buffers contiguous. *(D)*

5.10.4 The device writes the data, then the used-ring entry, then advances the used index; the driver reads the used index and then the data. *(D)*

Three questions arise for a driver: which addresses the device sees, whether the processor's cache agrees with memory, and in what order the writes land. The PDP-11 answered the first with map registers, which the driver loaded (`mapalloc`, 5.1), and on a Q-bus machine with a bounce buffer for controllers that could not reach all of memory (`sofub_alloc`, 5.1); the second hardly arose (that the 11/70's cache watched Unibus writes, so that DMA data appeared coherent, is *unverified*, as in 2.5); and the third by one bus that delivered writes in order. The pdp64 answers them in this way:

- **Addresses.** Today the descriptor holds a physical address and the device may use any (5.10.2, P). When the IOMMU of chapter 2 (2.11) exists, the descriptor holds a **device address** (an address in the device's own mapped space, which the IOMMU turns into a physical address or refuses); the driver asks the kernel to map a buffer for the device and puts the returned address in the descriptor, and `VIRTIO_F_ACCESS_PLATFORM` (feature 33) says so to the device. The five recommendations of errata 85 (translation on by default, a domain per device, no kernel pointers in descriptors, permanent ring mappings, small buffers bounced) shape what that mapping call does. Which feature bits the pdp64 declares is not specified (5.4.4).
- **Coherence.** Buffers and rings are mapped uncached (memory type 6.7.4), so that the processor's cache never holds a stale copy of what a device wrote and the driver never cleans a line. OpenBSD's `vioblk.c` calls `bus_dmamap_sync` with `PREWRITE`, `PREREAD`, `POSTREAD` and `POSTWRITE` around each request (read); on the pdp64 those calls have nothing to do (5.13.3). The cost is that the processor reads received data from uncached memory, which is slow.
- **Order.** The processor's `FENCE` before the doorbell, the device's data-before-used-entry-before-used-index, and the interrupt that cannot pass the data (5.9.4) are the whole contract; chapter 2 (2.5, 2.8) states them.

Commentary. **Chain.** PDP-11: 18 address bits, so map registers (`UBMAP` at `0170200`) translate; `physio` assumed a contiguous buffer. VAX: `ubalonce` for map registers and **buffered data paths** that a driver purged before reading what a device had written (`UBA_PURGE780`, `ubareg.h`, read). PCI and PCI Express: a bus master uses physical addresses, and Linux and BSD wrap the work in a DMA-mapping layer (`bus_dma` in OpenBSD, read) that places cache maintenance on machines that need it and copies into

a **bounce buffer** (a buffer in memory the device can reach; 2.11BSD's soft Unibus map is the same idea on the PDP-11) when a device cannot reach the data (`swiotlb` in Linux, *unverified*). That x86 DMA is coherent while ARM and MIPS DMA often is not is *unverified*. pdp64: uncached memory for coherence, descriptors per page for scattered buffers, an IOMMU for the addresses. **Trade-offs.** Uncached buffers make the processor's reads slow and make the driver unable to forget a cache operation; a device that is not coherent would call for cache-maintenance instructions. With no IOMMU there is no protection from a faulty or malicious device. **Impact.** *Kernel:* no cache clean or invalidate in any driver; a mapping call that reduces to the identity until the IOMMU exists. *Compiler:* none. *Hardware:* DMA goes around the processor's data cache, so the cache needs no snoop port for devices.

5.11 Errors, departure and recovery

5.11.1 A request that fails completes with the status of its device class (for a virtio-blk request, a status byte in the last descriptor of its chain); a device that is broken sets its needs-reset bit in `device_status`. *(D)*

5.11.2 A device that is reset leaves its queues in memory untouched; the driver reprograms the queue registers and resubmits the chains that are not in the used ring. *(P)*

5.11.3 A device that leaves the bus leaves its queued work in memory; the driver finds it by comparing the available ring with the used ring. *(P)*

5.11.4 Requests are repeatable where possible (reads, writes of the same data, sends, buffer posts), so that resending an unfinished chain is safe; a request that must not run twice is tracked by its class driver, which can tell "never started" from "started, outcome unknown" only by the request's own status. *(P)*

On the PDP-11 an error was the ERR bit of the CSR, the error word `RKER`, and the driver's choice: `rkintr` reset the controller and retried up to ten times before it set `B_ERROR`. A virtio-blk request reports a status of 0, 1 (I/O error) or 2 (unsupported) in its last byte, and no retry happens in the device. A driver that finds the device stuck resets it. OpenBSD's `vioblk_reset` (read) stops the device with `virtio_reset`, runs `virtio_check_vq` to complete what finished, and **fails every other request** with a driver error; its `virtio_reinit_start` then repeats the handshake and `virtio_init_vq` **zeroes the ring memory and restarts both indices at 0**. Two things follow for statements 5.11.2 and 5.5.4: the queue memory is not left untouched by that driver, so the chains to resend must be copied out before the ring is rebuilt; and resending is the pdp64's proposal, not what the OpenBSD driver does. Whether the specification requires the indices to restart after a reset is *unverified* (the specification is not on this computer).

Commentary. **Chain.** PDP-11: errors in device registers, a retry loop in the driver, no device that can leave. VAX: `ubareset` resets the adapter and calls every driver's reset routine so that each re-issues its own pending work (read): resending as a design, driver by driver. PCI Express: an error completion and a link-down; hot-plug exists (2.4). The author's reason for leaving a departed device's work in memory is "so it can be read, saved, resent" (message 1889:2641; ledger, bus hotplug, DONE with the resend rule still *(P)*). NVMe and virtio drivers requeue outstanding requests after a reset (*unverified*; OpenBSD's `vioblk` fails them instead, as above). virtio: a status byte per request and a needs-reset bit. pdp64: one recovery routine for a failed, reset, replaced or departed device and a hand-over between cores, with the precise bus fault for a departed device (2.4.5, 2.9.1) and not all ones (an empty configuration position is the one read that returns all ones, 2.4.9). **Trade-offs.** The cost is a write to the used ring per chain and the ordering rule between data and the used index. **Impact.** *Kernel:* one recovery routine handles a failed, reset, replaced or departed device. *Compiler:* none. *Hardware:* the device writes data before the used entry before the used index.

5.12 Firmware for a device

A device that contains a small processor may need a program, **firmware**, loaded into it before it works. A PDP-11 peripheral needed none (4.1). On a PC the driver reads the blob from a file at attach time: OpenBSD's `loadfirmware(name, &buf, &len)` reads `/etc/firmware/<name>` (`dev/firmload.c`, read), and 19 files under `sys/dev/pci` call it (counted); Linux's `request_firmware` is *unverified*. The pdp64 has one statement on the subject, 4.8.1 *(P)*: that a device that wants firmware is given it "through a descriptor operation once the root file system is available", and that a device the boot depends on needs none. That statement was written for devices of eight registers with an `INIT` bit and a `READY` bit; under virtio the idea of `INIT` and `READY` stays and takes the form of the `device_status` handshake (5.5), and the register words themselves are withdrawn. The other half has no virtio counterpart: **no virtio header on this computer mentions firmware** (a search of all 29 `virtio_*.h` files and of QEMU's

hw/virtio), and each device class defines its own request set, so a firmware download would be a request of a class that none defines.

5.12.1 How a virtio device is handed firmware is not specified: virtio has no firmware operation, so a request type or a separate device would have to be defined, and a device the boot depends on (the disk, and the console if it is a device) needs none. *(S)*

Commentary. **Chain.** PDP-11: none. PC: a file per device, a loader in the kernel (firmload(9)) and a separate package of files. pdp64: errata 85 already sets one precedent, an entropy pool with "no updatable firmware", and 4.8.1 sets the other, a descriptor operation; neither settles how a network card or a GPU gets its program. **Trade-offs.** A firmware window lets a device be cheap (no flash) and makes an update a file replacement, at the cost of a header format and a device that rejects a wrong image safely. **Impact.** *Kernel:* a loader that runs after the root file system is up, and a rule that no boot device needs it. *Compiler:* none. *Hardware:* a device-side image check.

5.13 Where drivers run, and how they are written

5.13.1 Because a device's windows are whole pages, a driver can run in user space with only those pages and its buffers mapped. *(P)*

5.13.2 Until devices have an address-translation unit, a user-space driver can instruct its device to write anywhere in memory, so it is as trusted as the device. *(P)*

5.13.3 In OpenBSD the register accessors become loads and stores, the DMA mapping interface returns physical addresses with no cache-synchronisation work to do, and the autoconfiguration framework attaches a driver to each function the bus reports. *(P)*

In OpenBSD (read in the source tree at /home/david/claude/facetlang/pdp11/openbsd-src, version 8.0). A driver is a struct cfattach (the size of its per-device structure, the **softc**, a match and an attach function, and an optional detach) and a struct cfdriver. The virtio drivers attach below the transport virtio.c (1,075 lines) and virtio_pci.c (1,246 lines), which do the handshake of 5.5, the queues, and the MSI-X set-up; a class driver calls virtio_negotiate_features, virtio_alloc_vq and virtio_enqueue and sets vq_done. The device switch of 5.1 is still there, in the machine's conf.c: bdevsw[] rows are built by bdev_disk_init from open, close, strategy, ioctl, dump, size and flags. A virtio-over-memory-mapped-registers transport, virtio_mmio.c, exists for machines with a device tree; the pdp64's transport is the PCI Express one.

In user space. Microkernels and exokernels run drivers as ordinary programs where the hardware lets one device be mapped to one process (*unverified*); the PDP-11's Unibus gave every device a fixed address and no protection. Windows of whole pages make that possible here (5.13.1), and the IOMMU is what would make it safe: until it exists, a user-space driver is as trusted as its device (5.13.2). Linux VFIO and UIO and the DPDK libraries are the same idea and rely on an I/O translation unit (*unverified*). **Trade-offs.** A driver in user space can be tested, restarted and replaced without taking the kernel with it; its cost is a crossing for each request and the trust above.

In C, and the tool chain. A V7 driver is written in the PDP-11's C, where int is 16 bits and the register structure's fields are int and short. On the pdp64 int is 32 bits and long and pointers 64 (LP64, appendix D, D.1), so a register or a descriptor field is declared by its width (uint16_t, uint32_t, uint64_t); natural alignment gives the 16-byte descriptor, the 10-byte virtio_net_hdr and the offsets of the virtio structures with no packed attribute. The headers that define those structures are the Linux virtio_*.h files, each of which says that it "is BSD licensed so anyone can use the definitions to implement compatible drivers" (read in virtio_rng.h; the same line is in all 29), which fits the project's BSD 2-clause licence (errata 48); for the repository's own fixed devices the offsets are generated constants, pdp64-consts.h, made from spec/pdp64-system.hbnf, so that the device model, the test and a driver read one definition. A register is read and written through a volatile pointer: the compiler's value reuse is tested not to merge two reads of a volatile (tests/c-new/avail_volatile.c, function vtwice, read). The FENCE of 5.3.5 has no C intrinsic: the compiler's name table knows the mnemonic (arch/pdp64/pdp64-names.h in the pcc tree) and nothing else (read), so a driver today would call a function written in assembly. The two compilers are the C compiler pcc (working for pdp64/32 on the branch enc-prefix; the fallback system is Unix/32V) and the LLVM back end for OpenBSD, which has an assembler and a disassembler and no code generator yet (handoff.md), so no driver of this chapter can be compiled for the pdp64 by a compiler that exists for OpenBSD.

Commentary. **Chain.** PDP-11: a driver is one C file and a line in conf.c, in the language of the day with 16-bit int. VAX: the same, with config(8) writing the tables. OpenBSD: softc, cfattach, bus_dma, a framework of its own. pdp64: OpenBSD's framework, with the DMA calls reduced to the identity and the accessors to loads and stores. **Impact.** *Kernel:* the accessors

reduce to loads and stores, the DMA interface to physical addresses, and attach to the functions the bus reports. *Compiler:* fixed-width types, `volatile`, and a `FENCE` function or intrinsic. *Hardware:* windows of whole pages let the translation unit protect a device.

5.14 Testing a driver

What exists today (read in the repository):

- **`sim64`** has no device and no bus. `-K` starts the System v1 kernel-mode machine with flat physical memory and no MMU, and `-i N:LEVEL:VECTOR` raises an interrupt request of that level and vector once N instructions have started; `wfe` jumps to the next pending request. `tests/sim/sys-irq.S` and `sys-wfe.S` use it: a driver's handler can be entered, but there is nothing to talk to.
- **QEMU's `pdp64-virt` machine** with `kernel-mode=on` has the fixed timer and the fixed console of 5.7, an interrupt controller that is two wires, the vector table at `VBR + 8 × vector`, and an MMU. Its tests are the ones named above: `tests/qemu/con-tx.S` (transmit by polling), `con-rx.S` (receive by interrupt at level 4, vector 33, echo by polling, then transmit by interrupt at vector 34), `timer.S` (counter, compare, level 6, `wfe`) and `mini-kernel.S` (a tiny kernel with page tables, a timer tick at 20 ms, system calls and a demand-paged fault). They run under `tools/check-qemu.sh`.
- **Not implemented, anywhere in the repository:** a PCI Express root complex, configuration space, a virtio device, an MSI-X target, an interrupt controller beyond the two fixed wires, an IOMMU, a block device, a network device. A search of `qemu/`, `sim64/`, `common/` and `spec/pdp64-system.hbnf` for `pci`, `virtio`, `msi` and `iommu` finds nothing. The statement that "the same devices run in QEMU, `sim64` and the FPGA" (5.3.1) is an aim.
- **What QEMU's own sources provide.** `hw/virtio` holds the virtio devices (`virtio-rng.c`, `virtio-blk.c`, `virtio-net.c`, `virtio-gpu`, `virtio-snd.c`, `virtio-serial-bus.c`) and the PCI transport; QEMU's ARM and RISC-V `virt` machines attach them through a PCI Express host bridge (*unverified*: the machines' sources were not read). A pdp64 machine that attached them would need a root complex model, the interrupt controller of R1 and, for the IOMMU, a model of it, in `qemu/hw-pdp64/virt.c`; none is begun.

A virtio driver could be exercised before the machine has them by compiling its logic for the host and running it against a software model of a virtqueue; that is a proposal and nothing in the repository does it.

5.15 What was checked, and what was not

The virtio and PCI Express specifications are not on this computer. What the chapter rests on:

- **2.11BSD** (`unixtree/2.11BSD/sys`): `pdpuba/rk.c`, `rkreg.h`, `ubavar.h`, `pdp/conf.c` (the `bdevsw` and `cdevsw` rows), `h/conf.h`, `h/buf.h`, `h/uba.h`, `pdp/scb.s` (the vectors and levels of the RK11, the console and the clock), `pdp/cons.c`, `sys/tty_subr.c`, `h/clist.h`, `sys/vm_swp.c` (`physio`, `rawrw`), `pdp/machdep.c` (`mapalloc`), `sys/ufs_bio.c` (`biodone`), `autoconfig/` (`main.c`, `do_config.c`, `attach.c`, `rkauto.c`), `pdp/machparam.h` (`splx`). **V7** `usr/sys/dev/rk.c`.
- **4.3BSD** (`unixtree/4.3BSD/usr/src`): `sys/vaxuba/ubavar.h`, `uba.c` (`ubareset`), `rk.c`, `sys/vax/autoconf.c` (`unifind`), `etc/config/mkioconf.c`, `sys/vaxif/if_dereg.h`.
- **Linux headers** in `/usr/include/linux`: `virtio_pci.h` (the common-configuration offsets), `virtio_config.h`, `virtio_ring.h`, `virtio_ids.h`, `virtio_blk.h`, `virtio_net.h`, `virtio_console.h`, `virtio_snd.h`, `virtio_gpu.h`, `virtio_rng.h`, `virtio_rtc.h`, and a search of all `virtio_*.h` for "firmware" and "BSD licensed".
- **QEMU** (`/home/david/claude/qemu-src/hw`): the queues created by `virtio-rng.c`, `virtio-serial-bus.c` (including the emergency write in `set_config`), `virtio-blk.c`, `virtio-net.c`, `virtio-gpu-base.c`, `virtio-snd.c`; the pdp64 target in `qemu/hw-pdp64`.
- **OpenBSD 8.0** (`facetlang/pdp11/openbsd-src/sys`): `dev/pv/vioblk.c`, `viornd.c`, `viocon.c`, `viogpu.c`, `if_vio.c`, `virtio.c`, `dev/pci/virtio_pci.c`, `dev/firmload.c`, `scsi/sd.c`, `arch/amd64/amd64/conf.c`; line counts from `wc`. The older OpenBSD tree at `kernel-src/openbsd` has no `sys/dev/pv`.
- **The repository:** `spec/pdp64-system.hbnf`, `qemu/hw-pdp64`, `sim64/sim64.c`, `tests/qemu`, `tests/sim`, `tests/c-new/avail_volatile.c`, the pcc tree's `arch/pdp64/pdp64-names.h`, `docs/errata.md`, `docs/smp-decisions.md`, `docs/decisions-pending.md`, `docs/decision-log` (the briefing `B.md`, item Q6 and Q7, and the author's messages).
- **Unverified** (general knowledge): the PDP-11 caches and the contiguity of a process's memory beyond what `physio` assumes; the PCI and virtio history; that a virtio reset restarts the ring indices; that `request_firmware` is Linux's; Linux's `probe` and `remove`, `swiotlb`, `VFIO`, `UIO` and DPDK; that x86 DMA is coherent and some ARM and MIPS DMA is not; the VAX interval timer and console processor; device trees on ARM and RISC-V machines; that a USB-to-Ethernet

adapter appears as a network device; that QEMU's ARM and RISC-V machines attach virtio through a PCI Express host bridge.

- **The ledger** (`docs/decisions-and-status.md`) was read for devices, virtio, the standard GPU, NIC and audio interfaces, USB and NVMe, random numbers, device initialisation, hot-plug, interrupt entry and the first operating system; this chapter agrees with its Decided lines. Where it differs: it still lists the virtio-only rewrite as TO DO and says `errata.md` ends at 93; it lists the entropy and device-initialisation subjects as IN THE AIR, which the chapter says too.
- **Decided** by the author and recorded in `errata.md`: every statement tagged *(D)*. Nothing else in this chapter is a decision, and the console, timer, entropy, interrupt-controller, firmware and device-tree discussions are open.

5.16 Still open

The feature subset of each virtio device and the platform-ordering feature (5.4.4); the feature subset of virtio-blk (flush, block size, ordering) and the boot ROM's read of block 0 (5.6.2); the form of the console, the timer and the entropy source, and whether a device tree exists (5.7.1; briefing `B.md`, Q6; `decisions-pending.md` F11 and F12); the interrupt controller, the vector numbering and the routing (5.9; R1); DMA addressing and protection (R6, 5.10.2); errors raised by devices (R7); how a device is given firmware (5.12.1); the PCI Express root complex, interrupt controller and IOMMU models without which no driver can be tested (5.14); a `FENCE` in C; which virtio devices "it makes sense to support" in silicon, and the syntactic sugar of message 592:13. The working documents are `../decisions-pending.md` and `../pdp64-q64-bus.md`, and appendix B.

Chapter 6 — The kernel: modes, exceptions and memory management

An operating system on the pdp64 sees a status word with a mode and a priority, an exception mechanism that writes only registers, and a page table of three, four or five levels whose accessed and dirty bits the kernel maintains in software. The reader is taken to be a first-year computer-science student or a PDP-11 programmer who has read the Unix Version 6 or 7 kernel, and to know nothing that appeared after the 1970s. The chapter starts from that kernel (the status word, the vectors, `trap()`, the KT11 memory-management unit with its eight page registers per mode, `mfpi` and `mtpi`, swapping). Each later idea follows with the PDP-11 way first, the intermediate machines that changed it, and the pdp64 way with the reason. Pseudocode walks a system call, a page fault, a timer interrupt, a context switch and the idle loop. The design is System v1; the options and the comparisons with other architectures are in `../pdp64-system-architecture.md` (section 15) and `../pdp64-system-design.md`. Tags: *(D)* decided; *(P)* proposed; *(S)* unspecified. A fact about an older or another machine that could not be checked on this computer is marked *unverified* and listed in section 6.14.

How to read this chapter. A term is defined where it first appears, as the technical word followed by a plain restatement. In the pictures a box is a piece of memory or a register and an arrow is an address stored in it. Code blocks are pseudocode (C-like, `#` starts a comment) unless the text says they are PDP-11 or pdp64 assembly. The PDP-11 code is quoted from the V7 and 2.11BSD kernels on this machine (section 6.14). The pdp64 code is **an illustration written for this chapter**: no pdp64 kernel exists (the first operating system is OpenBSD, 6.12.3, and none of it is written), so none of it is tested. The decisions are the numbered statements. Where the repository does not say, the text says *not specified*.

6.1 What you already know: the kernel of a PDP-11

Take Unix Version 7 (or 2.11BSD, the same kernel grown up) on a PDP-11/45, 70 or 73. Six things about it carry the rest of the chapter.

The status word and the modes. The **processor status word** (PS, also called PSW: one 16-bit register holding the flags, the interrupt priority and the mode of the running program) sits at address 0177776. Bits 15-14 are the **current mode** (the privilege the program runs with: kernel, supervisor or user), bits 13-12 the **previous mode** (the mode running before the last trap), bits 7-5 the **priority** (the level at or below which interrupts are held back), bit 4 the **trace** bit (take a trap after every instruction) and bits 3-0 the flags N, Z, V and C. The 2.11BSD header `psl.h` says the same in C: `PSL_CURMOD` 0xc000, `PSL_PRVMOD` 0x3000, `PSL_IPL` 0xe0, `PSL_T` 0x10, the condition codes in 0xf. Each mode has its **own stack pointer** (R6 names a different register in each mode), so a trap arriving in user mode finds a kernel stack waiting. User mode may not execute `halt`, `reset`, `wait` or change the priority (*unverified*).

Vectors in low memory. A **trap** (the machine transferring control to the kernel because something happened) goes through a **vector**: two words at a fixed low address, the new program counter and the new PS. The hardware pushes the old PS and PC on the new mode's stack and loads the pair. This is the start of the V7 table, `conf/l.s` (the octal addresses are added; the file's first two words are a branch and a 4, the vectors follow):

```
        trap;  br7+0.          / 004  bus error
        trap;  br7+1.          / 010  illegal instruction
        trap;  br7+2.          / 014  bpt-trace trap
        trap;  br7+3.          / 020  iot trap
        trap;  br7+4.          / 024  power fail
        trap;  br7+5.          / 030  emulator trap
        start; br7+6.          / 034  system call (overlaid by 'trap')
        . = ZERO+60
        klin;  br4             / 060  console keyboard
        klou;  br4             / 064  console printer
```

```
        . = ZERO+100
        kwlp;  br6              / 100  line clock
```

The first word of each pair is the handler's address. The second is the new PS: `br7` is priority 7 (nothing may interrupt) plus a small number that the handler passes to `trap()` to say which trap it was. The device vectors carry the device's priority, 4 for the console and 6 for the clock. A handler ends with `rti` (return from interrupt: pop the PC and PS) or `rtt` (the same, but a pending trace trap is not taken at the first instruction).

`trap()`. Assembly code at the vector (`call` in the V7 file `mch_i.s`) saves the registers and calls one C function, `trap(dev, sp, r1, nps, r0, pc, ps)`; its arguments are, in the words of the V7 comment, "the words saved on the system stack by the hardware and software during the trap processing". A system call is one of these traps: the program executes `sys n` and `trap()` fetches that instruction back from user memory and uses its low six bits as an index (`callp = &sysent[fuiword((caddr_t)(a-1))&077]`).

The memory-management unit. A PDP-11 program uses 16-bit addresses (64 KB) while physical memory is wider: 18 bits (256 KB) on the Unibus machines, 22 bits on later ones (*unverified*, section 6.14). The **KT11** (the memory-management unit: the hardware between processor and memory that turns the program's addresses into memory addresses, a step called **translation**) has for each mode **eight pairs** of **page registers**: a **PAR** (page address register: where the segment starts in physical memory, in units of 64 bytes) and a **PDR** (page descriptor register: how long it is, up to 8 KB, and whether it may be read or written). The top three bits of a program's address pick a pair; the other thirteen are the offset in that 8 KB piece. 2.11BSD names the user's registers `UISA` and `UISD` (0177640 and 0177600) and the kernel's `KISA0` (0172340) and following. With **separate instruction and data space** (code and data each get their own 64 KB) there are sixteen pairs. `estabur()` fills a process's saved pairs from the sizes of its text, data and stack and fails with `ENOMEM` if they need more than eight segments; `sureg()` copies the saved pairs into the hardware registers when the process is switched in. Each pair describes **base and length** (a start and a size, the oldest form of memory protection), so a program's text, data and stack are each one **contiguous** run of memory, handed out by a first-fit allocator (`malloc.c`: "the core map unit is 64 bytes").

Reaching the other space. The kernel's address space is separate from the user's, so a kernel pointer to user memory means something else. `mfpi` and `mtpi` (move from and to the **previous** instruction space; `mfpd` and `mtpd` for data space) take the address from the kernel's registers but use the previous mode's page registers. `fubyte` and `subyte` are built from them, with a global named `nofault` that makes an error in the access return -1 instead of panicking.


Swapping. A process image was one block of memory. When memory ran short, `sched()` called `swapout()`, which wrote the whole image to the **swap device**, and `swapin()` read it back whole. No part of a program could be in memory without the rest.

What carries over. The pdp64 keeps three modes with a recognisable status word, a stack pointer per mode, vectors, `RTI`, a priority the kernel raises and lowers, a previous mode and an idle instruction. Eight things are new, each met where it first matters: entry stores state in registers instead of pushing it (6.3); exceptions are precise (6.4); control registers are reached by number (6.5); the eight page registers become a tree of page tables that the hardware walks (6.6, 6.7); a translation buffer caches the walk and must be kept honest (6.8); its entries carry an address-space number so a context switch need not empty it (6.8); the kernel half of the address space has its own table and direct-mapping windows for memory and devices (6.9); and `R7` is an ordinary register (errata 100): the PC is not a register at all and the stack pointer is `R14`.

6.2 Modes and the status word

The three modes keep their PDP-11 values: kernel 0, supervisor 1, user 3. Loading the reserved value 2 into the status word is an illegal instruction. The fields moved down to make room for one new bit:

	PDP-11 (`psl.h`)	pdp64
flags (four bits)	3-0	3-0
trace	4	4
priority	7-5	7-5
current mode	15-14	9-8
previous mode	13-12	11-10
user-memory guard	none	12



The **user-memory guard** (a status bit that says whether the kernel may touch user memory; section 6.10) is the new bit. The **previous mode** has the same job as on the PDP-11: after a trap from user mode it says where the kernel came from, and the instructions that act for the previous mode (`PROBER` and `PROBEW`, 6.10) use it. A **privileged instruction** (one that only the kernel may execute, because it could break the protection between programs) executed outside kernel mode **aborts** (is cancelled before it changes anything, 6.4) with the privileged-instruction vector, as `halt` and `reset` did on the PDP-11.

6.2.1 There are three modes, with the PDP-11's encoding: kernel 0, supervisor 1, user 3. The supervisor mode exists in the status word and in the banked registers, and no code uses it. *(D)*

6.2.2 The status word holds the flags in bits 0 to 3, the trace bit in bit 4, the interrupt priority in bits 5 to 7, the current mode in bits 8 and 9, the previous mode in bits 10 and 11, and the user-access guard in bit 12; the other bits are zero. *(D)*

6.2.3 `MTPS` in user mode writes only the flags; in kernel mode it writes every writable bit. `SPL #n` is kernel-only. *(D)*

6.2.4 The stack pointer `R14` and the direct-page register `DP` each have one copy per mode; the mode selects which one an instruction names. *(D)*

6.2.5 These instructions abort with the privileged-instruction vector outside kernel mode: `RTI`, `RTT`, `HALT`, `SPL`, `MTASID`, `MFASID`, `TLBI`, `TLBIA`, `TLBSYNC`, `MTDMW`, `MFSR`, `MTSR`, `PROBER`, `PROBEW`, `WFE`, `ISYNC`, `STUA`, `CLUA`, `PUSHX`, `POPX`. *(D)*

6.2.6 These are not privileged: `MTDP` and `MFDP` (in user mode, the thread pointer), `ICINV` and `ICINVA` (a JIT needs them), `FENCE`, `SEV`, `HINT`, `TRAP`, `BPT`, `NOP`, and `MTPS` and `MFPS` with the restriction above. *(D)*

`DP` is new to a PDP-11 reader. It is the **direct-page register** (a base register that makes one region addressable with a short displacement, descended from the 6502's zero page). The kernel's copy points to the structure of the core it is running on (the **per-CPU pointer**: which core am I, and where is its private data); a user program's copy points to its thread's private data, so a thread-local variable is one `MOVQ d(DP), Rd`.

Lineage. **PDP-11:** three modes, a stack pointer per mode, priority and mode fields in the status word; V7 used kernel and user, and 2.11BSD runs its network code in supervisor mode (`trap()` tests `SUPVMODE(ps)`, checked). **Between:** x86 has four rings of which two are used; AArch64 has exception levels 0 to 3; RISC-V has user, supervisor and machine modes (all *unverified*). Each later design kept a privilege ladder and a banked stack pointer. **pdp64:** the PDP-11's three modes and its stack-pointer banking, so entry from user mode needs no stack switch code, plus a banked `DP`. The third mode costs a third copy of two registers and no logic the kernel uses.

6.3 Exceptions, interrupts and traps: how the machine enters the kernel


The PDP-11 used one word, "trap", for three different events, and the pdp64 names them apart. An **exception** is the machine stopping an instruction because it cannot carry it out (a page that is not in memory, an illegal instruction, a division by zero); it belongs to the instruction. An **interrupt** is a device asking for attention; it belongs to no instruction and is taken between two of them. A **trap**, in the narrow sense used here, is a deliberate entry by an instruction that succeeds (`TRAP #n`, the system call). All three enter the kernel the same way.

The PDP-11's way. The hardware read the new PC and PS from the vector, pushed the old pair on the kernel stack and ran the handler. This is **entry through memory**: two words are written to the stack before one handler instruction runs.

The pdp64's way. Entry writes only registers and then reads one word. Four **system registers** (registers outside the general ones, reached with `MFSR` and `MTSR`, 6.5) receive the facts: `EPC` (exception program counter: where to resume), `EPSW` (the old status word), `EVA` (exception virtual address: the address that caused a fault) and `ECAUSE` (what happened: the vector number). The new status word is made, and the new program counter is read from the **vector table**: an array of 512 entries of 8 bytes, 4096 bytes in all, whose base is in the register `VBR` (vector base register). `kind` below is one of the families of 6.4:

```
enter(vector, kind):
    EPC    = (kind is abort or progress) ? address of this instruction
                                         : address of the next instruction
    EPSW   = PSW
    EVA    = (kind is abort) ? the faulting address : 0
    ECAUSE = vector
```

```
PSW.previous_mode = PSW.current_mode
PSW.current_mode  = kernel
PSW.priority      = 7
PSW.trace = 0 ; PSW.flags = 0 ; PSW.guard = 0        # the guard: section 6.10
PC = load64_physical(VBR + 8 * vector)               # a bus error here is a machine check
```



Three differences from the PDP-11 matter to a kernel writer. Entry **cannot fault**: writing registers cannot meet a missing page, as a push on a kernel stack could. Entry **leaves the saving to the handler**: the hardware pushes nothing, so a handler that may be interrupted first saves EPC and EPSW (one instruction, PUSHX), and one that cannot be interrupted need not save them. Entry is **the same for every cause**: V7's trap vectors say `br7` and its device vectors `br4` and `br6`, each vector choosing its own priority, while the pdp64 always enters at priority 7 and the handler lowers it. A second exception before the handler has saved EPC and EPSW would overwrite them. The first instructions of every handler, and the memory they touch, therefore must not fault, which is why the kernel's text and stacks are in pages every address space shares or in a direct-mapping window (6.9). (That consequence is this chapter's reading; the architecture document states a related rule, that the entry code and kernel stack are pinned until the save is done.)

The table. ECAUSE receives the vector number, so one handler can serve several vectors and tell them apart. Vectors 0 to 31 are for the processor, 32 to 63 for interrupts, 64 to 255 are reserved and 256 to 511 are one per TRAP number. In V7 every `sys n` shared the single vector at 034 and the number was fetched from the instruction.

6.3.1 Entry to an exception or an interrupt writes only registers: EPC receives the address of the faulting instruction (for an abort or a progress exception) or of the next instruction (for a trap or an interrupt), EPSW the old status word, EVA the faulting address (zero except for aborts), ECAUSE the vector number. *(D)*

6.3.2 The new status word has the current mode kernel, the previous mode the old current mode, priority 7, and the trace bit and the flags cleared. *(D)*

6.3.3 The new program counter is the 64-bit word at the physical address `VBR + 8 × vector`; a bus error on that fetch is a machine check that halts. *(D)*

6.3.4 The hardware pushes nothing. A handler that can be interrupted saves EPC and EPSW with PUSHX, lowers the priority with SPL, and before returning restores them with POPX and executes RTI. *(D)*

6.3.5 RTI loads the program counter from EPC and the status word from EPSW; RTT does the same and sets the trace bit after the return. *(D)*

6.3.6 The vector table has 512 entries and ECAUSE equals the vector number. *(D)*

Vectors	Meaning
0	reset (not used by the QEMU machine)

Vectors	Meaning
1	machine check
2, 3, 4, 5	illegal instruction, privileged instruction, misaligned access, non-canonical address
6, 7, 8	instruction, load and store page fault
9, 10, 11	protection violation on instruction, load and store
12, 13	divide by zero, bus fault
14, 15	landing-pad violation, breakpoint
16 to 31	reserved
32 to 63	interrupts (in the virt machine, 32 timer, 33 console input, 34 console output)
64 to 255	reserved (device interrupts are message-signalled, section 5.9)
256 + n	`TRAP #n` and `TRAPL #n`, n from 0 to 255

6.3.7 There are eight interrupt priority levels; the processor takes an interrupt between instructions when its level is greater than the priority in the status word; the timer is at level 6 and the console at level 4. *(D)*

The two levels are the PDP-11's: V7 vectors the line clock at priority 6 and the console at 4 (`l.s`, checked above). A **message-signalled interrupt** is a device raising an interrupt by writing a word to a memory address, so that no interrupt wire is needed (section 2.7). How such a write becomes a vector number, and which core receives it, is **not specified** (2.7.3, the interrupt-controller decision R1 of appendix B); vectors 64 to 255 are reserved for it.

Lineage. **PDP-11:** push PC and PS on the kernel stack, load a new pair from the vector; trap vectors conventionally held priority 7 (V7 `l.s`: every trap vector is `br7+code`). **Between:** the VAX pushed the program counter and the processor status longword, and raised the priority to the interrupt's level for an interrupt but not for an exception (*unverified*); x86 pushes five words on the stack (*unverified*); AArch64 and RISC-V latch the return address and status in registers (*unverified*). **pdp64:** the register form, so entry cannot fault and costs no memory write; priority 7 is fixed on entry so that no interrupt can overwrite the saved pair before the handler stores it. The kernel survey estimates a system-call entry at four or five instructions on paper, against 45 to 70 on the RISC kernels it examined; it is a paper estimate, not a measurement. Handlers written in C need a short assembler stub to save and restore registers.

6.4 Faults and restart: what "precise" means

When an instruction cannot finish (its page is absent, say), the machine must stop it, tell the kernel and, once the kernel has removed the cause, **restart** it (run it again from the start). Whether that works depends on what the instruction did before it stopped.

On the PDP-11 it did not always work. `cmp -(sp),-(sp)` changes a register (`sp` goes down by 2, twice) while it works out its operands, and may then fault on the second operand; rerun as it stands, it leaves `sp` 4 too low. The hardware therefore kept a small journal of the register changes (the register `MMR1`, on the machines that had one), and the kernel's `backup()` read it and undid them before the restart. The 2.11BSD `trap()` says that on the 11/40, which had no such register, "the routine backup/mch.s may fail", and then so may the automatic growth of the user stack, which relies on restarting. Floating-point errors were worse: V7 and 2.11BSD both say "the floating exception is an imprecise trap", meaning that by the time it was taken the processor had run on, and the saved PC no longer named the faulting instruction.

Between. The VAX saved resumable microstate and a status-word bit for instructions interrupted half way; the 68000 had no restart path for a bus error in its first form (both *unverified*, repository text). The next step was to make exceptions precise by design and let the compiler and hardware avoid the cases that were not.

On the pdp64 every exception that belongs to an instruction is **precise**. A **precise exception** (one taken so that the machine looks as if it ran one instruction at a time, in order: every earlier instruction has completed, and the faulting instruction and every later one have changed nothing) lets the kernel treat a page fault as a subroutine call the program never noticed. It matters here because the pdp64 is meant to be built both as a simple **in-order core** (one that runs instructions one after the other, as the PDP-11 did) and as an **out-of-order core** (one that looks ahead, starts later instructions whose inputs are ready before earlier ones have finished, and holds the results in a buffer until the earlier instructions are known not to have faulted; errata 68). In the second kind the faulting instruction is one of dozens in flight, some already half done; the machine must discard their results and report the fault as if none had started. The architecture makes this possible without a journal. An instruction has at most one memory operand, and the register update of an auto-increment or auto-decrement mode is held until the instruction **retires** (is certain to complete) and thrown away if it aborts (6.4.2; `docs/pdp64-isa.md` section

7.2 has the argument and 7.3 the table of every reference that can fault). The author's remark on this (2026-11-09): "pdp64 specifically designs the instructions for minimal uops, so we have minimal restart/recovery code needed, no?".

Four families. The kernel sees separately the cases that the PDP-11 mixed together:

Family	The instruction	`EPC` on entry	Restartable
trap	completes	the next instruction	not applicable
abort	annulled, as if it had not begun	the faulting instruction	yes, by `RTI`
progress	partly done, the progress is in registers	the faulting instruction	yes, by `RTI`
machine check	indeterminate	best effort	no

A **progress** exception belongs to the block instructions (`MCPY` and the others of the `MBLK` group, section 9.7). A copy of a megabyte may take 256 page faults; the instruction keeps its position in its own registers, so `RTI` re-executes it and it carries on from where it stopped. A **machine check** descends from the PDP-11's bus error at vector 004: something happened that the machine cannot repair or locate exactly (an uncorrectable memory error, a posted write that timed out), and the kernel can only stop the process or the machine. A **posted write** (a store the processor has handed on and no longer waits for) is the reason: when the bus reports the failure the instruction retired long ago.

6.4.1 Faults fall in four categories: traps (the instruction completes), aborts (it is annulled and restarted), progress (a block operation stopped part-way, restarted from its registers) and machine checks (not restartable). *(D)*

6.4.2 The register update of an auto-increment or auto-decrement mode is held until the instruction retires and discarded by an abort, so a handler never undoes anything. *(D)*

6.4.3 A read of non-existent memory is a precise abort with cause `BUSFAULT`; a posted write that times out and an uncorrectable memory error are machine checks. *(D)*

Three consequences. The undo buffer is a single entry, and row 3 of the fault matrix (an operand write) can never fault, so no journal or undo protocol exists. One small page-fault handler serves first touch, first write and demand paging (6.11), and there is no `backup()` and no `MMR1`. The `nofault` idiom of V6 and V7 `trap.c` (set the global, do the probe, `longjmp` out of the handler instead of panicking) remains the pattern for probing hardware, though `PROBER` and `PROBEW` cover address validation. A read of a configuration position that holds no device is not a fault at all (it returns all ones, 2.4.9), so a bus scan does not take a `BUSFAULT` for every empty slot. The pdp64 makes floating-point exceptions flags that never trap, so they need no imprecise case; whether current architectures keep exceptions precise for page faults and leave some floating-point and bus errors imprecise is *unverified*.

6.5 System registers: `MFSR` and `MTSR`

The PDP-11 reached its control registers by address. The KT11's page registers, the status word and the other control and status registers sit in the top 8 KB of the address space, the I/O page (`KISA6` at 0172354, `UISD` at 0177600, the PS at 0177776), and the kernel used ordinary `mov` instructions on them. The pdp64 cannot, because its address space is translated (6.6): a load or store to a control register would itself be translated, and an instruction that changes the translation would change the mapping of the access that reads it. Control registers are **system registers**, numbered 0 to 255, read and written by `MFSR Rd, name` (move from system register) and `MTSR name, Rs` (move to system register). Both are privileged (6.2.5).

6.5.1 The system registers are reached by `MFSR` and `MTSR` with an 8-bit register number. *(D)*

Number	Register	Meaning
0	`PTBR`	physical address of the level-2 page table
1	`EPC`	exception program counter
2	`EVA`	exception virtual address
3	`ECAUSE`	exception cause (the vector number)
4, 5	`DMW0`, `DMW1`	direct-mapping windows (stored; the format is unspecified)
6, 7	`USP`, `SSP`	the user and supervisor stack pointers
8	`EPSW`	exception status word
9	`VBR`	vector base register
10	`MMUCTL`	memory-management control (bit 0 enables translation)
11	`ASID`	address-space identifier
12	`CPUID`	the core number (read-only)
13 and up		reserved (feature and identification registers are proposed here)

EVA and ECAUSE are read only, as is CPUID; the rest read and write. PTBR is called a level-2 table for the three-level form; it holds the top table of whichever number of levels the machine has (6.6). USP is the user's stack pointer, needed because in kernel mode R14 is the kernel's; it replaces the PDP-11 idiom `mfpd sp`, and the kernel reads and writes it to build a signal frame, copy a process or switch context. SSP is the supervisor's and nothing uses it. The register that 6.9.1 calls KTBR has no number in this table.

6.5.2 A write to PTBR, ASID or MMUCTL, or an ICINV, is guaranteed to take effect only after the next ISYNC. *(D)*


ISYNC (instruction synchronisation) makes this safe on a machine with more than one instruction in progress. A pipelined or out-of-order core has already fetched and started the instructions after the MTSR under the old translation; ISYNC waits for every earlier instruction to finish, discards everything fetched after it and fetches again under the new rules. The PDP-11 needed no such instruction, because an instruction was fetched after the previous one had finished.

Lineage. **PDP-11:** control registers at fixed high addresses, reached with ordinary moves. **Between:** the VAX had MTPR and MFPR with an internal-register number; AArch64 has MRS and MSR, RISC-V CSRR and CSRW, PowerPC MFSPR and MTSPR. **pdp64:** the VAX's numbered form. A new register is a number and not an instruction, and the 243 unused numbers cost nothing until used. The kernel survey found privileged-register access to be 48% of all the compiler-invisible instructions in four kernels; the compiler reaches them through an intrinsic with a constant number.

6.6 From segments to pages: virtual memory

Two kinds of address. A **virtual address** is the number a program uses; a **physical address** is the number the memory chips answer to. The PDP-11 had both, 16 bits against 18 or 22, and the KT11 translated one into the other. A pdp64 program has 64-bit pointers of which only some bits count (below), and the physical address is 40 to 64 bits wide (errata 102): 40 bits is one terabyte, and the maximum, 2^{64}, is sixteen exabytes.


What the KT11 cost. The figure puts the PDP-11 scheme (left) beside the pdp64's (right). On the left, the three top bits of a 16-bit address pick one of eight page registers, which says where an 8 KB piece starts and how long it is. Nothing is looked up, because the whole map of the running program is in the eight pairs. Three costs follow. A process had at most 64 KB (eight pieces of 8 KB; 128 KB with separate instruction and data space), and `estabur()` returns ENOMEM for a program that needs a ninth segment. Each piece was one **contiguous** block of physical memory, so memory fragmented, and the allocator either found a hole big enough or the kernel swapped something out to make one. And with only eight registers there was no way to leave a hole in the middle of a program unmapped, to share half a segment, to start a program before all of it was in memory, or to learn which part had been used.



Between: pages. The VAX had the remedy that most machines since have copied (*unverified*, repository text): cut both address spaces into equal pieces and let any virtual piece sit in any physical piece. The virtual piece is a **page** and the physical piece a **frame** (the same size, here 4 KB). A virtual address is a **page number** and an **offset** within the page; translation replaces the page number by a frame number and keeps the offset. The map from page numbers to frame numbers is a **page**

table: an array indexed by page number, each element (a **page-table entry**, PTE, 6.7) saying where the frame is, who may touch it and whether it is present. With pages a program's memory need not be contiguous; a page can be absent (fetched from disk when touched, which is **demand paging**) or shared by two programs; and the kernel can tell which pages are in use.

The tree. One flat table is too large. A 39-bit virtual address with 4 KB pages has 2^{27} pages (134 million); at 8 bytes an entry the table is 1 GB for every process, nearly all of it empty. Instead the table is a **tree**. Each table is exactly one page, 4096/8 = 512 entries, so nine bits of index, and some of its entries point to tables of the next level rather than to frames. The address is cut into 9-bit fields, one per level, over a 12-bit offset: with **three levels** it has 9 + 9 + 9 + 12 = 39 bits. Translation is a **walk**:



Each table is 512 entries x 8 bytes = 4 KB. PTBR holds the physical address of the top table.
With four levels bits 47-39 index a level-3 table above these; with five, bits 56-48 index a level-4 table above that.
A leaf found at level 1 maps 2 MB and ends the walk there; a leaf at level 2 maps 1 GB.

```
translate(va, access, mode):                        # three, four or five levels
    if va is not canonical:  fault NONCANONICAL     # bits above the top one must equal it
    table = PTBR                                    # physical address of the top table
    for level = LEVELS-1 down to 0:
        index = (va >> (12 + 9*level)) & 511
        pte   = load64_physical(table + 8*index)    # one memory read per level
        if not pte.V or pte has a reserved bit set: fault PAGE_FAULT
        if pte.R or pte.W or pte.X:                 # a leaf: the walk ends here
            break
        if level == 0:       fault PAGE_FAULT       # a pointer where nothing is left to point to
        table = pte.PPN << 12                       # follow the pointer to the next table
    check the leaf (6.7): permissions for this mode, accessed and dirty (6.8)
    size  = 4 KB << (9*level)                       # level 0: 4 KB; level 1: 2 MB; level 2: 1 GB
    return (pte.PPN << 12) | (va & (size - 1))
```

The pseudocode renders statements 6.6.1, 6.7.1 and 6.7.2 and was checked against the walker of the QEMU model (`qemu/target-pdp64/mmu.c`); a leaf not aligned to its size is also a page fault there. The cost is one memory read per level, three to five. A program that touches a few megabytes has a handful of tables, and the **sparse** address space (most of the 512 GB unused) costs nothing, because an entry that is not valid has no table under it. A leaf found above level 0 maps a larger piece, 2 MB at level 1 and 1 GB at level 2: a **large page** (many times the basic size, mapped by one entry; used for the kernel's own mapping and for big buffers). Its frame address must be aligned to its size.

Three, four or five. The author decided (errata 96) that the walk may have three levels (39 virtual bits: what System v1 specifies and what the simulator and the emulator implement), four (48 bits) or five (57 bits), with the number discoverable at run time. Each level adds nine bits and one more memory read per miss. His own referent was the Loongson five-level table ("what other parts of the design are effected if we have 5 level tlb like loongson arch?"). A **canonical** address has all bits above the top virtual bit equal to that bit, so a 39-bit machine accepts a 64-bit pointer only if bits 63 to 38 are all the same. This rules out storing a tag in the unused high bits, which would stop working on a machine with more levels.

6.6.1 Virtual addresses are translated by three, four or five levels of nine bits over 4 KB pages, which gives virtual addresses of 39, 48 or 57 bits. With three levels, address bits 38 to 30 index level 2, 29 to 21 level 1 and 20 to 12 level 0; with four, bits 47 to 39 index level 3 above them; with five, bits 56 to 48 index level 4 above that; `PTBR` holds the physical address of the table of the top level. *(D)*

6.6.1a Software can find the number of levels of the machine at run time, so that a kernel adapts to the implementation without a build option; the register or field that reports it is not specified. *(S)* The simulator and the emulator implement three levels.

What is open about 6.6.1a. The repository's briefing (`docs/decision-log/data/shared/oq/A.md`, item Q2) lists how other machines let software find out, each verified in the QEMU source here: x86's `CPUID` leaf 0x80000008 (widths) and the `LA57` bit for five levels; AArch64's `ID_AA64MMFR0` field `PARange`; LoongArch's `CPUCFG1` fields `PALEN` and `VALEN`; RISC-V's `satp`, where software writes the mode it wants and reads back whether it stuck. For the pdp64 it sets out a read-only feature register at system register 13, a write-and-read-back probe in `MMUCTL`, both, a field in the boot-information block (4.6.2) and a user-readable copy. **None is decided**; the leaning in the briefing is the assistant's, not the author's. The physical width has the same problem (errata 102(b)).


6.6.2 Virtual addresses are 39, 48 or 57 bits, translated by three, four or five levels of nine bits over 4 KB pages (6.6.1) to a physical address of 40 to 64 bits, 40 in the present implementation (section 2.3.6). *(D)*

Lineage. **PDP-11:** eight base-and-length segments per mode, no tables. **Between:** the VAX had a linear page table per region with a hardware modify bit and no reference bit (*unverified*, repository text); RISC-V's Sv39, Sv48 and Sv57 are the three-, four- and five-level forms with nine bits per level (`satp` modes 8, 9 and 10, checked in the QEMU source); x86-64 uses four levels, and five on newer parts through `LA57`; LoongArch describes the width of each level in a register (`PWCL`, checked). **pdp64:** the Sv39 geometry, with the level count left to the implementation. A leaf at any level makes large pages free for the kernel's own mapping, and the walker only reads, so it is a small state machine. Position-independent code uses PC-relative addressing, and pointers must not carry tags in the high bits.

6.7 The page-table entry

Each entry is one 64-bit word. The diagram shows every bit.

a page-table entry: 64 bits, the physical page number in place



V	valid: the entry means something; clear is a page fault
R W X	read, write, execute; all three clear means "pointer to the next table"; W without R is reserved
U	user: user mode may touch it (kernel mode may read and write a user page, never execute one)
G	global: the entry ignores the address-space number
A D	accessed, dirty: set by the kernel, never by the hardware; a clear bit is a page fault
MT	memory type: 0 normal cached, 1 normal uncached, 2 device strongly ordered, 3 device weakly ordered
rsvd	bits 10-11 and 40-63 must be zero; a set bit is a page fault (for 40-bit physical addresses; wider ones are open, 6.7.1)

Bit positions are those of statement 6.7.1; bits 0 to 7 are in the same places as in RISC-V.

An entry has two shapes. A **leaf** maps: at least one of `R`, `W`, `X` is set, and the physical page number is the frame the page lives in. A **pointer** says that the next table is here: `V` is set, `R`, `W` and `X` are all clear, and the page number is the next table's. When

valid `V` is zero nothing is mapped, and the other 63 bits are the kernel's to use, for example for the place on the swap device where the page now lives.

Permissions and modes. `R`, `W` and `X` allow reads, writes and instruction fetches. `U` says user mode may use the page, and user mode needs it. Kernel mode may read and write a user page, which is what lets it copy to and from user memory directly (6.10), but may never **execute** one, so a kernel tricked into jumping to user memory takes a fault. `W` without `R` is not a valid combination and is a fault. `G` (global) marks a translation the hardware keeps whatever the address space (6.8). Any undefined bit must be zero in a valid entry, and a set reserved bit is a page fault, which lets the format grow and catches a wild value written by the kernel.

Memory types. Each page says how the memory system may treat accesses to it, in the field `MT`. **Normal cached** (0) is ordinary memory, which the **caches** (small fast memories near the processor holding copies of recently used memory) may keep. **Normal uncached** (1) must not be cached, as for a frame buffer that the display hardware reads and the processor writes. The two device types are for device registers: **device strongly ordered** (2) sends every access to the device in exactly the order written, one at a time and never combined, and **device weakly ordered** (3) lets the machine combine or reorder accesses, for device memory where only the final result matters. The architecture text gives the four names and numbers; the glosses of the last two are the usual meanings and are *unverified*. The PDP-11 had no memory type: everything at the top of the address space was a device. The pdp64 has **no address bit that says "device"** (errata 97). The memory type is what a driver sets when it maps a device, and a device window can be anywhere in the physical address space except the first few pages (errata 102, section 2.3.6).

6.7.1 A page-table entry is 64 bits: `V` (valid) in bit 0, `R`, `W`, `X`, `U` and `G` (global) in bits 1 to 5, `A` (accessed) and `D` (dirty) in bits 6 and 7, the memory type `MT` in bits 8 and 9, and the physical page number in bits 12 to 39, in place in the present implementation; all other bits are zero, and a set reserved bit is a page fault. *(D)* The format of the entry for a physical address of up to 64 bits (2.3.6) is open: a page number of 52 bits in place would take bits 12 to 63 and leave no bit above bit 11 for anything else, and whether the entry keeps that shape or changes is the author's question. *(S)*

6.7.2 A non-leaf entry has `V` set and `R`, `W` and `X` clear and points to the next table; a leaf at level 2 maps 1 GB, at level 1 maps 2 MB and at level 0 maps 4 KB, and where the levels exist a leaf at level 3 maps 512 GB and at level 4 maps 256 TB. *(D)*

6.7.3 A user-mode access needs `U`; kernel mode may read and write user pages but may not execute them; `W` without `R` is reserved. *(D)*

6.7.4 The memory type of a page is one of normal cached, normal uncached, device strongly ordered and device weakly ordered. *(D)*

6.7.5 A page-table entry carries the physical page number in place and read, write, execute and user permission bits; accessed and dirty bits are managed by software; one memory type per page selects cached, uncached, strongly ordered or weakly ordered. *(D)*

What is open about 6.7.1. A page number for a 64-bit physical address needs 52 bits (bits 12 to 63). In place, that takes every bit of the entry above bit 11 and leaves nowhere for a later flag (a protection key, a wider memory type, a no-execute bit separate from `X`). The briefing (`A.md`, item Q3) sets out six shapes: the page number in place to bit 63; a cap at 40 bits (a 52-bit physical address, four petabytes through page tables, with the 12 bits above for flags and the windows of 6.9 for anything higher); a shift of the page number down to bit 10 as RISC-V does (checked: its number is in bits 10 to 53 and its flags `N` and `PBMT` in bits 63 to 61); and a 16-byte entry, which would change the nine bits per level and with them the 39, 48 and 57. **No format is chosen.** The simulator, the QEMU model and `spec/pdp64-system.hbnf` use 40 bits, the minimum. They also still compare the memory type of a page with bit 39 of its physical address (the rule of errata 60 and 65 that errata 97 removed); that check belongs to the present implementation and goes when the implementation catches up.

Lineage. **PDP-11:** a PDR with length and access bits, no per-page type. **Between:** the VAX entry held a hardware modify bit and a four-bit protection field (*unverified*); RISC-V's low eight bits are `V R W X U G A D` in the same places as here (checked in `cpu_bits.h`); ARM's memory types and LoongArch's `DMW` cache attributes are the source of the four types, reduced to what a machine of this size can tell apart (`docs/pdp64-isa.md` section 8.2). **pdp64:** one entry shape at every level keeps the walker simple. A memory type per page, not per access, means the code that writes a frame buffer needs no cooperation to be uncached, and a driver maps a device register uncached and strongly ordered without a special instruction.

6.8 Accessed, dirty, the translation buffer and address-space numbers

Accessed and dirty. A kernel that runs programs larger than memory must choose pages to throw out. It needs two facts: whether a page has been used lately (**accessed**, `A`) and whether it has been written since it was brought in (**dirty**, `D`: a dirty page must be written to disk before its frame is reused, a clean one can simply be dropped). On the VAX the hardware set a modify bit and the kernel emulated the reference bit (*unverified*, repository text). Many later machines, x86-64 and AArch64 among them (*unverified*), have the **walker** (the part of the memory-management hardware that reads the tables) set both bits itself by writing the page-table entry. The pdp64's walker **never writes a page table**. An access to a page with `A` clear, or a write to a page with `D` clear, takes the page fault of its kind; the kernel sets the bit and runs the instruction again. These are **software-managed** accessed and dirty bits. The cost is one extra fault the first time each page is touched and one the first time it is written; precise exceptions (6.4) make that fault cheap, and the walker stays a small read-only state machine.


6.8.1 The accessed and dirty bits are managed by software: an access to a page with `A` clear, or a write to a page with `D` clear, raises the page fault of its kind and the kernel sets the bit; the hardware walker never writes a page table. *(D)*

The translation buffer. The walk costs a memory read per level, three to five reads for every load, store and instruction fetch, which is unaffordable. Every machine with a walk therefore has a **translation buffer** (TLB, translation lookaside buffer: a small, very fast memory in the processor that keeps recent translations, so that a repeated access to the same page needs no walk). It is a **cache** (a small copy of a larger store, kept for speed) of translations. The PDP-11 had none: its eight page registers were the translation, loaded whole at each process switch, and there was no table to be slow.

the translation buffer (TLB): a cache of finished translations

ASID	G	virtual page	physical page	R W X U	A D MT
7	0	0x00000412	0x0003a1	R W . U	A D 0
7	0	0x00000413	0x0007c2	R . X U	A . 0
-	1	0xFFFFFC001	0x000100	R W X .	A D 0
12	0	0x00000412	0x0009ff	R W . U	A D 0

the same virtual page 0x412 appears twice, for address spaces 7 and 12: that is what the ASID is for; the global entry (G) answers for every address space and has no ASID.



TLBI rN drops the entry for one page (this ASID and the global ones); TLBIA drops all; both reach every core; TLBSYNC waits until all have finished. The size and organisation are the implementation's: the FPGA plan assumes 4-way, 64 entries (section 6.14).

An access looks in the buffer first, by virtual page number and address-space number (below). On a match (a **hit**) the physical page and permissions come out and the access proceeds with no memory read for the translation. Otherwise (a **miss**) the walker reads the tables; if the walk ends in a valid leaf with the right permissions and the right `A` and `D` it **fills** the buffer and the access is retried, and if not the access takes the page fault of 6.3. A miss costs one read per level; a program that touches no more pages than the buffer holds pays only for its first touches. The size and organisation are the implementation's choice. The FPGA plan (`docs/pdp64-system-architecture.md`) assumes a four-way set-associative buffer of 64 entries (**set-associative**: an entry may live in any of a few places chosen by the low bits of the page number, which is cheaper than a buffer that can put an entry anywhere); a buffer entry holds a page number as wide as the physical address, 28 bits at 40.

Keeping it honest. The buffer holds copies. When the kernel changes a page-table entry it must see that no stale copy remains, or a page it has unmapped or made read-only would still be reachable. An **invalidate** (removing entries from the buffer; "flush" in the older word) is `TLBI rN`, which drops the translation of the page containing the address in `rN` for the current address space and the global entries, or `TLBIA`, which drops everything. Each core has its own buffer, so the invalidate must reach all of them. On the pdp64 both instructions are **broadcast** (sent to every core by the hardware) and `TLBSYNC` waits until every core has finished, so the kernel knows nobody holds the old translation. Other architectures leave this to software, which sends an inter-processor interrupt to every other core and waits for the answers (a **shootdown**); the pain-

points report (`docs/kernel-pain-points.md`) counts the IPI deadlock cases among the costs. Unmapping a page is then three lines, as chapter 7 says (7.9.2):

```
unmap_page(space, va):
    pte_of(space, va) = 0          # change the entry in memory first
    TLBI va                        # drop the old translation, on every core
    TLBSYNC                        # wait until every core has done so
    # now the frame may be reused
```

6.8.2 Translation is off at reset (`MMUCTL` is zero and every address is physical) and is enabled by bit 0 of `MMUCTL`; the `ASID` selects non-global entries. *(D)*

6.8.3 `TLBI rN` invalidates the translation of the page containing the address in `rN` for the current address space and the global entries; `TLBIA` invalidates all; both broadcast to every core and `TLBSYNC` waits for the broadcast to finish. *(D)*

Address-space numbers. A process switch changes the page tables. If the buffer cannot tell which process an entry belongs to, the old process's entries would answer for the new one, so the whole buffer must be emptied at every switch and the new process starts with all misses. On the PDP-11 the corresponding cost was `sureg()` writing the new process's eight (or sixteen) pairs into the page registers: sixteen (or thirty-two) register writes with nothing to flush. For tables walked from memory the cost is worse, because the emptied buffer refills one miss at a time. The remedy is to **tag** every buffer entry with the number of the address space it came from, the **address-space identifier** (ASID, 16 bits on the pdp64, set with `MTASID`). An entry matches only if its tag equals the current ASID or it is **global** (`G` set, so it answers in every address space, as the kernel's own pages do). A switch is then a write to `PTBR` and to `ASID` and an `ISYNC` (6.5.2): the old process's entries stay in the buffer, harmless, and answer again if that process runs soon. The whole switch is pictured in 6.11. The reference executor does not yet behave this way: its `MTASID` flushes the whole buffer, and the entry of `MFSR` in chapter 9 says that a write to `PTBR`, `ASID` or `MMUCTL` flushes it. That defeats the purpose of the tags and is listed in 6.15.

There are 65,536 numbers. When they run out the kernel starts again: it allocates in order, and when the counter wraps it invalidates everything (`TLBIA`) and starts a new **generation**, so that a process holding a number from before is given a fresh one when it next runs. The policy is the kernel's. The architecture has no invalidate by ASID, which is listed as open (6.15).

Lineage. **PDP-11:** no buffer, no tags; `sureg()` rewrote the registers at every switch. **Between:** the VAX emulated reference bits in software under 4.3BSD (*unverified*); MIPS refills its translation buffer in software (*unverified*); x86 added a process-context tag late (the `PCIDE` bit of `CR4`, checked in the QEMU source; its width is *unverified*); RISC-V's `satp` carries a 16-bit address-space number (`SATP64_ASID`, checked) and software flushes other cores' buffers; AArch64 has a broadcast invalidate (*unverified*). The ISA text takes the ASID and the `G` bit from the Commodore 128's memory-management unit, which had four sets of map registers selected by one store and a common region that no map set could hide (`docs/pdp64-isa.md` section 8.1). **pdp64:** a 16-bit tag and a global bit; broadcast invalidates, so the kernel has no shootdown code; a walker that only reads. Hardware-managed accessed and dirty bits, advertised in a feature register, are a possible extension. A core with no speculation has no page-table side channels, which is one reason for the small walker.

6.9 Splitting the space, direct-mapping windows and the layout of an address space

One space or two. On the PDP-11 the kernel had its own address space, with its own eight page registers, and the user could not see it. A kernel on a later machine usually sits in the upper part of every process's own address space, so it can reach the process's memory directly, and the permission bits keep the user out. That arrangement has a hole. A processor that **speculates** (runs instructions ahead before it knows they are allowed, discarding the results if they were not) could on some designs read kernel memory before the permission check caught up, and leave a trace in the caches that a user program could measure. This is the flaw class made public in 2018; that it is the reason for the split below is *unverified* here (the repository states the reason only as in 6.9.1). The pdp64's answer is that **the user does not walk the kernel's tables at all**.

6.9.1 The translation is split by the top bit of the virtual address (bit 38 with three levels, 47 with four, 56 with five): clear selects the lower half, translated from the table at `PTBR` (one per address space), and set selects the upper half, translated from the table at the system register `KTBR` (one for the whole system, the kernel's). In user mode the upper half is never walked: an access to it takes a translation fault without consulting any page table, so no kernel translation is present for a speculating core to read around a permission check. In kernel mode both halves are walked, so the copy routines of 6.10 need no change of root. Entry to an exception changes the mode in hardware and so changes the halves walked; no entry trampoline is

mapped in user space. Translation-buffer entries carry the half they came from, and a mode change flushes nothing. The register number of KTBR and the layout of the top-level tables of the two roots are unspecified. *(D)*


This is the proposal of research round 7 that the author accepted (errata 71). It is **not yet implemented**: the simulator and the QEMU model have one table base, PTBR, and test only that the high bits equal bit 38. The work needed is a system-register number, the walker and the tests.

Direct-mapping windows. The kernel must also reach all of physical memory (to write a page it has just allocated, a DMA descriptor or a page table) and the memory of devices. Walking tables for that is slow and uses buffer entries. A **direct-mapping window** (DMW: a range of virtual addresses that the hardware maps to a range of physical addresses by one addition, with no page table and no buffer entry) does it. The instruction-set text sketches two windows, DMW0 and DMW1, each with a virtual base, a size and a memory type, kernel only, translating as `PA = VA − VirtualBase + PhysicalBase`. It gives three reasons: the kernel stops taking translation misses on its own text and data; physical memory is reachable without mapping it; and early boot becomes simple (`docs/pdp64-isa.md` section 8.3). The idea is LoongArch's DMW registers, a tidier descendant of MIPS's fixed KSEG0 region (whose behaviour on the real machine is *unverified* here). The author's remark (2026-11-09) was "good thing we already had dmw in the design!": the kernel need not walk anything to reach petabytes of physical memory or a deep table. **The format of the registers is not specified.** The manual stores them and does nothing with them (6.9.2), so the sketch is a sketch. The architecture document says the machine comes up with DMW0 covering physical memory, which disagrees with 6.8.2 (translation is off at reset); the manual follows 6.8.2.

6.9.2 Two direct-mapping windows, DMW0 and DMW1, are stored and their format is unspecified; MMUCTL bit 0 enables translation and is zero at reset, so every address is physical until the kernel turns it on. *(D)*

The layout of a process's address space. On a three-level machine a process sees the picture below. The two halves and the windows are the architecture's; what goes where in each half is the kernel's to choose, and the figure is one example.

the 39-bit virtual space of three levels: one example arrangement



The halves are decided; what goes in them is not specified. Each half is 2^38 bytes = 256 GB with three levels, 128 TB with four, 64 PB with five. The order, the sizes of the regions and the placement of the windows are the kernel's choice; nothing here is tested.

The **user half** holds the program's text, data, heap and stack, in pages with U set, reached through the process's own tree (PTBR, selected by the ASID); address zero is left unmapped so that a null pointer faults. The **kernel half** holds the kernel's text and data (global pages: one copy of the entries answers in every address space), the per-CPU structures (the kernel's DP points at them), the kernel stacks, the direct-mapping windows and the windows of **devices**. A device's registers are mapped by page entries with the device memory type (6.7) at the physical address that PCI Express enumeration found for them (chapter 2); no address bit and no fixed page says "this is a device". Between the two halves lie the addresses that are not canonical, and an access to one takes the non-canonical-address fault (vector 5).

Lineage. **PDP-11:** separate kernel and user spaces, crossed with `mfpi` and `mtpi`. **Between:** the VAX divided its address space into a process half and a system half (*unverified*: the VAX manual is not on this machine, though the 4.3BSD sources are); MIPS had the fixed `KSEG0` region (*unverified*); x86 kernels shared the user's tables until 2018 and have since paid a table switch on every entry (*unverified*); AArch64 has two translation base registers, `TTBR0` and `TTBR1` (*unverified*, not in the QEMU source checked here); LoongArch added the `DMW` registers (the author's referent). **pdp64:** the PDP-11's separation recovered in the VAX's shape, by one half-selecting bit and a second root register, and MIPS's fixed region generalised to two windows. An entry trampoline (a page of kernel code that some architectures map into user space so that an exception has somewhere to land) is not needed. The cost is a second root register, a second walk to cache, one comparator pair and one adder per window and a half bit in each buffer entry; a kernel that wants more regions than two windows maps them with large pages.

6.10 The user-memory guard and system calls

Reaching the user's memory. On the PDP-11 the kernel's pointers and the user's pointers lived in different spaces, so reaching user memory took `mfpi` and `mtpi` (6.1), and a user pointer used by mistake in kernel code failed on its own because the same number meant something else. On the pdp64 kernel and user pages share one address space, so the two kinds of pointer are the same kind of number. The kernel can copy from a user buffer with an ordinary load, and a **buggy kernel** (one that follows a user-supplied pointer without checking) can do it by mistake, which is how many attacks work. The guard is a status-word bit, `UA`: with it clear, a kernel-mode data access to a user page faults. The kernel sets it (`STUA`) only around the copy and clears it (`CLUA`) after, and entry to every exception clears it.

6.10.1 With the guard bit `UA` clear, a kernel-mode data access to a user page faults; `STUA` sets it and `CLUA` clears it; exception entry clears it and `EPSW` keeps the old value. *(D)*

System calls. A system call is `TRAP #n`, or `TRAPL #n` for the long form. It enters through vector `256 + n`, the next instruction becomes `EPC`, and the call number and arguments travel in registers named by the ABI. Appendix D does not give the system-call convention, and this chapter does not invent it. In V7, `sys n` entered one vector, `trap()` fetched the number back from the user's instruction with `fuiword`, and the arguments were read from the user's stack by `fuword`.

6.10.2 `TRAP #n` (n up to 15, two bytes) and `TRAPL #n` (n up to 255) enter the kernel through vector 256 + n; the system-call number and arguments travel in registers by the ABI. *(D)*

6.10.3 A copy routine opens the guard, copies, and closes it; every error path out of the copy must close it, and entry clearing it bounds the damage if one does not. *(D)*

A copy routine, for the case that a user address is bad:

```
copyin(user_src, kernel_dst, n):
    if PROBER(user_src) == 0 or PROBER(user_src + n - 1) == 0:   # readable in the previous mode?
        return EFAULT                     # PROBER tests, and takes no fault
    STUA                                  # open the guard
    memcpy(kernel_dst, user_src, n)       # may still fault, if the file was truncated under us
    CLUA                                  # close it, on every path out
    return 0
```

Lineage. **PDP-11:** explicit `MFPI` and `MTPI`, so accidental access was impossible. **Between:** the VAX read user addresses directly after a `PROBER` check (*unverified*); x86 added `SMAP` with `STAC` and `CLAC`, AArch64 `PAN` and RISC-V `SUM` (`SUM` checked in the QEMU source; the others *unverified*). **pdp64:** the guard is a mode bit because it lives in the status word, which is saved anyway. A stray kernel pointer becomes a clean fault, at the cost of an open and a close around every user copy, and every error path must close it.

6.11 The kernel at work: five walks in pseudocode

Everything above is machinery; this section runs it. The pseudocode is **an illustration written for this chapter**, in the style of a V7 kernel, from the statements of this chapter. It is not from a pdp64 kernel (there is none) and is untested. Names such as `find_region`, `alloc_frame` and `tick` are what any Unix kernel has and are not specified by the architecture. The mnemonics (`PUSHX`, `POPX`, `SPL`, `MFSR`, `MTSR`, `TLBI`, `TLBSYNC`, `MTASID`, `ISYNC`, `WFE`, `RTI`) are real.

A system call. The program puts the call number and arguments in the registers the ABI names and executes `TRAP #0` (or whichever number the system uses). The processor does `enter(256 + n, trap)` of 6.3, which makes `EPC` the instruction after the `TRAP`:

```
vector 256+n  ->  syscall_entry:        # kernel mode, priority 7, R14 is the kernel stack
    PUSHX                               # save EPC and EPSW: one instruction
    save the registers the C code will clobber on the kernel stack
    SPL #0                              # let interrupts in: a system call may take a while
    number = the register the ABI names
    result = sysent[number].handler(args from the registers)     # copyin/copyout use STUA, CLUA
    put result and error in the registers the ABI names
    restore the registers
    SPL #7
    POPX                                # EPC and EPSW back
    RTI                                 # PC = EPC (the instruction after TRAP); PSW = EPSW: user mode again
```

A page fault. A load, store or instruction fetch whose translation is not valid, or whose A or D bit is clear, aborts with vector 7, 8 or 6 (6.3.6). EVA holds the address, EPC the faulting instruction, ECAUSE the kind. The handler below covers the page faults; vectors 9 to 11 (protection violations) are not handled in it.

```
page_fault:                             # vectors 6, 7, 8 (instruction, load, store)
    PUSHX
    save the registers the C code will clobber
    va    = MFSR EVA                    # read both before lowering the priority
    cause = MFSR ECAUSE
    SPL #0                              # we may sleep, reading the page from disk
    region = find_region(current_process, va)
    if region is none:                  # a wild pointer
        send SIGSEGV; goto leave        # (leave delivers the signal on the way out)
    if cause == STORE_FAULT and not region.writable:
        send SIGSEGV; goto leave
    pte = find_pte(current_process.space, va)        # the kernel walks the tree in software, too
    if pte is invalid:                               # the first touch
        frame = alloc_frame()
        fill frame from the file or with zeroes      # may sleep
        pte = make_pte(frame, region.permissions, A = 1, D = (cause == STORE_FAULT))
    else:                                            # valid, but A or D was clear
        pte.A = 1
        if cause == STORE_FAULT: pte.D = 1
    store pte
    TLBI va ; TLBSYNC                                # no stale copy of the old entry on any core
leave:
    SPL #7
    restore the registers
    POPX
    RTI                                              # EPC is the faulting instruction: it runs again
```


The same handler serves first touch, first write and paging in; only the bits it sets differ. The faulting instruction restarts because the abort was precise (6.4). A page fault taken by the kernel on a user address is the case the copy routines of 6.10 expect: under the proposal of 6.10.4 the handler looks up a **fixup** (a recovery address kept in a table, one per instruction that may fault) for the faulting EPC, and the copy returns an error.

A timer interrupt. The timer is vector 32 at level 6 (6.3.6, 6.3.7). This is the pdp64's `hardclock`:

```
timer_interrupt:                        # vector 32; entered at priority 7
    PUSHX
    save the registers the C code will clobber
    SPL #6                              # at the device's own level: only a higher one may interrupt
    tick()                              # advance time; charge the running process; run due timeouts
    if --current.time_slice <= 0: need_resched = 1
    SPL #7
    restore the registers
    if need_resched and the interrupted mode (EPSW) was user:
        call switch()                   # V7: "runrun"; see below
    POPX
    RTI
```

The V7 `call` routine does the same test (previous mode user, `_runrun` set) and makes an artificial trap number 12, "give up cpu", before it returns (`mch_i.s`, checked above).

A context switch. The kernel has decided to run another process. The user program's registers are already in the trap frame on its own kernel stack, so the switch deals only with the kernel's state and with the user stack pointer, which lives in a banked register that entry did not save. The picture shows what is touched; the V7 equivalents are `swtch()`, `resume()` and `sureg()`.




```
switch_to(old, new):                    # kernel mode, priority 7
    push the callee-saved registers (appendix D) on old's kernel stack
    old.ksp = R14                       # R14 in kernel mode is the kernel stack pointer
    old.usp = MFSR USP                  # the user's stack pointer is not in the trap frame
    R14     = new.ksp                   # one ordinary move: the stack changes here
    pop the callee-saved registers from new's kernel stack
    if new.space != old.space:
        MTSR PTBR, new.space.root       # the new top-level table
        MTASID new.space.asid           # the new address-space number
        ISYNC                           # both take effect now (6.5.2)
    return                              # to wherever new was when it called switch_to
                                        # (the return address was on the stack just loaded)

return_to_user(p):
    MTSR USP, p.usp                     # the user's own stack pointer; R14 is the kernel's
    restore the user registers from p's trap frame
    POPX                                # EPC and EPSW from p's trap frame
    RTI                                 # user mode, user PC
```

No entry in the translation buffer is touched: the entries of the process that stopped stay, tagged with its ASID, and are used again if it runs soon, and the kernel's own entries are global and serve both. How the kernel saves and restores a thread's **user** `DP` (the thread pointer, a banked register of user mode) at a thread switch is **not specified**: the system-register table (6.5.1) has no number for it, and `MTDP` and `MFDP` name only the current mode's copy. It is listed as open in 6.15.


The idle loop. With no process runnable the kernel waits for an interrupt. The PDP-11 lowered the priority so that an interrupt could be taken and executed `wait`; the V7 `idle` routine clears the priority bits and waits, and 2.11BSD's does `SPLLOW` and `wait` (both checked). The pdp64's `WFE` (wait for event) is the idle instruction (7.6.3), with the sequence of the proposal 7.6.2: `WFE` ends its sleep for an interrupt that is pending even though masked, so there is no gap between testing for work and sleeping:

```
idle():
    loop:
        SPL #7                          # mask everything while we look
        if run_queue is not empty:  SPL #0 ; return
```

```
        WFE                             # sleep until an event or an interrupt, masked or not
        SPL #0                          # now take the interrupt that woke us
```

6.12 Reset, the first pages and the first kernel

What the machine contains at power-on. There is no kernel yet. A boot ROM (chapter 4) reads one block into low memory and starts core 0. The architecture fixes that state, and the first pages of physical memory hold the vector table, the block, the information block and the stack:



(not to scale; the place and size of the boot-information block are not specified)
After reset: kernel mode, priority 7, translation off (every address physical), VBR 0, guard clear.
The PDP-11 kept its vectors in the low few hundred bytes (V7 goes past octal 0224) and booted from elsewhere; here the table is one whole page at

The **vector table** is 512 × 8 = 4096 bytes, exactly one page, at address 0 because `VBR` is zero at reset; the kernel moves it by writing `VBR` and executing `ISYNC`. The PDP-11 also had its vectors at address 0, but as a fixed table of a few hundred bytes (V7's `l.s` goes past octal 0224), and its boot ROMs lived elsewhere. The pdp64's block 0, the 512 bytes the ROM reads from the disk, goes to **0x1000**, an address still marked "to be chosen" (`docs/boot.md`), so the first stage runs above the table. The **boot-information block** (memory ranges, core count, the address of the root complex, the boot device, the console, a checksum and a version, 4.6.2) is pointed to by `r1`; its size and place are not specified. **`r14`**, the stack pointer, is the top of the first 64 KB of memory. By errata 102 no device window is mapped in **the first few pages**. How many that is has not been decided (the briefing, `A.md` item Q1, sets out six options from one page to a megabyte and leaves it to the author); the 64 KB of `r14` is only the stack's place.

6.12.1 At reset core 0 starts in kernel mode at priority 7 with translation off, the guard clear and `VBR` zero; the kernel sets `VBR`, builds page tables, writes `PTBR`, sets `MMUCTL` bit 0 and executes `ISYNC`. *(D for the QEMU machine; P for the architectural reset, chapter 4)*

6.12.2 The QEMU machine starts at the entry point of the ELF given with `-kernel`, with the kernel stack at the top of memory; the option `kernel-mode=on` turns off the system-call stand-in of user-mode programs so that `TRAP` enters the kernel. *(D)*

6.12.3 The first operating system is OpenBSD, with Unix/32V as the fallback if OpenBSD proves too hard. *(D)*

The first kernel in outline (illustration):

```
kernel_entry:                           # core 0, kernel mode, priority 7, translation off
    R14 is already a stack (the top of the first 64 KB)
    MTSR VBR, kernel_vector_table       # the table the kernel built or linked
    ISYNC
    read the boot-information block at r1 : memory ranges, core count, root complex
    build the kernel's page tables (the upper half, global pages; section 6.9)
    MTSR PTBR, user_root_for_process_0  # the lower half; ASID 0
    MTSR MMUCTL, 1                      # bit 0: translation on
    ISYNC                               # from here every address is virtual (see below)
    enumerate the bus (section 2.4); start the other cores (7.8); start the clock; run init
```

What is not settled. The instruction after `ISYNC` is fetched through the new tables, so the running code must already be reachable at its virtual address, and the repository does not say how. Boot code runs at physical addresses up to the enabling write; afterwards it continues only if the kernel has mapped its own code at the address it is running at, for that moment, or if a direct-mapping window covers physical memory. The window format is open (6.9.2), so the second way cannot be relied on yet. The question is in 6.15.

Lineage. **PDP-11:** the memory manager was turned on by writing a bit in its status register (V7 `mch_i.s` does `mov $1,SSR0`, checked), and the VAX did the same with a jump to a mapped address (*unverified*); each needed a transition in the boot code. **Between:** RISC-V's `satp` has a bare mode and AArch64 has `SCTLR.M` (*unverified*). **pdp64:** translation off at reset, one enable bit in `MMUCTL`, one `ISYNC`. The first kernel code is position-independent and uses no virtual address until translation is on.

6.13 System instructions, exceptions and interrupts

This section collects, in the vocabulary of the kernel, the statements of 6.2 to 6.10 that an implementer needs side by side. The entries of the instructions are in chapter 9.

6.13.1 There are three modes (kernel, supervisor, user); supervisor is defined and unused. System instructions executed outside kernel mode abort with the privileged-instruction vector. *(D)*

6.13.2 `TRAP #n` (0 to 15, two bytes) and `TRAPL #n` (vectors 0 to 255) enter the kernel; `RTI` returns, and `RTT` returns and sets the trace bit after. *(D)*

6.13.3 An exception or interrupt writes only registers: `EPC` receives the address of the faulting instruction (or the next one, for a trap or interrupt), `EPSW` the old status word, `EVA` the faulting address and `ECAUSE` the vector number; the new program counter is the 64-bit word at `VBR + 8 × vector`. *(D)*

6.13.4 Entry sets the priority to 7 for every exception and every interrupt; the handler lowers it. *(D)*

6.13.5 There are eight interrupt priority levels; `SPL #n` sets the priority without touching the flags. *(D)*

6.13.6 `MFSR` and `MTSR` read and write the system registers by number; `TLBI`, `TLBIA` and `TLBSYNC` invalidate translations (broadcast to other cores); `MTASID` and `MFASID` set the address-space tag; `ICINV` and `ICINVA` invalidate the instruction cache; `PROBER` and `PROBEW` test an address; `MFCPUID` identifies the processor. *(D)*

6.13.7 `UA` in the status word guards user memory: with it clear, a kernel-mode data access to a user page faults; `STUA` sets it and `CLUA` clears it; entry clears it. *(D)*

The modes and exceptions are 6.2 to 6.4 and the multiprocessor instructions are chapter 7. `PROBER` and `PROBEW` replace the `nofault` idiom for address checks, and `ISYNC` follows a write to the page-table base or the vector base. The compiler never emits these instructions except through intrinsics.

The instruction entries for this section are in chapter 9, section 9.14: each entry there is complete (syntax, encoding diagram, operation, flags, exceptions, status); the commentary above gives the reasons and the use.

Entry	Mnemonics
No operation and landing pad	`NOP`, `LPAD`
Return from interrupt or exception	`RTI`, `RTT`
Return from subroutine	`RET`
Halt the processor	`HALT`
Breakpoint	`BPT`
Memory fence	`FENCE`
Wait for an event	`WFE`
Send an event	`SEV`
Invalidate all translations; wait for translation invalidations; invalidate the whole instruction cache	`TLBIA`, `TLBSYNC`, `ICINVA`
Push and pop the exception state	`PUSHX`, `POPX`
Instruction synchronisation	`ISYNC`
Hint	`HINT`
Move from and to a system register	`MFSR`, `MTSR`
Move to and from the processor status word	`MTPS`, `MFPS`
Set the interrupt priority level	`SPL`
System call and trap	`TRAP`, `TRAPL`
Invalidate a translation	`TLBI`

Entry	Mnemonics
Move to and from the address-space identifier	`MTASID`, `MFASID`
Move to and from the direct pointer	`MTDP`, `MFDP`
Move to a direct-mapping window	`MTDMW`
Read the processor identifier	`MFCPUID`
Invalidate the instruction cache for an address	`ICINV`
Probe an address for read or write access	`PROBER`, `PROBEW`

6.14 What was checked, and what was not

The rule of the project is to check and not to guess. The handbooks for the PDP-11 and the VAX are not on this machine. What was available, and what each fact rests on:

- **Checked against the Unix sources on this machine** (`/home/david/claude/facetlang/unixtree`, files gzipped: the V7M kernel under `V7M/sys` and 2.11BSD under `2.11BSD/sys`): the V7 vector table (`conf/l.s`: the pairs `trap; br7+n`, the console at 060 and 064 at `br4`, the clock at 0100 at `br6`; the file has no `. = ZERO+4` line, the vectors follow a branch and the word 4 at 0 and 2); the processor-status address 0177776 (`PS` in 2.11BSD `mch_iopage.h`) and the status fields in `pdp/psl.h` (`PSL_CURMOD`, `PSL_PRVMOD`, `PSL_IPL`, `PSL_T`, the condition codes); the KT11 register addresses in `pdp/seg.h` (`UISD` 0177600, `UISA` 0177640, `KISA0` 0172340, `KISA6` 0172354); `trap(dev, sp, r1, nps, r0, pc, ps)` and its comment; the system-call dispatch `sysent[fuiword((caddr_t)(a-1))&077]` (V7 `sys/trap.c`); `estabur()` and `sureg()` (eight page-register pairs per mode, sixteen with separate instruction and data space, `ENOMEM` when the segments exceed eight or the image exceeds memory, the segment of at most 128 blocks of 64 bytes); the first-fit core allocator (`malloc.c`: "The core map unit is 64 bytes", "Algorithm is first-fit"); `mfpi`, `mtpi` and the `nofault` global in `mch_i.s`; the `wait` of the V7 and 2.11BSD idle routines; the artificial trap 12 "give up cpu" of the interrupt exit when `_runrun` is set, and the write of 1 to `SSR0` (`mch_i.s`); the comments that the floating exception is an imprecise trap and that `backup()` may fail on the 11/40 (2.11BSD `pdp/trap.c`); supervisor mode used by the 2.11BSD network (`SUPVMODE`); `sched()`, `swapout()` and `swapin()` by name; the comment about "18 bit controllers present in" 22-bit Q-bus systems (2.11BSD `machdep.c`).
- **Checked against the QEMU sources** (`/home/david/claude/qemu-src`): RISC-V's `satp` modes 8, 9 and 10 (Sv39, Sv48, Sv57), its 16-bit address-space field, its entry bits `V R W X U G A D` in bits 0 to 7 and its page number at bit 10, its `SUM` bit; x86's `CPUID` leaf 0x80000008 and the `PCIDE` bit of `CR4`; AArch64's `ID_AA64MMFR0` field `PARange`; LoongArch's `CPUCFG1` fields and `PWCL` register.
- **Checked against the repository:** the statements of this chapter against `docs/pdp64-isa.md` sections 7 and 8, `docs/pdp64-system-architecture.md`, `docs/errata.md` (43, 60, 65, 71, 96, 97, 100, 102, 103) and the walker of the QEMU model (`qemu/target-pdp64/mmu.c`), which implements the walk of 6.6 with three levels, the reserved-bit and alignment checks and software accessed and dirty bits, and implements neither the split of 6.9.1 nor the windows. The vector numbers and system-register numbers are those of `qemu/target-pdp64/gen/pdp64-consts.h`. The simulator's status word has no `UA` bit yet (its valid bits stop at bit 11); the guard of 6.10 is decided (errata 43) and not implemented.
- **The repository's sizing, not measured:** the plan for the translation buffer on the FPGA, four-way and 64 entries (`docs/pdp64-system-architecture.md`); the kernel survey's estimate of four or five instructions for a system-call entry, against 45 to 70 on RISC kernels (`docs/kernel-pain-points.md`).
- **Unverified** (general knowledge, the handbooks not being on this machine): the names **APF**, and the layouts of the **PAR** and **PDR** beyond what the 2.11BSD code shows (the length field and the access and extension bits); that the KT11 gave 18-bit physical addresses on the original models and 22 bits on later ones; that the I/O page is the top 8 KB of the physical space; the bit positions of the status word apart from those 2.11BSD's header gives; `MMR1` as the register that recorded the auto-increment changes (the repository's text says so, and the 2.11BSD `backup()` routine is its user); the VAX's regions, modify bit and missing reference bit, its entry sequence, its process and system halves, its `MTPR`, its protection field and its `PROBER` use; that the 68000 had no restart path; that MIPS `KSEG0` is a fixed unmapped region and that MIPS refills its buffer in software; the width of x86's process-context tag and the five words x86 pushes; AArch64's two translation base registers, `PAN`, hardware-managed accessed and dirty bits and broadcast invalidate; x86 rings, AArch64 exception levels and RISC-V modes; that the speculative-execution flaw of 2018 is the reason for the split of 6.9.1; the usual meanings of "strongly ordered" and "weakly ordered"; which instructions the PDP-11 forbade in user mode; that x86 kernels removed the kernel half from the user's tables only after 2018; that current architectures keep exceptions precise for page faults.
- **Decided by the author and recorded in `errata.md`:** everything stated as a decision with a tag *(D)*; the illustrations of 6.11 and 6.12 are not decisions.

6.15 Still open

Decisions the author has asked for, or that follow from the author's, and that are not made: (a) the register or field that tells software how many levels the machine has and how wide its physical address is (6.6.1a; errata 96, 102(b)); (b) the format of the page-table entry for a physical address wider than 40 bits (6.7.1; errata 102(c)); (c) `KTBR`: its system-register number and the layout of the top-level tables of the two roots, and whether the user half is the lower half in every case (6.9.1); (d) the format of the direct-mapping windows `DMW0` and `DMW1`, which are stored and have no effect (6.9.2); (e) how many pages "the first few" are, and the address of block 0 (6.12; errata 102(a)); (f) what covers the fetch after the write that turns translation on (6.12).

Smaller items, from the older text and from writing this chapter: the use of supervisor mode; hardware breakpoints and watchdogs; performance counters; machine-check reporting beyond halting; feature and identification registers from register 13 up; a translation-buffer invalidate by address-space tag, and the policy when the 16-bit tags run out; how the kernel saves and restores a thread's user `DP` (6.11); which registers carry the system-call number and arguments (6.10.2: "by the ABI", and appendix D does not give the convention); whether the software-managed accessed and dirty bits are to be joined by a hardware-managed option advertised in a feature register (6.8); the flush of the whole translation buffer on a write to `PTBR`, `ASID` or `MMUCTL` that the entry of `MFSR` states and the reference executor performs, against the purpose of the ASID (6.8); the check of the memory type against bit 39 that the implementation still performs (6.7), which errata 97 removed from the architecture (appendix B); and that the simulator's status word has no `UA` bit (6.14).

Chapter 7 — Multiple processors

The pdp64 is built so that adding a second core needs seventeen operations, one per-core register, and nothing a kernel writer has to work around: memory is sequentially consistent, the atomics are one instruction each, the per-CPU pointer is a register that already exists, and the other cores' translation buffers are invalidated by a single broadcast. The chapter collects everything the architecture adds for symmetric multiprocessing, what a kernel does with it, what is left out, and what the device side supplies. The instruction-set text is `../pdp64-isa.md`, section 17. Tags: *(D)* decided; *(P)* proposed.

7.1 The seventeen operations

7.1.1 The instructions that exist for multiple processors fall under one umbrella of seventeen operations: ten atomics and seven others. *(D)*

Group	Operations
Atomics (10)	compare-and-swap (`CAS`), swap (`SWAP`), fetch-and-add (`XADD`), fetch-and-and (`XAND`), fetch-and-or (`XOR_`), fetch-and-exclusive-or (`XXOR`), fetch-and-maximum (`XMAX`, with `XMAXU`), fetch-and-minimum (`XMIN`, with `XMINU`), load-linked (`LL`), store-conditional (`SC`)
Others (7)	`FENCE`, wait-for-event (`WFE`), send-event (`SEV`), `TLBI` (with `TLBIA` as its "all" form), `TLBSYNC`, instruction-cache invalidate (`ICINV`, with `ICINVA`), read the core number (`MFCPUID`)

7.1.2 Every atomic has a variant, `_DB`, that folds a barrier into the instruction, so that a lock acquire or release is one instruction. *(D)*

7.1.3 The atomics live in the atomic escape group and the other operations in the system group; the umbrella is conceptual, not an encoding. *(D)*

7.1.4 Supporting these are the banked direct-page register, the address-space tag, the global-page bit and the banked stack pointer (section 7.4). *(D)*

Commentary. **Precedent.** The PDP-11/70's read-modify-write instructions were indivisible on the Unibus (`DATIP` and `DATO`); the VAX added interlocked instructions (`BBSSI`, `ADAWI` and the queue instructions) and multiprocessor models, and the 4.3BSD kernel on them still used `spl` for exclusion. **Trade-offs.** The set is the union of the three designs found on other machines (compare-and-swap, load-linked and store-conditional, fetch-and-operate), which is more atomic operations than any architecture surveyed, in exchange for nothing a kernel writer has to emulate. **Improvements.** The `_DB` forms were taken from LoongArch: a lock acquire should be one instruction, with no separate fence. **Benefits.** The seven non-atomic operations are the minimum that a kernel cannot synthesise: which core am I, wait and signal, invalidate everywhere, and make the instruction fetch see what the data side wrote. **Modern comparables.** RISC-V's `LR`/`SC` and `AMO` set, AArch64's exclusive loads and stores and its large-system atomics, x86's `LOCK`-prefixed read-modify-write. **Impact.** *Kernel:* Each of the seventeen operations is one instruction in the kernel's lock, idle, shootdown and per-CPU code. *Compiler:* C11 atomics and the kernel's intrinsics map to them directly. *Hardware:* The atomics live in one escape group and the other seven in the system group, so the decoder has two places to look.

7.2 The memory model

7.2.1 Memory is sequentially consistent: the result is as if all cores' accesses happened in one order that respects each program's order. *(D)*

7.2.2 A store buffer is allowed, provided loads snoop it and stores drain in program order. *(D)*

7.2.3 Quad accesses are naturally aligned, so every access is atomic within its own size; no misaligned access can be torn across cores. *(D)*

7.2.4 The machine is in order and does not speculate, so no speculative side channel exists to be mitigated. *(D)*

7.2.5 The ABI says nothing about memory ordering, because with sequential consistency there is nothing to say. *(D)*

7.2.6 Memory is sequentially consistent per byte: a load returns, for each byte, the value written by the last store to that byte in the single order, and an aligned access of N bytes is single-copy atomic. A load that overlaps a buffered store of a different size either waits for the buffer to drain or merges the buffer and memory in one step; it never returns a mixture that no order of the stores could produce. *(D)*

Commentary. **Precedent.** The PDP-11 and VAX ran one processor at a time in the model that mattered, so the question did not arise; ARM's memory model took about a decade to formalise, and the C11 and C++11 models exist largely to paper over the differences between weak architectures. **Trade-offs.** Sequential consistency is the model with no cost to software and the highest cost to a large speculative core; software written against a weak model runs on a strong machine and not the reverse, so the choice is close to irreversible, which is why the choice is made once. If a large out-of-order core is ever built, total store order is the least painful retreat. **Benefits.** None of the barrier code that fills other kernels: the kernel survey found barrier vocabulary in 5,596 lines of Linux code and 3,016 lines of `memory-barriers.txt` documentation, and none of it arises here. **Modern comparables.** x86 and SPARC are total store order; ARM, POWER and RISC-V are weak. **Impact.** *Kernel:* None of the 5,596 lines of ordering code found in Linux, nor the barrier documentation, is needed. *Compiler:* The optimiser may move non-volatile accesses freely, and no fence is inserted for ordering. *Hardware:* In-order with a snooped store buffer; sequential consistency is nearly free on this core and the expensive part only appears on a speculative one.

7.3 The atomics in detail

7.3.1 `LL` takes a reservation on a granule of memory; a write to the granule by any initiator, core or device, clears it; `SC` succeeds exactly when the reservation is intact and otherwise writes nothing. *(D)*

7.3.2 A short `LL`/`SC` sequence must eventually succeed if no other initiator keeps writing the granule. *(D)*

7.3.3 The read-modify-write atomics are single-copy atomic with respect to every initiator; the memory system may build them from an exclusive access with hardware retry. *(D)*

7.3.4 A device that writes memory shared with a core takes part by clearing reservations. *(D)*

Commentary. **Precedent.** A bus lock, the Unibus's `DATIP`/`DATO` pair, is simple and a bottleneck as cores multiply; a monitor maps onto the exclusive access of AXI and the memory systems of FPGAs and modern chips. **Trade-offs.** A monitor needs forward-progress rules and, under contention, can livelock if not specified; RISC-V's guarantee of eventual success for constrained sequences is the model. The pain-points report records that the kernels' simple lock does not scale (OpenBSD's ticket kernel lock measured 155% worse than an Anderson lock in one developer's test) and that Linux moved from test-and-set through ticket locks to queued locks; the instruction set provides the primitives and the lock design is the kernel's. **Benefits.** A kernel's lock needs one instruction; lock-free queues need compare-and-swap. **Modern comparables.** RISC-V `LR`/`SC` with its constrained-loop guarantee, AArch64 load-exclusive and `CAS`, x86 `LOCK CMPXCHG`. **Use.** `CAS` for lock-free structures and lock words; `XADD` for counters and ticket numbers; `LL`/`SC` for everything else. **Impact.** *Kernel:* A lock is one `_DB` instruction. *Compiler:* A `LL`/`SC` loop must be emitted in the constrained form, with no other memory access between the two. *Hardware:* A reservation granule tag in the cache controller and an exclusive-access path to memory.

7.4 Per-CPU state and cheap context

7.4.1 `MFCPUID` returns the number of the core that executes it. It cannot be synthesised and per-CPU data needs it. *(D)*

7.4.2 `DP`, the direct-page register, has a copy per mode; in kernel mode it is the per-CPU pointer and a field of the per-CPU structure is one four-byte instruction, `MOVQ d(DP), Rd`. *(D)*

7.4.3 The address-space tag makes a context switch constant-time, and global page-table entries and the direct-mapping windows keep the kernel's own mappings out of the invalidation path. *(D)*

7.4.4 The stack pointer is banked by mode, so an interrupt arriving in user mode on any core finds that core's kernel stack without a search. *(D)*

Commentary. **Precedent.** Every SMP kernel builds a per-CPU base by hand: x86 uses the `GS` base and a `swapgs` instruction, ARM uses `TPIDR_EL1`, RISC-V the supervisor scratch register, MIPS reserves two registers; the kernel survey found seven architectures paying for the problem of having no free register at the moment of entry. **Improvements.** `DP` serves code density and is also what both an SMP kernel and a threaded C runtime need most, in the mode where each needs it, and the two copies do not conflict. **Benefits.** No `swapgs`, no reserved scratch register, no code spent finding the CPU. **Modern comparables.** `GS` and `TPIDR` as above. **Impact.** *Kernel:* Per-CPU data is one four-byte `MOVQ d(DP), Rd`, with no `swapgs` and no

reserved register. *Compiler:* The compiler addresses per-CPU variables relative to `DP`. *Hardware:* Three copies of `DP`, one per mode.

7.5 Translation and instruction-cache coherence

7.5.1 `TLBI` and `TLBIA` broadcast to all cores; `TLBSYNC` waits until the broadcast has completed everywhere. *(D)*

7.5.2 Instruction caches are not coherent with data caches; `ICINV` invalidates a line and `ICINVA` all of it, and neither is privileged, because a JIT needs them. *(D)*

7.5.3 A write to the page-table base, the address-space tag, the translation-enable bit or the vector base takes effect only after the next `ISYNC`. *(D)*

Commentary. **Precedent.** x86 flushes remote translation buffers with an inter-processor interrupt and a software handshake, which is slow and intricate; AMD added a broadcast invalidate only late. **Trade-offs.** A broadcast is simpler in hardware and far faster for two to four cores; it needs the completion barrier, because a broadcast one cannot wait for is no use. Making instruction caches coherent would cost a snoop port for a case that almost never happens. **Improvements.** The kernel's own mappings are global or window-mapped and never part of a shootdown. **Benefits.** The pain-points report finds that remote translation-buffer shootdown, a source of deadlocks in the BSDs and of much code in Linux, does not arise. **Modern comparables.** ARM's broadcast `TLBI` and `DSB`; RISC-V's `SFENCE.VMA` still needs software shootdown. **Impact.** *Kernel:* A shootdown is `TLBI` then `TLBSYNC`; a module or JIT write is `ICINV` then `ISYNC`. *Compiler:* A JIT or a trampoline generator must call `ICINV` after writing code. *Hardware:* A broadcast on the interconnect and a counter for completion; the instruction cache has an invalidate port but no snoop port.

7.6 Waiting and signalling

7.6.1 `WFE` sleeps until another core executes `SEV` or an interrupt arrives, and `HINT #1` is the spin-wait pause. *(D)*

7.6.2 `WFE` ends its sleep when an interrupt is pending even if the priority masks it, so that the idle loop is `SPL #7`, check for work, `WFE`, `SPL #0`, with no gap. *(P)*

7.6.3 On one core `WFE` is the idle instruction, and `WAIT` is its assembler alias. *(D)*

Commentary. **Precedent.** x86's `PAUSE` tells a spinning core to back off; ARM's `WFE` lets it stop until an event. V7's idle routine lowered the priority and executed `wait` in a loop that rechecked the run queue after every interrupt, so a missed wake-up cost one clock tick. **Trade-offs.** On an FPGA a spinning core consumes memory bandwidth the other cores want, which is the reason to prefer a real wait. **Benefits.** An idle core costs nothing and wakes on a signal. **Modern comparables.** ARM `WFE` and `SEV`, RISC-V `WFI`. **Impact.** *Kernel:* An idle core waits on `WFE` and costs no bandwidth. *Compiler:* Spin-wait loops use `HINT #1`. *Hardware:* `WFE` stalls or gates the core's clock until an event or an interrupt.

7.7 Cache coherence

7.7.1 Between processors, coherence is transparent to software, by snooping with three states (modified, shared, invalid), for the four cores of the first device. *(D)*

7.7.2 A DMA device is the opposite case: the buffers are uncached and the hand-off is explicit, because snooping the DMA path is expensive and DMA transfers are large, infrequent and have an explicit hand-off. *(D)*

7.7.3 The design supports at least four cores; sixteen or more is the preferred ceiling that no decision may preclude; the initial device has four cores, which it is hoped will fit the FPGA. *(D)*

7.7.4 The protocol for more than four coherent cores is open. The leaning of the SMP decisions is MESI with a snoop filter inside clusters of four and a directory between clusters, with dedicated cores as non-coherent partners that use uncached rings; the architecture promises only that memory is coherent and sequentially consistent. *(P)*

Commentary. **Trade-offs.** MESI would add an exclusive state to avoid a bus transaction when writing a clean line nobody else holds; at four cores the benefit is small and the state machine larger; a directory scales further and is not needed below about eight cores. Software-managed coherence is cheaper in hardware and is where concurrency bugs live, since every missing flush is a race that reproduces once a week. **Benefits.** The instruction set owes nothing to the coherence protocol, which keeps the two separate. **Modern comparables.** x86 snoops with MESIF or MOESI and directories across sockets; ARM's coherent interconnects use directories or snoop filters. **Impact.** *Kernel:* No coherence code, in either direction between cores. *Compiler:* None. *Hardware:* A snoop port on each data cache, about 500 lookup tables and a small state machine for three states, plus about 600 per core.

7.8 Starting and signalling the other cores

7.8.1 The controller holds every core but core 0 in reset; a write to a per-core start register gives a core an entry address and an argument and releases it into kernel mode at priority 7, with its number in `r0`. *(P)*

7.8.2 An inter-processor interrupt is a write to a per-core register in the interrupt controller; no APIC-like machinery is needed. *(P)*

7.8.3 The routing of device interrupts to cores, and a shared second-level cache or a coherent interconnect, are device-side and unspecified. *(P)*

7.8.4 Each core has a read-only identification register giving its class and capacity, defined from the first system although every core is alike, and a stop-and-drain register that a kernel writes to take a core offline: the core finishes its outstanding bus transactions and stops. *(D)*

7.8.5 In-order and out-of-order cores may share a die if software can tell which is which, which the class register of 7.8.4 reports; the memory model and the semantics of every instruction are identical on every core, and a core class may differ in speed and never in what a program can observe. *(D)*

7.8.6 At least one core is a secure core: every timing channel is removed (every instruction and every cache fetch takes a time independent of its data), it has private cache lines and takes no periodic timer tick, and it is stopped and preempted by an inter-processor interrupt. *(D)*

7.8.7 The author's recommendation is dedicated cores for graphics, for the network and for audio, then general-purpose cores. *(P)*

Commentary. **Precedent.** An x86 core wakes in 16-bit real mode and has to be walked through three modes by a trampoline (1,528 lines of start-up code and 1,258 of real-mode code in Linux); arm64 uses a firmware call in 124 lines or a spin table in 127; RISC-V 108 or 58; the VAX's console processor started the others. **Benefits.** A core can start in its normal mode at any address, so the whole protocol is one register write. **Modern comparables.** x86's INIT and START-UP interrupts, ARM's PSCI, RISC-V's hart-start call. **Impact.** *Kernel:* Starting a core is one register write, and a stuck core is reset by another. *Compiler:* None. *Hardware:* A start register and a reset-hold per core in the controller.

7.9 A kernel's view

7.9.1 The kernel starts a core by writing its start register, keeps its per-CPU structure at the address in `dp`, and takes a lock with one `_db` atomic. *(P)*

7.9.2 It unmaps a page by changing the entry, issuing `tlbi`, and waiting with `tlbsync`. *(D)*

7.9.3 It makes new instructions visible by writing them, issuing `icinv` and executing `isync`. *(D)*

7.9.4 It idles a core with `wfe` and wakes it with `sev` or an inter-processor interrupt. *(P)*

Commentary. Each item is one instruction or one register write, and each is a place where other architectures need a trampoline, a handshake or a fence.

7.10 What was avoided

7.10.1 The architecture has no weak ordering, no speculative execution, no hardware transactional memory, no software-managed coherence between processors, no coherent instruction caches, no inter-processor-interrupt shootdown as the main mechanism, and no memory-model-dependent ABI. *(D)*

Commentary. **Trade-offs.** Intel's transactional memory produced a decade of errata and side channels for a feature few programs used; compare-and-swap and `ll`/`sc` suffice. Each avoided item is a tax on every concurrent program, or on every implementation, in exchange for performance the small in-order core cannot use. **Impact.** *Kernel:* Each avoided feature is code a kernel does not have to write: no barriers, no software coherence, no shootdown interrupts. *Compiler:* Each is analysis the compiler does not have to do: no memory-model-dependent code generation. *Hardware:* Each is a block not built: no speculation, no transactional memory, no coherent instruction cache.

7.11 What the model does not give for free, and the road to out of order

7.11.1 A simple memory model does not make an atomic implementation simple by itself: cache coherence, exclusive ownership, invalidation, ordering and the interaction with interrupts still have to be designed and tested.

7.11.2 Out-of-order execution is not ruled out: the first implementations are in order, and the architecture is kept ready for a large out-of-order design. *(D)*

7.11.3 Sequential consistency on a speculative core needs loads that are replayed when another core intervenes; the readiness review calls this awkward but defined, and names the flag rules, the reservation rules and the `ISYNC` and `HINT` instructions as what a speculative core needs. *(D)*

Commentary. **Precedent.** One instruction set often spans small in-order and large out-of-order cores: ARM's small and large cores, RISC-V's Rocket and BOOM, the x86 Pentium and P6, Alpha's 21064 and 21264. **Trade-offs.** What the pdp64 gains by refusing speculation is a smaller design with fewer error cases and none of the speculative side channels; what it gives up is the performance of an aggressive core, which an FPGA or a small chip could not build anyway. The readiness document (`../pdp64-ooo-readiness.md`) and the hardware-vulnerabilities report give the rules a future core would follow. **Benefits.** The decision is reversible in the direction that matters: total store order can be the retreat for a large core. **Impact.** *Kernel:* None. *Compiler:* None. *Hardware:* A speculative core would need loads that replay when another core intervenes, and the flag and reservation rules keep that path open.

7.12 The atomic and ordering instructions

7.12.1 The atomic escape provides `CAS`, `SWAP`, `XADD`, `XAND`, `XOR_`, `XXOR`, `XMAX`, `XMIN`, `XMAXU` and `XMINU`, each with a `_DB` variant that adds a barrier, and `LL` and `SC`. *(opcode `0x11`)*

7.12.2 `LL` takes a reservation on a granule of memory; any write to it by any initiator clears it; `SC` succeeds exactly when the reservation is intact. A short `LL`/`SC` sequence must eventually succeed if no other initiator keeps writing the granule. *(D)*

7.12.3 The read-modify-write atomics are atomic with respect to every initiator, cores and devices alike. *(D)*

7.12.4 `FENCE` orders device accesses; `WFE` and `SEV` wait for and signal an event; `ISYNC` makes earlier system-register writes take effect; `HINT #n` has no architectural effect (1 pause, 2 speculation barrier, others reserved). *(D)*

Commentary. **Precedent.** The PDP-11's read-modify-write instructions were indivisible on the Unibus (the `DATIP`/`DATO` pair); the VAX had interlocked queue and bit instructions. **Trade-offs.** A bus lock is simple and does not scale as cores multiply; a monitor (reservation) maps onto the memory systems that FPGAs and modern chips use, at the cost of forward-progress rules. **Improvements.** The pdp64 offers all three designs found on other machines (load-linked/store-conditional, compare-and-swap, fetch-and-operate), more atomic operations than any architecture surveyed. **Benefits.** A kernel lock needs one instruction. **Modern comparables.** RISC-V `LR`/`SC` and the `AMO` set; AArch64 load-exclusive and its large-system atomics; x86 `LOCK`-prefixed read-modify-write. **Use.** `CAS` for lock-free structures; `XADD` for counters; `LL`/`SC` for anything else; `WFE` for the idle loop. **Impact.** *Kernel:* A lock is one instruction, and the `_DB` forms need no separate fence. *Compiler:* C11 atomics map one-to-one, no ordering fences are emitted under sequential consistency, and a `LL`/`SC` loop must be generated in the constrained form (short, no other memory access inside). *Hardware:* The reservation is a granule tag in the cache controller, and the read-modify-write atomics use an exclusive access with hardware retry.

The instruction entries for this section are in chapter 9, section 9.13: each entry there is complete (syntax, encoding diagram, operation, flags, exceptions, status); the commentary above gives the reasons and the use.

Entry	Mnemonics
Compare and swap	`CAS`, `CASDB`
Atomic exchange	`SWAP`, `SWAPDB`
Atomic fetch and add	`XADD`, `XADDDB`
Atomic fetch and and, or, xor	`XAND`, `XANDDB`, `XOR`, `XOR_DB`, `XXOR`, `XXORDB`
Atomic fetch and minimum or maximum	`XMAX`, `XMAXDB`, `XMIN`, `XMINDB`, `XMAXU`, `XMAXUDB`, `XMINU`, `XMINUDB`
Load-linked and store-conditional	`LL`, `SC`

7.13 Still open

The mapping of the bus's atomics onto PCI Express (the transport of decision R4 is settled by errata 80), the interrupt controller and routing (R1), starting the other cores (R2, B2), how coherence scales beyond four cores (R3), the wake rule of `WFE` (P1), and lock scaling above a few cores, which is a kernel design question the instruction set does not settle.

Chapter 8 — Vector work, AI and array languages: the device route

Wide data-parallel work, whether neural-network inference or the primitives of an array language, is done by memory-mapped devices with their own memory and driven by descriptors, not by SIMD registers in the processor. There is no vector register file and no AVX2-style instruction set in the pdp64. The chapter states that decision, the reason for it, and how it serves AI and large-language-model inference and the array languages APL and K. Graphics has its own chapter (chapter 3), since its devices are the first a user sees. It is the route ARM-based systems take for their neural-network and graphics engines, and the one the PDP-11 took for its attached array processors. The discussion of the alternatives is appendix B (S1 to S6); the accelerator designs are `../pdp64-lb64-accelerator.md` and section 12 of `../pdp64-fpga-plan.md`. Tags: *(D)* decided; *(P)* proposed.

8.1 The decision

8.1.1 The processor has no vector register file and no SIMD instruction set of the SSE, AVX2 or NEON kind. *(D)*

8.1.2 Wide work is described to a device by descriptors in memory: an operation, the addresses of the arrays and their length. *(D)*

8.1.3 The processor owes such a device what it owes every device: a memory type per page, a FENCE, and atomics that reach device memory; the instruction set is unchanged. *(D)*

8.1.4 Packed-lane operations in the ordinary integer registers (a handful of instructions for bytes, halves and words in a 64-bit register) are not part of this decision; they remain a possibility to be settled by measurement. *(P)*

Commentary. **Precedent.** The PDP-11's heavy numerical work went to attached array processors driven by library calls (the Floating Point Systems AP-120B attached to PDP-11 hosts, by the one brochure checked), and the VAX gave its 6000 series a vector extension of 16 registers of 64 elements, supported by VMS but little used by Unix. x86 went from MMX through SSE, AVX and AVX2 (256-bit) to AVX-512, a new width and a new set of state each time; ARM has NEON in the processor and scalable vectors beyond, and attaches its neural-network and graphics engines as memory-mapped devices; RISC-V has a scalable vector extension. **Trade-offs.** A device needs a setup (a descriptor) and a completion (a status), so small arrays are faster on the processor and large ones on the device; a SIMD register file has no setup and a cost in state, opcodes and width that grows with every generation. **Improvements.** The decision removes the questions that a vector register file raises: whether a context switch saves the vector state (x86's lazy saving of floating-point state was a security hole and Linux went back to eager restore), whether the kernel may use the registers, how wide they are, and what the calling convention does with them. **Benefits.** A processor that stays small and in order and that gains graphics and inference by adding devices. **Modern comparables.** ARM's Ethos neural engines and Mali graphics engines, Apple's matrix coprocessor reached through a library, Google's TPU on PCI Express. **Impact.** *Kernel:* no vector state to save at a context switch and no rule about the kernel using vector registers; a device is one more slot, mapped like any other. *Compiler:* no auto-vectoriser targets the device; the library and the language runtime call it at the level of an operation on an array. *Hardware:* no second register file, no wide load and store path, no opcodes spent; the processor's cost does not grow with the workload.

8.2 Why not SIMD in the processor

8.2.1 A SIMD register file is a second wide register file, which the instruction set deliberately avoided (floating point shares the general registers), and it brings wide loads and stores entangled with the alignment rules and a large demand on a first-page opcode map that is 58 of 64 full. *(D)*

8.2.2 A fixed-width design (128-bit NEON, 256-bit AVX2) bakes the width into every instruction, so a wider generation needs new instructions, and old binaries cannot use the new width. *(D)*

8.2.3 A scalable design (ARM SVE, RISC-V V) avoids that and is the most complex to specify and to implement; it is the only in-processor form that would suit this project's range from a small FPGA core to a possible large one. *(P)*

8.2.4 The compiled corpus shows little vectorisable code at the size-optimising setting; whether it shows more at higher optimisation is a measurement to make before any in-processor form is reconsidered. *(P)*

Commentary. **Precedent.** x86's history of SSE, AVX, AVX2 and AVX-512 is the argument against a fixed width: each added instructions and state, and AVX-512 was withdrawn from some client chips and later proposed to be unified. **Trade-offs.** A scalable vector extension would let one binary run on a small and a large implementation, at the price of the largest specification in the architecture and a compiler model that must handle an unknown vector length. **Improvements.** Moving the work to a device makes the length a descriptor field, which is the scalable idea without a register file. **Benefits.** The block RAM of a small FPGA, the scarce resource of the plan, is not spent on vector registers. **Modern comparables.** AVX2 on x86, NEON on ARM, SVE and the RISC-V vector extension. **Impact.** *Kernel:* nothing to save and no lazy-save hazard. *Compiler:* no vector types in the ABI and no vectorisation pass for the processor. *Hardware:* no area for a register file or wide data paths; the FPGA's memory goes to the caches and the device buffers.

8.3 AI and large-language-model inference

8.3.1 The inference accelerator, LB64, evaluates the layers of a binary-weight language model as sign-flip accumulates with no multipliers, taking a chain of descriptors and writing a status back on completion. *(D)*

8.3.2 A layer is two descriptors, the second accumulating into the first's result for the residual path, and a transformer block is a chain; the processor writes the chain once and is then idle. *(D)*

8.3.3 The work is partitioned between small engines, each doing one thing with its own local memory: LB64 for the projections and the feed-forward layers, a floating-point multiply-accumulate engine for the attention products, a vector engine for normalisation, softmax, activation and rotary position encoding, and the processor for the descriptor chains, sampling and the tokeniser. *(P)*

8.3.4 The accelerator has no instruction set: its computation has exactly one shape, so a programmable sequencer would spend its area on flexibility the work does not use. *(D)*

8.3.5 The processor keeps `POPCNT` and `XNORPOP` for the binary operations that small models and bitsets use; they are not what the accelerator uses. *(D)*

Commentary. **Precedent.** A descriptor chain is how every competent DMA engine since the PDP-11's RK11 has worked, and the partition into small single-purpose engines fed by chains is the idea of the 144-processor GA144 chip applied to a workload that suits it. **Trade-offs.** The accelerator is fast at what it does and does nothing else: attention is not helped, the element-wise work needs another engine, and a training accelerator is a different design again. The accelerator's descriptor is larger than the 32-byte descriptor of chapter 5, so the two must be reconciled: the proposal is that the standard descriptor's address points at a device-defined work block, which can chain, and the ring carries pointers to work blocks. **Benefits.** The lane count is set by the memory bandwidth and not by the amount of logic, so a small board can run a model the processor alone could not. **Modern comparables.** ARM's Ethos engines, Google's TPU, and the many inference accelerators on small boards. **Impact.** *Kernel:* a driver builds a chain and starts it; the kernel owns no model state and the only scheduling is of the device. *Compiler:* none; inference frameworks emit descriptors. *Hardware:* adders and sign-flip logic and no multipliers in LB64; the multiply-accumulate engine needs multiplier blocks; the memory interface sets the size.

8.4 Array languages: APL and K

8.4.1 Array languages express computation as operations on whole arrays: each primitive (add, multiply, compare, reduce, scan, index, where, sort) is one operation over contiguous data.

8.4.2 A device that takes a descriptor naming an operation, the addresses of the arrays and a length is the natural implementation of those primitives: one descriptor per primitive, the length in the descriptor. *(P)*

8.4.3 The interpreter stays on the processor and sends a primitive to the device when the array is long enough to repay the setup; short arrays run on the processor. *(P)*

8.4.4 There is no vector length in the language and none in a register: the length is a field of the descriptor, so one implementation serves any array size. *(P)*

8.4.5 A vector engine for such primitives would provide element-wise arithmetic and comparison, selection, reductions, scans, gather and scatter, compress (`where`) and index generation, on integer, floating-point and bit-array types. *(P)*

Commentary. **Precedent.** Iverson's APL made whole-array operations the language, and its descendants J and Arthur Whitney's K (the language of the kdb+ database) are interpreters whose speed comes from running long loops over contiguous arrays in a few tight kernels; the Cray vector machines were built around the same shape of loop, and DEC offered APL for the PDP-11 (not confirmed in the sources read). **Trade-offs.** Offloading a primitive has a fixed cost, so the benefit is for arrays above a size threshold; reductions and scans carry a dependence along the array that the device must support directly; sorting and gather are bandwidth-limited. **Improvements.** The language supplies the parallelism: the programmer says "add these two arrays", so there is no vectorising compiler to find it, which is the hardest part of making an ordinary language fast on SIMD hardware. The interpretive overhead is paid once per primitive, not once per element, and the device streams the data at memory bandwidth. **Benefits.** Vector languages are easier to support (a small interpreter with a library of primitives that map onto descriptors) and more efficient (the per-element work is hardware, and the per-primitive work is one descriptor), and the same device that serves the array languages serves the elementwise work of inference (section 8.3) and the lane-wise work of graphics. **Modern comparables.** K and kdb+ interpreters use AVX2 intrinsics heavily on x86 *(not confirmed in the sources read)*; array-language compilers for GPUs (Futhark, Co-dfns) target accelerators through offload, the same shape as this. **Impact.** *Kernel:* a language runtime that drives a device from user space needs the device's page mapped into its address space, with the protection caveat of chapter 5 (without a translation unit a user-space driver can direct its device to write anywhere). *Compiler:* none; the interpreter or compiler for the array language lowers primitives to descriptors, and a conventional compiler never sees a vector. *Hardware:* a streaming engine with a small set of element-wise, reduce, scan and gather units behind the ring engine, sized to the memory bandwidth.

8.5 Number formats

8.5.1 The processor handles `binary64`, `binary32` and `binary16` as scalar floating point; other formats (bfloat16, 8-bit integers with 32-bit accumulation, binary weights, 8-bit floating point) are the device's. *(D for the processor; P for the devices)*

8.5.2 Each vector device names its operations and formats in its identification block and feature bits, so a library can choose by asking. *(P)*

Commentary. **Trade-offs.** A format fixed in the processor's instruction set is a format that cannot change when the machine-learning field changes it, as it has several times; a format in a device is replaced by replacing the device. **Modern comparables.** x86 has half precision, bfloat16 and `VNNI` dot products in the instruction set; ARM has `BF16`, `SDOT` and matrix extensions; accelerators handle the rest. **Impact.** *Kernel:* none. *Compiler:* only the scalar formats; the machine-learning formats are descriptor fields. *Hardware:* the devices' multiply-accumulate units, not the processor's, are built for the formats in use.

8.6 Driving a vector device

8.6.1 A program fills a descriptor naming the operation and the arrays, executes `FENCE`, and writes the doorbell; the device processes the descriptor, writes the results and a status, and clears the ownership bit; the program polls or takes the interrupt. *(P)*

8.6.2 A chain of descriptors runs without the processor, and a work block that is a chain is how a transformer layer or a sequence of array primitives is expressed. *(P)*

8.6.3 The buffers are uncached, as for every device, so the processor's reads of results are slow; a large result is left in the device's memory or read back by the next descriptor. *(P)*

Commentary. This is the same driver skeleton as for a disk (chapter 5), with an operation field that means "add these arrays". **Trade-offs.** The slow uncached readback is the cost of the explicit hand-off; an interpreter that needs many small results back on the processor should leave them in device memory. **Impact.** *Kernel:* one driver skeleton. *Compiler:* none. *Hardware:* one ring engine shared with every device.

8.7 Still open

The reconciliation of the accelerators' descriptors with the standard descriptor, the formats and operation set of the vector engine, the target workloads, and the evidence that would reopen the question of packed integer lanes: compile the corpus


at higher optimisation and count vectorised loops, measure the share of time in memory and string routines, and estimate the block RAM cost (appendix B, S1 to S6).

Chapter 9 — The instruction set

The instruction set is built around one idea: the length of an instruction is known from its first two bits, so the cheapest instructions are two bytes and nothing is longer than six. The chapter covers how the 64 opcodes are divided, the properties and principles that hold throughout, the registers, the format and the addressing modes, each group of instructions, faults, restart and memory management, position-independent code, what is rejected, the idioms of the PDP-11 and VAX that are restored, lost or replaced, the comparison with the PDP-11 and VAX, what is taken from LoongArch, and what is open. Every instruction has its entry (syntax, encoding drawing, operation, flags, exceptions) in the section of its group below; the atomic instructions are in section 7.12 and the system instructions in section 6.13; the reference tables hold the second page, the aliases, the constants and the lists of mnemonics and opcodes. The full text with every encoding is `../pdp64-isa.md`; every number here comes from the grammars that the tools are generated from.

9.1 How the opcode space is divided

9.1.1 Every instruction begins with a 16-bit parcel with four fields: `len` (2 bits), `opcode` (6 bits), `reg` (4 bits) and `mode` or `rm` (4 bits).



9.1.2 There are 64 opcodes on the first page. An operation gets a top-level opcode if its common case is register to register, because only then can it be two bytes; every other operation lives in an escape group and costs nothing for it.

9.1.3 Six escape groups, `001100 (0x0C)` to `010001 (0x11)`, read a sub-opcode from the second parcel: `BESC` (bits, fields, rotates, UTF-8), `MBLK` (block memory), `AESC` (divide, remainder, absolute, minimum, maximum, set), `MESC` (unaligned access, ALU to memory), `FESC` (fused multiply-add, binary32 and binary16, divide, square root, classify) and `ATOM` (atomics).

9.1.4 Three groups, `010010 (0x12)` to `010100 (0x14)`, take their sub-opcode from the register field: `XFER` (indirect jump and call, tag dispatch), `SOP` (single-operand instructions, jump, call, push, pop) and `SYS` (system control).

9.1.5 Every other run of opcodes is one kind, and its low bits select the operation directly: twelve moves (`000000 (0x00)-001011 (0x0B)`), thirteen ALU operations (`010110 (0x16)-100010 (0x22)`), four floating-point operations (`100100 (0x24)-100111 (0x27)`), three compare-and-branch forms (`101000 (0x28)-101010 (0x2A)`) and sixteen branches (`110000 (0x30)-111111 (0x3F)`).

9.1.6 Fifty-eight of the sixty-four opcodes are assigned, one ALU slot (`100011 (0x23)`) is spare and five (`101011 (0x2B)-101111 (0x2F)`) are reserved.

9.1.7 When `len` is `11`, the instruction is a single parcel from a second page of 64 opcodes, 45 defined and 19 reserved, each an exact abbreviation of a first-page instruction.

Commentary. **Precedent.** The PDP-11 partitioned its opcodes by the addressing modes of the first word; the VAX by operand specifiers parsed in sequence; x86 by prefixes, opcode, ModR/M and SIB read one after another. Each step down that list costs more front-end logic before the address of the next instruction is known. **Trade-offs.** Putting an operation in an escape group makes its shortest form four bytes, since the sub-opcode lives in the second parcel, so the allocation is a frequency sort, and five groups sit in escapes for that reason (divide and remainder, rotate by a register count, floating-point divide and square root, and the read-modify-write memory forms), where the cost is nothing or almost nothing. **Improvements.** The six second-parcel escapes sit together so that "read a sub-opcode" is one range comparison on bits 13 to 8; the three register-field escapes sit together so that one range compare enables the mux that already feeds the register file's address inputs; the other runs are contiguous so their low bits are wired straight to the function selects. **Benefits.** The decoder is a few comparators and wires, and a new instruction usually costs a sub-opcode, not an opcode. **Modern comparables.** RISC-V groups its major opcodes by format and AArch64 by top-level encoding class; the pdp64 groups by the one property that matters most to its front end, whether the sub-opcode needs the second parcel. **Impact.** *Kernel:*

Nothing in the kernel depends on the opcode map except the privileged group, which sits in one place. *Compiler:* The instruction selector gets the two-byte form for every register-to-register operation and must charge four bytes for anything in an escape group, which its cost model has to know. *Hardware:* The decoder is a few range comparisons and wires: six escape groups are one compare on bits 13 to 8, three register-field escapes are one compare that enables a mux already feeding the register file, and every run's low bits go straight to its function select.

9.2 Properties and principles

9.2.1 The length of an instruction is a function of its `len` field alone: 0, 1 or 2 extension parcels, for 2, 4 or 6 bytes. *(D)*

9.2.2 At most one operand of an instruction may be a memory reference; the other, where present, is a register. The block operations are the one admitted exception. *(D)*

9.2.3 No instruction is longer than six bytes. *(D)*

9.2.4 A register is always written in full: narrow loads sign- or zero-extend, and there is no partial-register write. *(D)*

9.2.5 Anything that changes what an instruction means is, by default, visible state set by an instruction that names it, not hidden state; whether a mode bit is worth its cost is decided case by case (errata 83). Compatibility is by conversion instructions where that is cheap. *(D)*

9.2.6 Every instruction can be restarted after a fault, and exceptions are precise; the machine has no hidden instruction state. *(D)*

9.2.7 Floating point is done in the general registers; there is no separate floating-point register file. *(D)*

9.2.8 Memory is sequentially consistent between processors. *(D)*

9.2.9 The ALU has one width, 64 bits; sizes appear only on loads, stores and conversions. *(D)*

9.2.10 Addresses are canonical: 39, 48 or 57 bits of virtual address, according to the three, four or five levels of the page table (6.6.1), and a physical address of 40 to 64 bits, 40 in the present implementation (2.3.6). *(D)*

9.2.11 Instructions are aligned to two bytes; quad data accesses are naturally aligned, and the explicit unaligned forms exist for the cases that need them. *(D)*

9.2.12 An instruction does what its name says and nothing else; no flag is set that its entry does not list. *(D)*


Commentary. **Precedent.** 9.2.2 is x86's ModR/M idea made architectural; it is also what lets the exception machinery be small (the PDP-11 recorded at most two register side effects per instruction because it had two specifiers; with one memory operand there is at most one). 9.2.6 exists because the Motorola 68000, which was very nearly this machine, could not restart an instruction after a bus error and so could not do demand paging until its successor retrofitted a fault model. 9.2.4 is the rule x86-64 adopted for 32-bit writes and failed to apply to the 8- and 16-bit forms. 9.2.7 is the arrangement RISC-V standardised as Zfinx. **Trade-offs.** 9.2.9 means narrow arithmetic is done wide and converted, which costs an extension instruction after some narrow operations; whether that cost is large enough to justify 32-bit forms of add and subtract is an open question that the compiled corpus can answer (appendix B). 9.2.8 is the cheapest model on a small in-order core and the most expensive on a large speculative one. 9.2.10 lets the page table have three levels, as RISC-V's Sv39 does, or four or five as x86-64, AArch64 and Sv48 and Sv57 do, at a longer walk for each level. **Improvements.** The rules are soft defaults: each says what it protects and what breaking it costs. **Benefits.** Together they make the machine small, restartable and easy for a compiler; the measured code size is in chapter 1. **Modern comparables.** AArch64 and RISC-V have fixed-length register-to-register encodings and weak memory models; x86-64 has memory operands and total store order; the pdp64 takes memory operands, strong ordering and a bounded fault surface. **Impact.** *Kernel:* Restartable instructions and precise exceptions mean a page-fault handler repairs the mapping and returns, with no instruction-specific cases, and sequential consistency means no barrier code. *Compiler:* One memory operand keeps instruction selection and register allocation simple; a register written in full removes partial-register merges; the single ALU width costs an extension instruction after some narrow arithmetic. *Hardware:* One address generator, at most one register side effect, a single-entry undo buffer, no byte-lane multiplexing and a two-bit length are what keep the die small.

9.3 State: registers and flags

9.3.1 There are sixteen 64-bit general registers, `R0` to `R15`. `R14` is the stack pointer `SP`, with three copies (kernel, supervisor, user) chosen by the current mode; `R13` is the frame pointer by convention only; the others carry no meaning to the hardware. *(D)*

9.3.2 The program counter is not a general register, and `R7` is an ordinary general register, not a view of the program counter; the program counter is read with `LEA 0(PC), Rn`. *(D)*

9.3.3 The processor status word is 16 bits. *(D)*



(Bit positions as in System v1: `C` 0, `V` 1, `Z` 2, `N` 3, `T` 4, priority 5-7, current mode 8-9, previous mode 10-11, `UA` 12.)

9.3.4 The flags form two groups, `C` and `{N, Z, V}`, and no instruction writes part of `{N, Z, V}` or writes it conditionally. Moves, loads, stores and the compare-and-branch instructions write no flags; shifts write the same flags for every count; rotates and the funnel shift write none; the by-one left shift sets `V` to `N` xor `C`. *(D)*

9.3.5 `DP`, the direct-page base, has three copies by mode. It makes `d(DP)` the shortest address form (a 12-bit displacement in four bytes); in kernel mode it is the per-CPU pointer, and in user mode the thread pointer. *(D)*


9.3.6 Other special registers: `FPSR` (five sticky floating-point flags), `ASID`, `PTBR`, `DMW0` and `DMW1`, `EPC`, `EPSW`, `EVA`, `ECAUSE`, `VBR`, `MMUCTL`; the system registers are read and written by `MFSR` and `MTSR` with an 8-bit register number. *(D)*

9.3.7 A bit `DIT` in the status word (its position is unspecified) promises data-independent timing: while it is set no data-dependent timing effect of any kind remains, neither in instruction latency (divide, `MSCN`, `MCMP` and floating point included), nor in frequency or power management (a core that scales frequency holds it steady while the bit is set, or says in a feature register that it cannot), nor from any data-dependent prefetcher or value predictor (a core may have one, but it is off while the bit is set). User code may set it for its own use. *(D)*

Commentary. **Precedent.** The PDP-11's PC and SP were ordinary registers and its flags were set by nearly every instruction. The VAX put the PC in R15. **Trade-offs.** Keeping the PC out of the register file means a jump to a computed address uses `JMP`, not a write to a register, so that writing `SP` has no control-flow consequence and the hazard logic treats it like any other destination. Condition codes are kept (rather than a flagless design) because compare-and-branch and flag-setting arithmetic make for dense code; the flag rules make them cheap for an out-of-order implementation, because the compiled corpus shows that 68% of instructions write a flag and only 1.5% read one. **Improvements.** The status word carries a user-memory guard bit (9.14) and the per-mode `DP` serves two jobs, the per-CPU pointer in the kernel and the thread pointer in user mode. **Benefits.** An exception handler finds a kernel stack and a per-CPU pointer without first searching for them; a threaded program's thread-local variable is one instruction. **Modern comparables.** x86-64 keeps `FS` and `GS` base registers for the same two jobs; AArch64 has `TPIDR_EL0` and `TPIDR_EL1`; RISC-V uses `tp` and the supervisor scratch register. **Impact.** *Kernel:* Banked stack and direct-page registers let entry find a kernel stack and a per-CPU pointer with no code, and the status word is saved by one `PUSHX`. *Compiler:* The flag rules decide when a compare may fuse with its branch (1,893 pairs stay separate because a second branch reads the flags) and what the compiler may move between a compare and a branch. *Hardware:* Two flag groups need one or two rename targets, not one per bit; the register file is 16 by 64 with two read ports and one write (about 250 lookup tables of distributed memory); the banked copies are a three-way mux.

9.4 The instruction format

9.4.1 The first parcel holds `len`, the opcode and two four-bit fields; `len` is the number of extension parcels (0, 1 or 2) when it is less than 3. *(D)*



9.4.2 Instructions are parcel-aligned and little-endian; an instruction may cross any boundary of 8 bytes, a cache line or a page. *(D)*

9.4.3 Most instructions are two or four bytes: register-to-register work and the whole conversion set is one parcel; any memory operand within ±2 KB is two; displacements to ±128 MB, 32-bit immediates and branches to ±4 GB are three. *(D)*

9.4.4 Where an addressing mode names no base register (immediate, absolute, PC-relative), the register nibble of the second parcel carries payload, so those modes reach 16 bits at four bytes and 32 bits at six. *(D)*

9.4.5 A constant wider than 32 bits is loaded from a literal pool with `MOVQ =K, Rd`, written with an explicit `=`; nothing is pooled silently. *(D)*

Commentary. **Precedent.** The PDP-11 had the length in the first word, but as a function of both of its six-bit specifiers; UTF-8 made "the leading unit says how long" famous, but what matters here is that length is the *primary* partition, so the payload is budgeted by what each form needs and not carved from a fixed width. **Trade-offs.** Byte-granular encoding, as in x86, buys perhaps a tenth of the code size and costs a full alignment rotator and cross-line splice logic in the fetch path on a 64-bit datapath; the pdp64 refuses it. Forcing an instruction to stay inside an eight-byte window would simplify fetch and would cost 5% to 10% of code size in padding. **Improvements.** The `len` code `11` selects a second page of one-parcel abbreviations; the measured average is near three bytes per instruction. **Benefits.** The front end is a two-bit counter, a two-deep parcel buffer and no feedback. **Modern comparables.** Thumb-2 and RISC-V's compressed instructions mix 16- and 32-bit forms too, with the length read from the low bits. **Impact.** *Kernel:* Page-2 forms make kernel text smaller with no source change. *Compiler:* The assembler picks the shortest form, branch relaxation is a length choice, and the cost model knows only 2, 4 and 6 bytes. *Hardware:* The fetch unit is a two-bit down-counter and a two-deep parcel buffer with no feedback.

9.5 Addressing modes

9.5.1 Four bits select one of eight modes, present at four bytes and longer. *(D)*

Mode	Syntax	Effect
`0000`	`d(Rn)`	base plus displacement
`0001`	`d(Rn)(Rx*s)`	scaled index, `s` in {1, 2, 4, 8}
`0010`	`d(PC)`	PC-relative; the base is the first parcel of the instruction
`0011`	`d(DP)`	direct page
`0100`	`#imm`	immediate, sign-extended
`0101`	`@abs`	absolute, sign-extended
`0110`	`(Rn)+d`	post-increment by `d` (default: the operand size)
`0111`	`-(Rn)` or `(Rn)-d`	pre-decrement by the operand size, or by `d`

9.5.2 The deferred modes of the PDP-11 are removed; indirection is done with `JMPI`, `CALLI` and a load. *(D)*

9.5.3 At most one register side effect occurs per instruction, and it is committed at retirement; a fault discards it. *(D)*

Commentary. **Precedent.** The PDP-11 had eight modes for each of eight registers, with a deferred flavour of each, and it made `*p++` and `*--p` single instructions. **Trade-offs.** Dropping the deferred modes removes the case where a fault occurs after a register has been updated at an address that itself came from a load; keeping the strided autoincrement costs

nothing, because the undo information was already a delta (the PDP-11's `MMR1` recorded an amount for the same reason). **Improvements.** The increment is a stride, so walking an array of 16-byte records is one instruction; the PC-relative modes count from the instruction itself, so a branch needs no adjustment and `LEA` reads the PC. **Benefits.** Address generation is one adder pass, never load-then-add, which is the difference between one cycle and a long path on an FPGA. **Modern comparables.** AArch64 has pre- and post-indexed forms with an immediate; x86 has scaled index with a base; RISC-V has base plus immediate only. **Impact.** *Kernel:* A strided autoincrement walks a table of records, and `d(DP)` reaches the per-CPU structure in one instruction. *Compiler:* The modes match C idioms (`*p++`, `a[i]`) one-to-one, and dropping the deferred modes removes the cases the selector would otherwise have to consider. *Hardware:* Address generation is one adder pass, never load-then-add, and the PC-relative base is the first parcel, so no adjustment is needed.

9.6 Moves, conversions and address formation

The instructions. Every instruction has an entry in the section of its group, laid out as in a processor reference manual: its mnemonics, its syntax, its encoding (a drawing of the parcels and the numbers), its operation in pseudocode, the flags it writes, the exceptions it can take, and where the manual explains the matter it touches (*Cf.*). Every instruction, the atomic and the system instructions included, has its official entry below (sections 9.13 and 9.14 for those two groups); the chapters on the kernel and on several processors give the reasons, and an entry may point back to them for a fuller explanation. In the pseudocode, ← is assignment, = and ≠ compare, × and ÷ multiply and divide, and `M[a]` is memory at address `a`. Numbers that are encodings (opcodes, sub-opcodes, field values) are written in binary with the hexadecimal value in brackets behind, as `010011 (0x13)`. Masks are binary too, with a subscript 2 to mark the base (`Rn & 111`$_2$ keeps the low three bits). The entries are generated from `spec/pdp64-mnemonics.hbnf`, the one place where the numbers of the architecture are written, so an encoding here cannot disagree with the assembler or the simulators; the words (operation, flags, exceptions) are checked against the reference executor, `common/pdp64exec.c`, which `sim64` and QEMU share, and the Status line of each entry says whether the executor implements the instruction. The one-parcel second page, the aliases, the constants and the lists of the mnemonics and the opcodes are in the reference tables.

The stories. An instruction that is not common (the PDP-11 core and the operations every architecture has carry none) is followed by *Why it is here*: the machine the idea came from and the reason it was chosen, with the measurements that bear on it. Where no reason is recorded, the paragraph says so. The documents behind the paragraphs are listed in appendix F.

Notation. `Rd` is the destination register (the `reg` field of parcel 0), `Rs` the first source (`low`), `Rt` the second (`t` of parcel 1), `Ru` the third (`x`); the assembler writes the destination last. `rm` is a general operand: a register at `len = 00`, or a memory operand, an immediate or an absolute address by one of the eight addressing modes (section 9.5). `EA(rm)` is its effective address. `M[a]` is memory, `M8[a]` one byte. `sext` and `zext` sign- and zero-extend. A `len = 01` instruction is two parcels (four bytes) and a `len = 10` instruction three (six bytes); `len = 11` is page 2. `N Z V C` are the condition flags. In the drawings the bits of a parcel are numbered from 15 at the left, a shaded box is a fixed value, and a white box is a field that varies.

Cf. section 6.7 for the memory types that decide whether an access is cached, and section 6.4 for what a faulting load leaves behind.

9.6.1 `MOVQ`, `MOVL`, `MOVW` and `MOVB` load and store 64, 32, 16 and 8 bits; the loads sign-extend. `MOVZL`, `MOVZW` and `MOVZB` load with zero extension. *(opcodes `000000 (0x00)`-`001010 (0x0A)`)*

9.6.2 With a register operand, the same opcodes are the conversion set: `MOVB R1, R2` sign-extends the low byte, `MOVZW R1, R2` zero-extends the low word.

9.6.3 `LEA` forms an effective address; `LEA 0(PC), Rn` reads the program counter. *(opcode `001011 (0x0B)`)*

9.6.4 Moves, loads and stores write no flags. *(D)*

9.6.5 The explicit unaligned forms `MOVUB`, `MOVUW`, `MOVUL` and `MOVUQ` exist in both directions, in the memory escape. *(D)*

9.6.6 Page 2 abbreviates the common cases to one parcel: loads and stores through `(rn)`, loads and stores at small offsets from `SP`, `LEA` from `SP`, and `MOVQ #imm, rd` with a four-bit immediate. *(D)*

Commentary. **Precedent.** The PDP-11 had `MOV` and `MOVB` with a byte sign-extended into a register; the VAX had a sized `MOV` for every width. **Trade-offs.** Keeping the sized loads costs four extra opcodes against a quad-only design, but without `MOVL` a struct field load becomes two `MOVWS`, a shift and an or, and ELF, timestamps and most on-disk and wire structures are full of 32- and 16-bit fields. **Improvements.** There is no separate `CVT` group: the conversions are the moves with a register source, so they cost nothing. **Benefits.** No partial-register state anywhere. **Modern comparables.** AArch64 and RISC-V

have the same sized loads with sign and zero extension; x86-64 keeps 8- and 16-bit register writes that preserve the upper bits, which makes narrow writes depend on the old value. **Use.** `LEA 0(PC)` is how a position-independent program finds itself; the unaligned forms are for packed on-disk and network structures. **Impact.** *Kernel:* `LEA 0(PC)` lets position-independent kernel code find itself; the unaligned forms read packed on-disk and network structures. *Compiler:* Sized loads avoid the shift, mask and or of a struct-field read, and the conversions are moves, so no separate conversion selection exists. *Hardware:* No partial-register write anywhere; the conversions reuse the load-extend path.


MOV: Move, load and store (64, 32, 16 and 8 bits)

Mnemonics: `MOVQ`, `MOVL`, `MOVW`, `MOVB`

Syntax

```
MOVQ rm, Rd        ; load
MOVQ Rs, rm        ; store
MOVL, MOVW, MOVB likewise
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
`MOVQ`	`000000 (0x00), 000001 (0x01)`
`MOVL`	`000010 (0x02), 000011 (0x03)`
`MOVW`	`000100 (0x04), 000101 (0x05)`
`MOVB`	`000110 (0x06), 000111 (0x07)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
size = 8 (MOVQ), 4 (MOVL), 2 (MOVW) or 1 (MOVB) bytes
load :  Rd ← sext(M[EA(rm)], size)          ; len = 00: Rd ← sext(Rs[8×size-1:0])
store:  M[EA(rm)] ← Rs[8×size-1:0]          ; len = 00: Rd ← sext(Rs[8×size-1:0])
```

Flags None written.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.


A register is always written in full: a narrow load sign-extends to 64 bits and there is no partial-register write anywhere. At `len = 00` the same opcodes are the conversion set: `MOVB R1, R2` sign-extends the low byte of `R1` into `R2`. Page 2 abbreviates the loads and stores through `(rn)`, at small offsets from `SP` and from a register, and `MOVQ #imm, rd` with a 4-bit immediate (see the page-2 table).

Cf. 6.7 for the memory type that decides whether the access is cached; 6.4 for what a faulting access leaves behind.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

MOVQ


MOVQ, opcode 000000, three parcels (modes base, postinc, predec) (6 bytes)




MOVQ, opcode 000000, three parcels (modes index) (6 bytes)




MOVQ, opcode 000000, three parcels (modes pcrel, imm, abs) (6 bytes)




MOVQ, opcode 000000, three parcels (modes dp) (6 bytes)




MOVQ, opcode 000001, three parcels (modes base, postinc, predec) (6 bytes)




MOVQ, opcode 000001, three parcels (modes index) (6 bytes)




MOVQ, opcode 000001, three parcels (modes pcrel, imm, abs) (6 bytes)




MOVQ, opcode 000001, three parcels (modes dp) (6 bytes)




MOVQ, opcode 000000, two parcels (modes base, postinc, predec) (4 bytes)




MOVQ, opcode 000000, two parcels (modes index) (4 bytes)




MOVQ, opcode 000000, two parcels (modes pcrel, imm, abs) (4 bytes)




MOVQ, opcode 000000, two parcels (modes dp) (4 bytes)




MOVQ, opcode 000001, two parcels (modes base, postinc, predec) (4 bytes)




MOVQ, opcode 000001, two parcels (modes index) (4 bytes)




MOVQ, opcode 000001, two parcels (modes pcrel, imm, abs) (4 bytes)




MOVQ, opcode 000001, two parcels (modes dp) (4 bytes)



MOVQ, opcode 000000, one parcel (2 bytes)



MOVQ, opcode 000001, one parcel (2 bytes)





```
MOVQ rm, Rd
MOVQ Rs, rm
```

Mnemonic	Opcode
MOVQ	000000 (0x00), 000001 (0x01)


Operation, flags and exceptions as for the entry MOV above; 18 layout forms, each a chart of its own (above).

MOVL


MOVL, opcode 000010, three parcels (modes base, postinc, predec) (6 bytes)




MOVL, opcode 000010, three parcels (modes index) (6 bytes)




MOVL, opcode 000010, three parcels (modes pcrel, imm, abs) (6 bytes)




MOVL, opcode 000010, three parcels (modes dp) (6 bytes)




MOVL, opcode 000011, three parcels (modes base, postinc, predec) (6 bytes)




MOVL, opcode 000011, three parcels (modes index) (6 bytes)




MOVL, opcode 000011, three parcels (modes pcrel, imm, abs) (6 bytes)




MOVL, opcode 000011, three parcels (modes dp) (6 bytes)




MOVL, opcode 000010, two parcels (modes base, postinc, predec) (4 bytes)




MOVL, opcode 000010, two parcels (modes index) (4 bytes)




MOVL, opcode 000010, two parcels (modes pcrel, imm, abs) (4 bytes)




MOVL, opcode 000010, two parcels (modes dp) (4 bytes)




MOVL, opcode 000011, two parcels (modes base, postinc, predec) (4 bytes)




MOVL, opcode 000011, two parcels (modes index) (4 bytes)




MOVL, opcode 000011, two parcels (modes pcrel, imm, abs) (4 bytes)




MOVL, opcode 000011, two parcels (modes dp) (4 bytes)



MOVL, opcode 000010, one parcel (2 bytes)



MOVL, opcode 000011, one parcel (2 bytes)





```
MOVL, MOVW, MOVB likewise
```

Mnemonic	Opcode
MOVL	000010 (0x02), 000011 (0x03)


Operation, flags and exceptions as for the entry MOV above; 18 layout forms, each a chart of its own (above).

MOVW


MOVW, opcode 000100, three parcels (modes base, postinc, predec) (6 bytes)




MOVW, opcode 000100, three parcels (modes index) (6 bytes)




MOVW, opcode 000100, three parcels (modes pcrel, imm, abs) (6 bytes)




MOVW, opcode 000100, three parcels (modes dp) (6 bytes)




MOVW, opcode 000101, three parcels (modes base, postinc, predec) (6 bytes)




MOVW, opcode 000101, three parcels (modes index) (6 bytes)




MOVW, opcode 000101, three parcels (modes pcrel, imm, abs) (6 bytes)




MOVW, opcode 000101, three parcels (modes dp) (6 bytes)




MOVW, opcode 000100, two parcels (modes base, postinc, predec) (4 bytes)




MOVW, opcode 000100, two parcels (modes index) (4 bytes)




MOVW, opcode 000100, two parcels (modes pcrel, imm, abs) (4 bytes)




MOVW, opcode 000100, two parcels (modes dp) (4 bytes)




MOVW, opcode 000101, two parcels (modes base, postinc, predec) (4 bytes)




MOVW, opcode 000101, two parcels (modes index) (4 bytes)




MOVW, opcode 000101, two parcels (modes pcrel, imm, abs) (4 bytes)




MOVW, opcode 000101, two parcels (modes dp) (4 bytes)



MOVW, opcode 000100, one parcel (2 bytes)



MOVW, opcode 000101, one parcel (2 bytes)




Mnemonic	Opcode
MOVW	000100 (0x04), 000101 (0x05)


Operation, flags and exceptions as for the entry MOV above; 18 layout forms, each a chart of its own (above).

MOVB


MOVB, opcode 000110, three parcels (modes base, postinc, predec) (6 bytes)




MOVB, opcode 000110, three parcels (modes index) (6 bytes)




MOVB, opcode 000110, three parcels (modes pcrel, imm, abs) (6 bytes)




MOVB, opcode 000110, three parcels (modes dp) (6 bytes)




MOVB, opcode 000111, three parcels (modes base, postinc, predec) (6 bytes)




MOVB, opcode 000111, three parcels (modes index) (6 bytes)




MOVB, opcode 000111, three parcels (modes pcrel, imm, abs) (6 bytes)




MOVB, opcode 000111, three parcels (modes dp) (6 bytes)




MOVB, opcode 000110, two parcels (modes base, postinc, predec) (4 bytes)




MOVB, opcode 000110, two parcels (modes index) (4 bytes)




MOVB, opcode 000110, two parcels (modes pcrel, imm, abs) (4 bytes)




MOVB, opcode 000110, two parcels (modes dp) (4 bytes)




MOVB, opcode 000111, two parcels (modes base, postinc, predec) (4 bytes)




MOVB, opcode 000111, two parcels (modes index) (4 bytes)




MOVB, opcode 000111, two parcels (modes pcrel, imm, abs) (4 bytes)




MOVB, opcode 000111, two parcels (modes dp) (4 bytes)



MOVB, opcode 000110, one parcel (2 bytes)



MOVB, opcode 000111, one parcel (2 bytes)



Mnemonic	Opcode
MOVB	000110 (0x06), 000111 (0x07)

Operation, flags and exceptions as for the entry MOV above; 18 layout forms, each a chart of its own (above).


MOVZ: Move zero-extended (32, 16 and 8 bits)

Mnemonics: MOVZL, MOVZW, MOVZB

Syntax

```
MOVZL rm, Rd
MOVZW rm, Rd
MOVZB rm, Rd
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
MOVZL	001000 (0x08)
MOVZW	001001 (0x09)
MOVZB	001010 (0x0A)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
Rd ← zext(M[EA(rm)], size)      ; len = 00: Rd ← zext(Rs[8×size-1:0])
```

Flags None written.


Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

There is no zero-extending 64-bit move (it would be `MOVQ`). At `len = 00` these are the zero-extending half of the conversion set.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

MOVZL


MOVZL, opcode 001000, three parcels (modes base, postinc, predec) (6 bytes)




MOVZL, opcode 001000, three parcels (modes index) (6 bytes)




MOVZL, opcode 001000, three parcels (modes pcrel, imm, abs) (6 bytes)




MOVZL, opcode 001000, three parcels (modes dp) (6 bytes)




MOVZL, opcode 001000, two parcels (modes base, postinc, predec) (4 bytes)




MOVZL, opcode 001000, two parcels (modes index) (4 bytes)




MOVZL, opcode 001000, two parcels (modes pcrel, imm, abs) (4 bytes)



MOVZL, opcode 001000, two parcels (modes dp) (4 bytes)



MOVZL, opcode 001000, one parcel (2 bytes)





```
MOVZL rm, Rd
```

Mnemonic	Opcode
MOVZL	001000 (0x08)


Operation, flags and exceptions as for the entry MOVZ above; 9 layout forms, each a chart of its own (above).

MOVZW


MOVZW, opcode 001001, three parcels (modes base, postinc, predec) (6 bytes)




MOVZW, opcode 001001, three parcels (modes index) (6 bytes)




MOVZW, opcode 001001, three parcels (modes pcrel, imm, abs) (6 bytes)




MOVZW, opcode 001001, three parcels (modes dp) (6 bytes)




MOVZW, opcode 001001, two parcels (modes base, postinc, predec) (4 bytes)




MOVZW, opcode 001001, two parcels (modes index) (4 bytes)




MOVZW, opcode 001001, two parcels (modes pcrel, imm, abs) (4 bytes)



MOVZW, opcode 001001, two parcels (modes dp) (4 bytes)



MOVZW, opcode 001001, one parcel (2 bytes)





```
MOVZW rm, Rd
```

Mnemonic	Opcode
MOVZW	001001 (0x09)


Operation, flags and exceptions as for the entry MOVZ above; 9 layout forms, each a chart of its own (above).

MOVZB


MOVZB, opcode 001010, three parcels (modes base, postinc, predec) (6 bytes)




MOVZB, opcode 001010, three parcels (modes index) (6 bytes)




MOVZB, opcode 001010, three parcels (modes pcrel, imm, abs) (6 bytes)




MOVZB, opcode 001010, three parcels (modes dp) (6 bytes)




MOVZB, opcode 001010, two parcels (modes base, postinc, predec) (4 bytes)




MOVZB, opcode 001010, two parcels (modes index) (4 bytes)




MOVZB, opcode 001010, two parcels (modes pcrel, imm, abs) (4 bytes)



MOVZB, opcode 001010, two parcels (modes dp) (4 bytes)



MOVZB, opcode 001010, one parcel (2 bytes)





```
MOVZB rm, Rd
```

Mnemonic	Opcode
MOVZB	001010 (0x0A)


Operation, flags and exceptions as for the entry MOVZ above; 9 layout forms, each a chart of its own (above).

LEA: Load effective address


LEA, opcode 001011, three parcels (modes base, postinc, predec) (6 bytes)




LEA, opcode 001011, three parcels (modes index) (6 bytes)




LEA, opcode 001011, three parcels (modes pcrel, imm, abs) (6 bytes)




LEA, opcode 001011, three parcels (modes dp) (6 bytes)



LEA, opcode 001011, two parcels (modes base, postinc, predec) (4 bytes)




LEA, opcode 001011, two parcels (modes index) (4 bytes)




LEA, opcode 001011, two parcels (modes pcrel, imm, abs) (4 bytes)



LEA, opcode 001011, two parcels (modes dp) (4 bytes)



LEA, opcode 001011, one parcel (2 bytes)




Mnemonics: `LEA`

Syntax

```
LEA d(Rn), Rd
LEA d(PC), Rd
LEA d(Rn)(Rx×s), Rd
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
`LEA`	`001011 (0x0B)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
Rd ← EA(rm)          ; no memory access
```

Flags None written.

Exceptions The operand must name memory; `len = 00` (a register) and the immediate mode are reserved. No memory access is made, so the instruction takes no memory fault. A reserved encoding aborts with the illegal-instruction vector.

`LEA 0(PC), Rd` is how the program counter is read: it puts the address of the `LEA` itself in `Rd`. At `len = 10` it forms any address within ±2 GB of itself PC-relatively in six bytes. The base of every PC-relative displacement is the address of the first parcel of the instruction.

Why it is here. The PDP-11 and the VAX made the program counter a register (R7, R15). Here the program counter is kept out of the register file, because every register write would then be a potential branch, and a read-only view of it (R7 as a view of the PC) is refused, because it would fix for ever *which* PC is meant (ARM32 is stuck with `PC+8`). `LEA 0(PC), Rn` gives the capability without the commitment: the address of the instruction itself, in one instruction. The same instruction forms any address PC-relatively, which is what makes position-independent code free (section 9.16).

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


MOVU: Unaligned load and store

Mnemonics: `MOVUB`, `MOVUW`, `MOVUL`, `MOVUQ`

Syntax

```
MOVUQ rm, Rd        ; load, any alignment
MOVUQ Rs, rm        ; store, any alignment
MOVUW, MOVUL, MOVUB likewise
```

Encoding



The chart is the layout `r20-mesc-1`, Memory escape (MESC), two parcels (`len = 01`): Addressing modes (`low`) that use this layout: `base` 0000, `index` 0001, `pcrel` 0010, `dp` 0011, `imm` 0100, `abs` 0101, `postinc` 0110, `predec` 0111. `low` of parcel 0 is an addressing mode; parcel 1 holds the sub-opcode, `rm` and the first 8 bits of the displacement.

Mnemonic	Opcode	Sub-opcode
`MOVUB`	`001111 (0x0F)`	`0000 (0x0)`
`MOVUW`	`001111 (0x0F)`	`0010 (0x2)`
`MOVUL`	`001111 (0x0F)`	`0100 (0x4)`
`MOVUQ`	`001111 (0x0F)`	`0110 (0x6)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mesc-1`, `r20-mesc-2`.

Operation

```
size = 1, 2, 4 or 8 bytes
load :  Rd ← sext(M[EA(rm)], size)           ; the access may cross an alignment boundary
store:  M[EA(rm)] ← Rs[8×size-1:0]
```

Flags None written.

Exceptions Page and protection faults and bus errors as for any memory operand; **no alignment fault**.

The ordinary moves fault on a misaligned address (the alignment fault is the tag check of section 9.5); these are the explicit forms for data that is not aligned, in `MESC`.


Why it is here. Data alignment is architectural on this machine (9.2.11): an ordinary quad access to an address that is not a multiple of 8 aborts, and that abort doubles as the tag check for tagged pointers; a load form that ignores low pointer bits is rejected for that reason. Packed on-disk and network structures still need unaligned access, so `MESC` carries explicit unaligned forms rather than weakening the rule for every load. No further reason is recorded for these four.

Cf. 6.6, 6.4.

Status specified; **not yet implemented** in the reference executor.

MOVUB

MOVUB, opcode 001111, three parcels, sub-opcode 0000 (modes base, index, pcrel, dp, imm,



MOVUB, opcode 001111, two parcels, sub-opcode 0000 (modes base, index, pcrel, dp, imm, a




Mnemonic	Opcode	Sub-opcode
MOVUB	001111 (0x0F)	0000 (0x0)


Operation, flags and exceptions as for the entry MOVU above; 2 layout forms, each a chart of its own (above).

MOVUW

MOVUW, opcode 001111, three parcels, sub-opcode 0010 (modes base, index, pcrel, dp, imm



MOVUW, opcode 001111, two parcels, sub-opcode 0010 (modes base, index, pcrel, dp, imm, a





```
MOVUW, MOVUL, MOVUB likewise
```

Mnemonic	Opcode	Sub-opcode
MOVUW	001111 (0x0F)	0010 (0x2)


Operation, flags and exceptions as for the entry MOVU above; 2 layout forms, each a chart of its own (above).

MOVUL

MOVUL, opcode 001111, three parcels, sub-opcode 0100 (modes base, index, pcrel, dp, imm,



MOVUL, opcode 001111, two parcels, sub-opcode 0100 (modes base, index, pcrel, dp, imm, a




Mnemonic	Opcode	Sub-opcode
MOVUL	001111 (0x0F)	0100 (0x4)


Operation, flags and exceptions as for the entry MOVU above; 2 layout forms, each a chart of its own (above).

MOVUQ

MOVUQ, opcode 001111, three parcels, sub-opcode 0110 (modes base, index, pcrel, dp, imm



MOVUQ, opcode 001111, two parcels, sub-opcode 0110 (modes base, index, pcrel, dp, imm, a




```
MOVUQ rm, Rd
MOVUQ Rs, rm
```

Mnemonic	Opcode	Sub-opcode
MOVUQ	001111 (0x0F)	0110 (0x6)

Operation, flags and exceptions as for the entry MOVU above; 2 layout forms, each a chart of its own (above).

9.7 Integer arithmetic

Cf. section 6.3 for the divide-by-zero vector (DIV, DIVU, MOD, MODU).

9.7.1 ADD, SUB, CMP, MUL and MULH are two bytes with register operands; MULHU (high half of an unsigned product), DIV, DIVU, MOD and MODU are in the arithmetic escape. *(D)*

9.7.2 CMP is written `CMP Rd, rm`, register first, and computes `Rd - rm`. *(D)*

9.7.3 ADD sets C on a carry; SUB and CMP set C on a borrow, the PDP-11 sense, so BHIS and BCC mean "no borrow", unsigned greater or equal. *(D)*

9.7.4 ADC and SBC add and subtract the carry; INC, DEC, NEG, CLR and TST are single-operand forms that work on a register or memory. *(opcode group SOP)*


9.7.5 `SET cc, Rd` (write 1 if the condition holds, else 0) is in the arithmetic escape. *(D)*

9.7.6 ABS, MIN, MINU, MAX and MAXU are assembler aliases, not native instructions: ABS is the absolute value, and the others the smaller or the larger of two registers, signed or unsigned, with N and Z from the result, C unchanged, and V cleared (set by ABS on the most negative number). *(D)* Their expansion is open *(P)*: the flag-driven conditional select has no form yet, and a candidate over the branch-free MASKEQZ and MASKNEZ (a comparison, SET into a scratch register, the two masks and BIS) needs a scratch register and changes C. The present assembler still encodes the five words as sub-opcodes of the arithmetic escape; their dictionary entries show that encoding as the build's, not the design's. *(D)*


Commentary. **Precedent.** ADD, SUB, CMP, BIT, BIS, BIC and the single-operand set are the PDP-11's, unchanged in name and meaning except for the order of CMP's operands. **Trade-offs.** The PDP-11 wrote `CMP a, b` to compute `a - b`; since the destination of an ALU operation here must be a register, a literal `src, dst` reading would force every comparison against an immediate or memory to be reversed, so the register comes first. Divide is in the escape group, at four bytes, because compilers turn division by a constant into MULH plus a shift, so a real divide is rare. **Improvements.** The high-half multiply that bignum code needs is present; a second unsigned multiply is the same instruction as the first and is not provided. **Benefits.** SET replaces a branch around a move for the very common "store the truth value of a comparison", and absolute value, minimum and maximum (as aliases) remove a compare-and-branch from small loops. **Modern comparables.** RISC-V has MULH, MULHU and MULHSU, and AArch64 SMULH and UMULH; x86 has a one-operand multiply that produces both halves; AArch64's conditional select and set instructions are the nearest to SET. **Use.** MULH and MULHU are for multi-precision arithmetic and for division by constants; ADC and SBC carry a multi-word add or subtract; MIN, MAX and ABS (aliases) appear under a tenth of a percent of compiled code but each replaces a branch. **Impact.** *Kernel:* ADC and SBC carry multiword arithmetic for the kernel's 128-bit counters and for the bignum code in the base system. *Compiler:* MULH turns division by a constant into a multiply and a shift; SET materialises a comparison without a branch; CMP takes the register first, as the compiler orders its operands. *Hardware:* One adder on the carry chain; on an FPGA the multiplier is built from two to four multiplier blocks over four to eight cycles; the divide is a sequencer.

ADD: Add


ADD, opcode 010110, three parcels (modes base, postinc, predec) (6 bytes)




ADD, opcode 010110, three parcels (modes index) (6 bytes)




ADD, opcode 010110, three parcels (modes pcrel, imm, abs) (6 bytes)




ADD, opcode 010110, three parcels (modes dp) (6 bytes)




ADD, opcode 010110, two parcels (modes base, postinc, predec) (4 bytes)




ADD, opcode 010110, two parcels (modes index) (4 bytes)




ADD, opcode 010110, two parcels (modes pcrel, imm, abs) (4 bytes)



ADD, opcode 010110, two parcels (modes dp) (4 bytes)



ADD, opcode 010110, one parcel (2 bytes)




Mnemonics: `ADD`

Syntax

```
ADD rm, Rd
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
ADD	010110 (0x16)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
Rd ← Rd + rm
```

Flags `N` and `Z` from the result, `V` set on signed overflow, `C` set on a carry out of bit 63.


Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

All ALU operations are 64 bits, with no size field. Page 2 has `ADD #imm, rd` with a 4-bit immediate and `ADD #(8*n), SP`.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

SUB: Subtract


SUB, opcode 010111, three parcels (modes base, postinc, predec) (6 bytes)




SUB, opcode 010111, three parcels (modes index) (6 bytes)




SUB, opcode 010111, three parcels (modes pcrel, imm, abs) (6 bytes)




SUB, opcode 010111, three parcels (modes dp) (6 bytes)




SUB, opcode 010111, two parcels (modes base, postinc, predec) (4 bytes)




SUB, opcode 010111, two parcels (modes index) (4 bytes)




SUB, opcode 010111, two parcels (modes pcrel, imm, abs) (4 bytes)



SUB, opcode 010111, two parcels (modes dp) (4 bytes)



SUB, opcode 010111, one parcel (2 bytes)




Mnemonics: `SUB`

Syntax

```
SUB rm, Rd
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
SUB	010111 (0x17)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
Rd ← Rd - rm
```

Flags `N` and `Z` from the result, `V` set on signed overflow, `C` set on a **borrow** (the PDP-11 sense): `C` = 1 when the unsigned operand being subtracted is the larger.


Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

Page 2 has `SUB #(8*n), SP`.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

CMP: Compare


CMP, opcode 011010, three parcels (modes base, postinc, predec) (6 bytes)




CMP, opcode 011010, three parcels (modes index) (6 bytes)




CMP, opcode 011010, three parcels (modes pcrel, imm, abs) (6 bytes)




CMP, opcode 011010, three parcels (modes dp) (6 bytes)




CMP, opcode 011010, two parcels (modes base, postinc, predec) (4 bytes)




CMP, opcode 011010, two parcels (modes index) (4 bytes)




CMP, opcode 011010, two parcels (modes pcrel, imm, abs) (4 bytes)



CMP, opcode 011010, two parcels (modes dp) (4 bytes)



CMP, opcode 011010, one parcel (2 bytes)




Mnemonics: `CMP`

Syntax

```
CMP Rd, rm        ; register first
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
`CMP`	`011010 (0x1A)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
tmp ← Rd - rm         ; the result is discarded
```

Flags `N` and `Z` from the result, `V` set on signed overflow, `C` set on a **borrow** (the PDP-11 sense): `C` = 1 when the unsigned operand being subtracted is the larger.


Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

The operands are in the order register, then the other operand, the reverse of the PDP-11 `CMP src,dst`: `CMP Rd, rm` computes `Rd - rm`, so a compare of a register against an immediate or memory operand does not reverse its branch condition. After `CMP`, `BHIS`/`BCC` mean unsigned `>=` (no borrow) and `BLO`/`BCS` mean a borrow occurred.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

MUL: Multiply, low 64 bits


MUL, opcode 011110, three parcels (modes base, postinc, predec) (6 bytes)




MUL, opcode 011110, three parcels (modes index) (6 bytes)




MUL, opcode 011110, three parcels (modes pcrel, imm, abs) (6 bytes)




MUL, opcode 011110, three parcels (modes dp) (6 bytes)



MUL, opcode 011110, two parcels (modes base, postinc, predec) (4 bytes)




MUL, opcode 011110, two parcels (modes index) (4 bytes)




MUL, opcode 011110, two parcels (modes pcrel, imm, abs) (4 bytes)



MUL, opcode 011110, two parcels (modes dp) (4 bytes)



MUL, opcode 011110, one parcel (2 bytes)




Mnemonics: `MUL` (aliases: `MULU`)

Syntax

```
MUL rm, Rd
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
`MUL`	`011110 (0x1E)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
Rd ← (Rd × rm)[63:0]        ; sign-agnostic
```

Flags `N` and `Z` from the result, `V` set when the signed 128-bit product does not fit in 64 bits, `C` unchanged.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.


The low 64 bits of a two's-complement product are the same whether the operands are read as signed or unsigned, so there is one low-half multiply. The mnemonic `MULU` is an alias of `MUL`. The high half is `MULH` (signed) and `MULHU` (unsigned).

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


`MULU` is an alias of `MUL`: the assembler writes it as that word.

MULH: Multiply, high 64 bits, signed


MULH, opcode 011111, three parcels (modes base, postinc, predec) (6 bytes)




MULH, opcode 011111, three parcels (modes index) (6 bytes)




MULH, opcode 011111, three parcels (modes pcrel, imm, abs) (6 bytes)




MULH, opcode 011111, three parcels (modes dp) (6 bytes)




MULH, opcode 011111, two parcels (modes base, postinc, predec) (4 bytes)




MULH, opcode 011111, two parcels (modes index) (4 bytes)




MULH, opcode 011111, two parcels (modes pcrel, imm, abs) (4 bytes)



MULH, opcode 011111, two parcels (modes dp) (4 bytes)



MULH, opcode 011111, one parcel (2 bytes)




Mnemonics: `MULH`

Syntax

```
MULH rm, Rd
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
MULH	011111 (0x1F)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
Rd ← (sext(Rd) × sext(rm))[127:64]
```

Flags `N` and `Z` from the result, `V` cleared, `C` unchanged.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

With `MULH`, division by a constant is a multiply by a reciprocal and a shift, which is what compilers emit.

Why it is here. The low 64 bits of a two's-complement product are identical signed or unsigned, so a second multiply (`MULU`) would duplicate `MUL`; what the architecture needs in that place is the *high* half of the product. Without it a 64 by 64 to 128-bit multiply, every bignum multiply, 128-bit fixed point and divide-by-a-constant by multiplying by the reciprocal are impossible. `MULH` is that instruction. It is also why a divide is rare in compiled code: compilers turn division by a constant into `MULH` and a shift.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


ADDM: ALU operation with a memory destination

Mnemonics: `ADDM`, `SUBM`, `BICM`, `BISM`

Syntax

```
ADDM Rs, rm
SUBM Rs, rm
BICM Rs, rm
BISM Rs, rm
```

Encoding



The chart is the layout `r20-mesc-1`, Memory escape (MESC), two parcels (`len = 01`): Addressing modes (`low`) that use this layout: `base` 0000, `index` 0001, `pcrel` 0010, `dp` 0011, `imm` 0100, `abs` 0101, `postinc` 0110, `predec` 0111. `low` of parcel 0 is an addressing mode; parcel 1 holds the sub-opcode, `rm` and the first 8 bits of the displacement.

Mnemonic	Opcode	Sub-opcode
ADDM	001111 (0x0F)	1000 (0x8)

Mnemonic	Opcode	Sub-opcode
SUBM	001111 (0x0F)	1001 (0x9)
BICM	001111 (0x0F)	1010 (0xA)
BISM	001111 (0x0F)	1011 (0xB)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-mesc-1, r20-mesc-2.

Operation

```
ADDM: M[EA] ← M[EA] + Rs
SUBM: M[EA] ← M[EA] - Rs
BICM: M[EA] ← M[EA] AND NOT Rs
BISM: M[EA] ← M[EA] OR Rs
```

Flags As for ADD, SUB, BIC and BIS.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause BUSFAULT). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires. Write permission is checked during the read access, so the write cannot fault after the read has succeeded.


Parcel 0's low nibble is a mode, as in the ordinary memory format, so these are MESC forms with a memory destination (len >= 01). INC, DEC, NEG, COM and CLR on a memory operand are in SOP.

Why it is here. These are the read-modify-write forms with a memory destination. An instruction with a memory destination is at least four bytes anyway, so they live in MESC at no cost; the opcode map follows one rule, that a top-level opcode is for an operation whose common case is register to register. They cover the case where the second operand is a register, for example BISM Rmask, flags(DP). The compiled corpus has 265 sites (1.6 KB), so they earn their place in the escape group but not in the opcode space.


Status specified; **not yet implemented** in the reference executor.

ADDM

ADDM, opcode 001111, three parcels, sub-opcode 1000 (modes base, index, pcrel, dp, imm, a



ADDM, opcode 001111, two parcels, sub-opcode 1000 (modes base, index, pcrel, dp, imm, ab





```
ADDM Rs, rm
```

Mnemonic	Opcode	Sub-opcode
ADDM	001111 (0x0F)	1000 (0x8)


Operation, flags and exceptions as for the entry ADDM above; 2 layout forms, each a chart of its own (above).

SUBM

SUBM, opcode 001111, three parcels, sub-opcode 1001 (modes base, index, pcrel, dp, imm, a



SUBM, opcode 001111, two parcels, sub-opcode 1001 (modes base, index, pcrel, dp, imm, ab





```
SUBM Rs, rm
```

Mnemonic	Opcode	Sub-opcode
SUBM	001111 (0x0F)	1001 (0x9)

Operation, flags and exceptions as for the entry ADDM above; 2 layout forms, each a chart of its own (above).

BICM

BICM, opcode 001111, three parcels, sub-opcode 1010 (modes base, index, pcrel, dp, imm, a



BICM, opcode 001111, two parcels, sub-opcode 1010 (modes base, index, pcrel, dp, imm, abs





```
BICM Rs, rm
```

Mnemonic	Opcode	Sub-opcode
BICM	001111 (0x0F)	1010 (0xA)

Operation, flags and exceptions as for the entry ADDM above; 2 layout forms, each a chart of its own (above).

BISM

BISM, opcode 001111, three parcels, sub-opcode 1011 (modes base, index, pcrel, dp, imm, a



BISM, opcode 001111, two parcels, sub-opcode 1011 (modes base, index, pcrel, dp, imm, abs





```
BISM Rs, rm
```

Mnemonic	Opcode	Sub-opcode
BISM	001111 (0x0F)	1011 (0xB)


Operation, flags and exceptions as for the entry ADDM above; 2 layout forms, each a chart of its own (above).

INC: Increment


INC, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




INC, opcode 010011, three parcels (modes index) (6 bytes)




INC, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




INC, opcode 010011, three parcels (modes dp) (6 bytes)




INC, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




INC, opcode 010011, two parcels (modes index) (4 bytes)




INC, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



INC, opcode 010011, two parcels (modes dp) (4 bytes)



INC, opcode 010011, one parcel (2 bytes)




Mnemonics: `INC`

Syntax

```
INC rm
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	`reg`
`INC`	`010011 (0x13)`	`0010 (0x2)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.

Operation

```
rm ← rm + 1
```


Flags `N`, `Z` and `V` as for `ADD`; `C` **unchanged**.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

DEC: Decrement


DEC, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




DEC, opcode 010011, three parcels (modes index) (6 bytes)




DEC, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




DEC, opcode 010011, three parcels (modes dp) (6 bytes)




DEC, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




DEC, opcode 010011, two parcels (modes index) (4 bytes)




DEC, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



DEC, opcode 010011, two parcels (modes dp) (4 bytes)



DEC, opcode 010011, one parcel (2 bytes)



Mnemonics: `DEC`

Syntax

```
DEC rm
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
DEC	010011 (0x13)	0011 (0x3)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.

Operation

```
rm ← rm - 1
```


Flags `N`, `Z` and `V` as for `SUB`; `C` **unchanged**.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

NEG: Negate


NEG, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




NEG, opcode 010011, three parcels (modes index) (6 bytes)




NEG, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




NEG, opcode 010011, three parcels (modes dp) (6 bytes)




NEG, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




NEG, opcode 010011, two parcels (modes index) (4 bytes)




NEG, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



NEG, opcode 010011, two parcels (modes dp) (4 bytes)



NEG, opcode 010011, one parcel (2 bytes)




Mnemonics: `NEG`

Syntax

```
NEG rm
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	`reg`
`NEG`	`010011 (0x13)`	`0100 (0x4)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.

Operation

```
rm ← 0 - rm
```


Flags `N` and `Z` from the result, `V` set on signed overflow, `C` set on a **borrow** (the PDP-11 sense): `C` = 1 when the unsigned operand being subtracted is the larger. (`C` = 1 unless the operand was 0.)

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

ADC: Add carry


ADC, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




ADC, opcode 010011, three parcels (modes index) (6 bytes)




ADC, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




ADC, opcode 010011, three parcels (modes dp) (6 bytes)




ADC, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




ADC, opcode 010011, two parcels (modes index) (4 bytes)




ADC, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



ADC, opcode 010011, two parcels (modes dp) (4 bytes)



ADC, opcode 010011, one parcel (2 bytes)




Mnemonics: `ADC`

Syntax

```
ADC rm
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
ADC	010011 (0x13)	0110 (0x6)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.

Operation

```
rm ← rm + C
```

Flags `N` and `Z` from the result, `V` set on signed overflow, `C` set on a carry out of bit 63.


Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

With `ADD`, multi-word addition.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

SBC: Subtract carry


SBC, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




SBC, opcode 010011, three parcels (modes index) (6 bytes)




SBC, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




SBC, opcode 010011, three parcels (modes dp) (6 bytes)



SBC, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




SBC, opcode 010011, two parcels (modes index) (4 bytes)




SBC, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



SBC, opcode 010011, two parcels (modes dp) (4 bytes)



SBC, opcode 010011, one parcel (2 bytes)




Mnemonics: `SBC`

Syntax

```
SBC rm
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	`reg`
`SBC`	`010011 (0x13)`	`0111 (0x7)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.

Operation

```
rm ← rm - C
```

Flags `N` and `Z` from the result, `V` set on signed overflow, `C` set on a **borrow** (the PDP-11 sense): `C` = 1 when the unsigned operand being subtracted is the larger.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


DIV: Divide and remainder, signed and unsigned

Mnemonics: `DIV`, `DIVU`, `MOD`, `MODU`

Syntax

```
DIV Ra, Rb, Rd
DIVU Ra, Rb, Rd
MOD Ra, Rb, Rd
MODU Ra, Rb, Rd
```

Encoding



The chart is the layout `r20-aesc-1`, Arithmetic (AESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
DIV	001110 (0x0E)	00000000 (0x00)
DIVU	001110 (0x0E)	00000001 (0x01)
MOD	001110 (0x0E)	00000010 (0x02)
MODU	001110 (0x0E)	00000011 (0x03)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-aesc-1`, `r20-aesc-2`.

Operation

```
if Rb = 0 then divide-by-zero abort
DIV : Rd ← Ra ÷ Rb  (signed, rounded toward zero; INT_MIN ÷ -1 = INT_MIN)
DIVU: Rd ← Ra ÷ Rb  (unsigned)
MOD : Rd ← Ra mod Rb (signed, the sign of Ra; any value mod -1 = 0)
MODU: Rd ← Ra mod Rb (unsigned)
```

Flags None written.

Exceptions Division by zero aborts with the divide-by-zero vector (cause `DIVZERO`). There is no overflow trap: `INT_MIN / -1` returns `INT_MIN`.


Division by a constant is a `MULH` and a shift, so a real divide is rare; this is why divide has no two-byte form.

Cf. 6.3 (the divide-by-zero vector).


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

DIV

DIV, opcode 001110, three parcels, sub-opcode 00000000 (6 bytes)



DIV, opcode 001110, two parcels, sub-opcode 00000000 (4 bytes)





```
DIV Ra, Rb, Rd
```

Mnemonic	Opcode	Sub-opcode
DIV	001110 (0x0E)	00000000 (0x00)


Operation, flags and exceptions as for the entry DIV above; 2 layout forms, each a chart of its own (above).

DIVU

DIVU, opcode 001110, three parcels, sub-opcode 00000001 (6 bytes)



DIVU, opcode 001110, two parcels, sub-opcode 00000001 (4 bytes)





```
DIVU Ra, Rb, Rd
```

Mnemonic	Opcode	Sub-opcode
DIVU	001110 (0x0E)	00000001 (0x01)


Operation, flags and exceptions as for the entry DIV above; 2 layout forms, each a chart of its own (above).

MOD

MOD, opcode 001110, three parcels, sub-opcode 00000010 (6 bytes)



MOD, opcode 001110, two parcels, sub-opcode 00000010 (4 bytes)





```
MOD Ra, Rb, Rd
```

Mnemonic	Opcode	Sub-opcode
MOD	001110 (0x0E)	00000010 (0x02)


Operation, flags and exceptions as for the entry DIV above; 2 layout forms, each a chart of its own (above).

MODU

MODU, opcode 001110, three parcels, sub-opcode 00000011 (6 bytes)



MODU, opcode 001110, two parcels, sub-opcode 00000011 (4 bytes)





```
MODU Ra, Rb, Rd
```

Mnemonic	Opcode	Sub-opcode
MODU	001110 (0x0E)	00000011 (0x03)


Operation, flags and exceptions as for the entry DIV above; 2 layout forms, each a chart of its own (above).

MULHU: Multiply, high 64 bits, unsigned

MULHU, opcode 001110, three parcels, sub-opcode 00000100 (6 bytes)



MULHU, opcode 001110, two parcels, sub-opcode 00000100 (4 bytes)




Mnemonics: `MULHU`

Syntax

```
MULHU Ra, Rb, Rd
```

Encoding



The chart is the layout `r20-aesc-1`, Arithmetic (AESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
MULHU	001110 (0x0E)	00000100 (0x04)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-aesc-1`, `r20-aesc-2`.

Operation

```
Rd ← (Ra × Rb)[127:64]    ; unsigned
```

Flags None written.

Exceptions None.


MULHSU (signed by unsigned) is reserved and not committed.

Why it is here. The unsigned partner of MULH, for the same reason (the high half of the product). It is in AESC, where arithmetic belongs. MULHSU, signed times unsigned for a bignum's top limb, is reserved because it can be built from MULH with one correction.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

ABS: Absolute value (assembler alias)

ABS, opcode 001110, three parcels, sub-opcode 00001000 (6 bytes)



ABS, opcode 001110, two parcels, sub-opcode 00001000 (4 bytes)




Mnemonics: ABS

Alias *(D)* ABS is an assembler alias, not a native instruction (the author's decision, errata 98). Meaning: `Rd <- |Rs|`, with the flags below, which the alias must keep or the decision that defines it must change. Expansion: open *(P)*; the flag-driven conditional select (CMOV, CSEL) is on hold and has no form in the records (ISA section 12 item 15); the only select the records define is the branch-free MASKEQZ/MASKNEZ (errata 85), which reads a register and no flag. A candidate over it, not decided: compare the operands, SET the condition into a scratch register, then MASKEQZ, MASKNEZ and BIS (the constant-time select `d = c ? a : b` of the MASKEQZ entry) for the minimum and maximum, and the same around the negated value for ABS; it needs a scratch register and leaves C as the comparison set it, which the native word does not do, so the flags would change. Which expansion, and whether the select the author meant is this one, is the author's question. The present assembler still encodes the word as the arithmetic-escape sub-opcode of the chart below.

Syntax

```
ABS Rs, Rd
```

Encoding (the present encoding of the build, as the grammar gives it; not the design)



The chart is the layout `r20-aesc-1`, Arithmetic (AESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
ABS	001110 (0x0E)	00001000 (0x08)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-aesc-1`, `r20-aesc-2`.

Operation

```
Rd ← |Rs|
```

Flags N and Z from the result, V set if Rs is the most negative value (the result is then still negative), C unchanged.

Exceptions None.

Why it is here. Integer absolute value is the counterpart of FABS. It was added as a native sub-opcode and the author then decided (2026-11-10) that it is an assembler alias over the conditional select, which is not yet defined. The cost of the native word was about 150 to 250 lookup tables, no new operation by the folding rule (integer against float and signed against unsigned are qualifiers), and the compiler's work of recognising `x < 0 ? -x : x`, which is the real cost. The compiled corpus has 18 uses of `abs` and 5 of its unsigned form, under 0.1% of code, so the case is clarity and the idiom more than size.

Status by decision an assembler alias (errata 98); the present assembler, simulator, QEMU and LLVM still encode and execute the word as the arithmetic-escape sub-opcode shown above, so the word is implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

MINMAX: Minimum and maximum, signed and unsigned (assembler aliases)


Mnemonics: MIN, MINU, MAX, MAXU

Alias *(D)* MIN, MINU, MAX and MAXU are assembler aliases, not native instructions (the author's decision, errata 98). Meaning: the smaller or the larger of Ra and Rb, signed for MIN and MAX and unsigned for MINU and MAXU, with the flags below, which an alias must keep or the decision that defines it must change. Expansion: open *(P)*; the flag-driven conditional select (CMOV, CSEL) is on hold and has no form in the records (ISA section 12 item 15); the only select the records define is the branch-free MASKEQZ/MASKNEZ (errata 85), which reads a register and no flag. A candidate over it, not decided: compare the operands, SET the condition into a scratch register, then MASKEQZ, MASKNEZ and BIS (the constant-time select `d = c ? a : b` of the MASKEQZ entry) for the minimum and maximum, and the same around the negated value for ABS; it needs a scratch register and leaves C as the comparison set it, which the native word does not do, so the flags would change. Which expansion, and whether the select the author meant is this one, is the author's question. The present assembler still encodes each word as an arithmetic-escape sub-opcode, as the chart below shows.

Syntax

```
MIN Ra, Rb, Rd
MINU Ra, Rb, Rd
MAX Ra, Rb, Rd
MAXU Ra, Rb, Rd
```

Encoding (the present encoding of the build, as the grammar gives it; not the design)



The chart is the layout `r20-aesc-1`, Arithmetic (AESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
MIN	001110 (0x0E)	00010000 (0x10)
MINU	001110 (0x0E)	00010001 (0x11)
MAX	001110 (0x0E)	00010010 (0x12)
MAXU	001110 (0x0E)	00010011 (0x13)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-aesc-1`, `r20-aesc-2`.

Operation

```
MIN : Rd ← smaller of Ra, Rb (signed)        MINU: unsigned
MAX : Rd ← larger of Ra, Rb (signed)         MAXU: unsigned
```

Flags N and Z from the result, V = 0, C unchanged.


Exceptions None.

Why it is here. The integer counterparts of FMIN and FMAX, provided with ABS; the author decided (2026-11-10) that they are assembler aliases over the conditional select, which is not yet defined. By the folding rule they add no operation, and the native hardware reused the subtract-and-compare that CMP already does plus a 64-bit select. The corpus has 171 uses of MIN and 52 of MAX across 95 files, under 0.1% of code in all. A general conditional select is the alternative; it is open (9.21) for want of a speed model.


Status by decision an assembler alias (errata 98); the present assembler, simulator, QEMU and LLVM still encode and execute the word as the arithmetic-escape sub-opcode shown above, so the word is implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

MIN

MIN, opcode 001110, three parcels, sub-opcode 00010000 (6 bytes)



MIN, opcode 001110, two parcels, sub-opcode 00010000 (4 bytes)





```
MIN Ra, Rb, Rd
```

Mnemonic	Opcode	Sub-opcode
MIN	001110 (0x0E)	00010000 (0x10)


Operation, flags and exceptions as for the entry MINMAX above; 2 layout forms, each a chart of its own (above).

MINU

MINU, opcode 001110, three parcels, sub-opcode 00010001 (6 bytes)



MINU, opcode 001110, two parcels, sub-opcode 00010001 (4 bytes)





```
MINU Ra, Rb, Rd
```

Mnemonic	Opcode	Sub-opcode
MINU	001110 (0x0E)	00010001 (0x11)


Operation, flags and exceptions as for the entry MINMAX above; 2 layout forms, each a chart of its own (above).

MAX

MAX, opcode 001110, three parcels, sub-opcode 00010010 (6 bytes)



MAX, opcode 001110, two parcels, sub-opcode 00010010 (4 bytes)





```
MAX Ra, Rb, Rd
```

Mnemonic	Opcode	Sub-opcode
MAX	001110 (0x0E)	00010010 (0x12)


Operation, flags and exceptions as for the entry MINMAX above; 2 layout forms, each a chart of its own (above).

MAXU

MAXU, opcode 001110, three parcels, sub-opcode 00010011 (6 bytes)



MAXU, opcode 001110, two parcels, sub-opcode 00010011 (4 bytes)





```
MAXU Ra, Rb, Rd
```

Mnemonic	Opcode	Sub-opcode
MAXU	001110 (0x0E)	00010011 (0x13)


Operation, flags and exceptions as for the entry MINMAX above; 2 layout forms, each a chart of its own (above).

SET: Set a register from a condition

SET, opcode 001110, three parcels, sub-opcode 00100000 (6 bytes)



SET, opcode 001110, two parcels, sub-opcode 00100000 (4 bytes)




Mnemonics: `SET`

Syntax

```
SET cc, Rd        ; for example SET EQ, R1
```

Encoding



The chart is the layout `r20-aesc-1`, Arithmetic (AESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
`SET`	`001110 (0x0E)`	`00100000 (0x20)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-aesc-1`, `r20-aesc-2`.

Operation

```
Rd ← 1 if condition cc holds on the current flags, else 0
```

Flags None written.

Exceptions None.

The condition is the `x` field of parcel 1, numbered as the low nibble of the branch opcodes (`al` 0, `ne` 1, `eq` 2, ... `los` 14).

Why it is here. The first instruction written with a condition word: one instruction, `SET cc, Rd`, rather than one opcode per condition, with the condition in a field numbered like the low nibble of the branch opcodes. It turns a comparison used

as a value into 0 or 1 without a branch. gcc `-Os` for amd64 emits 673 `set<cc>` on the corpus, and `SET` would remove about six bytes per site, around 0.4% of code; the compiler's first pass turns such a comparison into branches before its second pass sees it, so the saving is not reached in compiled code.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

9.8 Logic, shifts and rotates

9.8.1 `AND`, `BIC` (bit clear), `BIS` (bit set, the or), `XOR` and `BIT` (test) are two-byte ALU operations; `COM` is one's complement. *(opcodes `011000 (0x18)`, `011001 (0x19)`, `011011 (0x1B)`, `011100 (0x1C)`, `011101 (0x1D)`)*

9.8.2 `SHL`, `SHR` and `SAR` shift by a count taken from `rm` (a register, an immediate, or memory); `ASL` and `ASR` are the by-one forms in two bytes. *(D)*

9.8.3 A shift count of 64 or more shifts the value entirely away; `C` receives the last bit that left. *(D)*


9.8.4 `ROR` rotates right by a register count and `RORI` by an immediate; `ROL Rd, Rs, #n` assembles to `RORI` with `64 - n`; `RORI32` rotates the low 32 bits and sign-extends. Rotates write no flags. *(D)*

9.8.5 `DSHR` is a double-width funnel shift. It writes no flags. *(D)*


Commentary. **Precedent.** The PDP-11 had `ASL`, `ASR`, `ROL` and `ROR` by one through the carry; x86's `SHRD` and ARM's `EXTR` are the funnel shifts. **Trade-offs.** One rotate direction is enough, so there is no by-one `ROL` in a two-byte slot; rotates are not through the carry because a carry chain is fragile when the carry flag is shared. **Improvements.** The shift count comes from `rm`, not from a fixed register like x86's `CL`, which costs a register shuffle in every hand-written loop. **Benefits.** Multi-precision shifting is `DSHR`, two instructions for any distance. **Modern comparables.** RISC-V and AArch64 have rotates by register and by immediate; x86 has `ROL`/`ROR` through the carry as well. **Use.** `RORI` and `RORI32` are for hashes and ciphers, which rotate by constants; `DSHR` shifts a bignum. **Impact.** *Kernel:* Bit tests and mask operations on the status and page-table words are single instructions. *Compiler:* The shift count may be any register, immediate or memory operand, so the compiler never has to move a count into a fixed register; hashes and ciphers rotate by constants. *Hardware:* The barrel shifter (about 450 lookup tables) serves shifts and rotates, and writing no flag for rotates removes a result path.

BIC: Bit clear


BIC, opcode 011000, three parcels (modes base, postinc, predec) (6 bytes)




BIC, opcode 011000, three parcels (modes index) (6 bytes)




BIC, opcode 011000, three parcels (modes pcrel, imm, abs) (6 bytes)




BIC, opcode 011000, three parcels (modes dp) (6 bytes)




BIC, opcode 011000, two parcels (modes base, postinc, predec) (4 bytes)




BIC, opcode 011000, two parcels (modes index) (4 bytes)




BIC, opcode 011000, two parcels (modes pcrel, imm, abs) (4 bytes)



BIC, opcode 011000, two parcels (modes dp) (4 bytes)



BIC, opcode 011000, one parcel (2 bytes)




Mnemonics: `BIC`

Syntax

```
BIC rm, Rd
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
`BIC`	`011000 (0x18)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
Rd ← Rd AND NOT rm
```

Flags `N` and `Z` from the result, `V` cleared, `C` unchanged.


Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

The assembler also accepts `BIC #imm, rm` as `AND #~imm, rm`.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

BIS: Bit set (inclusive or)


BIS, opcode 011001, three parcels (modes base, postinc, predec) (6 bytes)




BIS, opcode 011001, three parcels (modes index) (6 bytes)




BIS, opcode 011001, three parcels (modes pcrel, imm, abs) (6 bytes)




BIS, opcode 011001, three parcels (modes dp) (6 bytes)




BIS, opcode 011001, two parcels (modes base, postinc, predec) (4 bytes)




BIS, opcode 011001, two parcels (modes index) (4 bytes)




BIS, opcode 011001, two parcels (modes pcrel, imm, abs) (4 bytes)



BIS, opcode 011001, two parcels (modes dp) (4 bytes)



BIS, opcode 011001, one parcel (2 bytes)




Mnemonics: `BIS`

Syntax

```
BIS rm, Rd
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
`BIS`	`011001 (0x19)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
Rd ← Rd OR rm
```


Flags `N` and `Z` from the result, `V` cleared, `C` unchanged.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

BIT: Bit test


BIT, opcode 011011, three parcels (modes base, postinc, predec) (6 bytes)




BIT, opcode 011011, three parcels (modes index) (6 bytes)




BIT, opcode 011011, three parcels (modes pcrel, imm, abs) (6 bytes)




BIT, opcode 011011, three parcels (modes dp) (6 bytes)




BIT, opcode 011011, two parcels (modes base, postinc, predec) (4 bytes)




BIT, opcode 011011, two parcels (modes index) (4 bytes)




BIT, opcode 011011, two parcels (modes pcrel, imm, abs) (4 bytes)



BIT, opcode 011011, two parcels (modes dp) (4 bytes)



BIT, opcode 011011, one parcel (2 bytes)




Mnemonics: `BIT`

Syntax

```
BIT rm, Rd
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
`BIT`	`011011 (0x1B)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
tmp ← Rd AND rm         ; the result is discarded
```


Flags `N` and `Z` from the result, `V` cleared, `C` unchanged.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

XOR: Exclusive or


XOR, opcode 011100, three parcels (modes base, postinc, predec) (6 bytes)




XOR, opcode 011100, three parcels (modes index) (6 bytes)




XOR, opcode 011100, three parcels (modes pcrel, imm, abs) (6 bytes)




XOR, opcode 011100, three parcels (modes dp) (6 bytes)




XOR, opcode 011100, two parcels (modes base, postinc, predec) (4 bytes)




XOR, opcode 011100, two parcels (modes index) (4 bytes)




XOR, opcode 011100, two parcels (modes pcrel, imm, abs) (4 bytes)



XOR, opcode 011100, two parcels (modes dp) (4 bytes)



XOR, opcode 011100, one parcel (2 bytes)




Mnemonics: `XOR`

Syntax

```
XOR rm, Rd
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
XOR	011100 (0x1C)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
Rd ← Rd XOR rm
```


Flags `N` and `Z` from the result, `V` cleared, `C` unchanged.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

AND: And


AND, opcode 011101, three parcels (modes base, postinc, predec) (6 bytes)




AND, opcode 011101, three parcels (modes index) (6 bytes)




AND, opcode 011101, three parcels (modes pcrel, imm, abs) (6 bytes)




AND, opcode 011101, three parcels (modes dp) (6 bytes)




AND, opcode 011101, two parcels (modes base, postinc, predec) (4 bytes)




AND, opcode 011101, two parcels (modes index) (4 bytes)




AND, opcode 011101, two parcels (modes pcrel, imm, abs) (4 bytes)



AND, opcode 011101, two parcels (modes dp) (4 bytes)



AND, opcode 011101, one parcel (2 bytes)




Mnemonics: `AND`

Syntax

```
AND rm, Rd
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
AND	011101 (0x1D)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
Rd ← Rd AND rm
```

Flags `N` and `Z` from the result, `V` cleared, `C` unchanged.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


SHIFT: Shift left, shift right logical, shift right arithmetic

Mnemonics: `SHL`, `SHR`, `SAR`

Syntax

```
SHL rm, Rd
SHR rm, Rd
SAR rm, Rd
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
SHL	100000 (0x20)
SHR	100001 (0x21)
SAR	100010 (0x22)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
n ← rm                                  ; the count: a register, an immediate, or memory
SHL: Rd ← (n ≥ 64) ? 0 : Rd << n
SHR: Rd ← (n ≥ 64) ? 0 : Rd >>u n
SAR: Rd ← (n ≥ 64) ? (Rd < 0 ? -1 : 0) : Rd >>s n
```

Flags `N` and `Z` from the result, `V` cleared, `C` the last bit shifted out (bit 63 for `SHL`, bit 0 for `SHR` and `SAR`). **The same flags are written for every count**: a count of zero gives `N` and `Z` from the unchanged operand, `V` = 0 and `C` = 0.


Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

The count is read as an unsigned 64-bit value, so a count of 64 or more shifts the value entirely away. Page 2 has the three shifts by an immediate 0 to 15. `ASL` and `ASR` (in `SOP`) are the by-one forms in two bytes; rotates are in `BESC`.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

SHL


SHL, opcode 100000, three parcels (modes base, postinc, predec) (6 bytes)




SHL, opcode 100000, three parcels (modes index) (6 bytes)




SHL, opcode 100000, three parcels (modes pcrel, imm, abs) (6 bytes)




SHL, opcode 100000, three parcels (modes dp) (6 bytes)




SHL, opcode 100000, two parcels (modes base, postinc, predec) (4 bytes)




SHL, opcode 100000, two parcels (modes index) (4 bytes)




SHL, opcode 100000, two parcels (modes pcrel, imm, abs) (4 bytes)



SHL, opcode 100000, two parcels (modes dp) (4 bytes)



SHL, opcode 100000, one parcel (2 bytes)





```
SHL rm, Rd
```

Mnemonic	Opcode
SHL	100000 (0x20)


Operation, flags and exceptions as for the entry SHIFT above; 9 layout forms, each a chart of its own (above).

SHR


SHR, opcode 100001, three parcels (modes base, postinc, predec) (6 bytes)




SHR, opcode 100001, three parcels (modes index) (6 bytes)




SHR, opcode 100001, three parcels (modes pcrel, imm, abs) (6 bytes)




SHR, opcode 100001, three parcels (modes dp) (6 bytes)




SHR, opcode 100001, two parcels (modes base, postinc, predec) (4 bytes)




SHR, opcode 100001, two parcels (modes index) (4 bytes)




SHR, opcode 100001, two parcels (modes pcrel, imm, abs) (4 bytes)



SHR, opcode 100001, two parcels (modes dp) (4 bytes)



SHR, opcode 100001, one parcel (2 bytes)





```
SHR rm, Rd
```

Mnemonic	Opcode
SHR	100001 (0x21)


Operation, flags and exceptions as for the entry SHIFT above; 9 layout forms, each a chart of its own (above).

SAR


SAR, opcode 100010, three parcels (modes base, postinc, predec) (6 bytes)




SAR, opcode 100010, three parcels (modes index) (6 bytes)




SAR, opcode 100010, three parcels (modes pcrel, imm, abs) (6 bytes)




SAR, opcode 100010, three parcels (modes dp) (6 bytes)




SAR, opcode 100010, two parcels (modes base, postinc, predec) (4 bytes)




SAR, opcode 100010, two parcels (modes index) (4 bytes)




SAR, opcode 100010, two parcels (modes pcrel, imm, abs) (4 bytes)



SAR, opcode 100010, two parcels (modes dp) (4 bytes)



SAR, opcode 100010, one parcel (2 bytes)





```
SAR rm, Rd
```

Mnemonic	Opcode
SAR	100010 (0x22)


Operation, flags and exceptions as for the entry SHIFT above; 9 layout forms, each a chart of its own (above).

CLR: Clear


CLR, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




CLR, opcode 010011, three parcels (modes index) (6 bytes)




CLR, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




CLR, opcode 010011, three parcels (modes dp) (6 bytes)




CLR, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




CLR, opcode 010011, two parcels (modes index) (4 bytes)




CLR, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



CLR, opcode 010011, two parcels (modes dp) (4 bytes)



CLR, opcode 010011, one parcel (2 bytes)




Mnemonics: `CLR`

Syntax

```
CLR rm
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
CLR	010011 (0x13)	0000 (0x0)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.

Operation

```
rm ← 0
```


Flags N = 0, Z = 1, V = 0, C = 0.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause BUSFAULT). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

COM: Complement


COM, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




COM, opcode 010011, three parcels (modes index) (6 bytes)




COM, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




COM, opcode 010011, three parcels (modes dp) (6 bytes)



COM, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




COM, opcode 010011, two parcels (modes index) (4 bytes)




COM, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



COM, opcode 010011, two parcels (modes dp) (4 bytes)



COM, opcode 010011, one parcel (2 bytes)




Mnemonics: `COM`

Syntax

```
COM rm
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	`reg`
`COM`	`010011 (0x13)`	`0001 (0x1)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.

Operation

```
rm ← NOT rm
```

Flags `N` and `Z` from the result, `V` = 0, `C` = 1 (the PDP-11 rule).


Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

A two-byte instruction for a register operand.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

TST: Test


TST, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




TST, opcode 010011, three parcels (modes index) (6 bytes)




TST, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




TST, opcode 010011, three parcels (modes dp) (6 bytes)




TST, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




TST, opcode 010011, two parcels (modes index) (4 bytes)




TST, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



TST, opcode 010011, two parcels (modes dp) (4 bytes)



TST, opcode 010011, one parcel (2 bytes)



Mnemonics: TST

Syntax

```
TST rm
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
TST	010011 (0x13)	0101 (0x5)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.

Operation

```
set flags from rm; nothing is written
```


Flags `N` and `Z` from the operand, `V` = 0, `C` = 0.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

ASL: Arithmetic shift left by one


ASL, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




ASL, opcode 010011, three parcels (modes index) (6 bytes)




ASL, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




ASL, opcode 010011, three parcels (modes dp) (6 bytes)




ASL, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




ASL, opcode 010011, two parcels (modes index) (4 bytes)




ASL, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



ASL, opcode 010011, two parcels (modes dp) (4 bytes)



ASL, opcode 010011, one parcel (2 bytes)




Mnemonics: ASL

Syntax

```
ASL rm
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
ASL	010011 (0x13)	1000 (0x8)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.

Operation

```
C ← rm[63] ; rm ← rm << 1
```

Flags N and Z from the result, C the bit shifted out of bit 63, V = N xor C (set if the sign changed: the PDP-11 rule).


Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause BUSFAULT). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

The by-one form of SHL in two bytes.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

ASR: Arithmetic shift right by one


ASR, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




ASR, opcode 010011, three parcels (modes index) (6 bytes)




ASR, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




ASR, opcode 010011, three parcels (modes dp) (6 bytes)




ASR, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




ASR, opcode 010011, two parcels (modes index) (4 bytes)




ASR, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



ASR, opcode 010011, two parcels (modes dp) (4 bytes)



ASR, opcode 010011, one parcel (2 bytes)




Mnemonics: `ASR`

Syntax

```
ASR rm
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
ASR	010011 (0x13)	1001 (0x9)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.

Operation

```
C ← rm[0] ; rm ← rm >>s 1
```

Flags N and Z from the result, C the bit shifted out of bit 0, V = 0.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause BUSFAULT). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

The by-one form of SAR in two bytes.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

9.9 Bits, bytes and text

9.9.1 The bit-and-field escape provides CLZ, CTZ, CLO, CTO (count leading and trailing zeros and ones), POPCNT, BSWAP, BSWAPW, BSWAPL and BITREV. *(opcode `001100 (0x0C)`)*

9.9.2 EXTB and EXTZB extract a bitfield at a position and width, sign- or zero-extended, and INSB inserts one; the position and width are in the third parcel, so these are six bytes. *(D)*

9.9.3 XNORPOP computes the population count of the exclusive-nor of two registers. *(D)*

9.9.4 CLMULL and CLMULH are the low and high halves of a carry-less multiply; no polynomial is built into the architecture. *(D)*

9.9.5 UTF8LEN, UTF8DEC and UTF8ENC find the length of, decode and encode a UTF-8 sequence, and reject overlong forms, surrogates, out-of-range values and bad continuation bytes. *(D)*

Commentary. **Precedent.** The PDP-11 had SWAB; the VAX had bit-field instructions and a table-driven CRC; x86 added POPCNT, LZCNT and PCLMULQDQ late, and committed CRC32 to one polynomial. **Trade-offs.** A bit unit is one shared structure: POPCNT, XNORPOP and a garbage collector's mark-bitmap scan all want the same 64-input adder tree, and CLZ and its relatives want a priority encoder over the same operand. **Improvements.** A carry-less multiply stands in for a CRC instruction: no polynomial is baked in, and the same instruction serves CRC, the Galois-counter-mode authentication used in TLS, and hashing. Every UTF-8 security hole of the past is three comparators, which an instruction cannot omit and software often does. **Benefits.** The bit unit and the UTF-8 decoder together cost less than 5% of the die. **Modern comparables.** RISC-V's bit-manipulation and carry-less-multiply extensions, AArch64's CLZ, RBIT, REV and PMULL, and x86's PCLMULQDQ. **Use.** POPCNT for bitsets and Hamming distance; XNORPOP for binary-weight neural networks and bitset intersection; CLMUL for CRC, GCM and fingerprinting; UTF8* for text validation in parsers and kernels. **Impact.** *Kernel:* CTZ and CLZ find the first set bit in a run-queue or free-page bitmap; POPCNT counts bits in bitmaps; BSWAP converts network byte order. *Compiler:* The compiler maps `__builtin_clz`, `__builtin_popcount` and `__builtin_bswap` directly, and a carry-less multiply is the primitive for CRC and hashing code. *Hardware:* One bit unit holds a shared 64-input adder tree and a priority encoder, and the UTF-8 comparators are about 300 lookup tables.


COUNT: Count leading and trailing zeros and ones

Mnemonics: CLZ, CTZ, CLO, CTO

Syntax

```
CLZ Rs, Rd
CTZ Rs, Rd
CLO Rs, Rd
CTO Rs, Rd
```

Encoding



The chart is the layout `r20-besc-1`, Bits and fields (BESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
`CLZ`	`001100 (0x0C)`	`00000000 (0x00)`
`CTZ`	`001100 (0x0C)`	`00000001 (0x01)`
`CLO`	`001100 (0x0C)`	`00000010 (0x02)`
`CTO`	`001100 (0x0C)`	`00000011 (0x03)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-besc-1`, `r20-besc-2`.

Operation

```
CLZ: Rd ← number of leading zero bits of Rs        (64 if Rs = 0)
CTZ: Rd ← number of trailing zero bits of Rs       (64 if Rs = 0)
CLO: Rd ← number of leading one bits of Rs         (64 if Rs = all ones)
CTO: Rd ← number of trailing one bits of Rs        (64 if Rs = all ones)
```

Flags None written.

Exceptions None.


CTZ is the VAX FFS. Bit manipulation is core on a machine that does filesystem and bignum work, not an extension.

Why it is here. BESC is the bit-manipulation group: bit manipulation is not an extension on a machine that does filesystem work, bignum arithmetic and the like. The counts are the VAX FFS and FFC idiom (find first set, find first clear). LoongArch is the model for putting them in the base: it has CLO, CLZ, CTO, CTZ there, which is the decisive argument for giving BESC a top-level opcode. The compiler emits none of them, since C has no operator for them; the corpus shows zero uses.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

CLZ

CLZ, opcode 001100, three parcels, sub-opcode 00000000 (6 bytes)



CLZ, opcode 001100, two parcels, sub-opcode 00000000 (4 bytes)





```
CLZ Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
CLZ	001100 (0x0C)	00000000 (0x00)


Operation, flags and exceptions as for the entry COUNT above; 2 layout forms, each a chart of its own (above).

CTZ

CTZ, opcode 001100, three parcels, sub-opcode 00000001 (6 bytes)



CTZ, opcode 001100, two parcels, sub-opcode 00000001 (4 bytes)





```
CTZ Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
CTZ	001100 (0x0C)	00000001 (0x01)


Operation, flags and exceptions as for the entry COUNT above; 2 layout forms, each a chart of its own (above).

CLO

CLO, opcode 001100, three parcels, sub-opcode 00000010 (6 bytes)



CLO, opcode 001100, two parcels, sub-opcode 00000010 (4 bytes)





```
CLO Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
CLO	001100 (0x0C)	00000010 (0x02)


Operation, flags and exceptions as for the entry COUNT above; 2 layout forms, each a chart of its own (above).

CTO

CTO, opcode 001100, three parcels, sub-opcode 00000011 (6 bytes)



CTO, opcode 001100, two parcels, sub-opcode 00000011 (4 bytes)





```
CTO Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
CTO	001100 (0x0C)	00000011 (0x03)


Operation, flags and exceptions as for the entry COUNT above; 2 layout forms, each a chart of its own (above).

POPCNT: Population count

POPCNT, opcode 001100, three parcels, sub-opcode 00000100 (6 bytes)



POPCNT, opcode 001100, two parcels, sub-opcode 00000100 (4 bytes)




Mnemonics: POPCNT

Syntax

```
POPCNT Rs, Rd
```

Encoding



The chart is the layout `r20-besc-1`, Bits and fields (BESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
POPCNT	001100 (0x0C)	00000100 (0x04)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-besc-1`, `r20-besc-2`.

Operation

```
Rd ← number of one bits in Rs
```

Flags None written.

Exceptions None.

Why it is here. One of the counts of `BESC`; it is also the building block of `XNORPOP`. A compiler needs `__builtin_popcount` to emit it, so the corpus shows no use (see `COUNT`).

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


BSWAP: Byte swap

Mnemonics: `BSWAP`, `BSWAPW`, `BSWAPL`

Syntax

```
BSWAP Rs, Rd
BSWAPW Rs, Rd
BSWAPL Rs, Rd
```

Encoding



The chart is the layout `r20-besc-1`, Bits and fields (BESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
BSWAP	001100 (0x0C)	00000101 (0x05)
BSWAPW	001100 (0x0C)	00000110 (0x06)
BSWAPL	001100 (0x0C)	00000111 (0x07)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-besc-1`, `r20-besc-2`.

Operation

```
BSWAP : Rd ← Rs with all 8 bytes reversed
BSWAPW: Rd ← Rs with the bytes of each 16-bit word reversed
BSWAPL: Rd ← Rs with the bytes of each 32-bit long reversed
```

Flags None written.

Exceptions None.


The generalisation of the PDP-11 `SWAB` to 64 bits.

Why it is here. The PDP-11 `SWAB` swapped the bytes of a word; `BSWAP` generalises it to 64 bits, with word and long variants. `SWAB` is therefore subsumed, not lost (9.18).


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

BSWAP

BSWAP, opcode 001100, three parcels, sub-opcode 00000101 (6 bytes)



BSWAP, opcode 001100, two parcels, sub-opcode 00000101 (4 bytes)





```
BSWAP Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
BSWAP	001100 (0x0C)	00000101 (0x05)


Operation, flags and exceptions as for the entry BSWAP above; 2 layout forms, each a chart of its own (above).

BSWAPW

BSWAPW, opcode 001100, three parcels, sub-opcode 00000110 (6 bytes)



BSWAPW, opcode 001100, two parcels, sub-opcode 00000110 (4 bytes)





```
BSWAPW Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
BSWAPW	001100 (0x0C)	00000110 (0x06)


Operation, flags and exceptions as for the entry BSWAP above; 2 layout forms, each a chart of its own (above).

BSWAPL

BSWAPL, opcode 001100, three parcels, sub-opcode 00000111 (6 bytes)



BSWAPL, opcode 001100, two parcels, sub-opcode 00000111 (4 bytes)





```
BSWAPL Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
BSWAPL	001100 (0x0C)	00000111 (0x07)


Operation, flags and exceptions as for the entry BSWAP above; 2 layout forms, each a chart of its own (above).

BITREV: Reverse the bits

BITREV, opcode 001100, three parcels, sub-opcode 00001000 (6 bytes)



BITREV, opcode 001100, two parcels, sub-opcode 00001000 (4 bytes)




Mnemonics: `BITREV`

Syntax

```
BITREV Rs, Rd
```

Encoding



The chart is the layout `r20-besc-1`, Bits and fields (BESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
BITREV	001100 (0x0C)	00001000 (0x08)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-besc-1`, `r20-besc-2`.

Operation

```
Rd ← Rs with bit i moved to bit 63-i
```

Flags None written.


Exceptions None.

Why it is here. Part of the BESC group, borrowed with the other LoongArch bit operations (REVB, REVH, BITREV). No workload from the corpus is recorded.


Status implemented in the reference executor (common/pdp64exec.c, shared by sim64 and QEMU).

ROR: Rotate right by a register count

ROR, opcode 001100, three parcels, sub-opcode 00010000 (6 bytes)



ROR, opcode 001100, two parcels, sub-opcode 00010000 (4 bytes)




Mnemonics: ROR

Syntax

```
ROR Ra, Rb, Rd
```

Encoding



The chart is the layout r20-besc-1, Bits and fields (BESC), two parcels (len = 01): From len = 01. In this group low is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
ROR	001100 (0x0C)	00010000 (0x10)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-besc-1, r20-besc-2.

Operation

```
Rd ← Ra rotated right by (Rb mod 64)
```

Flags None written (rotates write no flags).

Exceptions None.


There is no rotate left instruction: `ROL rs, #n, rd` is an assembler spelling of `RORI rs, #(64-n), rd`. No rotate is through carry; multi-word shifting uses `DSHR`.

Why it is here. One rotate direction suffices and `ROR` is the one to keep: `ROL x, #n` is exactly `ROR x, #(64-n)`, and a funnel shifter yields `ROR` directly. No rotate is through carry (see `DSHR`). `ROR` is in `BESC`, not the ALU group: cryptographic code rotates by compile-time constants, so a four-byte immediate form is needed either way, and the register-count form has almost no users. Rotates write no flags.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

RORI: Rotate right by an immediate

RORI, opcode 001100, three parcels, sub-opcode 00010001 (6 bytes)



RORI, opcode 001100, two parcels, sub-opcode 00010001 (4 bytes)




Mnemonics: `RORI` (aliases: `ROL`)

Syntax

```
RORI Rs, #n, Rd
ROL Rs, #n, Rd        ; assembles to RORI Rs, #(64-n), Rd
```

Encoding



The chart is the layout `r20-besc-1-2`, Bits and fields (BESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
RORI	001100 (0x0C)	00010001 (0x11)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-besc-1-2`, `r20-besc-2-2`.

Operation

```
Rd ← Rs rotated right by (n mod 64)
```

Flags None written.

Exceptions None.

Four bytes: the count is in the low byte of parcel 1.


Why it is here. It has its own mnemonic because an immediate count and a register count are different encodings. `ROL Rs, #n, Rd` is accepted by the assembler as `RORI Rs, #(64-n), Rd`: the complement costs nothing at assembly time, so there is no reason to make programmers do it, and a register-count `ROL` is rejected so that one mnemonic stays one instruction.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


`ROL` is an alias of `RORI`: the assembler writes it as that word.

RORI32: Rotate right by an immediate, 32 bits

RORI32, opcode 001100, three parcels, sub-opcode 00010010 (6 bytes)



RORI32, opcode 001100, two parcels, sub-opcode 00010010 (4 bytes)




Mnemonics: `RORI32`

Syntax

```
RORI32 Rs, #n, Rd
```

Encoding



The chart is the layout `r20-besc-1-2`, Bits and fields (BESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
RORI32	001100 (0x0C)	00010010 (0x12)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-besc-1-2`, `r20-besc-2-2`.

Operation

```
Rd ← sext32(ror32(Rs[31:0], n mod 32))
```

Flags None written.

Exceptions None.


The 32-bit rotate with the result sign-extended like every 32-bit result; the primitive of most hash functions and ciphers.

Why it is here. A 32-bit rotate by a constant, the shape of crypto and hash inner loops, estimated together with `CBCC` at 22 KB (1.3%) of the compiled image. The result is sign-extended like the rest of the 32-bit operations, so that no instruction is needed after it. It removes 44 `MOVL` instructions in the corpus (the demand analysis already removes nearly all of them).


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

DSHR: Double-width funnel shift right

DSHR, opcode 001100, three parcels, sub-opcode 00100000 (6 bytes)



DSHR, opcode 001100, two parcels, sub-opcode 00100000 (4 bytes)




Mnemonics: `DSHR`

Syntax

```
DSHR Ra, Rb, #n, Rd
```

Encoding



The chart is the layout `r20-besc-1`, Bits and fields (BESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
DSHR	001100 (0x0C)	00100000 (0x20)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-besc-1`, `r20-besc-2-3`.

Operation

```
t ← Ra:Rb                    ; 128 bits, Ra the high half
Rd ← (t >> n)[63:0]          ; n = 0..63
```

Flags None written.

Exceptions None.

x86 SHRD, ARM EXTR. Six bytes (the count is in parcel 2). A 128-bit left shift by k is `DSHR hi, hi, lo, #(64-k)` then `SHL #k, lo`.

Why it is here. A double-width funnel shift (x86 SHRD, ARM EXTR), the right primitive for multi-word shifting. Two instructions shift a 128-bit value by any distance, where rotate-through-carry takes one bit per instruction, and that is why no rotate is through carry. It also subsumes ROR when both sources are the same register. It leaves every flag alone.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


EXTB: Extract a bit field

Mnemonics: EXTB, EXTZB

Syntax

```
EXTB Rs, #pos, #width, Rd        ; sign-extended
EXTZB Rs, #pos, #width, Rd       ; zero-extended
```

Encoding



The chart is the layout `r20-besc-1`, Bits and fields (BESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
EXTB	001100 (0x0C)	00100001 (0x21)

Mnemonic	Opcode	Sub-opcode
EXTZB	001100 (0x0C)	00100010 (0x22)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-besc-1`, `r20-besc-2-3`.

Operation

```
Rd ← ext((Rs >> pos)[width-1:0])          ; sext for EXTB, zext for EXTZB; width 0 or > 64 means 64
```

Flags None written.

Exceptions None.


Six bytes (position and width are in parcel 2), so these exist at `len = 10` only.

Why it is here. Bit-field extract and insert are the VAX `EXTV`, `EXTZV` and `INSV` idiom. The compiler does not use them: the shift-pair extraction pattern occurs 151 times in 26 files of the corpus, about 600 bytes at best (0.03%), and there are four true bit-field extracts in all. They are for hand-written protocol and bit-stream code.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

EXTB

EXTB, opcode 001100, three parcels, sub-opcode 00100001 (6 bytes)



EXTB, opcode 001100, two parcels, sub-opcode 00100001 (4 bytes)





```
EXTB Rs, #pos, #width, Rd
```

Mnemonic	Opcode	Sub-opcode
EXTB	001100 (0x0C)	00100001 (0x21)


Operation, flags and exceptions as for the entry EXTB above; 2 layout forms, each a chart of its own (above).

EXTZB

EXTZB, opcode 001100, three parcels, sub-opcode 00100010 (6 bytes)



EXTZB, opcode 001100, two parcels, sub-opcode 00100010 (4 bytes)





```
EXTZB Rs, #pos, #width, Rd
```

Mnemonic	Opcode	Sub-opcode
EXTZB	001100 (0x0C)	00100010 (0x22)


Operation, flags and exceptions as for the entry EXTB above; 2 layout forms, each a chart of its own (above).

INSB: Insert a bit field

INSB, opcode 001100, three parcels, sub-opcode 00100011 (6 bytes)



INSB, opcode 001100, two parcels, sub-opcode 00100011 (4 bytes)




Mnemonics: `INSB`

Syntax

```
INSB Rs, #pos, #width, Rd
```

Encoding



The chart is the layout `r20-besc-1`, Bits and fields (BESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
INSB	001100 (0x0C)	00100011 (0x23)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-besc-1`, `r20-besc-2-3`.


Operation

```
mask ← ((1 << width) - 1) << pos
Rd ← (Rd AND NOT mask) OR ((Rs << pos) AND mask)
```


Flags None written.
Exceptions None.
Six bytes. `Rd` is both source and destination.
Why it is here. The VAX `INSV` idiom, with `EXTB`. No use in the compiled corpus is recorded.
Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

XNORPOP: Population count of the equality of two words

XNORPOP, opcode 001100, three parcels, sub-opcode 00110000 (6 bytes)



XNORPOP, opcode 001100, two parcels, sub-opcode 00110000 (4 bytes)




Mnemonics: `XNORPOP`

Syntax

```
XNORPOP Ra, Rb, Rd
```

Encoding



The chart is the layout `r20-besc-1`, Bits and fields (BESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
`XNORPOP`	`001100 (0x0C)`	`00110000 (0x30)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-besc-1`, `r20-besc-2`.

Operation

```
Rd ← popcount(NOT (Ra XOR Rb))
```

Flags None written.

Exceptions None.

For binary-activation networks, Hamming distance and bitset intersection cardinality. It does **not** serve sub-1-bit language models (section 8.3).

Why it is here. It serves binary-activation networks, Hamming distance, bitset intersection counts and counting a collector's mark bitmap. It does not serve sub-1-bit language models: their activations (in the LittleBit work) are FP16 and the inner loop is a conditional add, not a popcount. The sub-1-bit kernel is bandwidth-bound and belongs to a bus-mastering accelerator, not an opcode (chapter 8).

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


CLMUL: Carry-less multiply

Mnemonics: `CLMULL`, `CLMULH`

Syntax

```
CLMULL Ra, Rb, Rd
CLMULH Ra, Rb, Rd
```

Encoding



The chart is the layout `r20-besc-1`, Bits and fields (BESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
`CLMULL`	`001100 (0x0C)`	`00110001 (0x31)`
`CLMULH`	`001100 (0x0C)`	`00110010 (0x32)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-besc-1`, `r20-besc-2`.

Operation

```
p ← carry-less (polynomial over GF(2)) product of Ra and Rb      ; 128 bits
CLMULL: Rd ← p[63:0]
CLMULH: Rd ← p[127:64]
```

Flags None written.

Exceptions None.


The primitive under every CRC (with a Barrett reduction), GF(2^k) arithmetic and GCM; no polynomial is committed to the architecture.

Why it is here. Carry-less multiply is the primitive beneath every CRC polynomial (a CRC is a carry-less multiply plus a Barrett reduction), GF(2^k) erasure codes and AES-GCM. It is chosen over a `CRC` instruction because x86 and ARM each committed a polynomial to the architecture; there are no `CRC32` or `CRC32C` words.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

CLMULL

CLMULL, opcode 001100, three parcels, sub-opcode 00110001 (6 bytes)



CLMULL, opcode 001100, two parcels, sub-opcode 00110001 (4 bytes)





```
CLMULL Ra, Rb, Rd
```

Mnemonic	Opcode	Sub-opcode
CLMULL	001100 (0x0C)	00110001 (0x31)


Operation, flags and exceptions as for the entry CLMUL above; 2 layout forms, each a chart of its own (above).

CLMULH

CLMULH, opcode 001100, three parcels, sub-opcode 00110010 (6 bytes)



CLMULH, opcode 001100, two parcels, sub-opcode 00110010 (4 bytes)





```
CLMULH Ra, Rb, Rd
```

Mnemonic	Opcode	Sub-opcode
CLMULH	001100 (0x0C)	00110010 (0x32)


Operation, flags and exceptions as for the entry CLMUL above; 2 layout forms, each a chart of its own (above).

UTF8LEN: Length of a UTF-8 sequence from its leading byte

UTF8LEN, opcode 001100, three parcels, sub-opcode 01000000 (6 bytes)



UTF8LEN, opcode 001100, two parcels, sub-opcode 01000000 (4 bytes)




Mnemonics: `UTF8LEN`

Syntax

```
UTF8LEN Rs, Rd
```

Encoding



The chart is the layout `r20-besc-1`, Bits and fields (BESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
UTF8LEN	001100 (0x0C)	01000000 (0x40)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-besc-1`, `r20-besc-2`.

Operation

```
Rd ← length (1 to 4) implied by the leading byte Rs[7:0]; 0 if it cannot begin a valid sequence
```

Flags None written.


Exceptions None.

Why it is here. Most of what UTF-8 needs is general bit manipulation, but the validity rules are where the bugs are, so the group has three instructions. `UTF8LEN` is the one that is nearly free: `CLO` on the leading byte, mapped to 1, 2, 3 or 4.


Status specified; **not yet implemented** in the reference executor.

UTF8DEC: Decode a UTF-8 sequence

UTF8DEC, opcode 001100, three parcels, sub-opcode 01000001 (6 bytes)



UTF8DEC, opcode 001100, two parcels, sub-opcode 01000001 (4 bytes)




Mnemonics: `UTF8DEC`

Syntax

```
UTF8DEC Rs, Rd
```

Encoding



The chart is the layout `r20-besc-1`, Bits and fields (BESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
`UTF8DEC`	`001100 (0x0C)`	`01000001 (0x41)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-besc-1`, `r20-besc-2`.

Operation

```
Rs holds up to 4 bytes, leading byte in bits 7..0
Rd ← the scalar value
V  ← 1 if the sequence is not a valid encoding
```

Flags `V` set for a bad continuation byte, an overlong form, a surrogate (U+D800 to U+DFFF), a value above U+10FFFF, or a leading byte of `11000000 (0xC0)`, `11000001 (0xC1)` or `11110101 (0xF5)` to `11111111 (0xFF)`; the length consumed is reported in a scratch field of the status word (details in the instruction-set text, section 4.6.1).


Exceptions None.

Why it is here. Not for speed but for correctness: overlong forms, surrogates, values above U+10FFFF and the bytes that can never begin a sequence are each a historical security hole, each is three comparators in hardware, and software implementations get them wrong or omit them for speed (about 300 lookup tables).


Status specified; **not yet implemented** in the reference executor.

UTF8ENC: Encode a Unicode scalar value

UTF8ENC, opcode 001100, three parcels, sub-opcode 01000010 (6 bytes)



UTF8ENC, opcode 001100, two parcels, sub-opcode 01000010 (4 bytes)




Mnemonics: `UTF8ENC`

Syntax

```
UTF8ENC Rs, Rd
```

Encoding



The chart is the layout `r20-besc-1`, Bits and fields (BESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
UTF8ENC	001100 (0x0C)	01000010 (0x42)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-besc-1, r20-besc-2.

Operation

```
Rd ← the UTF-8 bytes of the scalar value Rs, leading byte in bits 7..0
V  ← 1 if Rs is not a Unicode scalar value
```

Flags V set if Rs is not a Unicode scalar value (a surrogate or above U+10FFFF).

Exceptions None.

Why it is here. The encoding half of the UTF-8 pair; it refuses surrogates and values above U+10FFFF so that an encoder cannot produce what a decoder must reject.

Status specified; **not yet implemented** in the reference executor.

9.10 Branches and control flow

Cf. section 6.13 for TRAP, RTI and RTT, and section 6.3 for how a trap enters the kernel; section 9.16 for CALLI and JMPI in position-independent code.

9.10.1 There is an unconditional branch BR and fourteen conditional branches, two bytes with an 8-bit displacement, four with 16 bits, six with 32 bits, counting two-byte parcels from the first parcel of the branch: ±256 bytes, ±64 KB, ±4 GB. *(opcodes 110000 (0x30)-111110 (0x3E))*

9.10.2 The conditions are ne, eq, pl, mi, vc, vs, cc/hs, cs/lo, ge, lt, gt, le, hi and los.

9.10.3 SOB Rn, dst subtracts one from Rn and branches if the result is nonzero, forward or backward. *(opcode 111111 (0x3F))*

9.10.4 CBCC compares a register with a 5-bit immediate and branches (four bytes, ±1024 parcels); CBW takes a 16-bit immediate and a 16-bit displacement (six bytes); CBRR compares two registers and branches. None writes the flags. *(D)*

9.10.5 JMP and CALL take any address mode; RET returns; JMPI and CALLI jump and call through a pointer in memory; JTAG dispatches on the tag in the low three bits of a register; BTAG and BNTAG branch on a tag. *(D)*

9.10.6 A call pushes the return address on the stack; there is no link register. *(D)*

Commentary. **Precedent.** The complete PDP-11 branch set, which the long-branch problem of the PDP-11 (±256 bytes) made awkward, here reaches ±4 GB with no long-branch opcode and no trampoline, because the displacement widens with the length. SOB was the PDP-11's, which could only branch backward. **Trade-offs.** A compare-and-branch that writes no flags cannot feed a second branch that reads them, so a three-way compare is compare-then-branch; the compiler fuses only where the flags are dead afterwards, which costs about 0.4% in code size. **Improvements.** The tag branches serve a Lisp or other tagged runtime in one instruction. **Benefits.** Branch relaxation in the assembler is choosing a length. **Modern comparables.** RISC-V and MIPS are compare-and-branch machines with no flags; AArch64 has CBZ and TBZ; x86 uses flags like the pdp64's branches. **Use.** JMPI and CALLI are the shared-library call and the virtual call; JTAG is the dispatch of a dynamic-language interpreter. **Impact.** *Kernel:* JMPI, CALLI and JTAG are the shared-library call, the virtual call and the dispatch of an interpreter; SOB and CBCC are the loops of the kernel's inner routines. *Compiler:* Branch relaxation is choosing a length; fusing a compare and a branch is legal only where the flags are dead afterwards, so the compiler needs a flag-liveness analysis. *Hardware:* The next-PC mux takes the load-return path for the indirect forms; the compare-and-branch compare runs in the branch unit beside the ALU; displacements count parcels, so no shifter is needed.


BCC: Branch on condition

Mnemonics: BR, BNE, BEQ, BPL, BMI, BVC, BVS, BCC, BCS, BGE, BLT, BGT, BLE, BHI, BLOS (aliases: BHIS, BLO)

Syntax

```
BR target
BNE target
BEQ target ... and the rest
```

Encoding



The chart is the layout `r20-br-0`, Conditional branches, one parcel (`len = 00`): The displacement is signed and counts 2-byte parcels from the first parcel of the instruction.

Mnemonic	Opcode
BR	110000 (0x30)
BNE	110001 (0x31)
BEQ	110010 (0x32)
BPL	110011 (0x33)
BMI	110100 (0x34)
BVC	110101 (0x35)
BVS	110110 (0x36)
BCC	110111 (0x37)
BCS	111000 (0x38)
BGE	111001 (0x39)
BLT	111010 (0x3A)
BGT	111011 (0x3B)
BLE	111100 (0x3C)
BHI	111101 (0x3D)
BLOS	111110 (0x3E)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-br-0`, `r20-br-1`, `r20-br-2`.

Operation

```
if cond(c) then PC ← address of this instruction + 2 × disp
```

Flags None written.

Exceptions None; a branch to an unmapped or non-executable address faults on the fetch of the target.


Condition numbers: `al` 0 (`BR`), `ne` 1, `eq` 2, `pl` 3, `mi` 4, `vc` 5, `vs` 6, `cc`/`hs` 7, `cs`/`lo` 8, `ge` 9, `lt` 10, `gt` 11, `le` 12, `hi` 13, `los` 14. Conditions on the flags: `ne` `!Z`; `eq` `Z`; `pl` `!N`; `mi` `N`; `vc` `!V`; `vs` `V`; `cc` `!C`; `cs` `C`; `ge` `N == V`; `lt` `N != V`; `gt` `!Z and N == V`; `le` `Z or N != V`; `hi` `!C and !Z`; `los` `C or Z`. The displacement counts 2-byte parcels; the branch reaches ±4 GB with no long-branch instruction.

Cf. 6.13 for `TRAP`, `RTI` and `RTT`.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

BR

BR, opcode 110000, three parcels (6 bytes)



BR, opcode 110000, two parcels (4 bytes)



BR, opcode 110000, one parcel (2 bytes)





```
BR target
```

Mnemonic	Opcode
BR	110000 (0x30)

Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BNE

BNE, opcode 110001, three parcels (6 bytes)



BNE, opcode 110001, two parcels (4 bytes)



BNE, opcode 110001, one parcel (2 bytes)





```
BNE target
```

Mnemonic	Opcode
BNE	110001 (0x31)

Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BEQ

BEQ, opcode 110010, three parcels (6 bytes)



BEQ, opcode 110010, two parcels (4 bytes)



BEQ, opcode 110010, one parcel (2 bytes)





```
BEQ target ... and the rest
```

Mnemonic	Opcode
BEQ	110010 (0x32)

Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BPL

BPL, opcode 110011, three parcels (6 bytes)



BPL, opcode 110011, two parcels (4 bytes)



BPL, opcode 110011, one parcel (2 bytes)




Mnemonic	Opcode
BPL	110011 (0x33)

Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BMI

BMI, opcode 110100, three parcels (6 bytes)



BMI, opcode 110100, two parcels (4 bytes)



BMI, opcode 110100, one parcel (2 bytes)




Mnemonic	Opcode
BMI	110100 (0x34)


Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BVC


BVC, opcode 110101, three parcels (6 bytes)



BVC, opcode 110101, two parcels (4 bytes)



BVC, opcode 110101, one parcel (2 bytes)




Mnemonic	Opcode
BVC	110101 (0x35)

Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BVS


BVS, opcode 110110, three parcels (6 bytes)



BVS, opcode 110110, two parcels (4 bytes)



BVS, opcode 110110, one parcel (2 bytes)




Mnemonic	Opcode
BVS	110110 (0x36)


Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BCC


BCC, opcode 110111, three parcels (6 bytes)



BCC, opcode 110111, two parcels (4 bytes)



BCC, opcode 110111, one parcel (2 bytes)




Mnemonic	Opcode
BCC	110111 (0x37)

Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BCS

BCS, opcode 111000, three parcels (6 bytes)



BCS, opcode 111000, two parcels (4 bytes)



BCS, opcode 111000, one parcel (2 bytes)




Mnemonic	Opcode
BCS	111000 (0x38)


Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BGE


BGE, opcode 111001, three parcels (6 bytes)



BGE, opcode 111001, two parcels (4 bytes)



BGE, opcode 111001, one parcel (2 bytes)




Mnemonic	Opcode
BGE	111001 (0x39)

Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BLT


BLT, opcode 111010, three parcels (6 bytes)



BLT, opcode 111010, two parcels (4 bytes)



BLT, opcode 111010, one parcel (2 bytes)




Mnemonic	Opcode
BLT	111010 (0x3A)


Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BGT


BGT, opcode 111011, three parcels (6 bytes)



BGT, opcode 111011, two parcels (4 bytes)



BGT, opcode 111011, one parcel (2 bytes)




Mnemonic	Opcode
BGT	111011 (0x3B)

Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BLE

BLE, opcode 111100, three parcels (6 bytes)



BLE, opcode 111100, two parcels (4 bytes)



BLE, opcode 111100, one parcel (2 bytes)




Mnemonic	Opcode
BLE	111100 (0x3C)


Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BHI


BHI, opcode 111101, three parcels (6 bytes)



BHI, opcode 111101, two parcels (4 bytes)



BHI, opcode 111101, one parcel (2 bytes)




Mnemonic	Opcode
BHI	111101 (0x3D)

Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BLOS

BLOS, opcode 111110, three parcels (6 bytes)



BLOS, opcode 111110, two parcels (4 bytes)



BLOS, opcode 111110, one parcel (2 bytes)



Mnemonic	Opcode
BLOS	111110 (0x3E)

Operation, flags and exceptions as for the entry BCC above; 3 layout forms, each a chart of its own (above).

BHIS


An alias of BCC: the assembler writes it as that word.

BLO


An alias of BCS: the assembler writes it as that word.

SOB: Subtract one and branch

SOB, opcode 111111, three parcels (6 bytes)



SOB, opcode 111111, two parcels (4 bytes)




Mnemonics: `SOB`

Syntax

```
SOB Rn, target
```

Encoding



The chart is the layout `r20-sob-1`, SOB, two parcels (`len = 01`): The displacement is signed and counts parcels.

Mnemonic	Opcode
`SOB`	`111111 (0x3F)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sob-1`, `r20-sob-2`.

Operation

```
Rn ← Rn - 1
if Rn ≠ 0 then PC ← address of this instruction + 2 × disp
```

Flags None written.

Exceptions None.

From the PDP-11, where it could branch only backward; here the signed displacement goes either way. Four bytes at least.

Why it is here. Taken from the PDP-11, at the branch group's one free opcode. The PDP-11's could only branch backward (a 6-bit unsigned displacement); this one branches either way. Against the `cbnz` idiom of other architectures it does not save

bytes (DEC plus BNE is also four) but it saves an instruction issue, a cycle per iteration on a machine that does not pipeline: same size, one instruction fewer (static `dec; bne` pairs exist).

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

CBCC: Compare and branch on condition

Mnemonics: CBNE, CBEQ, CBPL, CBMI, CBVC, CBVS, CBCC, CBCS, CBGE, CBLT, CBGT, CBLE, CBHI, CBLOS (aliases: CBHIS, CBLO)

Syntax

```
CBNE Rd, #imm, target
CBEQ Ra, Rb, target ... and the rest
```

Encoding



The chart is the layout `r20-cb-1`, Compare and branch, two parcels (`len = 01`): `low` is the condition; the immediate and the displacement are signed.

Mnemonic	Opcode	low
CBNE	101000 (0x28), 101001 (0x29), 101010 (0x2A)	0001 (0x1), 0001 (0x1), 0001 (0x1)
CBEQ	101000 (0x28), 101001 (0x29), 101010 (0x2A)	0010 (0x2), 0010 (0x2), 0010 (0x2)
CBPL	101000 (0x28), 101001 (0x29), 101010 (0x2A)	0011 (0x3), 0011 (0x3), 0011 (0x3)
CBMI	101000 (0x28), 101001 (0x29), 101010 (0x2A)	0100 (0x4), 0100 (0x4), 0100 (0x4)
CBVC	101000 (0x28), 101001 (0x29), 101010 (0x2A)	0101 (0x5), 0101 (0x5), 0101 (0x5)
CBVS	101000 (0x28), 101001 (0x29), 101010 (0x2A)	0110 (0x6), 0110 (0x6), 0110 (0x6)
CBCC	101000 (0x28), 101001 (0x29), 101010 (0x2A)	0111 (0x7), 0111 (0x7), 0111 (0x7)
CBCS	101000 (0x28), 101001 (0x29), 101010 (0x2A)	1000 (0x8), 1000 (0x8), 1000 (0x8)
CBGE	101000 (0x28), 101001 (0x29), 101010 (0x2A)	1001 (0x9), 1001 (0x9), 1001 (0x9)
CBLT	101000 (0x28), 101001 (0x29), 101010 (0x2A)	1010 (0xA), 1010 (0xA), 1010 (0xA)
CBGT	101000 (0x28), 101001 (0x29), 101010 (0x2A)	1011 (0xB), 1011 (0xB), 1011 (0xB)
CBLE	101000 (0x28), 101001 (0x29), 101010 (0x2A)	1100 (0xC), 1100 (0xC), 1100 (0xC)
CBHI	101000 (0x28), 101001 (0x29), 101010 (0x2A)	1101 (0xD), 1101 (0xD), 1101 (0xD)
CBLOS	101000 (0x28), 101001 (0x29), 101010 (0x2A)	1110 (0xE), 1110 (0xE), 1110 (0xE)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-cb-1`, `r20-cb-1-2`, `r20-cb-2`, `r20-cb-2-2`, `r20-cb-2-3`.

Operation

```
tmp ← Rd - (imm or Rb)         ; as CMP, for the decision only
if cond(c) on that comparison then PC ← address of this instruction + 2 × disp
```

Flags None written: the instruction computes the comparison for its own decision and leaves `N Z V C` as they were.

Exceptions None.

Three encodings, chosen by the assembler: CBCC (`101000 (0x28)`, a 5-bit signed immediate -16 to 15, a displacement of ±1024 parcels at four bytes or 27 bits at six), CBW (`101001 (0x29)`, a 16-bit immediate and a 16-bit displacement, six bytes) and CBRR (`101010 (0x2A)`, two registers, ±2,048 parcels at four bytes or 28 bits at six). There is no `len = 00` form. A target in another section is refused.


Why it is here. A fused compare-and-branch in the reserved opcode `101000 (0x28)`, estimated with RORI32 at 22 KB (1.3%) of the image. The wide-immediate CBCC removes 11,735 instructions (3.4%) and 1,828 bytes; CBRR, the register-register compare-and-branch, removes 4,631 instructions (1.4%) and 142 bytes. It is not a replacement for flags: LoongArch and RISC-V

chose fused compare-and-branch instead of flags, and this architecture declines that (9.20) because it needs a comparator in the branch unit and a third read port; here the fused form is added beside the flags. CBCC writes no flags.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

CBNE


CBNE, opcode 101000, three parcels (6 bytes)



CBNE, opcode 101001, three parcels (6 bytes)



CBNE, opcode 101010, three parcels (6 bytes)



CBNE, opcode 101000, two parcels (4 bytes)



CBNE, opcode 101010, two parcels (4 bytes)





```
CBNE Rd, #imm, target
```

Mnemonic	Opcode	low
CBNE	101000 (0x28), 101001 (0x29), 101010 (0x2A)	0001 (0x1), 0001 (0x1), 0001 (0x1)


Operation, flags and exceptions as for the entry CBCC above; 5 layout forms, each a chart of its own (above).

CBEQ


CBEQ, opcode 101000, three parcels (6 bytes)



CBEQ, opcode 101001, three parcels (6 bytes)



CBEQ, opcode 101010, three parcels (6 bytes)



CBEQ, opcode 101000, two parcels (4 bytes)



CBEQ, opcode 101010, two parcels (4 bytes)





```
CBEQ Ra, Rb, target ... and the rest
```

Mnemonic	Opcode	low
CBEQ	101000 (0x28), 101001 (0x29), 101010 (0x2A)	0010 (0x2), 0010 (0x2), 0010 (0x2)


Operation, flags and exceptions as for the entry CBCC above; 5 layout forms, each a chart of its own (above).

CBPL


CBPL, opcode 101000, three parcels (6 bytes)



CBPL, opcode 101001, three parcels (6 bytes)



CBPL, opcode 101010, three parcels (6 bytes)



CBPL, opcode 101000, two parcels (4 bytes)



CBPL, opcode 101010, two parcels (4 bytes)




Mnemonic	Opcode	low
CBPL	101000 (0x28), 101001 (0x29), 101010 (0x2A)	0011 (0x3), 0011 (0x3), 0011 (0x3)


Operation, flags and exceptions as for the entry CBCC above; 5 layout forms, each a chart of its own (above).

CBMI


CBMI, opcode 101000, three parcels (6 bytes)



CBMI, opcode 101001, three parcels (6 bytes)



CBMI, opcode 101010, three parcels (6 bytes)



CBMI, opcode 101000, two parcels (4 bytes)



CBMI, opcode 101010, two parcels (4 bytes)




Mnemonic	Opcode	low
CBMI	101000 (0x28), 101001 (0x29), 101010 (0x2A)	0100 (0x4), 0100 (0x4), 0100 (0x4)


Operation, flags and exceptions as for the entry CBCC above; 5 layout forms, each a chart of its own (above).

CBVC


CBVC, opcode 101000, three parcels (6 bytes)



CBVC, opcode 101001, three parcels (6 bytes)



CBVC, opcode 101010, three parcels (6 bytes)



CBVC, opcode 101000, two parcels (4 bytes)



CBVC, opcode 101010, two parcels (4 bytes)




Mnemonic	Opcode	low
CBVC	101000 (0x28), 101001 (0x29), 101010 (0x2A)	0101 (0x5), 0101 (0x5), 0101 (0x5)


Operation, flags and exceptions as for the entry CBCC above; 5 layout forms, each a chart of its own (above).

CBVS


CBVS, opcode 101000, three parcels (6 bytes)



CBVS, opcode 101001, three parcels (6 bytes)



CBVS, opcode 101010, three parcels (6 bytes)



CBVS, opcode 101000, two parcels (4 bytes)



CBVS, opcode 101010, two parcels (4 bytes)




Mnemonic	Opcode	low
CBVS	101000 (0x28), 101001 (0x29), 101010 (0x2A)	0110 (0x6), 0110 (0x6), 0110 (0x6)


Operation, flags and exceptions as for the entry CBCC above; 5 layout forms, each a chart of its own (above).

CBCC


CBCC, opcode 101000, three parcels (6 bytes)



CBCC, opcode 101001, three parcels (6 bytes)



CBCC, opcode 101010, three parcels (6 bytes)



CBCC, opcode 101000, two parcels (4 bytes)



CBCC, opcode 101010, two parcels (4 bytes)




Mnemonic	Opcode	low
CBCC	101000 (0x28), 101001 (0x29), 101010 (0x2A)	0111 (0x7), 0111 (0x7), 0111 (0x7)


Operation, flags and exceptions as for the entry CBCC above; 5 layout forms, each a chart of its own (above).

CBCS


CBCS, opcode 101000, three parcels (6 bytes)



CBCS, opcode 101001, three parcels (6 bytes)




CBCS, opcode 101010, three parcels (6 bytes)



CBCS, opcode 101000, two parcels (4 bytes)



CBCS, opcode 101010, two parcels (4 bytes)




Mnemonic	Opcode	low
CBCS	101000 (0x28), 101001 (0x29), 101010 (0x2A)	1000 (0x8), 1000 (0x8), 1000 (0x8)


Operation, flags and exceptions as for the entry CBCC above; 5 layout forms, each a chart of its own (above).

CBGE


CBGE, opcode 101000, three parcels (6 bytes)



CBGE, opcode 101001, three parcels (6 bytes)



CBGE, opcode 101010, three parcels (6 bytes)



CBGE, opcode 101000, two parcels (4 bytes)



CBGE, opcode 101010, two parcels (4 bytes)




Mnemonic	Opcode	low
CBGE	101000 (0x28), 101001 (0x29), 101010 (0x2A)	1001 (0x9), 1001 (0x9), 1001 (0x9)


Operation, flags and exceptions as for the entry CBCC above; 5 layout forms, each a chart of its own (above).

CBLT


CBLT, opcode 101000, three parcels (6 bytes)



CBLT, opcode 101001, three parcels (6 bytes)



CBLT, opcode 101010, three parcels (6 bytes)



CBLT, opcode 101000, two parcels (4 bytes)



CBLT, opcode 101010, two parcels (4 bytes)




Mnemonic	Opcode	low
CBLT	101000 (0x28), 101001 (0x29), 101010 (0x2A)	1010 (0xA), 1010 (0xA), 1010 (0xA)


Operation, flags and exceptions as for the entry CBCC above; 5 layout forms, each a chart of its own (above).

CBGT


CBGT, opcode 101000, three parcels (6 bytes)



CBGT, opcode 101001, three parcels (6 bytes)



CBGT, opcode 101010, three parcels (6 bytes)



CBGT, opcode 101000, two parcels (4 bytes)



CBGT, opcode 101010, two parcels (4 bytes)




Mnemonic	Opcode	low
CBGT	101000 (0x28), 101001 (0x29), 101010 (0x2A)	1011 (0xB), 1011 (0xB), 1011 (0xB)


Operation, flags and exceptions as for the entry CBCC above; 5 layout forms, each a chart of its own (above).

CBLE


CBLE, opcode 101000, three parcels (6 bytes)



CBLE, opcode 101001, three parcels (6 bytes)



CBLE, opcode 101010, three parcels (6 bytes)



CBLE, opcode 101000, two parcels (4 bytes)



CBLE, opcode 101010, two parcels (4 bytes)




Mnemonic	Opcode	low
CBLE	101000 (0x28), 101001 (0x29), 101010 (0x2A)	1100 (0xC), 1100 (0xC), 1100 (0xC)


Operation, flags and exceptions as for the entry CBCC above; 5 layout forms, each a chart of its own (above).

CBHI


CBHI, opcode 101000, three parcels (6 bytes)



CBHI, opcode 101001, three parcels (6 bytes)



CBHI, opcode 101010, three parcels (6 bytes)



CBHI, opcode 101000, two parcels (4 bytes)



CBHI, opcode 101010, two parcels (4 bytes)




Mnemonic	Opcode	low
CBHI	101000 (0x28), 101001 (0x29), 101010 (0x2A)	1101 (0xD), 1101 (0xD), 1101 (0xD)


Operation, flags and exceptions as for the entry CBCC above; 5 layout forms, each a chart of its own (above).

CBLOS


CBLOS, opcode 101000, three parcels (6 bytes)



CBLOS, opcode 101001, three parcels (6 bytes)



CBLOS, opcode 101010, three parcels (6 bytes)



CBLOS, opcode 101000, two parcels (4 bytes)



CBLOS, opcode 101010, two parcels (4 bytes)



Mnemonic	Opcode	low
CBLOS	101000 (0x28), 101001 (0x29), 101010 (0x2A)	1110 (0xE), 1110 (0xE), 1110 (0xE)

Operation, flags and exceptions as for the entry CBCC above; 5 layout forms, each a chart of its own (above).

CBHIS
An alias of CBCC: the assembler writes it as that word.

CBLO
An alias of CBCS: the assembler writes it as that word.


BTAG: Branch on pointer tag

Mnemonics: BTAG, BNTAG

Syntax

```
BTAG Rn, #tag, target
BNTAG Rn, #tag, target
```

Encoding



The chart is the layout r20-tag-1, Tag branches, two parcels (len = 01): sense is 0 for BTAG and 1 for BNTAG; tag is the 3-bit tag.

Mnemonic	Opcode
BTAG	010101 (0x15)
BNTAG	010101 (0x15)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-tag-1, r20-tag-2.

Operation

```
BTAG : if (Rn & 111₂) = tag then PC ← address of this instruction + 2 × disp
BNTAG: if (Rn & 111₂) ≠ tag then PC ← address of this instruction + 2 × disp
```

Flags None written.

Exceptions None.

For runtimes that keep a 3-bit type tag in the low bits of a pointer (lowtag). Four bytes at least; the displacement is 16 bits (32 at len = 10).


Why it is here. The tag branches BTAG and BNTAG and the table dispatch JTAG make tagged pointers cheap to use rather than merely possible: three bits of tag and one of sense fit the low nibble exactly, so parcel 1 is a full displacement. Because quad-

aligned objects have zero in the low three bits, the tag is free, and an unaligned access is a fault. The compiler for C never emits them (the corpus shows none); they are for Lisp and other tagged runtimes.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

BTAG

BTAG, opcode 010101, three parcels (6 bytes)



BTAG, opcode 010101, two parcels (4 bytes)





```
BTAG Rn, #tag, target
```

Mnemonic	Opcode
BTAG	010101 (0x15)

Operation, flags and exceptions as for the entry BTAG above; 2 layout forms, each a chart of its own (above).

BNTAG

BNTAG, opcode 010101, three parcels (6 bytes)



BNTAG, opcode 010101, two parcels (4 bytes)





```
BNTAG Rn, #tag, target
```

Mnemonic	Opcode
BNTAG	010101 (0x15)


Operation, flags and exceptions as for the entry BTAG above; 2 layout forms, each a chart of its own (above).

JMP: Jump


JMP, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




JMP, opcode 010011, three parcels (modes index) (6 bytes)




JMP, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




JMP, opcode 010011, three parcels (modes dp) (6 bytes)




JMP, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




JMP, opcode 010011, two parcels (modes index) (4 bytes)




JMP, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



JMP, opcode 010011, two parcels (modes dp) (4 bytes)



JMP, opcode 010011, one parcel (2 bytes)




Mnemonics: `JMP`

Syntax

```
JMP rm        ; a register, or an address by any memory mode
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
JMP	010011 (0x13)	1100 (0xC)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.


Operation

```
PC ← (register operand) ? Rm : EA(rm)
```


Flags None written.
Exceptions A jump to an unmapped or non-executable address faults on the fetch of the target.
A switch is a `CMP` against the limit, a `BHIS` to the default and a `JMP` through a scaled index.
Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

CALL: Call


CALL, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




CALL, opcode 010011, three parcels (modes index) (6 bytes)




CALL, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




CALL, opcode 010011, three parcels (modes dp) (6 bytes)




CALL, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




CALL, opcode 010011, two parcels (modes index) (4 bytes)




CALL, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



CALL, opcode 010011, two parcels (modes dp) (4 bytes)



CALL, opcode 010011, one parcel (2 bytes)




Mnemonics: `CALL`

Syntax

```
CALL rm
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	`reg`
`CALL`	`010011 (0x13)`	`1101 (0xD)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.

Operation

```
t ← (register operand) ? Rm : EA(rm)
SP ← SP - 8 ; M[SP] ← address of the next instruction
PC ← t
```

Flags None written.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

The return address is on the data stack where every unwinder and debugger expects it. `RET` pops it.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


JMPI: Jump and call through memory

Mnemonics: `JMPI`, `CALLI`

Syntax

```
JMPI rm        ; PC ← M[EA]
CALLI rm       ; push the return address, then PC ← M[EA]
```

Encoding



The chart is the layout `r20-xfer-0`, Indirect transfers (XFER), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
JMPI	010010 (0x12)	0000 (0x0)
CALLI	010010 (0x12)	0001 (0x1)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-xfer-0`, `r20-xfer-1`, `r20-xfer-1-2`, `r20-xfer-1-3`, `r20-xfer-1-4`, `r20-xfer-2`, `r20-xfer-2-2`, `r20-xfer-2-3`, `r20-xfer-2-4`.

Operation

```
JMPI : PC ← M[EA(rm)]
CALLI: t ← M[EA(rm)] ; SP ← SP - 8 ; M[SP] ← address of the next instruction ; PC ← t
```

Flags None written.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires. For `CALLI` the order is specified: load the target, then push, then transfer; a fault on the load leaves nothing changed.


The one deferred reference the architecture admits, for control transfer only: the PLT stub (`JMPI got_slot(PC)`) and virtual-method dispatch (`CALLI vtbl_off(Robj)`). It needs a memory operand, so it is four bytes at least.

Why it is here. Exactly one deferred reference, for control transfer only, in `XFER`: the PLT stub of every dynamically linked program (`JMPI got_slot(PC)`) and virtual-method dispatch (`CALLI vtbl_off(Robj)`), each two instructions and a scratch register without it. It is admitted because it breaks none of the reasons deferred modes are removed (no register is side-effected, the reference is in the branch path and not the operand path, a fault is clean by ordering). Jump tables through `JMPI` are not smaller, because the table entries are 8 bytes against 8 for a case in a compare chain.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

JMPI


JMPI, opcode 010010, three parcels (modes base, postinc, predec) (6 bytes)




JMPI, opcode 010010, three parcels (modes index) (6 bytes)




JMPI, opcode 010010, three parcels (modes pcrel, imm, abs) (6 bytes)




JMPI, opcode 010010, three parcels (modes dp) (6 bytes)




JMPI, opcode 010010, two parcels (modes base, postinc, predec) (4 bytes)




JMPI, opcode 010010, two parcels (modes index) (4 bytes)




JMPI, opcode 010010, two parcels (modes pcrel, imm, abs) (4 bytes)



JMPI, opcode 010010, two parcels (modes dp) (4 bytes)



JMPI, opcode 010010, one parcel (2 bytes)





```
JMPI rm
```

Mnemonic	Opcode	reg
JMPI	010010 (0x12)	0000 (0x0)


Operation, flags and exceptions as for the entry JMPI above; 9 layout forms, each a chart of its own (above).

CALLI


CALLI, opcode 010010, three parcels (modes base, postinc, predec) (6 bytes)




CALLI, opcode 010010, three parcels (modes index) (6 bytes)




CALLI, opcode 010010, three parcels (modes pcrel, imm, abs) (6 bytes)




CALLI, opcode 010010, three parcels (modes dp) (6 bytes)




CALLI, opcode 010010, two parcels (modes base, postinc, predec) (4 bytes)




CALLI, opcode 010010, two parcels (modes index) (4 bytes)




CALLI, opcode 010010, two parcels (modes pcrel, imm, abs) (4 bytes)



CALLI, opcode 010010, two parcels (modes dp) (4 bytes)



CALLI, opcode 010010, one parcel (2 bytes)





```
CALLI rm
```

Mnemonic	Opcode	reg
CALLI	010010 (0x12)	0001 (0x1)


Operation, flags and exceptions as for the entry JMPI above; 9 layout forms, each a chart of its own (above).

JTAG: Jump through a tag table


JTAG, opcode 010010, three parcels (modes base, postinc, predec) (6 bytes)




JTAG, opcode 010010, three parcels (modes index) (6 bytes)




JTAG, opcode 010010, three parcels (modes pcrel, imm, abs) (6 bytes)




JTAG, opcode 010010, three parcels (modes dp) (6 bytes)




JTAG, opcode 010010, two parcels (modes base, postinc, predec) (4 bytes)




JTAG, opcode 010010, two parcels (modes index) (4 bytes)




JTAG, opcode 010010, two parcels (modes pcrel, imm, abs) (4 bytes)



JTAG, opcode 010010, two parcels (modes dp) (4 bytes)



JTAG, opcode 010010, one parcel (2 bytes)




Mnemonics: `JTAG`

Syntax

```
JTAG d(Rb)(Rx×s)
```

Encoding



The chart is the layout `r20-xfer-0`, Indirect transfers (XFER), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
JTAG	010010 (0x12)	0010 (0x2)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-xfer-0`, `r20-xfer-1`, `r20-xfer-1-2`, `r20-xfer-1-3`, `r20-xfer-1-4`, `r20-xfer-2`, `r20-xfer-2-2`, `r20-xfer-2-3`, `r20-xfer-2-4`.

Operation

```
PC ← M[Rb + d + 8 × (Rx & 111₂)]
```

Flags None written.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause BUSFAULT). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

Legal only with the scaled-index mode (`0001`). Dispatches on the low three bits of a tagged pointer through a table of eight entries; the 3-bit tag cannot index out of range.

Why it is here. The table-dispatch partner of BTAG. It is legal only in the scaled-index mode, the one mode with a free register slot for the tagged value. It replaces the PDP-11 dispatch-table idiom `@(Rn)+` better, because it needs no pointer register and cannot index out of range.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

9.11 The stack and block operations

Cf. section 6.4 for restarting a block operation after a fault (progress is held in registers) and section 6.6 for the page faults it can take; section 7.2 for how block operations order their accesses.

9.11.1 PUSH and POP move one register; PUSHM and POPM move a set named by a mask (a short mask form is in page 2). A mask containing R14 is reserved. *(D)*

9.11.2 PUSHX and POPX save and restore the exception state EPSW and EPC in one instruction each; both words are checked before either is accessed, so an abort leaves nothing changed. *(D)*

9.11.3 The block operations MCPY, MMOV (overlap-safe), MSET, MCMP, MSCN and MSCNN take a destination pointer, a source pointer or value and a count in registers; MVAL validates a buffer as UTF-8. *(opcode `001101 (0x0D)`)*

9.11.4 A block operation keeps its progress in its registers: when it completes, the count is zero and the pointers are one past the end; when it stops early or is interrupted, they point where it stopped, and it restarts by running again. *(D)*


9.11.5 An implementation may move more than a byte per step, provided the registers are consistent with byte-at-a-time progress wherever an exception can be taken. *(D)*

Commentary. **Precedent.** The VAX's MOVC5 is the canonical argument against such instructions: its operands could be memory, its architectural definition needed the original values to survive, and so it required hidden state and a first-part-done bit in the status word to resume. The PDP-10 had a block transfer, and x86's REP MOVS keeps its progress in registers as the pdp64's do. **Trade-offs.** This is the one admitted exception to the one-memory-operand rule, accepted because its mechanism, hidden state, is absent: the state is the registers, which are already architectural. A large copy can evict the whole data cache, and a non-temporal variant is an open question. **Improvements.** ARM reached the same design in 2022 with FEAT_MOPS, whose specification says the registers are updated so that progress is not lost. **Benefits.** The block-move sequencer is three counters and a byte-lane selector, about 1,500 transistors. **Modern comparables.** x86 REP MOVSB and REP STOSB with fast-string microcode; AArch64 CPYP/CPYM/CPYE and SETP/SETM/SETE; s390 MVC. **Use.** `memcpy`, `memmove`, `memset`, `memcmp` and `memchr` in the C library; MVAL in parsers and kernels. **Impact.** *Kernel:* PUSHM, POPM, PUSHX and POPX shorten entry, exit and the context switch, and


the block operations are `copyin`, `copyout`, page clearing and `memcpy`. *Compiler:* A prologue and an epilogue are one instruction each, and `memcpy` and `memset` lower to the block operations. *Hardware:* The block-move sequencer is three counters and a byte-lane selector, about 1,500 transistors, with no hidden state.

PUSHM: Push registers by mask


PUSHM, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




PUSHM, opcode 010011, three parcels (modes index) (6 bytes)




PUSHM, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




PUSHM, opcode 010011, three parcels (modes dp) (6 bytes)




PUSHM, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




PUSHM, opcode 010011, two parcels (modes index) (4 bytes)




PUSHM, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



PUSHM, opcode 010011, two parcels (modes dp) (4 bytes)



PUSHM, opcode 010011, one parcel (2 bytes)




Mnemonics: PUSHM

Syntax

```
PUSHM #mask        ; a 16-bit immediate, bit n is Rn
```

Encoding



The chart is the layout r20-sop-0, Single operand (SOP), one parcel (len = 00): The reg field is the sub-opcode; the operand is rm with its mode, at any length.

Mnemonic	Opcode	reg
PUSHM	010011 (0x13)	1010 (0xA)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4.

Operation

```
for n = 0 to 15, if mask bit n:
    SP ← SP - 8 ; M[SP] ← Rn
```

Flags None written.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause BUSFAULT). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires. A mask that includes R14 (SP) is reserved.

Four bytes (mode 0100, immediate). The registers are pushed in ascending order, so POPM with the same mask restores them. Page 2 has an 8-bit mask for R8 to R15.


Why it is here. The VAX procedure entry mask was the useful half of CALLS; PUSHM and POPM keep that half without the frame (hardware call frames ran slower than the sequence on later VAXes). They are in SOP because a 16-bit mask does not fit beside MBLK's sub-opcode; that uses SOP's last two free slots. The second page has 8-bit forms for R8 to R15, because all 2,392 push sites and 2,392 pop sites in the measured corpus use a mask within R8 to R15.

Cf. 6.4 for the restart rule.


Status implemented in the reference executor (common/pdp64exec.c, shared by sim64 and QEMU).

POPM: Pop registers by mask


POPM, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




POPM, opcode 010011, three parcels (modes index) (6 bytes)




POPM, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




POPM, opcode 010011, three parcels (modes dp) (6 bytes)




POPM, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




POPM, opcode 010011, two parcels (modes index) (4 bytes)




POPM, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



POPM, opcode 010011, two parcels (modes dp) (4 bytes)



POPM, opcode 010011, one parcel (2 bytes)



Mnemonics: `POPM`

Syntax

```
POPM #mask
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
POPM	010011 (0x13)	1011 (0xB)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.

Operation

```
for n = 15 down to 0, if mask bit n:
    Rn ← M[SP] ; SP ← SP + 8
```

Flags None written.


Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause BUSFAULT). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

The mirror of PUSHM; four bytes, with an 8-bit-mask form on page 2.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

PUSH: Push


PUSH, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




PUSH, opcode 010011, three parcels (modes index) (6 bytes)




PUSH, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




PUSH, opcode 010011, three parcels (modes dp) (6 bytes)




PUSH, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




PUSH, opcode 010011, two parcels (modes index) (4 bytes)




PUSH, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



PUSH, opcode 010011, two parcels (modes dp) (4 bytes)



PUSH, opcode 010011, one parcel (2 bytes)




Mnemonics: `PUSH`

Syntax

```
PUSH rm
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	`reg`
`PUSH`	`010011 (0x13)`	`1110 (0xE)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.

Operation

```
v ← rm ; SP ← SP - 8 ; M[SP] ← v
```

Flags None written.


Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

A one-parcel instruction for a register operand.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

POP: Pop


POP, opcode 010011, three parcels (modes base, postinc, predec) (6 bytes)




POP, opcode 010011, three parcels (modes index) (6 bytes)




POP, opcode 010011, three parcels (modes pcrel, imm, abs) (6 bytes)




POP, opcode 010011, three parcels (modes dp) (6 bytes)




POP, opcode 010011, two parcels (modes base, postinc, predec) (4 bytes)




POP, opcode 010011, two parcels (modes index) (4 bytes)




POP, opcode 010011, two parcels (modes pcrel, imm, abs) (4 bytes)



POP, opcode 010011, two parcels (modes dp) (4 bytes)



POP, opcode 010011, one parcel (2 bytes)




Mnemonics: `POP`

Syntax

```
POP rm
```

Encoding



The chart is the layout `r20-sop-0`, Single operand (SOP), one parcel (`len = 00`): The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
POP	010011 (0x13)	1111 (0xF)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sop-0`, `r20-sop-1`, `r20-sop-1-2`, `r20-sop-1-3`, `r20-sop-1-4`, `r20-sop-2`, `r20-sop-2-2`, `r20-sop-2-3`, `r20-sop-2-4`.

Operation

```
v ← M[SP] ; SP ← SP + 8 ; rm ← v
```

Flags None written.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


MCPY: Copy a block of bytes

Mnemonics: `MCPY`, `MMOV`

Syntax

```
MCPY Rd, Rs, Rn        ; destination pointer, source pointer, count
MMOV Rd, Rs, Rn        ; correct for overlap
```

Encoding



The chart is the layout `r20-mblk-1`, Block memory (MBLK), two parcels (`len = 01`): `reg` is the destination pointer, `low` the source pointer (or the value register), `Rn` the count register.

Mnemonic	Opcode	Sub-opcode
MCPY	001101 (0x0D)	00000000 (0x00)
MMOV	001101 (0x0D)	00000001 (0x01)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mblk-1`, `r20-mblk-2`.

Operation

```
MCPY:                           ; ascending; overlap is undefined
  while Rn ≠ 0:  M8[Rd] ← M8[Rs] ; Rd ← Rd + 1 ; Rs ← Rs + 1 ; Rn ← Rn - 1
MMOV: as MCPY, but the direction is chosen from the pointers so that an overlapping copy is correct
```

Flags None written.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires. The three registers are updated as work completes, so a fault leaves a consistent state and the instruction restarts from its registers.

The one granted exception to the one-memory-operand rule. All three registers are architectural state: on completion `Rn` is 0 and `Rd` and `Rs` point one past the end. An implementation may move more than a byte per step, so long as the register state at every point where an exception can be taken is consistent with a byte-at-a-time copy. The accesses made inside one block operation are unordered with respect to each other.


Why it is here. The block operations are the one granted exception to the one-memory-operand rule (an exception to a principle is allowed where there is a clear benefit), made safe by keeping the progress in architectural registers: the VAX `MOVC5` kept it in hidden microstate, which is why it is rejected, and ARM reached the same design in 2022 with `FEAT_MOPS`. The names `MCPY`, `MMOV` and `MSET` follow the memory operations of IBM System z; `MCMP` and `MSCN` complete the set. `MCPY` replaces the PDP-11 `MOV (R1)+,(R2)+` loop, and the `rep movsb` of x86, with one restartable instruction.

Cf. 6.4 (restart, progress faults); 7.2 (ordering of the accesses).


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

MCPY

MCPY, opcode 001101, three parcels, sub-opcode 00000000 (6 bytes)



MCPY, opcode 001101, two parcels, sub-opcode 00000000 (4 bytes)





```
MCPY Rd, Rs, Rn
```

Mnemonic	Opcode	Sub-opcode
MCPY	001101 (0x0D)	00000000 (0x00)


Operation, flags and exceptions as for the entry MCPY above; 2 layout forms, each a chart of its own (above).

MMOV

MMOV, opcode 001101, three parcels, sub-opcode 00000001 (6 bytes)



MMOV, opcode 001101, two parcels, sub-opcode 00000001 (4 bytes)





```
MMOV Rd, Rs, Rn
```

Mnemonic	Opcode	Sub-opcode
MMOV	001101 (0x0D)	00000001 (0x01)


Operation, flags and exceptions as for the entry MCPY above; 2 layout forms, each a chart of its own (above).

MSET: Fill a block of bytes

MSET, opcode 001101, three parcels, sub-opcode 00000010 (6 bytes)



MSET, opcode 001101, two parcels, sub-opcode 00000010 (4 bytes)




Mnemonics: `MSET`

Syntax

```
MSET Rd, Rv, Rn
```

Encoding



The chart is the layout `r20-mblk-1`, Block memory (MBLK), two parcels (`len = 01`): `reg` is the destination pointer, `low` the source pointer (or the value register), `Rn` the count register.

Mnemonic	Opcode	Sub-opcode
MSET	001101 (0x0D)	00000010 (0x02)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mblk-1`, `r20-mblk-2`.

Operation

```
while Rn ≠ 0:  M8[Rd] ← Rv[7:0] ; Rd ← Rd + 1 ; Rn ← Rn - 1
```

Flags None written.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

`MSET` with `Rv = 0` is the range-zeroing instruction: `bzero` and the clear of `calloc` are one instruction.


Why it is here. With a zero value it is the range-zeroing instruction, so `bzero` and the clearing of `calloc` need no separate opcode.

Cf. 6.4.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

MCMP: Compare two blocks of bytes

MCMP, opcode 001101, three parcels, sub-opcode 00000011 (6 bytes)



MCMP, opcode 001101, two parcels, sub-opcode 00000011 (4 bytes)




Mnemonics: `MCMP`

Syntax

```
MCMP Rd, Rs, Rn
```

Encoding



The chart is the layout `r20-mblk-1`, Block memory (MBLK), two parcels (`len = 01`): `reg` is the destination pointer, `low` the source pointer (or the value register), `Rn` the count register.

Mnemonic	Opcode	Sub-opcode
`MCMP`	`001101 (0x0D)`	`00000011 (0x03)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mblk-1`, `r20-mblk-2`.

Operation

```
while Rn ≠ 0:
    x ← M8[Rd] ; y ← M8[Rs]
    if x ≠ y then  flags ← flags of (x - y) ; stop      ; pointers left AT the differing byte
    Rd ← Rd + 1 ; Rs ← Rs + 1 ; Rn ← Rn - 1
if equal:  N = 0, Z = 1, V = 0, C = 0
```

Flags From the first differing byte as for `CMP` of the two bytes (`C` set if `x < y` unsigned, `N` and `V` from the signed difference); for equal blocks `N` = 0, `Z` = 1, `V` = 0, `C` = 0.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

When the instruction stops at a difference, `Rd` and `Rs` point at the differing bytes and `Rn` is the count remaining, so the position of the difference is in the registers.

Why it is here. Seven of the VAX's ten character-string instructions are present (`MOVC3`, `CMPC3`, `LOCC` and `SKPC` among them); the rejected ones are `EDITPC` and packed decimal. `MCMP` is the `CMPC3` equivalent.

Cf. 6.4.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


MSCN: Scan a block for a byte, or for a byte not equal to it

Mnemonics: `MSCN`, `MSCNN`

Syntax

```
MSCN Rd, Rv, Rn
MSCNN Rd, Rv, Rn
```

Encoding



The chart is the layout `r20-mblk-1`, Block memory (MBLK), two parcels (`len = 01`): `reg` is the destination pointer, `low` the source pointer (or the value register), `Rn` the count register.

Mnemonic	Opcode	Sub-opcode
`MSCN`	`001101 (0x0D)`	`00000100 (0x04)`
`MSCNN`	`001101 (0x0D)`	`00000101 (0x05)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mblk-1`, `r20-mblk-2`.

Operation

```
while Rn ≠ 0:
    hit ← (M8[Rd] = Rv[7:0])            ; MSCNN: hit ← (M8[Rd] ≠ Rv[7:0])
    if hit then  Z = 1 ; stop             ; Rd points AT the byte found
    Rd ← Rd + 1 ; Rn ← Rn - 1
not found: Z = 0
```

Flags All four flags are written: `Z` = 1 if the byte was found, else 0; `N`, `V` and `C` are cleared.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

`MSCN` is `memchr`; with an explicit count it gives `strnlen`, and composing it with `MCPY` gives a bounded `strcpy` in two instructions. There are no NUL-terminated string instructions.


Why it is here. `MSCN` is `LOCC` and `memchr`; `MSCNN` fills the `SKPC` gap (the first byte that is *not* equal). Both cost no opcode and almost no hardware. With an explicit count `MSCN` gives `strnlen`, and with `MCPY` a bounded `strcpy` in two instructions. NUL-terminated string instructions (the System/z `MVST`, `SRST`, `CLST`) are rejected, because they encode an unbounded read, the largest single source of memory-safety failures in C (9.17).

Cf. 6.4.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

MSCN

MSCN, opcode 001101, three parcels, sub-opcode 00000100 (6 bytes)



MSCN, opcode 001101, two parcels, sub-opcode 00000100 (4 bytes)





```
MSCN Rd, Rv, Rn
```

Mnemonic	Opcode	Sub-opcode
MSCN	001101 (0x0D)	00000100 (0x04)


Operation, flags and exceptions as for the entry MSCN above; 2 layout forms, each a chart of its own (above).

MSCNN

MSCNN, opcode 001101, three parcels, sub-opcode 00000101 (6 bytes)



MSCNN, opcode 001101, two parcels, sub-opcode 00000101 (4 bytes)





```
MSCNN Rd, Rv, Rn
```

Mnemonic	Opcode	Sub-opcode
MSCNN	001101 (0x0D)	00000101 (0x05)


Operation, flags and exceptions as for the entry MSCN above; 2 layout forms, each a chart of its own (above).

MVAL: Validate a block as UTF-8

MVAL, opcode 001101, three parcels, sub-opcode 00000110 (6 bytes)



MVAL, opcode 001101, two parcels, sub-opcode 00000110 (4 bytes)




Mnemonics: MVAL

Syntax

```
MVAL Rd, Rn
```

Encoding



The chart is the layout `r20-mblk-1`, Block memory (MBLK), two parcels (`len = 01`): `reg` is the destination pointer, `low` the source pointer (or the value register), `Rn` the count register.

Mnemonic	Opcode	Sub-opcode
`MVAL`	`001101 (0x0D)`	`00000110 (0x06)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mblk-1`, `r20-mblk-2`.

Operation

```
scan Rn bytes at Rd; stop at the first byte that cannot be part of a valid UTF-8 sequence (the rules of
UTF8DEC)
```

Flags On completion `Rn` is 0 and the buffer is valid; otherwise `Rd` points at the offending sequence and `Rn` counts the bytes remaining (details in the instruction-set text, section 4.7.1).

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

The `UTF8DEC` comparators wired to the block sequencer.

Why it is here. The UTF-8 validity comparators already built for `UTF8DEC`, wired to the `MBLK` streaming sequencer already built for `MCPY`, so it costs no opcode and almost no hardware. The alternative, a SWAR loop (SIMD within a register), runs at about two to three cycles a byte and is respectable, which is why the justification is cost and not throughput.

Cf. 6.4.

Status specified; **not yet implemented** in the reference executor.

9.12 Floating point

9.12.1 Floating point uses the general registers: a `binary64` value fills one register, and the instruction, not the register, decides how its bits are read. *(D)*

9.12.2 `FADD`, `FSUB`, `FMUL` and `FCMP` are two-byte instructions; `FDIV`, `FSQRT`, the fused multiply-add family, `FABS`, `FMIN`, `FMAX`, `FCLASS`, the roundings and the `binary32` forms are in the floating-point escape; `binary16` has seventeen operations and conversions. *(D)*

9.12.3 The five IEEE flags (invalid, divide by zero, overflow, underflow, inexact) accumulate in `FPSR`; no floating-point operation traps; `FSFLAGS` reads and clears them. *(D)*

9.12.4 Every NaN that an operation creates is the canonical quiet NaN. *(D)*

9.12.5 There are no rounding-mode or precision mode bits: the precision is in the opcode, and so is the rounding mode wherever it is not nearest-even. *(D)*

9.12.6 There are no transcendental instructions. *(D)*

Commentary. **Precedent.** The PDP-11's FP11 had `AC0` to `AC5` and mode bits for single and double precision; the VAX had F, D, G and H formats. **Trade-offs.** An integer operation applied to a register holding a `binary64` destroys it, with no trap and no tag; that is intended and the ABI states it. A separate register file would cost a second set of read ports and a floating-point context; on a small implementation the register file is among the largest blocks. **Improvements.** The fused

multiply-add is the largest single addition to the datapath (about 9,000 transistors) and the least negotiable; the IEEE exception flags are recorded without traps, which is what C99 `<fenv.h>` needs. **Benefits.** No transfer instructions between files and a single calling convention. **Modern comparables.** RISC-V Zfinx and Zdinx use the integer register file for the same reason; AArch64 and x86 have separate vector and floating-point files. **Use.** FCLASS begins every library maths function; FMA is the building block of accurate polynomial evaluation. **Impact.** *Kernel:* There is no separate floating-point state to save at a context switch beyond the registers already saved, and the sticky flags go with the status word. *Compiler:* One calling convention for integers and floats, fused multiply-add contraction, and no rounding-mode state for the compiler to track. *Hardware:* No second register file (one of the largest blocks of a small floating-point unit); the floating-point unit with fused multiply-add is about 34,000 transistors.


FADD: Floating add, subtract and multiply, binary64

Mnemonics: FADD, FSUB, FMUL (aliases: FADDD, FSUBD, FMULD)

Syntax

```
FADD rm, Rd
FSUB rm, Rd
FMUL rm, Rd
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
FADD	100100 (0x24)
FSUB	100101 (0x25)
FMUL	100110 (0x26)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
Rd ← Rd + rm   (FADD)
Rd ← Rd - rm   (FSUB)
Rd ← Rd × rm   (FMUL)       ; IEEE 754 binary64, round to nearest even
```

Flags None written. The five IEEE exception flags are ORed into FPSR; no instruction traps.


Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause BUSFAULT). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires. Floating-point exceptions never trap.

Floating-point values live in the general registers; there is no separate register file and no mode bit. A NaN result is the canonical quiet NaN `0x7FF8000000000000`. The alternative spellings FADDD, FSUBD, FMULD are aliases.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

FADD


FADD, opcode 100100, three parcels (modes base, postinc, predec) (6 bytes)




FADD, opcode 100100, three parcels (modes index) (6 bytes)




FADD, opcode 100100, three parcels (modes pcrel, imm, abs) (6 bytes)




FADD, opcode 100100, three parcels (modes dp) (6 bytes)




FADD, opcode 100100, two parcels (modes base, postinc, predec) (4 bytes)




FADD, opcode 100100, two parcels (modes index) (4 bytes)




FADD, opcode 100100, two parcels (modes pcrel, imm, abs) (4 bytes)



FADD, opcode 100100, two parcels (modes dp) (4 bytes)



FADD, opcode 100100, one parcel (2 bytes)





```
FADD rm, Rd
```

Mnemonic	Opcode
FADD	100100 (0x24)


Operation, flags and exceptions as for the entry FADD above; 9 layout forms, each a chart of its own (above).

FSUB


FSUB, opcode 100101, three parcels (modes base, postinc, predec) (6 bytes)




FSUB, opcode 100101, three parcels (modes index) (6 bytes)




FSUB, opcode 100101, three parcels (modes pcrel, imm, abs) (6 bytes)




FSUB, opcode 100101, three parcels (modes dp) (6 bytes)




FSUB, opcode 100101, two parcels (modes base, postinc, predec) (4 bytes)




FSUB, opcode 100101, two parcels (modes index) (4 bytes)




FSUB, opcode 100101, two parcels (modes pcrel, imm, abs) (4 bytes)



FSUB, opcode 100101, two parcels (modes dp) (4 bytes)



FSUB, opcode 100101, one parcel (2 bytes)





```
FSUB rm, Rd
```

Mnemonic	Opcode
FSUB	100101 (0x25)


Operation, flags and exceptions as for the entry FADD above; 9 layout forms, each a chart of its own (above).

FMUL


FMUL, opcode 100110, three parcels (modes base, postinc, predec) (6 bytes)




FMUL, opcode 100110, three parcels (modes index) (6 bytes)




FMUL, opcode 100110, three parcels (modes pcrel, imm, abs) (6 bytes)




FMUL, opcode 100110, three parcels (modes dp) (6 bytes)




FMUL, opcode 100110, two parcels (modes base, postinc, predec) (4 bytes)




FMUL, opcode 100110, two parcels (modes index) (4 bytes)




FMUL, opcode 100110, two parcels (modes pcrel, imm, abs) (4 bytes)



FMUL, opcode 100110, two parcels (modes dp) (4 bytes)



FMUL, opcode 100110, one parcel (2 bytes)




```
FMUL rm, Rd
```

Mnemonic	Opcode
FMUL	100110 (0x26)

Operation, flags and exceptions as for the entry FADD above; 9 layout forms, each a chart of its own (above).


FADDD
An alias of FADD: the assembler writes it as that word.

FSUBD
An alias of FSUB: the assembler writes it as that word.


FMULD
An alias of FMUL: the assembler writes it as that word.

FCMP: Floating compare, binary64


FCMP, opcode 100111, three parcels (modes base, postinc, predec) (6 bytes)




FCMP, opcode 100111, three parcels (modes index) (6 bytes)




FCMP, opcode 100111, three parcels (modes pcrel, imm, abs) (6 bytes)




FCMP, opcode 100111, three parcels (modes dp) (6 bytes)




FCMP, opcode 100111, two parcels (modes base, postinc, predec) (4 bytes)




FCMP, opcode 100111, two parcels (modes index) (4 bytes)




FCMP, opcode 100111, two parcels (modes pcrel, imm, abs) (4 bytes)



FCMP, opcode 100111, two parcels (modes dp) (4 bytes)



FCMP, opcode 100111, one parcel (2 bytes)




Mnemonics: `FCMP` (aliases: `FCMPD`)

Syntax

```
FCMP Rd, rm        ; register first
```

Encoding



The chart is the layout `r20-mem-0`, Moves, address formation and the ALU, one parcel (`len = 00`): `reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
FCMP	100111 (0x27)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-mem-0`, `r20-mem-1`, `r20-mem-1-2`, `r20-mem-1-3`, `r20-mem-1-4`, `r20-mem-2`, `r20-mem-2-2`, `r20-mem-2-3`, `r20-mem-2-4`.

Operation

```
N ← Rd < rm ; Z ← Rd = rm ; V ← unordered ; C ← 0
```

Flags `N` set if `Rd < rm`, `Z` if equal, `V` if the operands are unordered (either is a NaN), `C` cleared. A signalling NaN raises `NV` in `FPSR`.

Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

The signed branches do not treat the unordered case cleanly (`BLT` after an unordered compare takes `N xor V` = 1); this is an open item of the instruction set.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

`FCMPD` is an alias of `FCMP`: the assembler writes it as that word.


FDIV: Floating divide and square root, binary64

Mnemonics: `FDIV`, `FSQRT` (aliases: `FDIVD`, `FSQRTD`)

Syntax

```
FDIV Rs, Rd
FSQRT Rs, Rd
```

Encoding



The chart is the layout `r20-fesc-1`, Floating point (FESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
FDIV	010000 (0x10)	00000000 (0x00)
FSQRT	010000 (0x10)	00000001 (0x01)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-fesc-1`, `r20-fesc-2`.

Operation

```
FDIV : Rd ← Rd ÷ Rs
FSQRT: Rd ← sqrt(Rs)
```

Flags No integer flag is written. The IEEE exception flags raised are ORed into FPSR (NX inexact, UF underflow, OF overflow, DZ divide by zero, NV invalid); nothing traps.


Exceptions None.

FDIV and FSQRT are multi-cycle sequencer operations and rarely appear in a two-byte form, so they are in FESC. The alternative spellings FDIVD, FSQRTD are aliases.


Status implemented in the reference executor (common/pdp64exec.c, shared by sim64 and QEMU).

FDIV

FDIV, opcode 010000, three parcels, sub-opcode 00000000 (6 bytes)



FDIV, opcode 010000, two parcels, sub-opcode 00000000 (4 bytes)





```
FDIV Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FDIV	010000 (0x10)	00000000 (0x00)


Operation, flags and exceptions as for the entry FDIV above; 2 layout forms, each a chart of its own (above).

FSQRT

FSQRT, opcode 010000, three parcels, sub-opcode 00000001 (6 bytes)



FSQRT, opcode 010000, two parcels, sub-opcode 00000001 (4 bytes)




```
FSQRT Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FSQRT	010000 (0x10)	00000001 (0x01)

Operation, flags and exceptions as for the entry FDIV above; 2 layout forms, each a chart of its own (above).

FDIVD

An alias of FDIV: the assembler writes it as that word.

FSQRTD

An alias of FSQRT: the assembler writes it as that word.


FSINGLE: Floating arithmetic, binary32

Mnemonics: FADD32, FSUB32, FMUL32, FDIV32, FSQRT32, FCMP32 (aliases: FADDS, FSUBS, FMULS, FDIVS, FSQRTS, FCMPS)

Syntax

```
FADD32 Rs, Rd
FSUB32 Rs, Rd
FMUL32 Rs, Rd
FDIV32 Rs, Rd
FSQRT32 Rs, Rd
FCMP32 Rd, Rs
```

Encoding



The chart is the layout `r20-fesc-1`, Floating point (FESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
FADD32	010000 (0x10)	00001000 (0x08)
FSUB32	010000 (0x10)	00001001 (0x09)
FMUL32	010000 (0x10)	00001010 (0x0A)
FDIV32	010000 (0x10)	00001011 (0x0B)
FSQRT32	010000 (0x10)	00001100 (0x0C)
FCMP32	010000 (0x10)	00001101 (0x0D)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-fesc-1`, `r20-fesc-2`.

Operation

```
Rd ← Rd op Rs  (FADD32 FSUB32 FMUL32 FDIV32); Rd ← sqrt(Rs) (FSQRT32)
FCMP32: flags as FCMP, comparing Rd with Rs
```

Flags No integer flag is written. The IEEE exception flags raised are ORed into `FPSR` (`NX` inexact, `UF` underflow, `OF` overflow, `DZ` divide by zero, `NV` invalid); nothing traps. `FCMP32` writes `N Z V C` as `FCMP` does.

Exceptions None.


A `binary32` lives in the low 32 bits of a register, sign-extended to 64 like every 32-bit result. Results are correctly rounded to nearest even. The alternative spellings `FADDS`, `FSUBS`, ... are aliases.

Why it is here. `binary64` has first-class opcodes because on a 64-bit machine it is the common case; `binary32` is in `FESC` with the same operations, held in the low 32 bits of a register and sign-extended like every other 32-bit value (see also the ABI). The naming rule is an `F` in front of the integer mnemonic (`FADD`) and a size suffix for the other formats (`FADD16`); the older spellings (`FADDS` and so on) are aliases.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

FADD32

FADD32, opcode 010000, three parcels, sub-opcode 00001000 (6 bytes)



FADD32, opcode 010000, two parcels, sub-opcode 00001000 (4 bytes)





```
FADD32 Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FADD32	010000 (0x10)	00001000 (0x08)


Operation, flags and exceptions as for the entry FSINGLE above; 2 layout forms, each a chart of its own (above).

FSUB32

FSUB32, opcode 010000, three parcels, sub-opcode 00001001 (6 bytes)



FSUB32, opcode 010000, two parcels, sub-opcode 00001001 (4 bytes)





```
FSUB32 Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FSUB32	010000 (0x10)	00001001 (0x09)


Operation, flags and exceptions as for the entry FSINGLE above; 2 layout forms, each a chart of its own (above).

FMUL32

FMUL32, opcode 010000, three parcels, sub-opcode 00001010 (6 bytes)



FMUL32, opcode 010000, two parcels, sub-opcode 00001010 (4 bytes)





```
FMUL32 Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FMUL32	010000 (0x10)	00001010 (0x0A)


Operation, flags and exceptions as for the entry FSINGLE above; 2 layout forms, each a chart of its own (above).

FDIV32

FDIV32, opcode 010000, three parcels, sub-opcode 00001011 (6 bytes)



FDIV32, opcode 010000, two parcels, sub-opcode 00001011 (4 bytes)





```
FDIV32 Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FDIV32	010000 (0x10)	00001011 (0x0B)


Operation, flags and exceptions as for the entry FSINGLE above; 2 layout forms, each a chart of its own (above).

FSQRT32

FSQRT32, opcode 010000, three parcels, sub-opcode 00001100 (6 bytes)



FSQRT32, opcode 010000, two parcels, sub-opcode 00001100 (4 bytes)





```
FSQRT32 Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FSQRT32	010000 (0x10)	00001100 (0x0C)


Operation, flags and exceptions as for the entry FSINGLE above; 2 layout forms, each a chart of its own (above).

FCMP32

FCMP32, opcode 010000, three parcels, sub-opcode 00001101 (6 bytes)



FCMP32, opcode 010000, two parcels, sub-opcode 00001101 (4 bytes)




```
FCMP32 Rd, Rs
```

Mnemonic	Opcode	Sub-opcode
FCMP32	010000 (0x10)	00001101 (0x0D)

Operation, flags and exceptions as for the entry FSINGLE above; 2 layout forms, each a chart of its own (above).

FADDS
An alias of FADD32: the assembler writes it as that word.

FSUBS
An alias of FSUB32: the assembler writes it as that word.

FMULS
An alias of FMUL32: the assembler writes it as that word.

FDIVS
An alias of FDIV32: the assembler writes it as that word.

FSQRTS
An alias of FSQRT32: the assembler writes it as that word.

FCMPS
An alias of FCMP32: the assembler writes it as that word.

FMADD: Fused multiply-add, binary64


Mnemonics: FMADD, FMSUB, FNMADD, FNMSUB (aliases: FMADDD, FMSUBD, FNMADDD, FNMSUBD)

Syntax

```
FMADD Rs, Rt, Ru, Rd
FMSUB Rs, Rt, Ru, Rd
```

```
FNMADD Rs, Rt, Ru, Rd
FNMSUB Rs, Rt, Ru, Rd
```

Encoding



The chart is the layout `r20-fesc-1`, Floating point (FESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
FMADD	010000 (0x10)	00010000 (0x10)
FMSUB	010000 (0x10)	00010001 (0x11)
FNMADD	010000 (0x10)	00010010 (0x12)
FNMSUB	010000 (0x10)	00010011 (0x13)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-fesc-1`, `r20-fesc-2`.

Operation

```
FMADD : Rd ← Rs×Rt + Ru
FMSUB : Rd ← Rs×Rt - Ru
FNMADD: Rd ← -(Rs×Rt) - Ru
FNMSUB: Rd ← -(Rs×Rt) + Ru          ; each rounded once
```

Flags No integer flag is written. The IEEE exception flags raised are ORed into FPSR (NX inexact, UF underflow, OF overflow, DZ divide by zero, NV invalid); nothing traps.

Exceptions None.


Four register operands are available at `len = 01`. The alternative spellings FMADDD, ... are aliases.

Why it is here. The whole fused multiply-add family is in FESC, because its absence would be the single worst gap in the floating-point set: one rounding instead of two, and the inner step of dot products, polynomial evaluation and every matrix kernel. FESC gives it four register operands. It replaces the VAX POLY, which was the best answer before fused multiply-add.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

FMADD

FMADD, opcode 010000, three parcels, sub-opcode 00010000 (6 bytes)



FMADD, opcode 010000, two parcels, sub-opcode 00010000 (4 bytes)





```
FMADD Rs, Rt, Ru, Rd
```

Mnemonic	Opcode	Sub-opcode
FMADD	010000 (0x10)	00010000 (0x10)


Operation, flags and exceptions as for the entry FMADD above; 2 layout forms, each a chart of its own (above).

FMSUB

FMSUB, opcode 010000, three parcels, sub-opcode 00010001 (6 bytes)



FMSUB, opcode 010000, two parcels, sub-opcode 00010001 (4 bytes)





```
FMSUB Rs, Rt, Ru, Rd
```

Mnemonic	Opcode	Sub-opcode
FMSUB	010000 (0x10)	00010001 (0x11)


Operation, flags and exceptions as for the entry FMADD above; 2 layout forms, each a chart of its own (above).

FNMADD

FNMADD, opcode 010000, three parcels, sub-opcode 00010010 (6 bytes)



FNMADD, opcode 010000, two parcels, sub-opcode 00010010 (4 bytes)





```
FNMADD Rs, Rt, Ru, Rd
```

Mnemonic	Opcode	Sub-opcode
FNMADD	010000 (0x10)	00010010 (0x12)


Operation, flags and exceptions as for the entry FMADD above; 2 layout forms, each a chart of its own (above).

FNMSUB

FNMSUB, opcode 010000, three parcels, sub-opcode 00010011 (6 bytes)



FNMSUB, opcode 010000, two parcels, sub-opcode 00010011 (4 bytes)




```
FNMSUB Rs, Rt, Ru, Rd
```

Mnemonic	Opcode	Sub-opcode
FNMSUB	010000 (0x10)	00010011 (0x13)

Operation, flags and exceptions as for the entry FMADD above; 2 layout forms, each a chart of its own (above).

FMADDD

An alias of FMADD: the assembler writes it as that word.

FMSUBD

An alias of FMSUB: the assembler writes it as that word.

FNMADDD

An alias of FNMADD: the assembler writes it as that word.

FNMSUBD

An alias of FNMSUB: the assembler writes it as that word.


FMADD32: Fused multiply-add, binary32

Mnemonics: FMADD32, FMSUB32, FNMADD32, FNMSUB32 (aliases: FMADDS, FMSUBS, FNMADDS, FNMSUBS)

Syntax

```
FMADD32 Rs, Rt, Ru, Rd
FMSUB32 ...
FNMADD32 ...
FNMSUB32 ...
```

Encoding



The chart is the layout `r20-fesc-1`, Floating point (FESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
FMADD32	010000 (0x10)	00011000 (0x18)
FMSUB32	010000 (0x10)	00011001 (0x19)
FNMADD32	010000 (0x10)	00011010 (0x1A)
FNMSUB32	010000 (0x10)	00011011 (0x1B)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-fesc-1`, `r20-fesc-2`.

Operation

```
As FMADD, in binary32, rounded once
```

Flags No integer flag is written. The IEEE exception flags raised are ORed into `FPSR` (`NX` inexact, `UF` underflow, `OF` overflow, `DZ` divide by zero, `NV` invalid); nothing traps.


Exceptions None.

Why it is here. The `binary32` forms of the fused multiply-add family.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

FMADD32

FMADD32, opcode 010000, three parcels, sub-opcode 00011000 (6 bytes)



FMADD32, opcode 010000, two parcels, sub-opcode 00011000 (4 bytes)





```
FMADD32 Rs, Rt, Ru, Rd
```

Mnemonic	Opcode	Sub-opcode
FMADD32	010000 (0x10)	00011000 (0x18)


Operation, flags and exceptions as for the entry FMADD32 above; 2 layout forms, each a chart of its own (above).

FMSUB32

FMSUB32, opcode 010000, three parcels, sub-opcode 00011001 (6 bytes)



FMSUB32, opcode 010000, two parcels, sub-opcode 00011001 (4 bytes)





```
FMSUB32 ...
```

Mnemonic	Opcode	Sub-opcode
FMSUB32	010000 (0x10)	00011001 (0x19)


Operation, flags and exceptions as for the entry FMADD32 above; 2 layout forms, each a chart of its own (above).

FNMADD32

FNMADD32, opcode 010000, three parcels, sub-opcode 00011010 (6 bytes)



FNMADD32, opcode 010000, two parcels, sub-opcode 00011010 (4 bytes)





```
FNMADD32 ...
```

Mnemonic	Opcode	Sub-opcode
FNMADD32	010000 (0x10)	00011010 (0x1A)


Operation, flags and exceptions as for the entry FMADD32 above; 2 layout forms, each a chart of its own (above).

FNMSUB32

FNMSUB32, opcode 010000, three parcels, sub-opcode 00011011 (6 bytes)



FNMSUB32, opcode 010000, two parcels, sub-opcode 00011011 (4 bytes)




```
FNMSUB32 ...
```

Mnemonic	Opcode	Sub-opcode
FNMSUB32	010000 (0x10)	00011011 (0x1B)

Operation, flags and exceptions as for the entry FMADD32 above; 2 layout forms, each a chart of its own (above).

FMADDS
An alias of FMADD32: the assembler writes it as that word.

FMSUBS
An alias of FMSUB32: the assembler writes it as that word.

FNMADDS
An alias of FNMADD32: the assembler writes it as that word.

FNMSUBS
An alias of FNMSUB32: the assembler writes it as that word.


FSIGN: Sign operations on the bits

Mnemonics: FNEG, FABS, FCOPYSIGN

Syntax

```
FNEG Rs, Rd
FABS Rs, Rd
FCOPYSIGN Rs, Rt, Rd
```

Encoding



The chart is the layout r20-fesc-1, Floating point (FESC), two parcels (len = 01): From len = 01. In this group low is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
FNEG	010000 (0x10)	00100000 (0x20)
FABS	010000 (0x10)	00100001 (0x21)
FCOPYSIGN	010000 (0x10)	00100010 (0x22)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-fesc-1, r20-fesc-2.

Operation

```
FNEG     : Rd ← Rs with the sign bit flipped
FABS     : Rd ← Rs with the sign bit cleared
FCOPYSIGN: Rd ← magnitude of Rs, sign of Rt
```

Flags None. These operate on the bits, do not canonicalise a NaN and raise no exception flag.


Exceptions None.

Why it is here. Sign and selection operations (negate, absolute value and the like) work on the bits, do not canonicalise a NaN and raise no flag, so they cost almost nothing. The PowerPC 601 floating-point set has the same operations (stated from memory, not checked against a manual). No separate reason is recorded for these three.


Status implemented in the reference executor (common/pdp64exec.c, shared by sim64 and QEMU).

FNEG

FNEG, opcode 010000, three parcels, sub-opcode 00100000 (6 bytes)



FNEG, opcode 010000, two parcels, sub-opcode 00100000 (4 bytes)





```
FNEG Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FNEG	010000 (0x10)	00100000 (0x20)


Operation, flags and exceptions as for the entry FSIGN above; 2 layout forms, each a chart of its own (above).

FABS

FABS, opcode 010000, three parcels, sub-opcode 00100001 (6 bytes)



FABS, opcode 010000, two parcels, sub-opcode 00100001 (4 bytes)





```
FABS Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FABS	010000 (0x10)	00100001 (0x21)


Operation, flags and exceptions as for the entry FSIGN above; 2 layout forms, each a chart of its own (above).

FCOPYSIGN

FCOPYSIGN, opcode 010000, three parcels, sub-opcode 00100010 (6 bytes)



FCOPYSIGN, opcode 010000, two parcels, sub-opcode 00100010 (4 bytes)




```
FCOPYSIGN Rs, Rt, Rd
```

Mnemonic	Opcode	Sub-opcode
FCOPYSIGN	010000 (0x10)	00100010 (0x22)

Operation, flags and exceptions as for the entry FSIGN above; 2 layout forms, each a chart of its own (above).


FMIN: Floating minimum and maximum, binary64

Mnemonics: `FMIN`, `FMAX` (aliases: `FMIND`, `FMAXD`)

Syntax

```
FMIN Rs, Rt, Rd
FMAX Rs, Rt, Rd
```

Encoding



The chart is the layout `r20-fesc-1`, Floating point (FESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
FMIN	010000 (0x10)	00100011 (0x23)
FMAX	010000 (0x10)	00100100 (0x24)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-fesc-1`, `r20-fesc-2`.

Operation

```
if Rs is a NaN then Rd ← Rt ; else if Rt is a NaN then Rd ← Rs ; else Rd ← smaller (FMIN) or larger (FMAX)
if both are NaNs the result is the canonical quiet NaN
```

Flags No integer flag is written. The IEEE exception flags raised are ORed into `FPSR` (`NX` inexact, `UF` underflow, `OF` overflow, `DZ` divide by zero, `NV` invalid); nothing traps.

Exceptions None.


The alternative spellings `FMIND`, `FMAXD` are aliases.

Why it is here. The floating counterparts of the integer `MIN` and `MAX`. A NaN operand loses to a number and two NaNs give the canonical quiet NaN.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

FMIN

FMIN, opcode 010000, three parcels, sub-opcode 00100011 (6 bytes)



FMIN, opcode 010000, two parcels, sub-opcode 00100011 (4 bytes)





```
FMIN Rs, Rt, Rd
```

Mnemonic	Opcode	Sub-opcode
`FMIN`	`010000 (0x10)`	`00100011 (0x23)`


Operation, flags and exceptions as for the entry FMIN above; 2 layout forms, each a chart of its own (above).

FMAX

FMAX, opcode 010000, three parcels, sub-opcode 00100100 (6 bytes)



FMAX, opcode 010000, two parcels, sub-opcode 00100100 (4 bytes)




```
FMAX Rs, Rt, Rd
```

Mnemonic	Opcode	Sub-opcode
FMAX	010000 (0x10)	00100100 (0x24)

Operation, flags and exceptions as for the entry FMIN above; 2 layout forms, each a chart of its own (above).

FMIND

An alias of FMIN: the assembler writes it as that word.

FMAXD

An alias of FMAX: the assembler writes it as that word.


FCLASS: Classify a floating-point value

Mnemonics: FCLASS, FCLASS32, FCLASS16 (aliases: FCLASSD, FCLASSS)

Syntax

```
FCLASS Rs, Rd
FCLASS32 Rs, Rd
FCLASS16 Rs, Rd
```

Encoding



The chart is the layout r20-fesc-1, Floating point (FESC), two parcels (len = 01): From len = 01. In this group low is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
FCLASS	010000 (0x10)	00101000 (0x28)
FCLASS32	010000 (0x10)	00101001 (0x29)
FCLASS16	010000 (0x10)	01011100 (0x5C)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-fesc-1`, `r20-fesc-2`.

Operation

```
Rd ← a bit vector with exactly one bit set:
bit 0 -infinity      bit 1 -normal      bit 2 -subnormal   bit 3 -zero
bit 4 +zero          bit 5 +subnormal   bit 6 +normal      bit 7 +infinity
bit 8 signalling NaN bit 9 quiet NaN
```

Flags None.

Exceptions None.


Every libm function begins with this dispatch. The alternative spellings `FCLASSD`, `FCLASSS` are aliases.

Why it is here. Every libm function begins with this dispatch: one instruction returns which of ten kinds a value is (signalling or quiet NaN, infinity, normal, subnormal, zero, each signed), where software needs several compares and masks. It is justified by a workload, library mathematics, and not by compiled C, as the tag branches are. Nothing in the corpus emits it, because the compiler does not use it.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

FCLASS

FCLASS, opcode 010000, three parcels, sub-opcode 00101000 (6 bytes)



FCLASS, opcode 010000, two parcels, sub-opcode 00101000 (4 bytes)





```
FCLASS Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCLASS	010000 (0x10)	00101000 (0x28)


Operation, flags and exceptions as for the entry FCLASS above; 2 layout forms, each a chart of its own (above).

FCLASS32

FCLASS32, opcode 010000, three parcels, sub-opcode 00101001 (6 bytes)



FCLASS32, opcode 010000, two parcels, sub-opcode 00101001 (4 bytes)





```
FCLASS32 Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCLASS32	010000 (0x10)	00101001 (0x29)


Operation, flags and exceptions as for the entry FCLASS above; 2 layout forms, each a chart of its own (above).

FCLASS16

FCLASS16, opcode 010000, three parcels, sub-opcode 01011100 (6 bytes)



FCLASS16, opcode 010000, two parcels, sub-opcode 01011100 (4 bytes)




```
FCLASS16 Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCLASS16	010000 (0x10)	01011100 (0x5C)

Operation, flags and exceptions as for the entry FCLASS above; 2 layout forms, each a chart of its own (above).

FCLASSD
An alias of FCLASS: the assembler writes it as that word.

FCLASSS
An alias of FCLASS32: the assembler writes it as that word.


FRINT: Round to an integral value, binary64

Mnemonics: FRINT, FRINTZ, FRINTM, FRINTP, FRINTA (aliases: FRINTD, FRINTDZ, FRINTDM, FRINTDP, FRINTDA)

Syntax

```
FRINT Rs, Rd
FRINTZ Rs, Rd
FRINTM Rs, Rd
FRINTP Rs, Rd
FRINTA Rs, Rd
```

Encoding



The chart is the layout r20-fesc-1, Floating point (FESC), two parcels (len = 01): From len = 01. In this group low is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
FRINT	010000 (0x10)	00110000 (0x30)
FRINTZ	010000 (0x10)	00110001 (0x31)
FRINTM	010000 (0x10)	00110010 (0x32)
FRINTP	010000 (0x10)	00110011 (0x33)
FRINTA	010000 (0x10)	00110100 (0x34)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-fesc-1, r20-fesc-2.

Operation

```
FRINT : Rd ← Rs rounded to nearest, ties to even
FRINTZ: toward zero         FRINTM: toward -infinity
FRINTP: toward +infinity    FRINTA: to nearest, ties away from zero (C round())
```

Flags No integer flag is written. The IEEE exception flags raised are ORed into FPSR (NX inexact, UF underflow, OF overflow, DZ divide by zero, NV invalid); nothing traps.

Exceptions None.


The rounding mode is in the opcode, never in a mode bit. The alternative spellings FRINTD, FRINTDZ, ... are aliases.

Why it is here. Rounding to an integral value in each direction (nearest even, toward zero, down, up) is in the set, and FRINTA, ties away from zero, serves C's round(), which is common in libm; it is a qualifier of the round operation and so costs no new operation.


Status implemented in the reference executor (common/pdp64exec.c, shared by sim64 and QEMU).

FRINT

FRINT, opcode 010000, three parcels, sub-opcode 00110000 (6 bytes)



FRINT, opcode 010000, two parcels, sub-opcode 00110000 (4 bytes)





```
FRINT Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FRINT	010000 (0x10)	00110000 (0x30)


Operation, flags and exceptions as for the entry FRINT above; 2 layout forms, each a chart of its own (above).

FRINTZ

FRINTZ, opcode 010000, three parcels, sub-opcode 00110001 (6 bytes)



FRINTZ, opcode 010000, two parcels, sub-opcode 00110001 (4 bytes)





```
FRINTZ Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FRINTZ	010000 (0x10)	00110001 (0x31)


Operation, flags and exceptions as for the entry FRINT above; 2 layout forms, each a chart of its own (above).

FRINTM

FRINTM, opcode 010000, three parcels, sub-opcode 00110010 (6 bytes)



FRINTM, opcode 010000, two parcels, sub-opcode 00110010 (4 bytes)





```
FRINTM Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FRINTM	010000 (0x10)	00110010 (0x32)


Operation, flags and exceptions as for the entry FRINT above; 2 layout forms, each a chart of its own (above).

FRINTP

FRINTP, opcode 010000, three parcels, sub-opcode 00110011 (6 bytes)



FRINTP, opcode 010000, two parcels, sub-opcode 00110011 (4 bytes)





```
FRINTP Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FRINTP	010000 (0x10)	00110011 (0x33)


Operation, flags and exceptions as for the entry FRINT above; 2 layout forms, each a chart of its own (above).

FRINTA

FRINTA, opcode 010000, three parcels, sub-opcode 00110100 (6 bytes)



FRINTA, opcode 010000, two parcels, sub-opcode 00110100 (4 bytes)




```
FRINTA Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FRINTA	010000 (0x10)	00110100 (0x34)

Operation, flags and exceptions as for the entry FRINT above; 2 layout forms, each a chart of its own (above).

FRINTD
An alias of FRINT: the assembler writes it as that word.

FRINTDZ
An alias of FRINTZ: the assembler writes it as that word.

FRINTDM
An alias of FRINTM: the assembler writes it as that word.

FRINTDP
An alias of FRINTP: the assembler writes it as that word.

FRINTDA
An alias of FRINTA: the assembler writes it as that word.


FCVT: Floating conversions

Mnemonics: FCVTDQ, FCVTDQU, FCVTQD, FCVTQUD, FCVTDS, FCVTSD, FCVTSL, FCVTLS

Syntax

```
FCVTDQ Rs, Rd        ; binary64 to signed quad
FCVTDQU Rs, Rd       ; binary64 to unsigned quad
FCVTQD Rs, Rd        ; signed quad to binary64
FCVTQUD Rs, Rd       ; unsigned quad to binary64
FCVTDS Rs, Rd        ; binary64 to binary32
FCVTSD Rs, Rd        ; binary32 to binary64
FCVTSL Rs, Rd        ; binary32 to signed 32-bit integer
FCVTLS Rs, Rd        ; signed 32-bit integer to binary32
```

Encoding



The chart is the layout r20-fesc-1, Floating point (FESC), two parcels (len = 01): From len = 01. In this group low is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
FCVTDQ	010000 (0x10)	00111000 (0x38)
FCVTDQU	010000 (0x10)	00111110 (0x3E)
FCVTQD	010000 (0x10)	00111001 (0x39)
FCVTQUD	010000 (0x10)	00111111 (0x3F)
FCVTDS	010000 (0x10)	00111010 (0x3A)
FCVTSD	010000 (0x10)	00111011 (0x3B)
FCVTSL	010000 (0x10)	00111100 (0x3C)
FCVTLS	010000 (0x10)	00111101 (0x3D)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-fesc-1, r20-fesc-2.

Operation

```
float to integer: truncate toward zero, then saturate; a NaN gives the largest value
integer to float: round to nearest even
```

Flags No integer flag is written. The IEEE exception flags raised are ORed into `FPSR` (`NX` inexact, `UF` underflow, `OF` overflow, `DZ` divide by zero, `NV` invalid); nothing traps. A NaN or an out-of-range value raises `NV` and saturates.

Exceptions None.


Integer results are 64-bit (`FCVTDQ`, `FCVTDQU`) or 32-bit sign-extended (`FCVTSL`). Unsigned conversion of a negative value is invalid and gives 0.

Why it is here. `FCVTDQU` and `FCVTQUD` convert unsigned 64-bit integers to and from `binary64`. C needs both, and without them each takes a branch and several instructions.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

FCVTDQ

FCVTDQ, opcode 010000, three parcels, sub-opcode 00111000 (6 bytes)



FCVTDQ, opcode 010000, two parcels, sub-opcode 00111000 (4 bytes)





```
FCVTDQ Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCVTDQ	010000 (0x10)	00111000 (0x38)


Operation, flags and exceptions as for the entry FCVT above; 2 layout forms, each a chart of its own (above).

FCVTDQU

FCVTDQU, opcode 010000, three parcels, sub-opcode 00111110 (6 bytes)



FCVTDQU, opcode 010000, two parcels, sub-opcode 00111110 (4 bytes)





```
FCVTDQU Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCVTDQU	010000 (0x10)	00111110 (0x3E)


Operation, flags and exceptions as for the entry FCVT above; 2 layout forms, each a chart of its own (above).

FCVTQD

FCVTQD, opcode 010000, three parcels, sub-opcode 00111001 (6 bytes)



FCVTQD, opcode 010000, two parcels, sub-opcode 00111001 (4 bytes)





```
FCVTQD Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCVTQD	010000 (0x10)	00111001 (0x39)


Operation, flags and exceptions as for the entry FCVT above; 2 layout forms, each a chart of its own (above).

FCVTQUD

FCVTQUD, opcode 010000, three parcels, sub-opcode 00111111 (6 bytes)



FCVTQUD, opcode 010000, two parcels, sub-opcode 00111111 (4 bytes)





```
FCVTQUD Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCVTQUD	010000 (0x10)	00111111 (0x3F)


Operation, flags and exceptions as for the entry FCVT above; 2 layout forms, each a chart of its own (above).

FCVTDS

FCVTDS, opcode 010000, three parcels, sub-opcode 00111010 (6 bytes)



FCVTDS, opcode 010000, two parcels, sub-opcode 00111010 (4 bytes)





```
FCVTDS Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCVTDS	010000 (0x10)	00111010 (0x3A)


Operation, flags and exceptions as for the entry FCVT above; 2 layout forms, each a chart of its own (above).

FCVTSD

FCVTSD, opcode 010000, three parcels, sub-opcode 00111011 (6 bytes)



FCVTSD, opcode 010000, two parcels, sub-opcode 00111011 (4 bytes)





```
FCVTSD Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCVTSD	010000 (0x10)	00111011 (0x3B)


Operation, flags and exceptions as for the entry FCVT above; 2 layout forms, each a chart of its own (above).

FCVTSL

FCVTSL, opcode 010000, three parcels, sub-opcode 00111100 (6 bytes)



FCVTSL, opcode 010000, two parcels, sub-opcode 00111100 (4 bytes)





```
FCVTSL Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCVTSL	010000 (0x10)	00111100 (0x3C)


Operation, flags and exceptions as for the entry FCVT above; 2 layout forms, each a chart of its own (above).

FCVTLS

FCVTLS, opcode 010000, three parcels, sub-opcode 00111101 (6 bytes)



FCVTLS, opcode 010000, two parcels, sub-opcode 00111101 (4 bytes)





```
FCVTLS Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCVTLS	010000 (0x10)	00111101 (0x3D)


Operation, flags and exceptions as for the entry FCVT above; 2 layout forms, each a chart of its own (above).

FSFLAGS: Swap the floating-point exception flags

FSFLAGS, opcode 010000, three parcels, sub-opcode 01000000 (6 bytes)



FSFLAGS, opcode 010000, two parcels, sub-opcode 01000000 (4 bytes)




Mnemonics: FSFLAGS

Syntax

```
FSFLAGS Rs, Rd
```

Encoding



The chart is the layout `r20-fesc-1`, Floating point (FESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
FSFLAGS	010000 (0x10)	01000000 (0x40)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-fesc-1`, `r20-fesc-2`.

Operation

```
old ← FPSR
FPSR ← Rs[4:0]
Rd ← old
```

Flags None.

Exceptions None.

`FPSR` is the sticky five-bit register (`NX` bit 0, `UF` 1, `OF` 2, `DZ` 3, `NV` 4). C99 `<fenv.h>` is built on this one instruction.

Why it is here. IEEE 754 requires five status flags, and C99 `<fenv.h>` needs software access to them. The architecture has a sticky five-bit `FPSR`, laid out as RISC-V's `fflags`, written by every operation that can raise a flag and never trapping, and one swap instruction to read and write it. It is a record of what happened, not a mode, so the rule against mode bits is untouched.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


FHALF: Floating arithmetic, binary16

Mnemonics: `FADD16`, `FSUB16`, `FMUL16`, `FDIV16`, `FSQRT16`, `FCMP16`, `FMADD16`, `FMSUB16`, `FNMADD16`, `FNMSUB16`

Syntax

```
FADD16 Rs, Rd
FSUB16 Rs, Rd
FMUL16 Rs, Rd
FDIV16 Rs, Rd
FSQRT16 Rs, Rd
FCMP16 Rd, Rs
FMADD16 Rs, Rt, Ru, Rd ...
```

Encoding



The chart is the layout `r20-fesc-1`, Floating point (FESC), two parcels (`len = 01`): From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
FADD16	010000 (0x10)	01010000 (0x50)
FSUB16	010000 (0x10)	01010001 (0x51)
FMUL16	010000 (0x10)	01010010 (0x52)
FDIV16	010000 (0x10)	01010011 (0x53)
FSQRT16	010000 (0x10)	01010100 (0x54)
FCMP16	010000 (0x10)	01010101 (0x55)
FMADD16	010000 (0x10)	01011000 (0x58)
FMSUB16	010000 (0x10)	01011001 (0x59)
FNMADD16	010000 (0x10)	01011010 (0x5A)
FNMSUB16	010000 (0x10)	01011011 (0x5B)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-fesc-1`, `r20-fesc-2`.

Operation

```
as the binary32 words, in binary16: Rd ← Rd op Rs ; the fused forms take Rs, Rt, Ru, Rd
a half lives in the low 16 bits of a register, sign-extended to 64
```

Flags No integer flag is written. The IEEE exception flags raised are ORed into `FPSR` (`NX` inexact, `UF` underflow, `OF` overflow, `DZ` divide by zero, `NV` invalid); nothing traps. `FCMP16` writes `N Z V C` as `FCMP`.

Exceptions None.


Results are correctly rounded to nearest even, tininess judged after rounding; a NaN result is the canonical `0x7E00`. Half `FMIN`, `FMAX`, `FRINT*`, bfloat16 and conversions to and from 64-bit integers are open items.

Why it is here. Half precision began as a GPU format (NVIDIA's `half`, 2002), spread to machine learning and image formats, and is in CPUs (x86 `F16C` and AVX-512 FP16, ARMv8.2, RISC-V `Zfh` and `Zfhmin`); this account is from memory and not checked against a manual. Two levels are possible: conversions only (about 500 to 1,000 lookup tables, no new operation by the folding rule) and full arithmetic (about 2,000 to 3,500 tables; estimates), and the existing double datapath can compute half correctly rounded. The architecture has both conversions and arithmetic. The leftovers (half `FMIN`, `FRINT*`, bfloat16, 64-bit integer conversions) are open items. 16-bit *integer* arithmetic is not provided: the ALU has one width (9.2.9).


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

FADD16

FADD16, opcode 010000, three parcels, sub-opcode 01010000 (6 bytes)



FADD16, opcode 010000, two parcels, sub-opcode 01010000 (4 bytes)





```
FADD16 Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FADD16	010000 (0x10)	01010000 (0x50)


Operation, flags and exceptions as for the entry FHALF above; 2 layout forms, each a chart of its own (above).

FSUB16

FSUB16, opcode 010000, three parcels, sub-opcode 01010001 (6 bytes)



FSUB16, opcode 010000, two parcels, sub-opcode 01010001 (4 bytes)





```
FSUB16 Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FSUB16	010000 (0x10)	01010001 (0x51)


Operation, flags and exceptions as for the entry FHALF above; 2 layout forms, each a chart of its own (above).

FMUL16

FMUL16, opcode 010000, three parcels, sub-opcode 01010010 (6 bytes)



FMUL16, opcode 010000, two parcels, sub-opcode 01010010 (4 bytes)





```
FMUL16 Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FMUL16	010000 (0x10)	01010010 (0x52)


Operation, flags and exceptions as for the entry FHALF above; 2 layout forms, each a chart of its own (above).

FDIV16

FDIV16, opcode 010000, three parcels, sub-opcode 01010011 (6 bytes)



FDIV16, opcode 010000, two parcels, sub-opcode 01010011 (4 bytes)





```
FDIV16 Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FDIV16	010000 (0x10)	01010011 (0x53)


Operation, flags and exceptions as for the entry FHALF above; 2 layout forms, each a chart of its own (above).

FSQRT16

FSQRT16, opcode 010000, three parcels, sub-opcode 01010100 (6 bytes)



FSQRT16, opcode 010000, two parcels, sub-opcode 01010100 (4 bytes)





```
FSQRT16 Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FSQRT16	010000 (0x10)	01010100 (0x54)


Operation, flags and exceptions as for the entry FHALF above; 2 layout forms, each a chart of its own (above).

FCMP16

FCMP16, opcode 010000, three parcels, sub-opcode 01010101 (6 bytes)



FCMP16, opcode 010000, two parcels, sub-opcode 01010101 (4 bytes)





```
FCMP16 Rd, Rs
```

Mnemonic	Opcode	Sub-opcode
FCMP16	010000 (0x10)	01010101 (0x55)


Operation, flags and exceptions as for the entry FHALF above; 2 layout forms, each a chart of its own (above).

FMADD16

FMADD16, opcode 010000, three parcels, sub-opcode 01011000 (6 bytes)



FMADD16, opcode 010000, two parcels, sub-opcode 01011000 (4 bytes)





```
FMADD16 Rs, Rt, Ru, Rd ...
```

Mnemonic	Opcode	Sub-opcode
FMADD16	010000 (0x10)	01011000 (0x58)


Operation, flags and exceptions as for the entry FHALF above; 2 layout forms, each a chart of its own (above).

FMSUB16

FMSUB16, opcode 010000, three parcels, sub-opcode 01011001 (6 bytes)



FMSUB16, opcode 010000, two parcels, sub-opcode 01011001 (4 bytes)




Mnemonic	Opcode	Sub-opcode
FMSUB16	010000 (0x10)	01011001 (0x59)


Operation, flags and exceptions as for the entry FHALF above; 2 layout forms, each a chart of its own (above).

FNMADD16

FNMADD16, opcode 010000, three parcels, sub-opcode 01011010 (6 bytes)



FNMADD16, opcode 010000, two parcels, sub-opcode 01011010 (4 bytes)




Mnemonic	Opcode	Sub-opcode
FNMADD16	010000 (0x10)	01011010 (0x5A)


Operation, flags and exceptions as for the entry FHALF above; 2 layout forms, each a chart of its own (above).

FNMSUB16

FNMSUB16, opcode 010000, three parcels, sub-opcode 01011011 (6 bytes)



FNMSUB16, opcode 010000, two parcels, sub-opcode 01011011 (4 bytes)



Mnemonic	Opcode	Sub-opcode
FNMSUB16	010000 (0x10)	01011011 (0x5B)

Operation, flags and exceptions as for the entry FHALF above; 2 layout forms, each a chart of its own (above).


FCVTH: Conversions to and from binary16

Mnemonics: FCVTSH, FCVTHS, FCVTDH, FCVTHD, FCVTHL, FCVTLH

Syntax

```
FCVTSH Rs, Rd        ; binary32 to half
FCVTHS Rs, Rd        ; half to binary32
FCVTDH Rs, Rd        ; binary64 to half
FCVTHD Rs, Rd        ; half to binary64
FCVTHL Rs, Rd        ; half to signed 32-bit integer, toward zero
FCVTLH Rs, Rd        ; signed 32-bit integer to half
```

Encoding



The chart is the layout r20-fesc-1, Floating point (FESC), two parcels (len = 01): From len = 01. In this group low is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
FCVTSH	010000 (0x10)	01100000 (0x60)
FCVTHS	010000 (0x10)	01100001 (0x61)
FCVTDH	010000 (0x10)	01100010 (0x62)
FCVTHD	010000 (0x10)	01100011 (0x63)
FCVTHL	010000 (0x10)	01100100 (0x64)
FCVTLH	010000 (0x10)	01100101 (0x65)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-fesc-1, r20-fesc-2.

Operation

```
narrowing: round to nearest even ; widening: exact
FCVTHL of a NaN or an infinity is invalid and saturates; truncating a fraction is inexact
```

Flags No integer flag is written. The IEEE exception flags raised are ORed into FPSR (NX inexact, UF underflow, OF overflow, DZ divide by zero, NV invalid); nothing traps.


Exceptions None.

Why it is here. The conversion half of the binary16 support (see FHALF). The conversions are the part machine-learning code needs most, because a half is normally loaded and stored with MOVW, converted, computed in single or double, and converted back.


Status implemented in the reference executor (common/pdp64exec.c, shared by sim64 and QEMU).

FCVTSH

FCVTSH, opcode 010000, three parcels, sub-opcode 01100000 (6 bytes)



FCVTSH, opcode 010000, two parcels, sub-opcode 01100000 (4 bytes)





```
FCVTSH Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCVTSH	010000 (0x10)	01100000 (0x60)


Operation, flags and exceptions as for the entry FCVTH above; 2 layout forms, each a chart of its own (above).

FCVTHS

FCVTHS, opcode 010000, three parcels, sub-opcode 01100001 (6 bytes)



FCVTHS, opcode 010000, two parcels, sub-opcode 01100001 (4 bytes)





```
FCVTHS Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCVTHS	010000 (0x10)	01100001 (0x61)


Operation, flags and exceptions as for the entry FCVTH above; 2 layout forms, each a chart of its own (above).

FCVTDH

FCVTDH, opcode 010000, three parcels, sub-opcode 01100010 (6 bytes)



FCVTDH, opcode 010000, two parcels, sub-opcode 01100010 (4 bytes)





```
FCVTDH Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCVTDH	010000 (0x10)	01100010 (0x62)


Operation, flags and exceptions as for the entry FCVTH above; 2 layout forms, each a chart of its own (above).

FCVTHD

FCVTHD, opcode 010000, three parcels, sub-opcode 01100011 (6 bytes)



FCVTHD, opcode 010000, two parcels, sub-opcode 01100011 (4 bytes)





```
FCVTHD Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCVTHD	010000 (0x10)	01100011 (0x63)


Operation, flags and exceptions as for the entry FCVTH above; 2 layout forms, each a chart of its own (above).

FCVTHL

FCVTHL, opcode 010000, three parcels, sub-opcode 01100100 (6 bytes)



FCVTHL, opcode 010000, two parcels, sub-opcode 01100100 (4 bytes)





```
FCVTHL Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCVTHL	010000 (0x10)	01100100 (0x64)


Operation, flags and exceptions as for the entry FCVTH above; 2 layout forms, each a chart of its own (above).

FCVTLH

FCVTLH, opcode 010000, three parcels, sub-opcode 01100101 (6 bytes)



FCVTLH, opcode 010000, two parcels, sub-opcode 01100101 (4 bytes)




```
FCVTLH Rs, Rd
```

Mnemonic	Opcode	Sub-opcode
FCVTLH	010000 (0x10)	01100101 (0x65)

Operation, flags and exceptions as for the entry FCVTH above; 2 layout forms, each a chart of its own (above).

9.13 Atomics and ordering

Cf. chapter 7, section 7.12 (the atomic and ordering instructions), section 7.3 (the atomics in detail) and section 7.2 (the memory model).

9.13.1 The atomic escape ATOM (opcode 010001 (0x11)) holds CAS, SWAP, XADD, XAND, XOR_, XXOR, XMAX, XMIN, XMAXU and XMINU, each with a _DB variant that adds a barrier, and LL and SC; FENCE, WFE, SEV, ISYNC and HINT are in SYS. Their semantics, ordering rules and the reservation monitor are in chapter 7. *(opcode 010001 (0x11))*

9.13.2 CAS operates on 4 or 8 bytes; an 8-byte compare-and-swap may span two adjacent 4-byte fields, because the usual lock-and-count fast path of an operating system is exactly that (an 8-byte whole over two 4-byte members). *(D)* The encoding of the CAS size is unspecified. *(S)*

Commentary. The official entry of each instruction is below, in this section; chapter 7 gives the reasons, the memory model and the use. **Impact.** *Kernel:* the entries below are all a kernel needs to write its locks; chapter 7 explains how they compose. *Compiler:* a lock acquire is one _DB instruction. *Hardware:* a reservation monitor beside the data cache.


CAS: Compare and swap

Mnemonics: CAS, CASDB

Syntax

```
CAS expected, new, (address)       ; operand placement and size encoding unspecified; size is 4 or 8 bytes
CASDB ...                           ; with a full barrier
```

Encoding



The chart is the layout `r20-atom-1`, Atomics (ATOM), two parcels (`len = 01`): From `len = 01`. The placement of the operands is not specified.

Mnemonic	Opcode	Sub-opcode
CAS	010001 (0x11)	00000000 (0x00)
CASDB	010001 (0x11)	00000001 (0x01)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-atom-1`, `r20-atom-2`.

Operation

```
old ← M[address]                          ; 4 or 8 bytes, naturally aligned
if old = expected then M[address] ← new
result ← old          ; the program compares result with expected to learn whether the swap happened
```

Flags Not specified beyond “none for the read-modify-write forms”; `SC` reports success in its result register.

Exceptions Page fault, protection fault, alignment fault (the address must be naturally aligned) or bus error. The access is atomic with respect to every initiator, cores and devices alike.

The sub-opcodes and the semantics of this group are specified; the placement of the operands of each form is unspecified, and the forms below name the roles.


Why it is here. The barrier-fused variants are taken from LoongArch’s pragmatism: a lock acquire is one instruction rather than an atomic followed by a `FENCE`, and that pair is in every critical section of the system. With the other multiprocessor operations the atomics make the seventeen-operation SMP umbrella (7.1). They are defined on a reservation monitor and not on a bus lock (2.5).

Cf. 7.12 (the atomic instructions), 7.3 (the atomics in detail: the reservation monitor), 7.2 (the memory model).


Status specified; **not yet implemented** in the reference executor.

CAS

CAS, opcode 010001, three parcels, sub-opcode 00000000 (6 bytes)



CAS, opcode 010001, two parcels, sub-opcode 00000000 (4 bytes)





```
CAS expected, new, (address)
```

Mnemonic	Opcode	Sub-opcode
CAS	010001 (0x11)	00000000 (0x00)


Operation, flags and exceptions as for the entry CAS above; 2 layout forms, each a chart of its own (above).

CASDB

CASDB, opcode 010001, three parcels, sub-opcode 00000001 (6 bytes)



CASDB, opcode 010001, two parcels, sub-opcode 00000001 (4 bytes)




```
CASDB ...
```

Mnemonic	Opcode	Sub-opcode
CASDB	010001 (0x11)	00000001 (0x01)

Operation, flags and exceptions as for the entry CAS above; 2 layout forms, each a chart of its own (above).


SWAP: Atomic exchange

Mnemonics: SWAP, SWAPDB

Syntax

```
SWAP value, (address)
SWAPDB ...
```

Encoding



The chart is the layout r20-atom-1, Atomics (ATOM), two parcels (len = 01): From len = 01. The placement of the operands is not specified.

Mnemonic	Opcode	Sub-opcode
SWAP	010001 (0x11)	00000010 (0x02)
SWAPDB	010001 (0x11)	00000011 (0x03)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-atom-1, r20-atom-2.

Operation

```
old ← M[address] ; M[address] ← value ; result ← old
```

Flags Not specified beyond "none for the read-modify-write forms"; SC reports success in its result register.

Exceptions Page fault, protection fault, alignment fault (the address must be naturally aligned) or bus error. The access is atomic with respect to every initiator, cores and devices alike.

The sub-opcodes and the semantics of this group are specified; the placement of the operands of each form is unspecified, and the forms below name the roles.


Why it is here. One of the read-modify-write atomics of the ATOM group (see CAS). No separate reason is recorded for it.

Cf. 7.12 (the atomic instructions), 7.3 (the atomics in detail: the reservation monitor), 7.2 (the memory model).


Status specified; **not yet implemented** in the reference executor.

SWAP

SWAP, opcode 010001, three parcels, sub-opcode 00000010 (6 bytes)



SWAP, opcode 010001, two parcels, sub-opcode 00000010 (4 bytes)





```
SWAP value, (address)
```

Mnemonic	Opcode	Sub-opcode
SWAP	010001 (0x11)	00000010 (0x02)


Operation, flags and exceptions as for the entry SWAP above; 2 layout forms, each a chart of its own (above).

SWAPDB

SWAPDB, opcode 010001, three parcels, sub-opcode 00000011 (6 bytes)



SWAPDB, opcode 010001, two parcels, sub-opcode 00000011 (4 bytes)




```
SWAPDB ...
```

Mnemonic	Opcode	Sub-opcode
SWAPDB	010001 (0x11)	00000011 (0x03)

Operation, flags and exceptions as for the entry SWAP above; 2 layout forms, each a chart of its own (above).


XADD: Atomic fetch and add

Mnemonics: XADD, XADDDB

Syntax

```
XADD value, (address)
XADDDB ...
```

Encoding



The chart is the layout r20-atom-1, Atomics (ATOM), two parcels (len = 01): From len = 01. The placement of the operands is not specified.

Mnemonic	Opcode	Sub-opcode
XADD	010001 (0x11)	00000100 (0x04)
XADDDB	010001 (0x11)	00000101 (0x05)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-atom-1, r20-atom-2.

Operation

```
old ← M[address] ; M[address] ← old + value ; result ← old
```

Flags Not specified beyond "none for the read-modify-write forms"; SC reports success in its result register.

Exceptions Page fault, protection fault, alignment fault (the address must be naturally aligned) or bus error. The access is atomic with respect to every initiator, cores and devices alike.

The sub-opcodes and the semantics of this group are specified; the placement of the operands of each form is unspecified, and the forms below name the roles.


Why it is here. One of the fetch-and-operate atomics of ATOM (see CAS), in the place of the PDP-11's read-modify-write instructions, which were indivisible on the Unibus through the DATIP/DATO pair (7.1).

Cf. 7.12 (the atomic instructions), 7.3 (the atomics in detail: the reservation monitor), 7.2 (the memory model).


Status specified; **not yet implemented** in the reference executor.

XADD

XADD, opcode 010001, three parcels, sub-opcode 00000100 (6 bytes)



XADD, opcode 010001, two parcels, sub-opcode 00000100 (4 bytes)





```
XADD value, (address)
```

Mnemonic	Opcode	Sub-opcode
XADD	010001 (0x11)	00000100 (0x04)


Operation, flags and exceptions as for the entry XADD above; 2 layout forms, each a chart of its own (above).

XADDDB

XADDDB, opcode 010001, three parcels, sub-opcode 00000101 (6 bytes)



XADDDB, opcode 010001, two parcels, sub-opcode 00000101 (4 bytes)




```
XADDDB ...
```

Mnemonic	Opcode	Sub-opcode
XADDDB	010001 (0x11)	00000101 (0x05)

Operation, flags and exceptions as for the entry XADD above; 2 layout forms, each a chart of its own (above).


XAND: Atomic fetch and and, or, xor

Mnemonics: XAND, XANDDB, XOR, XOR_DB, XXOR, XXORDB

Syntax

```
XAND value, (address)
XOR_ value, (address)       ; the trailing underscore keeps the mnemonic distinct from XOR
XXOR value, (address)
each with a DB form
```

Encoding



The chart is the layout r20-atom-1, Atomics (ATOM), two parcels (len = 01): From len = 01. The placement of the operands is not specified.

Mnemonic	Opcode	Sub-opcode
XAND	010001 (0x11)	00000110 (0x06)
XANDDB	010001 (0x11)	00000111 (0x07)
XOR_	010001 (0x11)	00001000 (0x08)
XOR_DB	010001 (0x11)	00001001 (0x09)
XXOR	010001 (0x11)	00001010 (0x0A)
XXORDB	010001 (0x11)	00001011 (0x0B)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-atom-1, r20-atom-2.

Operation

```
old ← M[address]
XAND: M[address] ← old AND value
XOR_: M[address] ← old OR value
XXOR: M[address] ← old XOR value
result ← old
```

Flags Not specified beyond "none for the read-modify-write forms"; SC reports success in its result register.

Exceptions Page fault, protection fault, alignment fault (the address must be naturally aligned) or bus error. The access is atomic with respect to every initiator, cores and devices alike.

The sub-opcodes and the semantics of this group are specified; the placement of the operands of each form is unspecified, and the forms below name the roles.


Why it is here. The fetch-and-and, or and xor atomics of ATOM (see CAS). No separate reason is recorded for them.

Cf. 7.12 (the atomic instructions), 7.3 (the atomics in detail: the reservation monitor), 7.2 (the memory model).


Status specified; **not yet implemented** in the reference executor.

XAND

XAND, opcode 010001, three parcels, sub-opcode 00000110 (6 bytes)



XAND, opcode 010001, two parcels, sub-opcode 00000110 (4 bytes)





```
XAND value, (address)
```

Mnemonic	Opcode	Sub-opcode
XAND	010001 (0x11)	00000110 (0x06)


Operation, flags and exceptions as for the entry XAND above; 2 layout forms, each a chart of its own (above).

XANDDB

XANDDB, opcode 010001, three parcels, sub-opcode 00000111 (6 bytes)



XANDDB, opcode 010001, two parcels, sub-opcode 00000111 (4 bytes)




Mnemonic	Opcode	Sub-opcode
XANDDB	010001 (0x11)	00000111 (0x07)


Operation, flags and exceptions as for the entry XAND above; 2 layout forms, each a chart of its own (above).

XOR_

XOR_, opcode 010001, three parcels, sub-opcode 00001000 (6 bytes)



XOR_, opcode 010001, two parcels, sub-opcode 00001000 (4 bytes)





```
XOR_ value, (address)
```

Mnemonic	Opcode	Sub-opcode
XOR_	010001 (0x11)	00001000 (0x08)


Operation, flags and exceptions as for the entry XAND above; 2 layout forms, each a chart of its own (above).

XOR_DB

XOR_DB, opcode 010001, three parcels, sub-opcode 00001001 (6 bytes)



XOR_DB, opcode 010001, two parcels, sub-opcode 00001001 (4 bytes)




Mnemonic	Opcode	Sub-opcode
XOR_DB	010001 (0x11)	00001001 (0x09)


Operation, flags and exceptions as for the entry XAND above; 2 layout forms, each a chart of its own (above).

XXOR

XXOR, opcode 010001, three parcels, sub-opcode 00001010 (6 bytes)



XXOR, opcode 010001, two parcels, sub-opcode 00001010 (4 bytes)





```
XXOR value, (address)
```

Mnemonic	Opcode	Sub-opcode
XXOR	010001 (0x11)	00001010 (0x0A)


Operation, flags and exceptions as for the entry XAND above; 2 layout forms, each a chart of its own (above).

XXORDB

XXORDB, opcode 010001, three parcels, sub-opcode 00001011 (6 bytes)



XXORDB, opcode 010001, two parcels, sub-opcode 00001011 (4 bytes)



Mnemonic	Opcode	Sub-opcode
XXORDB	010001 (0x11)	00001011 (0x0B)

Operation, flags and exceptions as for the entry XAND above; 2 layout forms, each a chart of its own (above).


XMAX: Atomic fetch and minimum or maximum

Mnemonics: XMAX, XMAXDB, XMIN, XMINDB, XMAXU, XMAXUDB, XMINU, XMINUDB

Syntax

```
XMAX value, (address)
XMIN ..., XMAXU ..., XMINU ...
each with a DB form
```

Encoding



The chart is the layout r20-atom-1, Atomics (ATOM), two parcels (len = 01): From len = 01. The placement of the operands is not specified.

Mnemonic	Opcode	Sub-opcode
XMAX	010001 (0x11)	00001100 (0x0C)
XMAXDB	010001 (0x11)	00001101 (0x0D)
XMIN	010001 (0x11)	00001110 (0x0E)
XMINDB	010001 (0x11)	00001111 (0x0F)
XMAXU	010001 (0x11)	00010000 (0x10)
XMAXUDB	010001 (0x11)	00010001 (0x11)

Mnemonic	Opcode	Sub-opcode
XMINU	010001 (0x11)	00010010 (0x12)
XMINUDB	010001 (0x11)	00010011 (0x13)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-atom-1, r20-atom-2.

Operation

```
old ← M[address] ; M[address] ← max(old, value) (XMAX, XMAXU) or min (XMIN, XMINU) ; result ← old
signed for XMAX and XMIN, unsigned for the U forms
```

Flags Not specified beyond "none for the read-modify-write forms"; sc reports success in its result register.

Exceptions Page fault, protection fault, alignment fault (the address must be naturally aligned) or bus error. The access is atomic with respect to every initiator, cores and devices alike.

The sub-opcodes and the semantics of this group are specified; the placement of the operands of each form is unspecified, and the forms below name the roles.


Why it is here. The fetch-and-minimum and maximum atomics, borrowed from LoongArch's richer atomic set: each is a couple of hundred lookup tables and saves a compare-and-swap retry loop.

Cf. 7.12 (the atomic instructions), 7.3 (the atomics in detail: the reservation monitor), 7.2 (the memory model).


Status specified; **not yet implemented** in the reference executor.

XMAX

XMAX, opcode 010001, three parcels, sub-opcode 00001100 (6 bytes)



XMAX, opcode 010001, two parcels, sub-opcode 00001100 (4 bytes)





```
XMAX value, (address)
```

Mnemonic	Opcode	Sub-opcode
XMAX	010001 (0x11)	00001100 (0x0C)


Operation, flags and exceptions as for the entry XMAX above; 2 layout forms, each a chart of its own (above).

XMAXDB

XMAXDB, opcode 010001, three parcels, sub-opcode 00001101 (6 bytes)



XMAXDB, opcode 010001, two parcels, sub-opcode 00001101 (4 bytes)




Mnemonic	Opcode	Sub-opcode
XMAXDB	010001 (0x11)	00001101 (0x0D)


Operation, flags and exceptions as for the entry XMAX above; 2 layout forms, each a chart of its own (above).

XMIN

XMIN, opcode 010001, three parcels, sub-opcode 00001110 (6 bytes)



XMIN, opcode 010001, two parcels, sub-opcode 00001110 (4 bytes)





```
XMIN ..., XMAXU ..., XMINU ...
```

Mnemonic	Opcode	Sub-opcode
XMIN	010001 (0x11)	00001110 (0x0E)


Operation, flags and exceptions as for the entry XMAX above; 2 layout forms, each a chart of its own (above).

XMINDB

XMINDB, opcode 010001, three parcels, sub-opcode 00001111 (6 bytes)



XMINDB, opcode 010001, two parcels, sub-opcode 00001111 (4 bytes)




Mnemonic	Opcode	Sub-opcode
XMINDB	010001 (0x11)	00001111 (0x0F)


Operation, flags and exceptions as for the entry XMAX above; 2 layout forms, each a chart of its own (above).

XMAXU

XMAXU, opcode 010001, three parcels, sub-opcode 00010000 (6 bytes)



XMAXU, opcode 010001, two parcels, sub-opcode 00010000 (4 bytes)




Mnemonic	Opcode	Sub-opcode
XMAXU	010001 (0x11)	00010000 (0x10)


Operation, flags and exceptions as for the entry XMAX above; 2 layout forms, each a chart of its own (above).

XMAXUDB

XMAXUDB, opcode 010001, three parcels, sub-opcode 00010001 (6 bytes)



XMAXUDB, opcode 010001, two parcels, sub-opcode 00010001 (4 bytes)




Mnemonic	Opcode	Sub-opcode
XMAXUDB	010001 (0x11)	00010001 (0x11)


Operation, flags and exceptions as for the entry XMAX above; 2 layout forms, each a chart of its own (above).

XMINU

XMINU, opcode 010001, three parcels, sub-opcode 00010010 (6 bytes)



XMINU, opcode 010001, two parcels, sub-opcode 00010010 (4 bytes)




Mnemonic	Opcode	Sub-opcode
XMINU	010001 (0x11)	00010010 (0x12)


Operation, flags and exceptions as for the entry XMAX above; 2 layout forms, each a chart of its own (above).

XMINUDB

XMINUDB, opcode 010001, three parcels, sub-opcode 00010011 (6 bytes)



XMINUDB, opcode 010001, two parcels, sub-opcode 00010011 (4 bytes)



Mnemonic	Opcode	Sub-opcode
XMINUDB	010001 (0x11)	00010011 (0x13)

Operation, flags and exceptions as for the entry XMAX above; 2 layout forms, each a chart of its own (above).


LLSC: Load-linked and store-conditional

Mnemonics: LL, SC

Syntax

```
LL (address), Rd
SC value, (address), result
```

Encoding



The chart is the layout r20-atom-1, Atomics (ATOM), two parcels (len = 01): From len = 01. The placement of the operands is not specified.

Mnemonic	Opcode	Sub-opcode
LL	010001 (0x11)	00100000 (0x20)
SC	010001 (0x11)	00100001 (0x21)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-atom-1, r20-atom-2.

Operation

```
LL: Rd ← M[address] ; take a reservation on the granule containing address
SC: if the reservation is intact then M[address] ← value ; result ← 0 (success)
    else nothing is written ; result ← 1 (failure)
a write to the granule by any initiator, core or device, clears the reservation
```

Flags Not specified beyond "none for the read-modify-write forms"; SC reports success in its result register.

Exceptions Page fault, protection fault, alignment fault (the address must be naturally aligned) or bus error. The access is atomic with respect to every initiator, cores and devices alike.

A short LL/SC sequence must eventually succeed if no other initiator keeps writing the granule (the RISC-V guarantee for constrained sequences). The sub-opcodes and the semantics of this group are specified; the placement of the operands of each form is unspecified, and the forms below name the roles. The result convention shown for SC is the usual one and is unspecified.


Why it is here. Load-linked and store-conditional, with the reservation a monitor, because a monitor maps onto the exclusive access of AXI and of FPGA and modern memory systems, where the Unibus's locked read-modify-write (DATIP/DATO) does not scale as cores multiply. A short sequence must eventually succeed if no other initiator keeps writing the granule, the RISC-V rule.

Cf. 7.12 (the atomic instructions), 7.3 (the atomics in detail: the reservation monitor), 7.2 (the memory model).


Status specified; **not yet implemented** in the reference executor.

LL

LL, opcode 010001, three parcels, sub-opcode 00100000 (6 bytes)



LL, opcode 010001, two parcels, sub-opcode 00100000 (4 bytes)





```
LL (address), Rd
```

Mnemonic	Opcode	Sub-opcode
LL	010001 (0x11)	00100000 (0x20)


Operation, flags and exceptions as for the entry LLSC above; 2 layout forms, each a chart of its own (above).

SC

SC, opcode 010001, three parcels, sub-opcode 00100001 (6 bytes)



SC, opcode 010001, two parcels, sub-opcode 00100001 (4 bytes)




```
SC value, (address), result
```

Mnemonic	Opcode	Sub-opcode
SC	010001 (0x11)	00100001 (0x21)

Operation, flags and exceptions as for the entry LLSC above; 2 layout forms, each a chart of its own (above).

9.14 System instructions, exceptions and interrupts

Cf. chapter 6, section 6.13 (system instructions, exceptions and interrupts), section 6.3 (exceptions and interrupts) and section 6.5 (system registers).

9.14.1 The system escape SYS (opcode 010100 (0x14)) holds the privileged and system instructions: TRAP, TRAPL, RTI, RTT, RET, HALT, BPT, MTPS, MFPS, SPL, MFSR, MTSR, MTDP, MFDP, MFCPUID, PROBER, PROBEW, PUSHX, POPX, and the translation and cache maintenance instructions (TLBI, TLBIA, TLBSYNC, MTASID, MFASID, ICINV, ICINVA). The user-memory guard instructions STUA and CLUA are described with them. *(opcode 010100 (0x14))*

Commentary. The official entry of each instruction is below, in this section; the kernel chapter gives the modes, the entry sequence, the system registers and the reasons. **Impact.** *Kernel:* the entries below are the complete list of what the kernel may execute that user code may not, and of what both may; chapter 6 explains how they are used. *Compiler:* none, apart from TRAP in system-call stubs. *Hardware:* a class decode and one privilege check.


NOP: No operation and landing pad

Mnemonics: NOP, LPAD

Syntax

```
NOP
LPAD
```

Encoding



The chart is the layout `r20-sysn-0`, System, no operand, one parcel (`len = 00`): The `reg` field is the class (0); class 0 takes a minor opcode from `low`.

Mnemonic	Opcode	reg	low
NOP	010100 (0x14)	0000 (0x0)	0000 (0x0)
LPAD	010100 (0x14)	0000 (0x0)	1001 (0x9)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sysn-0`, `r20-sysn-1`, `r20-sysn-2`.

Operation

```
nothing
```

Flags None written.

Exceptions None.

`LPAD` marks a legal target of an indirect jump or call; no instruction enforces it in ABI version 1.


Why it is here. `NOP` is common and has no story; `LPAD` is the landing pad. Landing pads mark the legal targets of indirect jumps and calls so that jump-oriented attacks can be stopped at the transfer, as Intel's indirect-branch tracking and ARM's branch target identification do and OpenBSD enforces. ABI version 1 leaves them off (an open item of the instruction set, 9.21), and the assembler provides `.lpad`; the kernel pain-points and mitigations reports record why deciding later is more expensive (appendix A, section A.1).

Cf. Appendix A, section A.1 (landing pads).


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

NOP


NOP, opcode 010100, three parcels (6 bytes)



NOP, opcode 010100, two parcels (4 bytes)



NOP, opcode 010100, one parcel (2 bytes)





```
NOP
```

Mnemonic	Opcode	reg	low
NOP	010100 (0x14)	0000 (0x0)	0000 (0x0)


Operation, flags and exceptions as for the entry NOP above; 3 layout forms, each a chart of its own (above).

LPAD

LPAD, opcode 010100, three parcels (6 bytes)



LPAD, opcode 010100, two parcels (4 bytes)



LPAD, opcode 010100, one parcel (2 bytes)




```
LPAD
```

Mnemonic	Opcode	reg	low
LPAD	010100 (0x14)	0000 (0x0)	1001 (0x9)

Operation, flags and exceptions as for the entry NOP above; 3 layout forms, each a chart of its own (above).


RTI: Return from interrupt or exception

Mnemonics: `RTI`, `RTT`

Syntax

```
RTI
RTT
```

Encoding



The chart is the layout `r20-sysn-0`, System, no operand, one parcel (`len = 00`): The `reg` field is the class (0); class 0 takes a minor opcode from `low`.

Mnemonic	Opcode	reg	low
RTI	010100 (0x14)	0000 (0x0)	0001 (0x1)
RTT	010100 (0x14)	0000 (0x0)	0010 (0x2)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sysn-0`, `r20-sysn-1`, `r20-sysn-2`.

Operation

```
PC ← EPC ; PSW ← EPSW           ; a PSW with the reserved mode 2 in either mode field aborts
RTT: and then set the trace bit T after the return
```

Flags Replaced by `EPSW`, including the flags.

Exceptions Privileged: outside kernel mode the instruction aborts with the privileged-instruction vector.

`RTT` sets the trace bit *after* the return rather than before, which is what lets a debugger single-step out of its own trap handler.


Why it is here. `RTT` looks redundant against `RTI`, and stays: it sets the trace bit *after* the return rather than before, which is what lets a debugger single-step out of its own trap handler.

Cf. 6.3 (exceptions and interrupts), 6.13.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

RTI


RTI, opcode 010100, three parcels (6 bytes)



RTI, opcode 010100, two parcels (4 bytes)



RTI, opcode 010100, one parcel (2 bytes)





```
RTI
```

Mnemonic	Opcode	reg	low
RTI	010100 (0x14)	0000 (0x0)	0001 (0x1)


Operation, flags and exceptions as for the entry RTI above; 3 layout forms, each a chart of its own (above).

RTT

RTT, opcode 010100, three parcels (6 bytes)



RTT, opcode 010100, two parcels (4 bytes)



RTT, opcode 010100, one parcel (2 bytes)





```
RTT
```

Mnemonic	Opcode	reg	low
RTT	010100 (0x14)	0000 (0x0)	0010 (0x2)


Operation, flags and exceptions as for the entry RTI above; 3 layout forms, each a chart of its own (above).

RET: Return from subroutine


RET, opcode 010100, three parcels (6 bytes)



RET, opcode 010100, two parcels (4 bytes)



RET, opcode 010100, one parcel (2 bytes)



Mnemonics: `RET`

Syntax

```
RET
```

Encoding



The chart is the layout `r20-sysn-0`, System, no operand, one parcel (`len = 00`): The `reg` field is the class (0); class 0 takes a minor opcode from `low`.

Mnemonic	Opcode	reg	low
RET	010100 (0x14)	0000 (0x0)	0011 (0x3)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sysn-0`, `r20-sysn-1`, `r20-sysn-2`.

Operation

```
PC ← M[SP] ; SP ← SP + 8
```

Flags None written.


Exceptions Memory operand: page fault, protection fault, alignment fault or bus error (a read of non-existent memory is a precise abort with cause `BUSFAULT`). Every such fault is precise and the instruction restarts after it, because the register update of an auto-increment or auto-decrement mode is held until the instruction retires.

Not privileged, though it is in the system escape: it is the two-byte partner of `CALL`.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

HALT: Halt the processor


HALT, opcode 010100, three parcels (6 bytes)



HALT, opcode 010100, two parcels (4 bytes)



HALT, opcode 010100, one parcel (2 bytes)




Mnemonics: `HALT`

Syntax

```
HALT
```

Encoding



The chart is the layout `r20-sysn-0`, System, no operand, one parcel (`len = 00`): The `reg` field is the class (0); class 0 takes a minor opcode from `low`.

Mnemonic	Opcode	reg	low
HALT	010100 (0x14)	0000 (0x0)	0100 (0x4)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sysn-0`, `r20-sysn-1`, `r20-sysn-2`.


Operation

```
stop the processor
```


Flags None written.
Exceptions Privileged: outside kernel mode the instruction aborts with the privileged-instruction vector.
Cf. 6.12.
Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

BPT: Breakpoint


BPT, opcode 010100, three parcels (6 bytes)



BPT, opcode 010100, two parcels (4 bytes)



BPT, opcode 010100, one parcel (2 bytes)



Mnemonics: `BPT`

Syntax

```
BPT
```

Encoding



The chart is the layout `r20-sysn-0`, System, no operand, one parcel (`len = 00`): The `reg` field is the class (0); class 0 takes a minor opcode from `low`.

Mnemonic	Opcode	reg	low
BPT	010100 (0x14)	0000 (0x0)	0101 (0x5)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sysn-0`, `r20-sysn-1`, `r20-sysn-2`.

Operation

```
take the breakpoint vector with EPC = the address of the next instruction
```

Flags None written.

Exceptions Enters the kernel by the `BPT` vector.

A trap like any other, but kept as its own two-byte instruction because a debugger patches it over an existing instruction, so it must be the shortest instruction the machine has.


Why it is here. `BPT` is a trap vector, but a debugger patches it over an existing instruction, so it must be the shortest instruction the machine has; that is why it is kept although `IOT` and `EMT` are not.

Cf. 6.3.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

FENCE: Memory fence


FENCE, opcode 010100, three parcels (6 bytes)



FENCE, opcode 010100, two parcels (4 bytes)



FENCE, opcode 010100, one parcel (2 bytes)




Mnemonics: `FENCE`

Syntax

```
FENCE
```

Encoding



The chart is the layout `r20-sysn-0`, System, no operand, one parcel (`len = 00`): The `reg` field is the class (0); class 0 takes a minor opcode from `low`.

Mnemonic	Opcode	reg	low
FENCE	010100 (0x14)	0000 (0x0)	0110 (0x6)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sysn-0`, `r20-sysn-1`, `r20-sysn-2`.

Operation

```
order the memory accesses before it against those after it, for every initiator that observes them
```

Flags None written.

Exceptions None.

Owed to devices (one `FENCE` separates writing a device's registers from setting its go bit) and to other cores.


Why it is here. The memory model is sequentially consistent, so `FENCE` is needed only for what is outside the model: devices and the framebuffer (one `FENCE` between writing a device's registers and setting its go bit, section 3.15) and instruction streams. The `_DB` barrier forms of the atomics exist so that a `FENCE` is not needed in a lock acquire.

Cf. 7.2 (the memory model), 2.2 (what the processor owes the bus).


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

WFE: Wait for an event


WFE, opcode 010100, three parcels (6 bytes)



WFE, opcode 010100, two parcels (4 bytes)



WFE, opcode 010100, one parcel (2 bytes)




Mnemonics: `WFE` (aliases: `WAIT`)

Syntax

```
WFE
```

Encoding



The chart is the layout `r20-sysn-0`, System, no operand, one parcel (`len = 00`): The `reg` field is the class (0); class 0 takes a minor opcode from `low`.

Mnemonic	Opcode	`reg`	`low`
`WFE`	`010100 (0x14)`	`0000 (0x0)`	`0111 (0x7)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sysn-0`, `r20-sysn-1`, `r20-sysn-2`.

Operation

```
sleep until an interrupt is pending or another core executes SEV
```

Flags None written.


Exceptions Privileged: outside kernel mode the instruction aborts with the privileged-instruction vector.

`WAIT` is an assembler alias. Whether `WFE` wakes on a pending but masked interrupt (the idle-loop question) is open.


Why it is here. `WAIT` was a PDP-11 instruction (sleep until an interrupt); `WFE` subsumes it: it sleeps until an interrupt or another core's `SEV`, and on a uniprocessor it behaves exactly as `WAIT` did. `WFE` and `SEV` belong to the multiprocessor operations (7.6). The wake rule (whether a pending but masked interrupt wakes it) is open item P1.
Cf. 7.6 (waiting and signalling).
Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).
`WAIT` is an alias of `WFE`: the assembler writes it as that word.

SEV: Send an event


SEV, opcode 010100, three parcels (6 bytes)



SEV, opcode 010100, two parcels (4 bytes)



SEV, opcode 010100, one parcel (2 bytes)




Mnemonics: `SEV`

Syntax

```
SEV
```

Encoding



The chart is the layout `r20-sysn-0`, System, no operand, one parcel (`len = 00`): The `reg` field is the class (0); class 0 takes a minor opcode from `low`.

Mnemonic	Opcode	reg	low
SEV	010100 (0x14)	0000 (0x0)	1000 (0x8)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sysn-0`, `r20-sysn-1`, `r20-sysn-2`.

Operation

```
wake every core waiting in WFE
```

Flags None written.

Exceptions None.

Why it is here. The signalling half of `WFE`, so that a core waiting for a lock can sleep instead of spinning and be woken by the core that releases it.

Cf. 7.6.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

TLBA: Invalidate all translations; wait for translation invalidations; invalidate the whole instruction cache

Mnemonics: `TLBIA`, `TLBSYNC`, `ICINVA`

Syntax

```
TLBIA
TLBSYNC
ICINVA
```

Encoding



The chart is the layout `r20-sysn-0`, System, no operand, one parcel (`len = 00`): The `reg` field is the class (0); class 0 takes a minor opcode from `low`.

Mnemonic	Opcode	`reg`	`low`
`TLBIA`	`010100 (0x14)`	`0000 (0x0)`	`1010 (0xA)`
`TLBSYNC`	`010100 (0x14)`	`0000 (0x0)`	`1011 (0xB)`
`ICINVA`	`010100 (0x14)`	`0000 (0x0)`	`1100 (0xC)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sysn-0`, `r20-sysn-1`, `r20-sysn-2`.

Operation

```
TLBIA   : invalidate every translation-buffer entry on this core and, by broadcast, on the others
TLBSYNC : wait until the invalidations this core started have completed on every core
ICINVA  : invalidate the whole instruction cache
```

Flags None written.

Exceptions Privileged (`TLBIA`, `TLBSYNC`); the reference executor treats `ICINVA` as a no-op.


Why it is here. `TLBI` and `TLBIA` broadcast, `TLBSYNC` waits for the other cores, and `ICINV` and `ICINVA` invalidate the instruction cache: a Lisp runtime that compiles a function cannot work without an instruction-cache invalidate.

Cf. 7.5 (translation and instruction-cache coherence).


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

TLBIA

TLBIA, opcode 010100, three parcels (6 bytes)



TLBIA, opcode 010100, two parcels (4 bytes)



TLBIA, opcode 010100, one parcel (2 bytes)





```
TLBIA
```

Mnemonic	Opcode	reg	low
TLBIA	010100 (0x14)	0000 (0x0)	1010 (0xA)


Operation, flags and exceptions as for the entry TLBA above; 3 layout forms, each a chart of its own (above).

TLBSYNC


TLBSYNC, opcode 010100, three parcels (6 bytes)



TLBSYNC, opcode 010100, two parcels (4 bytes)



TLBSYNC, opcode 010100, one parcel (2 bytes)





```
TLBSYNC
```

Mnemonic	Opcode	reg	low
TLBSYNC	010100 (0x14)	0000 (0x0)	1011 (0xB)


Operation, flags and exceptions as for the entry TLBA above; 3 layout forms, each a chart of its own (above).

ICINVA

ICINVA, opcode 010100, three parcels (6 bytes)



ICINVA, opcode 010100, two parcels (4 bytes)



ICINVA, opcode 010100, one parcel (2 bytes)




```
ICINVA
```

Mnemonic	Opcode	reg	low
ICINVA	010100 (0x14)	0000 (0x0)	1100 (0xC)

Operation, flags and exceptions as for the entry TLBA above; 3 layout forms, each a chart of its own (above).


PUSHX: Push and pop the exception state

Mnemonics: PUSHX, POPX

Syntax

```
PUSHX
POPX
```

Encoding



The chart is the layout r20-sysx-0, System, SYSX, one parcel (len = 00): Class 0, minor 15: the sub-opcode is in parcel 1.

Mnemonic	Opcode	reg	low	Sub-opcode
PUSHX	010100 (0x14)	0000 (0x0)	1111 (0xF)	00000000 (0x00)
POPX	010100 (0x14)	0000 (0x0)	1111 (0xF)	00000001 (0x01)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-sysx-0, r20-sysx-1.

Operation

```
PUSHX: SP ← SP - 16 ; M[SP] ← EPSW ; M[SP + 8] ← EPC
POPX : EPSW ← M[SP] ; EPC ← M[SP + 8] ; SP ← SP + 16
```

Flags None written.

Exceptions Privileged: outside kernel mode the instruction aborts with the privileged-instruction vector. SP must be 8-byte aligned (a misaligned-access abort); both words are checked before either is touched.

Four bytes (the SYSX escape, sub-opcodes 0 and 1) and two bytes on page 2. For a handler that wants to be interrupted: it can save the exception state and lower the priority.


Why it is here. A handler that can be interrupted must save EPC and EPSW before it lowers the priority; with only MFSR that costs two moves and two stores (sixteen bytes) on every such kernel entry, and the same to restore. The instructions may not show up high in the instruction count, but they save bytes and cycles in a tight, very often used kernel loop. Page 2 has the two-byte forms.

Cf. 6.3, 6.13.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

PUSHX

PUSHX, opcode 010100, two parcels, sub-opcode 00000000 (4 bytes)



PUSHX, opcode 010100, one parcel, sub-opcode 00000000 (2 bytes)





```
PUSHX
```

Mnemonic	Opcode	reg	low	Sub-opcode
PUSHX	010100 (0x14)	0000 (0x0)	1111 (0xF)	00000000 (0x00)

Operation, flags and exceptions as for the entry PUSHX above; 2 layout forms, each a chart of its own (above).

POPX

POPX, opcode 010100, two parcels, sub-opcode 00000001 (4 bytes)



POPX, opcode 010100, one parcel, sub-opcode 00000001 (2 bytes)





```
POPX
```

Mnemonic	Opcode	reg	low	Sub-opcode
POPX	010100 (0x14)	0000 (0x0)	1111 (0xF)	00000001 (0x01)


Operation, flags and exceptions as for the entry PUSHX above; 2 layout forms, each a chart of its own (above).

ISYNC: Instruction synchronisation

ISYNC, opcode 010100, two parcels, sub-opcode 00000010 (4 bytes)



ISYNC, opcode 010100, one parcel, sub-opcode 00000010 (2 bytes)




Mnemonics: `ISYNC`

Syntax

```
ISYNC
```

Encoding



The chart is the layout `r20-sysx-0`, System, SYSX, one parcel (`len = 00`): Class 0, minor 15: the sub-opcode is in parcel 1.

Mnemonic	Opcode	reg	low	Sub-opcode
ISYNC	010100 (0x14)	0000 (0x0)	1111 (0xF)	00000010 (0x02)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sysx-0`, `r20-sysx-1`.

Operation

```
make earlier writes to PTBR, ASID, MMUCTL and VBR, and earlier ICINVs, take effect for the instructions that
follow
```

Flags None written.

Exceptions Privileged: outside kernel mode the instruction aborts with the privileged-instruction vector. A non-zero pad byte is an illegal instruction.

The architecture promises the effect only after the next `ISYNC`; an in-order implementation may make it immediate, and software must not rely on that.


Why it is here. Taken from the out-of-order readiness review: it makes earlier writes to `PTBR`, `ASID`, `MMUCTL` and `VBR` take effect for what follows, so an in-order machine may make them immediate and a speculative one has a place to serialise. It serves the aim that the architecture is efficient on both in-order and out-of-order cores (1.4.4).

Cf. 7.5, 6.5.


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

HINT: Hint

HINT, opcode 010100, two parcels, sub-opcode 00000011 (4 bytes)



HINT, opcode 010100, one parcel, sub-opcode 00000011 (2 bytes)




Mnemonics: `HINT`

Syntax

```
HINT #n        ; n = 0 to 255
```

Encoding



The chart is the layout `r20-sysx-0`, System, SYSX, one parcel (`len = 00`): Class 0, minor 15: the sub-opcode is in parcel 1.

Mnemonic	Opcode	reg	low	Sub-opcode
HINT	010100 (0x14)	0000 (0x0)	1111 (0xF)	00000011 (0x03)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sysx-0`, `r20-sysx-1`.

Operation

```
no architectural effect
```

Flags None written.

Exceptions None.

Defined codes: 0 a plain no-op hint, 1 pause (spin-wait), 2 speculation barrier. Every other code is a reserved hint that executes as a no-op; software shall not use it. Not privileged.

Why it is here. Defined with ISYNC: a no-op with a byte of code, defined for `0` (plain), `1` (pause, for spin-wait loops) and `2` (speculation barrier), every other code a reserved hint that executes as a no-op so that a later machine can give it a meaning without breaking an old binary.

Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


MFSR: Move from and to a system register

Mnemonics: MFSR, MTSR

Syntax

```
MFSR Rd, name
MTSR name, Rs
```

Encoding



The chart is the layout `r20-sysreg-0`, System registers (MFSR, MTSR), one parcel (`len = 00`): Class 0: the system register number is in parcel 1.

Mnemonic	Opcode	reg	low
MFSR	010100 (0x14)	0000 (0x0)	1101 (0xD)
MTSR	010100 (0x14)	0000 (0x0)	1110 (0xE)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sysreg-0`, `r20-sysreg-1`.

Operation

```
MFSR: Rd ← system register `name`
MTSR: system register `name` ← Rs        ; read-only registers are an illegal instruction
```

Flags None written.

Exceptions Privileged: outside kernel mode the instruction aborts with the privileged-instruction vector. An unassigned system register is an illegal instruction.

The register is chosen by name (a number in parcel 1); the instruction is four bytes. A write to PTBR, ASID or MMUCTL flushes the translation buffer.

Name	Number	Access
PTBR	0	read and write
EPC	1	read and write
EVA	2	read only
ECAUSE	3	read only
DMW0	4	read and write
DMW1	5	read and write
USP	6	read and write
SSP	7	read and write
EPSW	8	read and write

Name	Number	Access
VBR	9	read and write
MMUCTL	10	read and write
ASID	11	read and write
CPUID	12	read only


Why it is here. A paging operating system must install a page table and learn why it was entered, which needs instructions to write PTBR and read EPC, EVA and ECAUSE. One general pair reaches all of the system registers by number. The user and supervisor stack pointers are in the set because any kernel must read and write the user stack pointer to build a signal frame, copy a process or switch context.

Cf. 6.5 (system registers).


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

MFSR

MFSR, opcode 010100, two parcels (4 bytes)



MFSR, opcode 010100, one parcel (2 bytes)





```
MFSR Rd, name
```

Mnemonic	Opcode	reg	low
MFSR	010100 (0x14)	0000 (0x0)	1101 (0xD)


Operation, flags and exceptions as for the entry MFSR above; 2 layout forms, each a chart of its own (above).

MTSR

MTSR, opcode 010100, two parcels (4 bytes)



MTSR, opcode 010100, one parcel (2 bytes)




```
MTSR name, Rs
```

Mnemonic	Opcode	reg	low
MTSR	010100 (0x14)	0000 (0x0)	1110 (0xE)

Operation, flags and exceptions as for the entry MFSR above; 2 layout forms, each a chart of its own (above).


MTPS: Move to and from the processor status word

Mnemonics: MTPS, MFPS

Syntax

```
MTPS Rs
MFPS Rd
```

Encoding



The chart is the layout r20-sys-0, System, one parcel (len = 00): The reg field is the class; the other classes take a register or a 4-bit immediate from low.

Mnemonic	Opcode	reg
MTPS	010100 (0x14)	0001 (0x1)
MFPS	010100 (0x14)	0010 (0x2)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-sys-0, r20-sys-1, r20-sys-2.

Operation

```
MTPS: PSW ← Rs          ; in user mode only the flags N Z V C are written
MFPS: Rd ← PSW
```

Flags MTPS writes the flags from Rs; MFPS writes none.


Exceptions A MTPS value with the reserved mode 2 in a mode field aborts.

Cf. 6.2 (modes and the status word).


Status implemented in the reference executor (common/pdp64exec.c, shared by sim64 and QEMU).

MTPS


MTPS, opcode 010100, three parcels (6 bytes)



MTPS, opcode 010100, two parcels (4 bytes)



MTPS, opcode 010100, one parcel (2 bytes)





```
MTPS Rs
```

Mnemonic	Opcode	reg
MTPS	010100 (0x14)	0001 (0x1)


Operation, flags and exceptions as for the entry MTPS above; 3 layout forms, each a chart of its own (above).

MFPS

MFPS, opcode 010100, three parcels (6 bytes)



MFPS, opcode 010100, two parcels (4 bytes)



MFPS, opcode 010100, one parcel (2 bytes)





```
MFPS Rd
```

Mnemonic	Opcode	reg
MFPS	010100 (0x14)	0010 (0x2)


Operation, flags and exceptions as for the entry MTPS above; 3 layout forms, each a chart of its own (above).

SPL: Set the interrupt priority level


SPL, opcode 010100, three parcels (6 bytes)



SPL, opcode 010100, two parcels (4 bytes)



SPL, opcode 010100, one parcel (2 bytes)




Mnemonics: `SPL`

Syntax

```
SPL #n        ; n = 0 to 7
```

Encoding



The chart is the layout `r20-sys-0`, System, one parcel (`len = 00`): The `reg` field is the class; the other classes take a register or a 4-bit immediate from `low`.

Mnemonic	Opcode	`reg`
`SPL`	`010100 (0x14)`	`0011 (0x3)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sys-0`, `r20-sys-1`, `r20-sys-2`.

Operation

```
PSW.priority ← n
```

Flags None written. The condition flags are untouched.

Exceptions Privileged: outside kernel mode the instruction aborts with the privileged-instruction vector. A priority above 7 is an illegal instruction.

Kept despite MTPS writing the whole word because it sets the priority alone: a kernel raising priority around a critical section must not clobber the flags.

Why it is here. SPL stays although MTPS writes the whole status word: it sets the priority alone, leaving the condition codes untouched, so a kernel raising priority around a critical section does not clobber flags. It is the PDP-11 instruction of the same name.

Cf. 6.3.

Status implemented in the reference executor (common/pdp64exec.c, shared by sim64 and QEMU).


TRAP: System call and trap

Mnemonics: TRAP, TRAPL

Syntax

```
TRAP #n        ; n = 0 to 15, two bytes
TRAPL #n       ; n = 0 to 255, four bytes
```

Encoding



The chart is the layout r20-sys-0, System, one parcel (len = 00): The reg field is the class; the other classes take a register or a 4-bit immediate from low.

Mnemonic	Opcode	reg
TRAP	010100 (0x14)	0100 (0x4)
TRAPL	010100 (0x14)	1111 (0xF)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-sys-0, r20-sys-1, r20-sys-2, r20-sys-1-3.

Operation

```
enter the kernel by vector (TRAP_BASE + n), with EPC = the address of the next instruction
```

Flags None written.

Exceptions Enters the kernel; not privileged.

The replacement for the PDP-11 IOT and EMT. TRAPL reaches the vectors 0 to 255 with n in the high byte of parcel 1.


Why it is here. TRAPL exists so that the vector range of 256 and the two-byte common case can both be kept: TRAP #n for n below 16 is two bytes and the long form reaches 256. IOT and EMT, which were TRAP at two particular vectors on the PDP-11, are not provided.

Cf. 6.3, 6.10 (system calls).


Status implemented in the reference executor (common/pdp64exec.c, shared by sim64 and QEMU).

TRAP


TRAP, opcode 010100, three parcels (6 bytes)



TRAP, opcode 010100, two parcels (4 bytes)



TRAP, opcode 010100, one parcel (2 bytes)





```
TRAP #n
```

Mnemonic	Opcode	reg
TRAP	010100 (0x14)	0100 (0x4)


Operation, flags and exceptions as for the entry TRAP above; 3 layout forms, each a chart of its own (above).

TRAPL

TRAPL, opcode 010100, three parcels (6 bytes)



TRAPL, opcode 010100, two parcels (4 bytes)



TRAPL, opcode 010100, one parcel (2 bytes)





```
TRAPL #n
```

Mnemonic	Opcode	reg
TRAPL	010100 (0x14)	1111 (0xF)


Operation, flags and exceptions as for the entry TRAP above; 3 layout forms, each a chart of its own (above).

TLBI: Invalidate a translation


TLBI, opcode 010100, three parcels (6 bytes)



TLBI, opcode 010100, two parcels (4 bytes)



TLBI, opcode 010100, one parcel (2 bytes)




Mnemonics: `TLBI`

Syntax

```
TLBI Rs
```

Encoding



The chart is the layout `r20-sys-0`, System, one parcel (`len = 00`): The `reg` field is the class; the other classes take a register or a 4-bit immediate from `low`.

Mnemonic	Opcode	`reg`
`TLBI`	`010100 (0x14)`	`0101 (0x5)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sys-0`, `r20-sys-1`, `r20-sys-2`.

Operation

```
invalidate the translation-buffer entry for the page containing the address in Rs, on this core and by
broadcast on the others
```

Flags None written.
Exceptions Privileged: outside kernel mode the instruction aborts with the privileged-instruction vector.

Why it is here. It broadcasts: a translation changed by one core must be invalidated on all of them, and `TLBSYNC` waits for it.
Cf. 7.5, 6.8.
Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).


MTASID: Move to and from the address-space identifier

Mnemonics: `MTASID`, `MFASID`

Syntax

```
MTASID Rs
MFASID Rd
```

Encoding



The chart is the layout `r20-sys-0`, System, one parcel (`len = 00`): The `reg` field is the class; the other classes take a register or a 4-bit immediate from `low`.

Mnemonic	Opcode	`reg`
`MTASID`	`010100 (0x14)`	`0110 (0x6)`
`MFASID`	`010100 (0x14)`	`0111 (0x7)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sys-0`, `r20-sys-1`, `r20-sys-2`.


Operation

```
MTASID: ASID ← Rs[15:0]          ; the translation buffer is flushed in the reference executor
MFASID: Rd ← ASID
```


Flags None written.
Exceptions Privileged: outside kernel mode the instruction aborts with the privileged-instruction vector.
The `ASID` tags translation-buffer entries so a context switch is one store.
Why it is here. The `ASID` tags translation-buffer entries so a context switch is one store and no flush. No further reason is recorded.
Cf. 6.8.
Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

MTASID


MTASID, opcode 010100, three parcels (6 bytes)



MTASID, opcode 010100, two parcels (4 bytes)



MTASID, opcode 010100, one parcel (2 bytes)





```
MTASID Rs
```

Mnemonic	Opcode	reg
MTASID	010100 (0x14)	0110 (0x6)


Operation, flags and exceptions as for the entry MTASID above; 3 layout forms, each a chart of its own (above).

MFASID


MFASID, opcode 010100, three parcels (6 bytes)



MFASID, opcode 010100, two parcels (4 bytes)



MFASID, opcode 010100, one parcel (2 bytes)




```
MFASID Rd
```

Mnemonic	Opcode	reg
MFASID	010100 (0x14)	0111 (0x7)

Operation, flags and exceptions as for the entry MTASID above; 3 layout forms, each a chart of its own (above).


MTDP: Move to and from the direct pointer

Mnemonics: `MTDP`, `MFDP`

Syntax

```
MTDP Rs
MFDP Rd
```

Encoding



The chart is the layout `r20-sys-0`, System, one parcel (`len = 00`): The `reg` field is the class; the other classes take a register or a 4-bit immediate from `low`.

Mnemonic	Opcode	reg
MTDP	010100 (0x14)	1000 (0x8)
MFDP	010100 (0x14)	1001 (0x9)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sys-0`, `r20-sys-1`, `r20-sys-2`.

Operation

```
MTDP: DP ← Rs
MFDP: Rd ← DP
```

Flags None written.

Exceptions None.

`DP` is the thread pointer in user mode and the per-CPU pointer in kernel mode; there is one copy per mode.


Why it is here. `DP` descends from the 6502's zero page and is kept for code density (a 12-bit displacement in four bytes); it is also the thread pointer in user mode and, in kernel mode, the per-CPU pointer that an SMP kernel wants (7.4). `MTDP` and `MFDP` read and write the current mode's copy.

Cf. 7.4 (per-CPU state).


Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

MTDP


MTDP, opcode 010100, three parcels (6 bytes)



MTDP, opcode 010100, two parcels (4 bytes)



MTDP, opcode 010100, one parcel (2 bytes)





```
MTDP Rs
```

Mnemonic	Opcode	reg
MTDP	010100 (0x14)	1000 (0x8)


Operation, flags and exceptions as for the entry MTDP above; 3 layout forms, each a chart of its own (above).

MFDP

MFDP, opcode 010100, three parcels (6 bytes)



MFDP, opcode 010100, two parcels (4 bytes)



MFDP, opcode 010100, one parcel (2 bytes)





```
MFDP Rd
```

Mnemonic	Opcode	reg
MFDP	010100 (0x14)	1001 (0x9)


Operation, flags and exceptions as for the entry MTDP above; 3 layout forms, each a chart of its own (above).

MTDMW: Move to a direct-mapping window


MTDMW, opcode 010100, three parcels (6 bytes)



MTDMW, opcode 010100, two parcels (4 bytes)



MTDMW, opcode 010100, one parcel (2 bytes)




Mnemonics: `MTDMW`

Syntax

```
MTDMW Rs
```

Encoding



The chart is the layout `r20-sys-0`, System, one parcel (`len = 00`): The `reg` field is the class; the other classes take a register or a 4-bit immediate from `low`.

Mnemonic	Opcode	`reg`
`MTDMW`	`010100 (0x14)`	`1010 (0xA)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sys-0`, `r20-sys-1`, `r20-sys-2`.

Operation

```
DMW0 ← Rs          ; storage only: the operand names no window and the format of the windows is unspecified
```

Flags None written.


Exceptions Privileged: outside kernel mode the instruction aborts with the privileged-instruction vector.

The direct-mapping windows have no defined format.


Why it is here. Taken from LoongArch's direct-mapping windows, which stop the kernel taking translation-buffer misses on its own text. The windows are deferred: the instruction is storage only.
Cf. 6.9.
Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

MFCPUID: Read the processor identifier


MFCPUID, opcode 010100, three parcels (6 bytes)



MFCPUID, opcode 010100, two parcels (4 bytes)



MFCPUID, opcode 010100, one parcel (2 bytes)




Mnemonics: `MFCPUID`

Syntax

```
MFCPUID Rd
```

Encoding



The chart is the layout `r20-sys-0`, System, one parcel (`len = 00`): The `reg` field is the class; the other classes take a register or a 4-bit immediate from `low`.

Mnemonic	Opcode	`reg`
`MFCPUID`	`010100 (0x14)`	`1011 (0xB)`

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): `r20-sys-0`, `r20-sys-1`, `r20-sys-2`.


Operation

```
Rd ← CPUID
```


Flags None written.
Exceptions None.
The index of this core, for per-CPU data.
Why it is here. Part of the multiprocessor operations, because per-CPU data needs each core to know which one it is.
Cf. 7.4, 7.8.
Status implemented in the reference executor (`common/pdp64exec.c`, shared by `sim64` and QEMU).

ICINV: Invalidate the instruction cache for an address


ICINV, opcode 010100, three parcels (6 bytes)



ICINV, opcode 010100, two parcels (4 bytes)



ICINV, opcode 010100, one parcel (2 bytes)




Mnemonics: `ICINV`

Syntax

```
ICINV Rs
```

Encoding



The chart is the layout `r20-sys-0`, System, one parcel (`len = 00`): The `reg` field is the class; the other classes take a register or a 4-bit immediate from `low`.

Mnemonic	Opcode	reg
ICINV	010100 (0x14)	1100 (0xC)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-sys-0, r20-sys-1, r20-sys-2.

Operation

```
invalidate the instruction-cache line containing the address in Rs
```

Flags None written.

Exceptions The reference executor treats it as a no-op; privilege as for the other cache-maintenance instructions.

Why it is here. Instruction-cache invalidation, by address (ICINV) and whole (ICINVA). The reason is the one given for TLBA: a runtime that compiles a function cannot work without it.

Cf. 7.5.

Status implemented in the reference executor (common/pdp64exec.c, shared by sim64 and QEMU).


PROBE: Probe an address for read or write access

Mnemonics: PROBER, PROBEW

Syntax

```
PROBER Rd, Rs
PROBEW Rd, Rs
```

Encoding



The chart is the layout r20-sys-0, System, one parcel (len = 00): The reg field is the class; the other classes take a register or a 4-bit immediate from low.

Mnemonic	Opcode	reg
PROBER	010100 (0x14)	1101 (0xD)
PROBEW	010100 (0x14)	1110 (0xE)

All the layouts of this entry (a chart for each, with its fields and the sub-opcode of each mnemonic, in the bit layouts of every opcode): r20-sys-0, r20-sys-1-2, r20-sys-2.

Operation

```
Rd ← 1 if the address in Rs is readable (PROBER) or writable (PROBEW) in the previous mode, else 0
no fault is taken
```

Flags None written.

Exceptions Privileged: outside kernel mode the instruction aborts with the privileged-instruction vector.

Taken from the VAX PROBER and PROBEW: the kernel validates a user address before using it.


Why it is here. Taken from the VAX PROBER and PROBEW: the kernel validates a user address before using it, and it replaces the nofault global of the V7 kernel for the address-validation case.

Cf. 6.10 (the user-memory guard), 6.6.


Status implemented in the reference executor (common/pdp64exec.c, shared by sim64 and QEMU).

PROBER

PROBER, opcode 010100, three parcels (6 bytes)



PROBER, opcode 010100, two parcels (4 bytes)



PROBER, opcode 010100, one parcel (2 bytes)





```
PROBER Rd, Rs
```

Mnemonic	Opcode	reg
PROBER	010100 (0x14)	1101 (0xD)


Operation, flags and exceptions as for the entry PROBE above; 3 layout forms, each a chart of its own (above).

PROBEW

PROBEW, opcode 010100, three parcels (6 bytes)



PROBEW, opcode 010100, two parcels (4 bytes)



PROBEW, opcode 010100, one parcel (2 bytes)




```
PROBEW Rd, Rs
```

Mnemonic	Opcode	reg
PROBEW	010100 (0x14)	1110 (0xE)

Operation, flags and exceptions as for the entry PROBE above; 3 layout forms, each a chart of its own (above).

9.15 Faults, restart and memory management

Cf. chapter 6, section 6.4 (faults and restart) and sections 6.6 to 6.9 (memory management).

9.15.1 A fault is a trap, an abort, a progress stop in a block operation or a machine check, and every instruction either completes or is annulled and restarted with no state to undo (MCPY and its kin keep their progress in registers); the page-table format, the memory types and the translation registers are in the kernel chapter. *(D)*

Commentary. The instruction-set consequence is the restart rule: the register update of an auto-increment mode is held until the instruction retires. **Impact.** *Kernel:* see 6.4. *Compiler:* no scheduling restriction arises from faults. *Hardware:* a single-entry undo buffer and a read-only walker.

9.16 Position-independent code

9.16.1 Position-independent code costs nothing extra on this machine: every access to code or data in the same module is PC-relative by an ordinary addressing mode, so there is no GOT register and no prologue to set one up. *(D)*

9.16.2 A call to an imported function is `CALLI got_slot(PC)` and a PLT stub is the single instruction `JMPI got_slot(PC)`; an imported variable's address is one `MOVQ got_slot(PC), Rd`. *(D)*

9.16.3 A position-independent access to a global is no longer than an absolute one: four bytes within 32 KB and six within 2 GB, against six for a 32-bit absolute address. *(D)*

9.16.4 The thread pointer is DP, so the local-exec thread-local model is one four-byte `MOVQ tls_offset(DP), Rd`. *(D)*

9.16.5 A branch at the middle length reaches 4 GB, so no linker veneers are needed for any binary smaller than that; the assembler's and the linker's branch relaxation both reduce to choosing a length. *(D)*

9.16.6 `R12` is the linker's scratch register. The ABI (appendix D) decides that imports are called without a PLT stub; lazy against eager binding is open. *(D for `R12` and no stub; open for binding)*

Commentary. **Precedent.** On i386 a position-independent executable reserved `%ebx` (one of eight registers) for the GOT base and set it in every prologue, which cost a few percent of size and speed; x86-64 fixed that with RIP-relative addressing, and AArch64 needs linker veneers because its branches reach only 128 MB. **Trade-offs.** The two-byte PC-relative form is the shortest, so position-independent data access is slightly smaller than absolute access; the price is a GOT load per imported call site where a PLT stub would cost a load per function. **Improvements.** Position-independence is a side effect of three decisions made for other reasons: PC-relative as an ordinary mode (adopted because the PC left the register file), variable-length encoding (for density) and `DP` (a 6502 zero-page descendant kept for density), which is exactly the thread pointer. **Benefits.** OpenBSD builds everything position-independent by default, and here that costs nothing. **Modern comparables.** x86-64 RIP-relative addressing; AArch64 `ADRP` with a GOT load and veneers for far calls. **Impact.** *Kernel:* a loader applies only relocations for data pointers, and write-xor-execute and randomisation come with no code penalty. *Compiler:* `-fPIE` is the default and emits the same instructions as `-fno-pic` for local data; no reserved register, no per-function setup. *Hardware:* nothing; the PC-relative mode is in the address adder already.

9.17 What was rejected

9.17.1 The architecture refuses, by design, every feature that adds hidden state, an unbounded instruction, a second operand path or a mode bit that changes what other instructions mean. *(D)*

9.17.2 From the PDP-11 and VAX it refuses general memory-to-memory operands, deferred addressing as a general form (only `JMPI` and `CALLI` are deferred), unbounded instructions with hidden microstate (`MOVC5`, `EDITPC`), packed decimal, hardware call frames (`CALLS`, `CALLG`), the PC as a general register, multiple floating-point formats, `POLY`, the `IOT`, `EMT`, `WAIT` and `RESET` instructions, a distinct low-half unsigned multiply, and the PDP-11's compare operand order. *(D)*

9.17.3 From x86 it refuses partial-register writes that preserve upper bits, operand-size and `REX` prefixes, segmentation, flag writes that vary by instruction, implicit registers for multiply, divide and shift count, the x87 stack, transcendental instructions and byte-granular instruction fetch. *(D)*

9.17.4 From the RISC family it refuses a register hardwired to zero (a sixteenth of a 16-register file), fused compare-and-branch in place of flags, branch delay slots, register windows and software-refilled translation buffers. *(D)*

9.17.5 It also refuses features of its own invention: NUL-terminated string instructions (`MSCN` with an explicit maximum gives a bounded `strlen`), `CRC32` words (carry-less multiply is the primitive under every CRC), reciprocal-estimate instructions, NaN payload propagation, a 32-bit profile, an eight-byte instruction alignment, `MOVT` and `MOVK` partial-immediate inserts, hardware tag checking, store-with-write-barrier, a self-synchronising encoding, and a scalar instruction for sub-1-bit inference (the accelerator of chapter 8 does it). *(D)*

Commentary. **Precedent.** The VAX's `EDITPC` is a bytecode interpreter in microcode, and DEC needed a separate control chip for the PDP-11's commercial instruction set and shipped none; the VAX's hardware call frames ran slower than the equivalent sequence on later models; ARM32's `PC+8` and MIPS's delay slot expose one implementation's pipeline forever. **Trade-offs.** Each refusal gives up a real convenience: the lost `MOV (R1)+,(R2)+` copy loop, the byte-wide `ADDB`, the inline-argument `JSR`. Section 9.18 says what replaces each. **Improvements.** The common pattern is that a refused feature was either subsumed by a more general one (`MCPY` for the copy loop) or paid its cost in every implementation for a few users (`EDITPC`). **Benefits.** An instruction set a small in-order core can implement completely and a compiler can target without exceptions. **Modern comparables.** RISC-V and AArch64 also refuse memory-to-memory operands and delay slots; AArch64 keeps flags where RISC-V refuses them. **Impact.** *Kernel:* no instruction has a restart state except the three that keep their progress in architectural registers, so a fault is always restartable. *Compiler:* no special cases: every operand rule is uniform, one memory operand and the rest registers. *Hardware:* no microcode engine, no second operand path, no hidden-state latch, no alignment rotator in the fetch path.

9.18 Idioms: restored, lost and replaced

9.18.1 Several idioms that the PDP-11 and VAX had and later RISC designs dropped are restored: subtract-one-and-branch (`SOB`, here in both directions), probe an address without faulting (`PROBER`, `PROBEW`), bit-field extract and insert, find-first-set (`CTZ`,

clz), byte swap, block move, fill, compare and scan with their progress held in registers, the register-save mask (pushm, popm, the useful half of calls), and carry-less multiply. *(D)*

9.18.2 The VAX's counted-string instructions are largely present: movc3 is mcpy, cmpc3 is mcmp, locc is mscn, skpc is mscnn, and movc5 is mcpy plus mset. Table-translated move, table scans and substring search are absent because a per-byte table lookup stops a block operation from streaming. *(D)*

9.18.3 Deliberately lost, with their replacements: memory-to-memory mov (replaced by mcpy); autoincrement-deferred and the dispatch-table idiom (replaced by jtag for tag dispatch and a scaled-index jmp for the rest); jsr Rn and rts Rn with inline arguments and cheap coroutines (replaced by call and ret with the return address on the stack where every unwinder and debugger expects it); the VAX case and index instructions (replaced by a compare, branch and scaled jmp); byte and word ALU operations (movzb, the operation, movb: three instructions where the PDP-11 had one); and the flag set and clear instructions. *(D)*

9.18.4 Subsumed, so not losses: sxt (the conversion moves), swab (bswap), mark (the convention it served is gone), ash and ashc (the shifts take a register count), mfpi and mtpi (prober with the previous-mode bits and the user-memory guard), mulu (identical to mul in the low half), and rol (an assembler alias for ror). *(D)*

9.18.5 Measurements decide what is included: the compiler uses set cc, rd (about 0.4% of code), not integer abs, min or max (under 0.1%), not the bit-field instructions (0.03%) and not the auto-increment modes (0.1%); the second opcode page is about 7% of the instructions emitted. *(D)*

Commentary. **Precedent.** The PDP-11's jsr Rn put the return address in a register of the caller's choosing, which made coroutines a pair of jsrs and inline arguments free; the VAX replaced it with calls and a frame, which was slower than the code it replaced. **Trade-offs.** The most frequently felt loss in hand-written code is the byte-wide read-modify-write; the compiler never notices it. A bounds-checked index for Pascal and Ada is a possible addition. **Improvements.** sob branches either way, with four reaches; the block operations keep their progress in registers, which is what the VAX got wrong, so a fault restarts for free. **Benefits.** The code a compiler emits is the code the table above measures, and the extras are for the people who write assembler. **Modern comparables.** x86 keeps loop and the string instructions with rep; AArch64 has bit-field moves and no memory-to-memory forms; RISC-V has none of them in the base. **Impact.** *Kernel:* prober and probew replace the nofault global in the user-copy routines. *Compiler:* idioms the compiler never emits are not built for it, so the compiler's instruction selection stays small. *Hardware:* each restored idiom is a few hundred gates of existing datapath, and each lost one is a decode that never existed.

9.19 Side by side: the PDP-11, the VAX and the pdp64

9.19.1 The word is 64 bits against the PDP-11's 16 and the VAX's 32, the registers are 16 as on the VAX, the virtual address is 39, 48 or 57 bits with 40 physical in the present implementation, and the instruction count is 58 assigned opcodes plus 45 on the second page, against the VAX's 304. *(D)*

9.19.2 The program counter is not a register, there is no argument pointer, and the frame pointer and the linker scratch are ordinary software conventions. *(D)*

9.19.3 An instruction has one or two operands (three for the block operations) and at most one memory operand, against the PDP-11's two and the VAX's six. *(D)*

9.19.4 The condition codes are the same four, n, z, v and c; floating point is in the base and in the general registers, with three IEEE formats (half, single, double) and no mode bits that change the meaning of other instructions, where the PDP-11 had fps.fd, fl and ft and the VAX had rounding bits in the status word. *(D)*

9.19.5 An instruction is two, four or six bytes (one to three parcels of 16 bits) with a one-parcel second page, against the PDP-11's two to six and the VAX's one to more than fifty. *(D)*

Commentary. **Precedent.** The PDP-11 and VAX instruction formats, with their encodings drawn side by side, are in the instruction-set text, section 13. **Trade-offs.** The pdp64 keeps what made the PDP-11 pleasant, orthogonal addressing and a small register set, and what made the VAX powerful, flags, a register-save mask and string operations, and drops what made both expensive: memory-to-memory operands and unbounded instructions. **Improvements.** The compiler's code averages about 3.3 bytes an instruction, measured on the fair corpus before the second page. **Benefits.** A processor that is smaller than either predecessor while running 64-bit code. **Modern comparables.** The closest family is AArch64 in the number of registers and addressing modes and RISC-V compressed in density; neither has flags and a variable length

together. **Impact.** *Kernel:* the exception model is the PDP-11's with the VAX's per-mode stacks. *Compiler:* one memory operand makes instruction selection a register-allocation problem, as on a RISC. *Hardware:* a decoder that reads two bits to find the length, and no microcode.

9.20 What was taken from LoongArch, and what was not

9.20.1 LoongArch64 is the most recent clean-room instruction set designed without an ideological commitment: it borrowed from MIPS, RISC-V and ARM as each had the better answer, which is the posture of the pdp64.

9.20.2 Adopted from it: bit manipulation in the base (`CLO`, `CLZ`, `CTZ`, bit-field moves, byte reverse), atomics with the barrier folded in (the `_DB` variants), a richer atomic set (fetch-and-minimum and maximum), and memory type as a page attribute. *(D)*

9.20.3 Declined, with reasons: `R0` hardwired to zero (a sixteenth of a 16-register file, and `CLR` and `NEG` are one parcel already); no condition codes (a third read port in the branch unit against a four-bit latch); `FCSR` rounding-mode bits (hidden state that changes other instructions); four PC-relative address-formation instructions (one `LEA` carries 32 bits); 32 registers (this encoding has no bit to spare for the field); and separate vector register files (chapter 8). *(D)*

9.20.4 Under consideration: separate floating-point condition flags, software-visible translation-buffer manipulation (to pin an entry for a real-time kernel), and a conditional select for constant-time code. *(P)*

Commentary. **Precedent.** LoongArch has a fixed 32-bit encoding with room for two register fields and a displacement, so it can afford compare-and-branch and needs four instructions to form an address; this machine's variable length reverses both trade-offs. **Trade-offs.** The direct-mapping windows LoongArch uses to avoid translation-buffer misses on kernel text are deferred: `DMW0` and `DMW1` are stored without effect (6.9.2). **Improvements.** The same idea is right or wrong depending on the encoding around it, and each adoption is judged against this encoding. **Benefits.** Borrowing the tested parts saves design time and avoids their bugs. **Modern comparables.** LoongArch itself; the RISC-V bit-manipulation extensions (Zbb, Zbs) do much of the same. **Impact.** *Kernel:* atomics with barriers make a lock acquire one instruction. *Compiler:* bit operations in the base mean the compiler can use them without a feature test. *Hardware:* each adopted idea is a few hundred lookup tables and each declined one is a block not built.

9.21 What is still open in the instruction set

9.21.1 Open, with the reasoning in appendix B or in the instruction-set text, section 12: the thin 6-bit displacement of the shortest scaled-index form; the landing-pad decision (optional first, mandatory later); atomics against the bus (the lock against the monitor; the monitor is chosen); worst-case instruction latency for the block operations (an interrupt-latency claim must state the block granularity); the floating-point condition flags (the signed branches do not treat unordered cleanly); the block operations and the cache (a streaming memory type or a non-temporal variant); directed rounding for arithmetic (a rounding field in the instruction); the leftovers of half precision (minimum, maximum, rounding, bfloat16); conditional select; lazy against eager binding in the ABI; the verification of the memory model against published litmus tests; and the coherence protocol beyond four cores (the design supports at least four and prefers sixteen or more, errata 92; the leanings are in `docs/smp-decisions.md`). *(P and open)*

9.21.2 Settled: the reserved-opcode discipline (a top-level opcode is for an operation whose common case is register to register), the fourth parcel (absent; the code `11` is a second page of 64 one-parcel opcodes), UTF-8 scope (`MVAL` is committed), and the measured length distribution (2, 4, 6 and 8 bytes at 46.5, 42.8, 10.6 and 0.1 percent, before the second page). *(D)*

Commentary. **Trade-offs.** None of the open items blocks the first implementation; the three that must be settled before silicon, the memory model verification, the coherence choice and the worst-case latency figure, are verification tasks, not design changes. **Impact.** *Kernel:* the open items touching the kernel are the user-memory guard, the floating-point state and the block-operation granularity. *Compiler:* conditional select and directed rounding would change instruction selection. *Hardware:* the coherence protocol must be chosen before the cache is built, not after.

Chapter 10 — Conclusion: from FPGA to silicon

The pdp64 is built to be run first on a modest FPGA, to be small enough that its whole core is about sixteen thousand lookup tables or ninety thousand transistors, and to reach silicon only after an OpenBSD built by the project's own toolchain can be logged into over `ssh`. The chapter gives the FPGA plan and its numbers, the transistor budget for a chip, why the first implementations are in order and how the architecture is kept ready for a faster one, and the path from the present toolchain to the finish line. Tags: *(D)* decided; *(E)* an estimate, not a measurement.

10.1 The FPGA plan

10.1.1 The first implementation is a soft core on a system-on-chip FPGA whose hard ARM cores serve as the bring-up harness: they load programs, run the tests and provide the console while the pdp64 core is still being debugged. *(D)*

10.1.2 The first board is the Terasic DE10-Nano (Cyclone V SE: about 110,000 logic elements, dual Cortex-A9, 1 GB of memory on the hard processor, HDMI, and the MiSTer ecosystem); the Digilent Zybo Z7-20 or the AMD Kria KV260 are the move when timing becomes the limit; the open-toolchain ULX3S is kept in view but loses the hard-core harness. The device chat staged devices first on a Zynq UltraScale+ (`decisions-pending.md` E6). *(P)*

10.1.3 A complete core is about 16,000 six-input lookup tables, 10 to 16 multiplier blocks and 11 block RAMs, with an error of about ±40%: the register file is 250 lookup tables of distributed RAM, the 64-bit ALU 600, the barrel shifter 450, the caches 300 and 500 plus 8 block RAMs, the bus bridge 600. *(E)*

10.1.4 Block RAM, not logic, is the scarce resource: the caches, the translation buffer, the framebuffer and the blitter scratch compete for about 5.5 megabits. *(E)*

10.1.5 The clock the FPGA design aims at is 200 to 300 MHz. *(D)* The estimated clock is 50 to 80 MHz on the Cyclone V, 90 to 130 MHz on a Zynq 7020 and 180 to 250 MHz on an UltraScale+; every one of those estimates is below the target except the upper part of the UltraScale+ range, and reaching the target means pipeline stages in the datapath. *(E)* A correct machine at a lower clock still comes before a fast broken one.

10.1.6 The work is staged in phases, each ending in a demonstration and a regression suite: specification and tools; an integer core; exceptions; the memory-management unit; the memory system; floating point; a booting kernel; peripherals; and, last, the other cores: the design supports at least four, and the initial device has four. *(D)*

10.1.7 Phase 2, the fault model, is not optional and does not move; the block operations are built with it, because their whole specification is about what state is visible when an exception arrives. *(D)*

10.1.8 On the paper estimates of the SMP decisions, four cores with the floating-point unit fit only a board of the Kria KV260 class, and sixteen cores fit none of the boards of the plan; no core has been synthesised. *(E)*

Commentary. **Precedent.** The PDP-11's own microprocessor, the T-11, was about 12,000 transistors, a complete integer core without a memory-management unit or floating point; the J-11 that implemented the full PDP-11/70 was about 120,000. The MicroVAX 78032 was 125,000 transistors for a subset of the VAX, with 175 of its 304 instructions and no floating point. **Trade-offs.** The 64-bit carry chain is slow on an FPGA and gates the clock more than it would in silicon, the barrel shifter is a large multiplexer tree, and flags serialise branch resolution behind the ALU; none of that argues for changing the instruction set, only for where the pipeline registers go, for example a virtually indexed, physically tagged first-level cache so that the translation buffer is off the critical path. A multiplier built from two to four multiplier blocks over four to eight cycles closes timing where a full combinational one will not. **Improvements.** The register-transfer description is kept vendor-neutral, with every vendor primitive in one thin directory (under 500 lines), so that moving between boards costs that directory and nothing else. **Benefits.** A single engineer working part-time can reach a booting system with floating point in roughly 10 to 19 months, by the plan's wide-error-bar estimate, with phases 2 and 3 the ones that historically double. **Modern comparables.** The RISC-V soft cores Rocket and VexRiscv are the usual FPGA reference points; the plan treats the compiler back end as the schedule risk, as it is for any new architecture.

10.2 The chip: a transistor budget

10.2.1 For a non-pipelined or short-pipeline implementation in a modern process, the whole core excluding caches is estimated at about 92,000 transistors. *(E)*

Block	Transistors (E)
register file, 16 × 64, two read ports and one write	~6,000
ALU, shifter, address adder	~15,000
decode and sequencer	~6,500
bit unit (popcount tree, count zeros, bitfields)	~3,500
block-move sequencer	~1,500
UTF-8 decode and validity	~1,200
translation buffer (32 entries), walker, window compare	~19,000
floating-point unit with fused multiply-add, classify, min and max	~34,000
control, status word, exceptions, undo buffer	~5,500
total, excluding caches	**~92,000**

10.2.2 The bit unit and the UTF-8 decoder together cost less than 5% of the die; the fused multiply-add datapath is the largest single addition and the least negotiable. *(E)*

Commentary. **Precedent.** The figure sits between the T-11 and the MicroVAX: it is a 64-bit machine with floating point and memory management below the 78032's 125,000 transistors, which had neither. **Trade-offs.** The estimate is not a measurement and excludes caches, which dominate the area of a real chip; an implementation of the translation buffer as a content-addressable memory is larger than the figure assumes, which is why the FPGA build uses a four-way set-associative one. **Benefits.** A chip this size fits in the budget of a small process node with room for caches and the bus controller. **Modern comparables.** The ARM1 of 1985 was about 25,000 transistors without a memory-management unit or floating point; the Intel 80386 about 275,000.

10.3 In order first, ready for out of order

10.3.1 The first implementations, on the FPGA and in silicon, are small in-order cores without speculation; the architecture is kept ready for a large out-of-order design. *(D)*

10.3.2 The condition flags were the structural obstacle: 68.2% of compiled instructions wrote a flag and only 1.5% read one, so the flags form two groups that nothing writes in part, and moves, loads, stores and the compare-and-branch instructions write none. *(D)*

10.3.3 An in-order, non-speculative core has none of the speculative side channels of the last decade, and an out-of-order core must keep that property; the rules that keep a future faster core from repeating them are collected in the hardware-vulnerabilities report, and include no speculation across protection domains, no shared predictor state across privilege boundaries without a flush, and operand-independent timing for a declared set of instructions. *(D as a design aim; the rules are proposals)*

10.3.4 Sequential consistency is nearly free on a small in-order core and is the most expensive memory model for a large speculative one; if a large core is built it may be necessary to move to total store order, which is the least painful retreat. *(P)*

Commentary. **Precedent.** One instruction set has often spanned in-order and out-of-order cores: the ARM small cores beside the large ones, the RISC-V Rocket beside the BOOM, x86 from the Pentium to the P6, Alpha from the 21064 to the 21264. The VAX's long, orthogonal instructions with many side effects are generally blamed for making its later fast implementations so hard. **Trade-offs.** Readiness has a cost, visible here as the compiled-code size paid for the flag rules (0.39%) and as design effort spent on a core that may never be built. **Improvements.** The pain-points report finds that the pdp64 avoids the largest classes of kernel pain by design (barriers, floating-point state, a faulting entry, remote translation flushes, the speculative family) and is exposed in a few places: a single page-table base if a core ever speculates, software accessed and dirty bits, uncached DMA buffers, and no specified constant-time or Rowhammer protection. **Benefits.** Any of these can be addressed in the specification while it is still being written, which is cheaper than after silicon. **Modern comparables.** The common vulnerability-driven changes of recent years, page-table isolation and speculation barriers, are what a speculative core of this architecture would have to add.

10.4 The finish line, and the path to it

10.4.1 Before silicon the project delivers five things: an assembler, a linker, an LLVM compiler back end, an emulator, and a port of OpenBSD that can be logged into with `ssh`. *(D)*

10.4.2 The architecture manual, which includes the instruction set but covers the whole machine, is the primary deliverable; the toolchain is advanced as needed to write and check it. *(D)*

10.4.3 The assembler and linker exist; the assembler lacks the atomics and the linker lacks shared libraries; the pcc compiler back end passes 516 C tests on the simulator and on QEMU; the LLVM back end has its machine-code layer, checked against the project's own assembler on 62 programs and 6,304 instruction forms with no disagreement; the simulator and QEMU run a kernel-mode machine with exceptions, a memory-management unit, a timer and a console; no part of OpenBSD is ported. *(measured)*

10.4.4 The long pole is the LLVM back end and clang. OpenBSD's kernel and base cannot be built by pcc, and the fallback of porting Unix/32V with pcc would not reach the goal, because it has no network stack and no `ssh`. *(D)*

10.4.5 The path, in order, with a test for each step: finish the toolchain gaps (atomics, the user-memory guard, the ABI version); an LLVM back end that passes the C tests; clang, the compiler runtime and `lld`; a machine model for the operating system with an enumerating bus, a disk, a network card and an entropy source (virtio devices first, for speed); the kernel booting to single-user; the userland to a login prompt; the network and `sshd`, and then `ssh user@localhost -p 2222` gives a shell; and finally the same system on the FPGA. *(P)*

Commentary. **Precedent.** OpenBSD's riscv64 port is its newest and smallest, and it measures at 35,600 lines of machine-dependent code, of which 14,873 are the core, 11,771 platform drivers, 4,513 the loader and 4,443 headers; arm64 is 61,613 and amd64 79,167. **Trade-offs.** The pdp64 port should be smaller than the riscv64 one in several places: no firmware tables to parse, uniform eight-register devices instead of a platform's driver zoo, a trivial loader, no cache-maintenance code and no floating-point state code; the core machine-dependent code of about 15,000 lines is the part that has to be written by hand *(estimate)*. The LLVM back end is estimated at three to six months for one experienced engineer, a figure that has not been tested. **Benefits.** An OpenBSD that can be logged into is a demonstration that the architecture, the toolchain and the operating-system interface are complete in the way that matters to users, and it forces every piece (the compiler, the linker, the bus, the devices, the boot) to work together. **Modern comparables.** OpenBSD ports to new architectures have followed this shape; the RISC-V port is the nearest in kind.

10.5 What remains open

The open items are collected, with their options and benefits, in appendix B; ideas that are not decisions are in appendix A. The principal open choices are the transport and interrupt controller (chapters 2 and 5), the details of the device layout, the interrupt controller and virtualization position, the vector-math position, and the several smaller instruction-set proposals.

Part II — The instruction reference tables

The instruction reference tables

This is the reference part of the manual: **one entry for each instruction**, in the layout of a processor reference manual. Each entry gives its mnemonics, its syntax, its encoding (the parcel diagram and the numbers), its operation in pseudocode, the flags it writes, the exceptions it can take, and where the manual explains it. The entries are generated from `spec/pdp64-mnemonics.hbnf`, the one place where the numbers of the architecture are written, so an encoding here cannot disagree with the assembler or the simulators; the words (operation, flags, exceptions) are in `tools/manual/isa_entries.py` and are checked against the reference executor, `common/pdp64exec.c`, which `sim64` and QEMU share. The Status line of each entry says whether the executor implements the instruction.

Notation. `Rd` is the destination register (the `reg` field of parcel 0), `Rs` the first source (`low`), `Rt` the second (`t` of parcel 1), `Ru` the third (`x`); the assembler writes the destination last. `rm` is a general operand: a register at `len = 00`, or a memory operand, an immediate or an absolute address by one of the eight addressing modes (section 9.5). `EA(rm)` is its effective address. `M[a]` is memory, `M8[a]` one byte. `sext` and `zext` sign- and zero-extend. A `len = 01` instruction is two parcels (four bytes) and a `len = 10` instruction three (six bytes); `len = 11` is page 2. `N Z V C` are the condition flags. Bit diagrams number the bits of a parcel from 15 at the left.

Cf. lines point to the chapter that explains the matter an instruction touches: the kernel (chapter 6), the multiprocessor model (chapter 7), the bus (chapter 2).

Where the entries are

- Section 9.6, Moves, conversions and address formation: `MOVQ`, `MOVZL`, `LEA`, `MOVUB`
- Section 9.7, Integer arithmetic: `ADD`, `SUB`, `CMP`, `MUL`, `MULH`, `ADDM`, `INC`, `DEC`, `NEG`, `ADC`, `SBC`, `DIV`, `MULHU`, `ABS`, `MIN`, `SET`
- Section 9.8, Logic, shifts and rotates: `BIC`, `BIS`, `BIT`, `XOR`, `AND`, `SHL`, `CLR`, `COM`, `TST`, `ASL`, `ASR`
- Section 9.9, Bits, bytes and text: `CLZ`, `POPCNT`, `BSWAP`, `BITREV`, `ROR`, `RORI`, `RORI32`, `DSHR`, `EXTB`, `INSB`, `XNORPOP`, `CLMULL`, `UTF8LEN`, `UTF8DEC`, `UTF8ENC`
- Section 9.10, Branches and control flow: `BR`, `SOB`, `CBNE`, `BTAG`, `JMP`, `CALL`, `JMPI`, `JTAG`
- Section 9.11, The stack and block operations: `PUSHM`, `POPM`, `PUSH`, `POP`, `MCPY`, `MSET`, `MCMP`, `MSCN`, `MVAL`
- Section 9.12, Floating point: `FADD`, `FCMP`, `FDIV`, `FADD32`, `FMADD`, `FMADD32`, `FNEG`, `FMIN`, `FCLASS`, `FRINT`, `FCVTDQ`, `FSFLAGS`, `FADD16`, `FCVTSH`
- Section 9.13, Atomics and ordering: `CAS`, `SWAP`, `XADD`, `XAND`, `XMAX`, `LL`
- Section 9.14, System instructions, exceptions and interrupts: `NOP`, `RTI`, `RET`, `HALT`, `BPT`, `FENCE`, `WFE`, `SEV`, `TLBIA`, `PUSHX`, `ISYNC`, `HINT`, `MFSR`, `MTPS`, `SPL`, `TRAP`, `TLBI`, `MTASID`, `MTDP`, `MTDMW`, `MFCPUID`, `ICINV`, `PROBER`

The tables

- The second page: one-parcel abbreviations
- Assembler aliases and alternative spellings
- The architectural constants
- The mnemonics, alphabetically
- The opcodes, in order
- The bit layouts of every opcode: a chart for each layout, generated from the grammar


The specification of pdp64/r20 has 270 mnemonic words (234 instructions and 36 aliases) and 45 page-2 opcodes; the reference executor implements 200 of the 234 instructions; the Status line of the entry of each of the rest says that it is not implemented. There are 106 instruction entries, 67 bit-layout charts of the layouts, and an entry for each of the 234 instructions with a chart of each of its 897 forms.

Generated by `tools/mkmanual.py`; do not edit.

The second page: one-parcel abbreviations

Page 2 (`len = 11`) is a second opcode map of 64 one-parcel instructions, 45 of them defined. **Every page-2 instruction is exactly the page-1 instruction it abbreviates**: the same result, the same flags and the same faults. The assembler chooses the shortest encoding, so a mnemonic still assembles to one instruction and a program can never change meaning by using a page-2 form. The opcode numbers of page 2 are independent of those of page 1. `reg` is the register (or the high part of an immediate) named first, `low` the field named second.

Generated by `tools/mkmanual.py` from `spec/pdp64-mnemonics.hbnf` and `tools/manual/isa_entries.py`; do not edit.



Opcode	Name	Operation	reg	low	Long form it abbreviates
000000 (0x00)	ld.q	MOVQ load through (rn)	rd	rn	MOVQ (rn), rd
000001 (0x01)	st.q	MOVQ store through (rn)	rs	rn	MOVQ rs, (rn)
000010 (0x02)	ld.l	MOVL load through (rn)	rd	rn	MOVL (rn), rd
000011 (0x03)	st.l	MOVL store through (rn)	rs	rn	MOVL rs, (rn)
000100 (0x04)	ld.w	MOVW load through (rn)	rd	rn	MOVW (rn), rd
000101 (0x05)	st.w	MOVW store through (rn)	rs	rn	MOVW rs, (rn)
000110 (0x06)	ld.b	MOVB load through (rn)	rd	rn	MOVB (rn), rd
000111 (0x07)	st.b	MOVB store through (rn)	rs	rn	MOVB rs, (rn)
001000 (0x08)	ldz.l	MOVZL load through (rn)	rd	rn	MOVZL (rn), rd
001001 (0x09)	ldz.w	MOVZW load through (rn)	rd	rn	MOVZW (rn), rd
001010 (0x0A)	ldz.b	MOVZB load through (rn)	rd	rn	MOVZB (rn), rd
001011 (0x0B)	lea.sp	LEA 8*d(SP), rd	rd	d (0 to 15)	LEA 8*d(SP), rd
001100 (0x0C)	ldq.sp0	MOVQ load from SP, offset 8*low, 0 to 120	rd	offset / 8	MOVQ d(SP), rd
001101 (0x0D)	ldq.sp1	MOVQ load from SP, offset 8*(16+low), 128 to 248	rd	offset / 8 - 16	MOVQ d(SP), rd
001110 (0x0E)	stq.sp	MOVQ store to SP, offset 8*low, 0 to 120	rs	offset / 8	MOVQ rs, d(SP)
010000 (0x10)	ldl.sp0	MOVL load from SP, offset 4*low, 0 to 60	rd	offset / 4	MOVL d(SP), rd
010001 (0x11)	ldl.sp1	MOVL load from SP, offset 4*(16+low), 64 to 124	rd	offset / 4 - 16	MOVL d(SP), rd
010010 (0x12)	stl.sp0	MOVL store to SP, offset 4*low, 0 to 60	rs	offset / 4	MOVL rs, d(SP)
010011 (0x13)	stl.sp1	MOVL store to SP, offset 4*(16+low), 64 to 124	rs	offset / 4 - 16	MOVL rs, d(SP)
010100 (0x14)	ldq.d1	MOVQ load from rn at offset 8	rd	rn	MOVQ 8(rn), rd
010101 (0x15)	ldq.d2	MOVQ load from rn at offset 16	rd	rn	MOVQ 16(rn), rd
010110 (0x16)	ldq.d3	MOVQ load from rn at offset 24	rd	rn	MOVQ 24(rn), rd
010111 (0x17)	ldq.d4	MOVQ load from rn at offset 32	rd	rn	MOVQ 32(rn), rd
011000 (0x18)	stq.d1	MOVQ store to rn at offset 8	rs	rn	MOVQ rs, 8(rn)
011001 (0x19)	stq.d2	MOVQ store to rn at offset 16	rs	rn	MOVQ rs, 16(rn)
011010 (0x1A)	ldl.d1	MOVL load from rn at offset 4	rd	rn	MOVL 4(rn), rd
011011 (0x1B)	ldl.d2	MOVL load from rn at offset 8	rd	rn	MOVL 8(rn), rd
011100 (0x1C)	ldl.d3	MOVL load from rn at offset 12	rd	rn	MOVL 12(rn), rd
011101 (0x1D)	ldl.d4	MOVL load from rn at offset 16	rd	rn	MOVL 16(rn), rd
011110 (0x1E)	pushm8	push the registers R8 to R15 named by the 8-bit mask reg:low (bit i is R(8+i))	mask high	mask low	PUSHM #(mask << 8)
011111 (0x1F)	popm8	pop the registers named by the mask, as pushm8	mask high	mask low	POPM #(mask << 8)
100000 (0x20)	sub.sp	SUB #(8*n), SP, n = reg:low (0 to 255)	n high	n low	SUB #(8*n), SP
100001 (0x21)	add.sp	ADD #(8*n), SP, n = reg:low	n high	n low	ADD #(8*n), SP
100010 (0x22)	movq.i	MOVQ #imm, rd, imm sign-extended 4 bits (-8 to 7)	rd	imm	MOVQ #imm, rd
100011 (0x23)	shl.i	SHL by low (0 to 15)	rd	count	SHL #n, rd

Opcode	Name	Operation	reg	low	Long form it abbreviates
100100 (0x24)	shr.i	SHR by low (0 to 15)	rd	count	SHR #n, rd
100101 (0x25)	sar.i	SAR by low (0 to 15)	rd	count	SAR #n, rd
100110 (0x26)	and.i	AND with a 4-bit sign-extended immediate	rd	imm	AND #imm, rd
100111 (0x27)	bis.i	BIS with a 4-bit sign-extended immediate	rd	imm	BIS #imm, rd
101000 (0x28)	xor.i	XOR with a 4-bit sign-extended immediate	rd	imm	XOR #imm, rd

Opcode	Name	Operation	reg	low	Long form it abbreviates
101001 (0x29)	add.i	ADD with a 4-bit sign-extended immediate	rd	imm	ADD #imm, rd
101010 (0x2A)	pushx	PUSHX (reg and low zero)	0	0	SYSX sub-opcode 0
101011 (0x2B)	popx	POPX (reg and low zero)	0	0	SYSX sub-opcode 1
101100 (0x2C)	isync	ISYNC (reg and low zero)	0	0	SYSX sub-opcode 2
101101 (0x2D)	hint	HINT #n, n = reg:low (0 to 255)	n high	n low	SYSX sub-opcode 3

Every page-2 opcode not listed (001111 (0x0F) and 101110 (0x2E) to 111111 (0x3F), 19 of 64) is reserved; a reserved page-2 opcode is an illegal-instruction abort.

Why there is a second page

Instructions are at most six bytes: an eight-byte form would serve 48-bit immediates and 44-bit displacements, and only 49 of 373,635 compiled instructions (0.013%) would use it. The length code 11 is therefore a second page of one-parcel instructions, each an exact abbreviation of a long form, chosen from the forms the compiler emits most. The estimate from static counts on the 827-file corpus is about 118 KB, 7% of the 1.67 MB image. The rule that governs the page: a page-2 instruction has the same result, flags and faults as the long form it abbreviates, so the assembler choosing the shortest encoding can never change what a program does.

Assembler aliases and old spellings

A mnemonic that assembles to another instruction. One mnemonic is one instruction (section 9.18); the disassembler never prints an alias.

Generated by `tools/mkmanual.py` from `spec/pdp64-mnemonics.hbnf`; do not edit.

Written	Assembles to	Group
BHIS	BCC	branch
BLO	BCS	branch
CBHIS	CBCC	cbranch
CBLO	CBCS	cbranch
FADDD	FADD	alu
FADDS	FADD32	fesc
FCLASSD	FCLASS	fesc
FCLASSS	FCLASS32	fesc
FCMPD	FCMP	alu
FCMPS	FCMP32	fesc
FDIVD	FDIV	fesc
FDIVS	FDIV32	fesc
FMADDD	FMADD	fesc
FMADDS	FMADD32	fesc
FMAXD	FMAX	fesc
FMIND	FMIN	fesc
FMSUBD	FMSUB	fesc
FMSUBS	FMSUB32	fesc
FMULD	FMUL	alu
FMULS	FMUL32	fesc
FNMADDD	FNMADD	fesc
FNMADDS	FNMADD32	fesc
FNMSUBD	FNMSUB	fesc
FNMSUBS	FNMSUB32	fesc
FRINTD	FRINT	fesc
FRINTDA	FRINTA	fesc
FRINTDM	FRINTM	fesc
FRINTDP	FRINTP	fesc
FRINTDZ	FRINTZ	fesc
FSQRTD	FSQRT	fesc
FSQRTS	FSQRT32	fesc
FSUBD	FSUB	alu
FSUBS	FSUB32	fesc
MULU	MUL	alu
ROL	RORI	besc
WAIT	WFE	sys-none
ROL rs, #n, rd	RORI rs, #(64-n), rd	assembler, immediate count only

The architectural constants

The numbers of the processor status word, the modes, the exception vectors, the page-table entry, the memory types, the translation geometry, the system registers, the addressing modes and the condition codes, each read from the machine-readable specification (`spec/pdp64-system.hbnf` and `spec/pdp64-mnemonics.hbnf`).
Generated by `tools/mkmanual.py`; do not edit.

The processor status word (16 bits)

Field	Bit	Width	Meaning
`C`	0	1	carry (borrow after a subtract)
`V`	1	1	signed overflow
`Z`	2	1	zero
`N`	3	1	negative
`T`	4	1	trace: take a trace trap after the next instruction
`PRI`	5	3	interrupt priority level, 0 to 7
`MODE`	8	2	current mode
`PREV`	10	2	previous mode (the mode before the last exception)

Bits 12 to 15 are reserved and read as zero. Bit 12 is the user-memory guard `UA`.

The modes

Mode	Value
kernel	0
supervisor	1
user	3

Value 2 is reserved: loading it into either mode field of the status word is an illegal instruction.

The exception vectors

The table has 512 entries of eight bytes at the physical address `VBR + 8 * vector`; `ECAUSE` equals the vector number.

Vector	Number	Cause
`RESET`	0	processor reset: the first instruction fetch
`ILLEGAL`	2	a reserved or undefined opcode, a reserved encoding or an unassigned system register
`PRIVILEGED`	3	a system instruction executed outside kernel mode
`MISALIGNED`	4	a data access whose address is not a multiple of its size (the `MOVU` forms excepted)
`NONCANONICAL`	5	a virtual address whose bits 63 to 39 differ from bit 38
`IFAULT`	6	instruction fetch from a page that is not mapped
`LFAULT`	7	load from a page that is not mapped
`SFAULT`	8	store to a page that is not mapped
`IPROT`	9	instruction fetch denied by the page permissions
`LPROT`	10	load denied by the page permissions
`SPROT`	11	store denied by the page permissions
`DIVZERO`	12	division by zero (`DIV`, `DIVU`, `MOD`, `MODU`)
`BUSFAULT`	13	a read of non-existent memory (a precise abort)
`LPAD`	14	an indirect transfer that did not land on `LPAD` (enforcement off in ABI version 1)
`BPT`	15	the `BPT` instruction
`TIMER`	32	the timer interrupt (level 6)
`COUNT`	512	the number of vectors; the table has this many eight-byte entries

The page-table entry (64 bits)

Field	Bit	Width	Meaning
`V`	0	1	valid
`R`	1	1	readable
`W`	2	1	writable
`X`	3	1	executable
`U`	4	1	accessible from user mode
`G`	5	1	global: ignores the ASID
`A`	6	1	accessed (managed by software)
`D`	7	1	dirty (managed by software)
`MT`	8	2	memory type
`PPN`	12	28	physical page number: physical address bits 12 to 39, in place

A non-leaf entry has `V` = 1 and `R` = `W` = `X` = 0 and points to the next table. Every bit not named is zero.

The memory types (`MT`)

Type	Value
cached	0
uncached	1
device	2

The translation geometry

Quantity	Value
levels	3

The system registers (`MFSR`, `MTSR`)

Name	Number	Access
`PTBR`	0	read and write
`EPC`	1	read and write
`EVA`	2	read only
`ECAUSE`	3	read only
`DMW0`	4	read and write
`DMW1`	5	read and write
`USP`	6	read and write
`SSP`	7	read and write
`EPSW`	8	read and write
`VBR`	9	read and write
`MMUCTL`	10	read and write
`ASID`	11	read and write
`CPUID`	12	read only

The addressing modes

Mode	Value
base	`0000`
index	`0001`
pcrel	`0010`
dp	`0011`
imm	`0100`
abs	`0101`
postinc	`0110`
predec	`0111`

Modes `1000` to `1111` are reserved. The syntax and the parcel layout of each mode are in section 9.5.

The condition codes

Name	Number	Aliases
al	0	
ne	1	
eq	2	
pl	3	
mi	4	
vc	5	
vs	6	
cc	7	hs
cs	8	lo
ge	9	
lt	10	
gt	11	
le	12	
hi	13	
los	14	

The mnemonics, alphabetically

Generated by `tools/mkmanual.py`; do not edit.

Mnemonic	Entry	Opcode	Sub	Layouts	Group
ABS	ABS (section 9.7)	001110 (0x0E)	00001000 (0x08)	2, entry	Arithmetic (AESC)
ADC	ADC (section 9.7)	010011 (0x13)	0110 (0x6)	9, entry	Single operand (SOP)
ADD	ADD (section 9.7)	010110 (0x16)		9, entry	Moves, address formation and the ALU
ADDM	ADDM (section 9.7)	001111 (0x0F)	00001000 (0x08)	2, entry	Memory escape (MESC)
AND	AND (section 9.8)	011101 (0x1D)		9, entry	Moves, address formation and the ALU
ASL	ASL (section 9.8)	010011 (0x13)	1000 (0x8)	9, entry	Single operand (SOP)
ASR	ASR (section 9.8)	010011 (0x13)	1001 (0x9)	9, entry	Single operand (SOP)
BCC	BCC (section 9.10)	110111 (0x37)		3, entry	Branches
BCS	BCC (section 9.10)	111000 (0x38)		3, entry	Branches
BEQ	BCC (section 9.10)	110010 (0x32)		3, entry	Branches
BGE	BCC (section 9.10)	111001 (0x39)		3, entry	Branches
BGT	BCC (section 9.10)	111011 (0x3B)		3, entry	Branches
BHI	BCC (section 9.10)	111101 (0x3D)		3, entry	Branches
BHIS (alias of BCC)	BCC (section 9.10)	110111 (0x37)		3, entry	Branches
BIC	BIC (section 9.8)	011000 (0x18)		9, entry	Moves, address formation and the ALU
BICM	ADDM (section 9.7)	001111 (0x0F)	00001010 (0x0A)	2, entry	Memory escape (MESC)
BIS	BIS (section 9.8)	011001 (0x19)		9, entry	Moves, address formation and the ALU
BISM	ADDM (section 9.7)	001111 (0x0F)	00001011 (0x0B)	2, entry	Memory escape (MESC)
BIT	BIT (section 9.8)	011011 (0x1B)		9, entry	Moves, address formation and the ALU
BITREV	BITREV (section 9.9)	001100 (0x0C)	00001000 (0x08)	2, entry	Bits and fields (BESC)
BLE	BCC (section 9.10)	111100 (0x3C)		3, entry	Branches
BLO (alias of BCS)	BCC (section 9.10)	111000 (0x38)		3, entry	Branches
BLOS	BCC (section 9.10)	111110 (0x3E)		3, entry	Branches
BLT	BCC (section 9.10)	111010 (0x3A)		3, entry	Branches
BMI	BCC (section 9.10)	110100 (0x34)		3, entry	Branches
BNE	BCC (section 9.10)	110001 (0x31)		3, entry	Branches
BNTAG	BTAG (section 9.10)	010101 (0x15)	00000001 (0x01)	2, entry	Branches
BPL	BCC (section 9.10)	110011 (0x33)		3, entry	Branches
BPT	BPT (section 9.14)	010100 (0x14)	0101 (0x5)	3, entry	System (SYS)
BR	BCC (section 9.10)	110000 (0x30)		3, entry	Branches
BSWAP	BSWAP (section 9.9)	001100 (0x0C)	00000101 (0x05)	2, entry	Bits and fields (BESC)
BSWAPL	BSWAP (section 9.9)	001100 (0x0C)	00000111 (0x07)	2, entry	Bits and fields (BESC)
BSWAPW	BSWAP (section 9.9)	001100 (0x0C)	00000110 (0x06)	2, entry	Bits and fields (BESC)
BTAG	BTAG (section 9.10)	010101 (0x15)	00000000 (0x00)	2, entry	Branches
BVC	BCC (section 9.10)	110101 (0x35)		3, entry	Branches
BVS	BCC (section 9.10)	110110 (0x36)		3, entry	Branches
CALL	CALL (section 9.10)	010011 (0x13)	1101 (0xD)	9, entry	Single operand (SOP)
CALLI	JMPI (section 9.10)	010010 (0x12)	0001 (0x1)	9, entry	Indirect transfers (XFER)
CAS	CAS (section 9.13)	010001 (0x11)	00000000 (0x00)	2, entry	Atomics (ATOM)
CASDB	CAS (section 9.13)	010001 (0x11)	00000001 (0x01)	2, entry	Atomics (ATOM)

Mnemonic	Entry	Opcode	Sub	Layouts	Group
CBCC	CBCC (section 9.10)	101000 (0x28)	00000111 (0x07)	5, entry	Branches
CBCS	CBCC (section 9.10)	101000 (0x28)	00001000 (0x08)	5, entry	Branches
CBEQ	CBCC (section 9.10)	101000 (0x28)	00000010 (0x02)	5, entry	Branches
CBGE	CBCC (section 9.10)	101000 (0x28)	00001001 (0x09)	5, entry	Branches

Mnemonic	Entry	Opcode	Sub	Layouts	Group
CBGT	CBCC (section 9.10)	101000 (0x28)	00001011 (0x0B)	5, entry	Branches
CBHI	CBCC (section 9.10)	101000 (0x28)	00001101 (0x0D)	5, entry	Branches
CBHIS (alias of CBCC)	CBCC (section 9.10)	101000 (0x28)	00000111 (0x07)	5, entry	Branches
CBLE	CBCC (section 9.10)	101000 (0x28)	00001100 (0x0C)	5, entry	Branches
CBLO (alias of CBCS)	CBCC (section 9.10)	101000 (0x28)	00001000 (0x08)	5, entry	Branches
CBLOS	CBCC (section 9.10)	101000 (0x28)	00001110 (0x0E)	5, entry	Branches
CBLT	CBCC (section 9.10)	101000 (0x28)	00001010 (0x0A)	5, entry	Branches
CBMI	CBCC (section 9.10)	101000 (0x28)	00000100 (0x04)	5, entry	Branches
CBNE	CBCC (section 9.10)	101000 (0x28)	00000001 (0x01)	5, entry	Branches
CBPL	CBCC (section 9.10)	101000 (0x28)	00000011 (0x03)	5, entry	Branches
CBVC	CBCC (section 9.10)	101000 (0x28)	00000101 (0x05)	5, entry	Branches
CBVS	CBCC (section 9.10)	101000 (0x28)	00000110 (0x06)	5, entry	Branches
CLMULH	CLMUL (section 9.9)	001100 (0x0C)	00110010 (0x32)	2, entry	Bits and fields (BESC)
CLMULL	CLMUL (section 9.9)	001100 (0x0C)	00110001 (0x31)	2, entry	Bits and fields (BESC)
CLO	COUNT (section 9.9)	001100 (0x0C)	00000010 (0x02)	2, entry	Bits and fields (BESC)
CLR	CLR (section 9.8)	010011 (0x13)	0000 (0x0)	9, entry	Single operand (SOP)
CLZ	COUNT (section 9.9)	001100 (0x0C)	00000000 (0x00)	2, entry	Bits and fields (BESC)
CMP	CMP (section 9.7)	011010 (0x1A)		9, entry	Moves, address formation and the ALU
COM	COM (section 9.8)	010011 (0x13)	0001 (0x1)	9, entry	Single operand (SOP)
CTO	COUNT (section 9.9)	001100 (0x0C)	00000011 (0x03)	2, entry	Bits and fields (BESC)
CTZ	COUNT (section 9.9)	001100 (0x0C)	00000001 (0x01)	2, entry	Bits and fields (BESC)
DEC	DEC (section 9.7)	010011 (0x13)	0011 (0x3)	9, entry	Single operand (SOP)
DIV	DIV (section 9.7)	001110 (0x0E)	00000000 (0x00)	2, entry	Arithmetic (AESC)
DIVU	DIV (section 9.7)	001110 (0x0E)	00000001 (0x01)	2, entry	Arithmetic (AESC)
DSHR	DSHR (section 9.9)	001100 (0x0C)	00100000 (0x20)	2, entry	Bits and fields (BESC)
EXTB	EXTB (section 9.9)	001100 (0x0C)	00100001 (0x21)	2, entry	Bits and fields (BESC)
EXTZB	EXTB (section 9.9)	001100 (0x0C)	00100010 (0x22)	2, entry	Bits and fields (BESC)
FABS	FSIGN (section 9.12)	010000 (0x10)	00100001 (0x21)	2, entry	Floating point (FESC)
FADD	FADD (section 9.12)	100100 (0x24)		9, entry	Moves, address formation and the ALU
FADD16	FHALF (section 9.12)	010000 (0x10)	01010000 (0x50)	2, entry	Floating point (FESC)
FADD32	FSINGLE (section 9.12)	010000 (0x10)	00001000 (0x08)	2, entry	Floating point (FESC)
FADDD (alias of FADD)	FADD (section 9.12)	100100 (0x24)		9, entry	Moves, address formation and the ALU
FADDS (alias of FADD32)	FSINGLE (section 9.12)	010000 (0x10)	00001000 (0x08)	2, entry	Floating point (FESC)
FCLASS	FCLASS (section 9.12)	010000 (0x10)	00101000 (0x28)	2, entry	Floating point (FESC)
FCLASS16	FCLASS (section 9.12)	010000 (0x10)	01011100 (0x5C)	2, entry	Floating point (FESC)
FCLASS32	FCLASS (section 9.12)	010000 (0x10)	00101001 (0x29)	2, entry	Floating point (FESC)

Mnemonic	Entry	Opcode	Sub	Layouts	Group
FCLASSD (alias of FCLASS)	FCLASS (section 9.12)	010000 (0x10)	00101000 (0x28)	2, entry	Floating point (FESC)
FCLASSS (alias of FCLASS32)	FCLASS (section 9.12)	010000 (0x10)	00101001 (0x29)	2, entry	Floating point (FESC)
FCMP	FCMP (section 9.12)	100111 (0x27)		9, entry	Moves, address formation and the ALU
FCMP16	FHALF (section 9.12)	010000 (0x10)	01010101 (0x55)	2, entry	Floating point (FESC)
FCMP32	FSINGLE (section 9.12)	010000 (0x10)	00001101 (0x0D)	2, entry	Floating point (FESC)
FCMPD (alias of FCMP)	FCMP (section 9.12)	100111 (0x27)		9, entry	Moves, address formation and the ALU
FCMPS (alias of FCMP32)	FSINGLE (section 9.12)	010000 (0x10)	00001101 (0x0D)	2, entry	Floating point (FESC)
FCOPYSIGN	FSIGN (section 9.12)	010000 (0x10)	00100010 (0x22)	2, entry	Floating point (FESC)
FCVTDH	FCVTH (section 9.12)	010000 (0x10)	01100010 (0x62)	2, entry	Floating point (FESC)
FCVTDQ	FCVT (section 9.12)	010000 (0x10)	00111000 (0x38)	2, entry	Floating point (FESC)
FCVTDQU	FCVT (section 9.12)	010000 (0x10)	00111110 (0x3E)	2, entry	Floating point (FESC)
FCVTDS	FCVT (section 9.12)	010000 (0x10)	00111010 (0x3A)	2, entry	Floating point (FESC)
FCVTHD	FCVTH (section 9.12)	010000 (0x10)	01100011 (0x63)	2, entry	Floating point (FESC)
FCVTHL	FCVTH (section 9.12)	010000 (0x10)	01100100 (0x64)	2, entry	Floating point (FESC)
FCVTHS	FCVTH (section 9.12)	010000 (0x10)	01100001 (0x61)	2, entry	Floating point (FESC)
FCVTLH	FCVTH (section 9.12)	010000 (0x10)	01100101 (0x65)	2, entry	Floating point (FESC)
FCVTLS	FCVT (section 9.12)	010000 (0x10)	00111101 (0x3D)	2, entry	Floating point (FESC)
FCVTQD	FCVT (section 9.12)	010000 (0x10)	00111001 (0x39)	2, entry	Floating point (FESC)

Mnemonic	Entry	Opcode	Sub	Layouts	Group
FCVTQUD	FCVT (section 9.12)	010000 (0x10)	00111111 (0x3F)	2, entry	Floating point (FESC)
FCVTSD	FCVT (section 9.12)	010000 (0x10)	00111011 (0x3B)	2, entry	Floating point (FESC)
FCVTSH	FCVTH (section 9.12)	010000 (0x10)	01100000 (0x60)	2, entry	Floating point (FESC)
FCVTSL	FCVT (section 9.12)	010000 (0x10)	00111100 (0x3C)	2, entry	Floating point (FESC)
FDIV	FDIV (section 9.12)	010000 (0x10)	00000000 (0x00)	2, entry	Floating point (FESC)
FDIV16	FHALF (section 9.12)	010000 (0x10)	01010011 (0x53)	2, entry	Floating point (FESC)
FDIV32	FSINGLE (section 9.12)	010000 (0x10)	00001011 (0x0B)	2, entry	Floating point (FESC)
FDIVD (alias of FDIV)	FDIV (section 9.12)	010000 (0x10)	00000000 (0x00)	2, entry	Floating point (FESC)
FDIVS (alias of FDIV32)	FSINGLE (section 9.12)	010000 (0x10)	00001011 (0x0B)	2, entry	Floating point (FESC)
FENCE	FENCE (section 9.14)	010100 (0x14)	0110 (0x6)	3, entry	System (SYS)
FMADD	FMADD (section 9.12)	010000 (0x10)	00010000 (0x10)	2, entry	Floating point (FESC)
FMADD16	FHALF (section 9.12)	010000 (0x10)	01011000 (0x58)	2, entry	Floating point (FESC)
FMADD32	FMADD32 (section 9.12)	010000 (0x10)	00011000 (0x18)	2, entry	Floating point (FESC)
FMADDD (alias of FMADD)	FMADD (section 9.12)	010000 (0x10)	00010000 (0x10)	2, entry	Floating point (FESC)
FMADDS (alias of FMADD32)	FMADD32 (section 9.12)	010000 (0x10)	00011000 (0x18)	2, entry	Floating point (FESC)
FMAX	FMIN (section 9.12)	010000 (0x10)	00100100 (0x24)	2, entry	Floating point (FESC)
FMAXD (alias of FMAX)	FMIN (section 9.12)	010000 (0x10)	00100100 (0x24)	2, entry	Floating point (FESC)
FMIN	FMIN (section 9.12)	010000 (0x10)	00100011 (0x23)	2, entry	Floating point (FESC)
FMIND (alias of FMIN)	FMIN (section 9.12)	010000 (0x10)	00100011 (0x23)	2, entry	Floating point (FESC)
FMSUB	FMADD (section 9.12)	010000 (0x10)	00010001 (0x11)	2, entry	Floating point (FESC)
FMSUB16	FHALF (section 9.12)	010000 (0x10)	01011001 (0x59)	2, entry	Floating point (FESC)
FMSUB32	FMADD32 (section 9.12)	010000 (0x10)	00011001 (0x19)	2, entry	Floating point (FESC)

Mnemonic	Entry	Opcode	Sub	Layouts	Group
FMSUBD (alias of FMSUB)	FMADD (section 9.12)	010000 (0x10)	00010001 (0x11)	2, entry	Floating point (FESC)
FMSUBS (alias of FMSUB32)	FMADD32 (section 9.12)	010000 (0x10)	00011001 (0x19)	2, entry	Floating point (FESC)
FMUL	FADD (section 9.12)	100110 (0x26)		9, entry	Moves, address formation and the ALU
FMUL16	FHALF (section 9.12)	010000 (0x10)	01010010 (0x52)	2, entry	Floating point (FESC)
FMUL32	FSINGLE (section 9.12)	010000 (0x10)	00001010 (0x0A)	2, entry	Floating point (FESC)
FMULD (alias of FMUL)	FADD (section 9.12)	100110 (0x26)		9, entry	Moves, address formation and the ALU
FMULS (alias of FMUL32)	FSINGLE (section 9.12)	010000 (0x10)	00001010 (0x0A)	2, entry	Floating point (FESC)
FNEG	FSIGN (section 9.12)	010000 (0x10)	00100000 (0x20)	2, entry	Floating point (FESC)
FNMADD	FMADD (section 9.12)	010000 (0x10)	00010010 (0x12)	2, entry	Floating point (FESC)
FNMADD16	FHALF (section 9.12)	010000 (0x10)	01011010 (0x5A)	2, entry	Floating point (FESC)
FNMADD32	FMADD32 (section 9.12)	010000 (0x10)	00011010 (0x1A)	2, entry	Floating point (FESC)
FNMADDD (alias of FNMADD)	FMADD (section 9.12)	010000 (0x10)	00010010 (0x12)	2, entry	Floating point (FESC)
FNMADDS (alias of FNMADD32)	FMADD32 (section 9.12)	010000 (0x10)	00011010 (0x1A)	2, entry	Floating point (FESC)
FNMSUB	FMADD (section 9.12)	010000 (0x10)	00010011 (0x13)	2, entry	Floating point (FESC)
FNMSUB16	FHALF (section 9.12)	010000 (0x10)	01011011 (0x5B)	2, entry	Floating point (FESC)
FNMSUB32	FMADD32 (section 9.12)	010000 (0x10)	00011011 (0x1B)	2, entry	Floating point (FESC)
FNMSUBD (alias of FNMSUB)	FMADD (section 9.12)	010000 (0x10)	00010011 (0x13)	2, entry	Floating point (FESC)
FNMSUBS (alias of FNMSUB32)	FMADD32 (section 9.12)	010000 (0x10)	00011011 (0x1B)	2, entry	Floating point (FESC)
FRINT	FRINT (section 9.12)	010000 (0x10)	00110000 (0x30)	2, entry	Floating point (FESC)
FRINTA	FRINT (section 9.12)	010000 (0x10)	00110100 (0x34)	2, entry	Floating point (FESC)
FRINTD (alias of FRINT)	FRINT (section 9.12)	010000 (0x10)	00110000 (0x30)	2, entry	Floating point (FESC)
FRINTDA (alias of FRINTA)	FRINT (section 9.12)	010000 (0x10)	00110100 (0x34)	2, entry	Floating point (FESC)
FRINTDM (alias of FRINTM)	FRINT (section 9.12)	010000 (0x10)	00110010 (0x32)	2, entry	Floating point (FESC)
FRINTDP (alias of FRINTP)	FRINT (section 9.12)	010000 (0x10)	00110011 (0x33)	2, entry	Floating point (FESC)
FRINTDZ (alias of FRINTZ)	FRINT (section 9.12)	010000 (0x10)	00110001 (0x31)	2, entry	Floating point (FESC)
FRINTM	FRINT (section 9.12)	010000 (0x10)	00110010 (0x32)	2, entry	Floating point (FESC)
FRINTP	FRINT (section 9.12)	010000 (0x10)	00110011 (0x33)	2, entry	Floating point (FESC)
FRINTZ	FRINT (section 9.12)	010000 (0x10)	00110001 (0x31)	2, entry	Floating point (FESC)
FSFLAGS	FSFLAGS (section 9.12)	010000 (0x10)	01000000 (0x40)	2, entry	Floating point (FESC)
FSQRT	FDIV (section 9.12)	010000 (0x10)	00000001 (0x01)	2, entry	Floating point (FESC)
FSQRT16	FHALF (section 9.12)	010000 (0x10)	01010100 (0x54)	2, entry	Floating point (FESC)
FSQRT32	FSINGLE (section 9.12)	010000 (0x10)	00001100 (0x0C)	2, entry	Floating point (FESC)

Mnemonic	Entry	Opcode	Sub	Layouts	Group
FSQRTD (alias of FSQRT)	FDIV (section 9.12)	010000 (0x10)	00000001 (0x01)	2, entry	Floating point (FESC)
FSQRTS (alias of FSQRT32)	FSINGLE (section 9.12)	010000 (0x10)	00001100 (0x0C)	2, entry	Floating point (FESC)
FSUB	FADD (section 9.12)	100101 (0x25)		9, entry	Moves, address formation and the ALU
FSUB16	FHALF (section 9.12)	010000 (0x10)	01010001 (0x51)	2, entry	Floating point (FESC)
FSUB32	FSINGLE (section 9.12)	010000 (0x10)	00001001 (0x09)	2, entry	Floating point (FESC)
FSUBD (alias of FSUB)	FADD (section 9.12)	100101 (0x25)		9, entry	Moves, address formation and the ALU
FSUBS (alias of FSUB32)	FSINGLE (section 9.12)	010000 (0x10)	00001001 (0x09)	2, entry	Floating point (FESC)
HALT	HALT (section 9.14)	010100 (0x14)	0100 (0x4)	3, entry	System (SYS)

Mnemonic	Entry	Opcode	Sub	Layouts	Group
HINT	HINT (section 9.14)	010100 (0x14)	0011 (0x3)	2, entry	System (SYS)
ICINV	ICINV (section 9.14)	010100 (0x14)	1100 (0xC)	3, entry	System (SYS)
ICINVA	TLBA (section 9.14)	010100 (0x14)	1100 (0xC)	3, entry	System (SYS)
INC	INC (section 9.7)	010011 (0x13)	0010 (0x2)	9, entry	Single operand (SOP)
INSB	INSB (section 9.9)	001100 (0x0C)	00100011 (0x23)	2, entry	Bits and fields (BESC)
ISYNC	ISYNC (section 9.14)	010100 (0x14)	0010 (0x2)	2, entry	System (SYS)
JMP	JMP (section 9.10)	010011 (0x13)	1100 (0xC)	9, entry	Single operand (SOP)
JMPI	JMPI (section 9.10)	010010 (0x12)	0000 (0x0)	9, entry	Indirect transfers (XFER)
JTAG	JTAG (section 9.10)	010010 (0x12)	0010 (0x2)	9, entry	Indirect transfers (XFER)
LEA	LEA (section 9.6)	001011 (0x0B)		9, entry	Moves, address formation and the ALU
LL	LLSC (section 9.13)	010001 (0x11)	00100000 (0x20)	2, entry	Atomics (ATOM)
LPAD	NOP (section 9.14)	010100 (0x14)	1001 (0x9)	3, entry	System (SYS)
MAX	MINMAX (section 9.7)	001110 (0x0E)	00010010 (0x12)	2, entry	Arithmetic (AESC)
MAXU	MINMAX (section 9.7)	001110 (0x0E)	00010011 (0x13)	2, entry	Arithmetic (AESC)
MCMP	MCMP (section 9.11)	001101 (0x0D)	00000011 (0x03)	2, entry	Block memory (MBLK)
MCPY	MCPY (section 9.11)	001101 (0x0D)	00000000 (0x00)	2, entry	Block memory (MBLK)
MFASID	MTASID (section 9.14)	010100 (0x14)	0111 (0x7)	3, entry	System (SYS)
MFCPUID	MFCPUID (section 9.14)	010100 (0x14)	1011 (0xB)	3, entry	System (SYS)
MFDP	MTDP (section 9.14)	010100 (0x14)	1001 (0x9)	3, entry	System (SYS)
MFPS	MTPS (section 9.14)	010100 (0x14)	0010 (0x2)	3, entry	System (SYS)
MFSR	MFSR (section 9.14)	010100 (0x14)	1101 (0xD)	2, entry	System (SYS)
MIN	MINMAX (section 9.7)	001110 (0x0E)	00010000 (0x10)	2, entry	Arithmetic (AESC)
MINU	MINMAX (section 9.7)	001110 (0x0E)	00010001 (0x11)	2, entry	Arithmetic (AESC)
MMOV	MCPY (section 9.11)	001101 (0x0D)	00000001 (0x01)	2, entry	Block memory (MBLK)
MOD	DIV (section 9.7)	001110 (0x0E)	00000010 (0x02)	2, entry	Arithmetic (AESC)
MODU	DIV (section 9.7)	001110 (0x0E)	00000011 (0x03)	2, entry	Arithmetic (AESC)
MOVB	MOV (section 9.6)	000110 (0x06)		9, entry	Moves, address formation and the ALU
MOVL	MOV (section 9.6)	000010 (0x02)		9, entry	Moves, address formation and the ALU
MOVQ	MOV (section 9.6)	000000 (0x00)		9, entry	Moves, address formation and the ALU
MOVUB	MOVU (section 9.6)	001111 (0x0F)	00000000 (0x00)	2, entry	Memory escape (MESC)
MOVUL	MOVU (section 9.6)	001111 (0x0F)	00000100 (0x04)	2, entry	Memory escape (MESC)
MOVUQ	MOVU (section 9.6)	001111 (0x0F)	00000110 (0x06)	2, entry	Memory escape (MESC)
MOVUW	MOVU (section 9.6)	001111 (0x0F)	00000010 (0x02)	2, entry	Memory escape (MESC)
MOVW	MOV (section 9.6)	000100 (0x04)		9, entry	Moves, address formation and the ALU
MOVZB	MOVZ (section 9.6)	001010 (0x0A)		9, entry	Moves, address formation and the ALU
MOVZL	MOVZ (section 9.6)	001000 (0x08)		9, entry	Moves, address formation and the ALU
MOVZW	MOVZ (section 9.6)	001001 (0x09)		9, entry	Moves, address formation and the ALU
MSCN	MSCN (section 9.11)	001101 (0x0D)	00000100 (0x04)	2, entry	Block memory (MBLK)
MSCNN	MSCN (section 9.11)	001101 (0x0D)	00000101 (0x05)	2, entry	Block memory (MBLK)
MSET	MSET (section 9.11)	001101 (0x0D)	00000010 (0x02)	2, entry	Block memory (MBLK)

Mnemonic	Entry	Opcode	Sub	Layouts	Group
MTASID	MTASID (section 9.14)	010100 (0x14)	0110 (0x6)	3, entry	System (SYS)
MTDMW	MTDMW (section 9.14)	010100 (0x14)	1010 (0xA)	3, entry	System (SYS)
MTDP	MTDP (section 9.14)	010100 (0x14)	1000 (0x8)	3, entry	System (SYS)
MTPS	MTPS (section 9.14)	010100 (0x14)	0001 (0x1)	3, entry	System (SYS)

Mnemonic	Entry	Opcode	Sub	Layouts	Group
MTSR	MFSR (section 9.14)	010100 (0x14)	1110 (0xE)	2, entry	System (SYS)
MUL	MUL (section 9.7)	011110 (0x1E)		9, entry	Moves, address formation and the ALU
MULH	MULH (section 9.7)	011111 (0x1F)		9, entry	Moves, address formation and the ALU
MULHU	MULHU (section 9.7)	001110 (0x0E)	00000100 (0x04)	2, entry	Arithmetic (AESC)
MULU (alias of MUL)	MUL (section 9.7)	011110 (0x1E)		9, entry	Moves, address formation and the ALU
MVAL	MVAL (section 9.11)	001101 (0x0D)	00000110 (0x06)	2, entry	Block memory (MBLK)
NEG	NEG (section 9.7)	010011 (0x13)	0100 (0x4)	9, entry	Single operand (SOP)
NOP	NOP (section 9.14)	010100 (0x14)	0000 (0x0)	3, entry	System (SYS)
POP	POP (section 9.11)	010011 (0x13)	1111 (0xF)	9, entry	Single operand (SOP)
POPCNT	POPCNT (section 9.9)	001100 (0x0C)	00000100 (0x04)	2, entry	Bits and fields (BESC)
POPM	POPM (section 9.11)	010011 (0x13)	1011 (0xB)	9, entry	Single operand (SOP)
POPX	PUSHX (section 9.14)	010100 (0x14)	0001 (0x1)	2, entry	System (SYS)
PROBER	PROBE (section 9.14)	010100 (0x14)	1101 (0xD)	3, entry	System (SYS)
PROBEW	PROBE (section 9.14)	010100 (0x14)	1110 (0xE)	3, entry	System (SYS)
PUSH	PUSH (section 9.11)	010011 (0x13)	1110 (0xE)	9, entry	Single operand (SOP)
PUSHM	PUSHM (section 9.11)	010011 (0x13)	1010 (0xA)	9, entry	Single operand (SOP)
PUSHX	PUSHX (section 9.14)	010100 (0x14)	0000 (0x0)	2, entry	System (SYS)
RET	RET (section 9.14)	010100 (0x14)	0011 (0x3)	3, entry	System (SYS)
ROL (alias of RORI)	RORI (section 9.9)	001100 (0x0C)	00010001 (0x11)	2, entry	Bits and fields (BESC)
ROR	ROR (section 9.9)	001100 (0x0C)	00010000 (0x10)	2, entry	Bits and fields (BESC)
RORI	RORI (section 9.9)	001100 (0x0C)	00010001 (0x11)	2, entry	Bits and fields (BESC)
RORI32	RORI32 (section 9.9)	001100 (0x0C)	00010010 (0x12)	2, entry	Bits and fields (BESC)
RTI	RTI (section 9.14)	010100 (0x14)	0001 (0x1)	3, entry	System (SYS)
RTT	RTI (section 9.14)	010100 (0x14)	0010 (0x2)	3, entry	System (SYS)
SAR	SHIFT (section 9.8)	100010 (0x22)		9, entry	Moves, address formation and the ALU
SBC	SBC (section 9.7)	010011 (0x13)	0111 (0x7)	9, entry	Single operand (SOP)
SC	LLSC (section 9.13)	010001 (0x11)	00100001 (0x21)	2, entry	Atomics (ATOM)
SET	SET (section 9.7)	001110 (0x0E)	00100000 (0x20)	2, entry	Arithmetic (AESC)
SEV	SEV (section 9.14)	010100 (0x14)	1000 (0x8)	3, entry	System (SYS)
SHL	SHIFT (section 9.8)	100000 (0x20)		9, entry	Moves, address formation and the ALU
SHR	SHIFT (section 9.8)	100001 (0x21)		9, entry	Moves, address formation and the ALU
SOB	SOB (section 9.10)	111111 (0x3F)	00111111 (0x3F)	2, entry	Branches
SPL	SPL (section 9.14)	010100 (0x14)	0011 (0x3)	3, entry	System (SYS)
SUB	SUB (section 9.7)	010111 (0x17)		9, entry	Moves, address formation and the ALU
SUBM	ADDM (section 9.7)	001111 (0x0F)	00001001 (0x09)	2, entry	Memory escape (MESC)
SWAP	SWAP (section 9.13)	010001 (0x11)	00000010 (0x02)	2, entry	Atomics (ATOM)

Mnemonic	Entry	Opcode	Sub	Layouts	Group
SWAPDB	SWAP (section 9.13)	010001 (0x11)	00000011 (0x03)	2, entry	Atomics (ATOM)
TLBI	TLBI (section 9.14)	010100 (0x14)	0101 (0x5)	3, entry	System (SYS)
TLBIA	TLBA (section 9.14)	010100 (0x14)	1010 (0xA)	3, entry	System (SYS)
TLBSYNC	TLBA (section 9.14)	010100 (0x14)	1011 (0xB)	3, entry	System (SYS)
TRAP	TRAP (section 9.14)	010100 (0x14)	0100 (0x4)	3, entry	System (SYS)
TRAPL	TRAP (section 9.14)	010100 (0x14)	1111 (0xF)	3, entry	System (SYS)
TST	TST (section 9.8)	010011 (0x13)	0101 (0x5)	9, entry	Single operand (SOP)
UTF8DEC	UTF8DEC (section 9.9)	001100 (0x0C)	01000001 (0x41)	2, entry	Bits and fields (BESC)
UTF8ENC	UTF8ENC (section 9.9)	001100 (0x0C)	01000010 (0x42)	2, entry	Bits and fields (BESC)
UTF8LEN	UTF8LEN (section 9.9)	001100 (0x0C)	01000000 (0x40)	2, entry	Bits and fields (BESC)
WAIT (alias of WFE)	WFE (section 9.14)	010100 (0x14)	0111 (0x7)	3, entry	System (SYS)
WFE	WFE (section 9.14)	010100 (0x14)	0111 (0x7)	3, entry	System (SYS)
XADD	XADD (section 9.13)	010001 (0x11)	00000100 (0x04)	2, entry	Atomics (ATOM)
XADDDB	XADD (section 9.13)	010001 (0x11)	00000101 (0x05)	2, entry	Atomics (ATOM)
XAND	XAND (section 9.13)	010001 (0x11)	00000110 (0x06)	2, entry	Atomics (ATOM)
XANDDB	XAND (section 9.13)	010001 (0x11)	00000111 (0x07)	2, entry	Atomics (ATOM)
XMAX	XMAX (section 9.13)	010001 (0x11)	00001100 (0x0C)	2, entry	Atomics (ATOM)
XMAXDB	XMAX (section 9.13)	010001 (0x11)	00001101 (0x0D)	2, entry	Atomics (ATOM)

Mnemonic	Entry	Opcode	Sub	Layouts	Group
XMAXU	XMAX (section 9.13)	010001 (0x11)	00010000 (0x10)	2, entry	Atomics (ATOM)
XMAXUDB	XMAX (section 9.13)	010001 (0x11)	00010001 (0x11)	2, entry	Atomics (ATOM)
XMIN	XMAX (section 9.13)	010001 (0x11)	00001110 (0x0E)	2, entry	Atomics (ATOM)
XMINDB	XMAX (section 9.13)	010001 (0x11)	00001111 (0x0F)	2, entry	Atomics (ATOM)
XMINU	XMAX (section 9.13)	010001 (0x11)	00010010 (0x12)	2, entry	Atomics (ATOM)
XMINUDB	XMAX (section 9.13)	010001 (0x11)	00010011 (0x13)	2, entry	Atomics (ATOM)
XNORPOP	XNORPOP (section 9.9)	001100 (0x0C)	00110000 (0x30)	2, entry	Bits and fields (BESC)
XOR	XOR (section 9.8)	011100 (0x1C)		9, entry	Moves, address formation and the ALU
XOR_	XAND (section 9.13)	010001 (0x11)	00001000 (0x08)	2, entry	Atomics (ATOM)
XOR_DB	XAND (section 9.13)	010001 (0x11)	00001001 (0x09)	2, entry	Atomics (ATOM)
XXOR	XAND (section 9.13)	010001 (0x11)	00001010 (0x0A)	2, entry	Atomics (ATOM)
XXORDB	XAND (section 9.13)	010001 (0x11)	00001011 (0x0B)	2, entry	Atomics (ATOM)

The opcodes, in order

Generated by `tools/mkmanual.py`; do not edit.
The opcodes of the original encoding. The bit layout of each is in the bit layouts of every opcode.

Page 1

Opcode	Use
000000 (0x00)	MOVQ
000001 (0x01)	reserved
000010 (0x02)	MOVL
000011 (0x03)	reserved
000100 (0x04)	MOVW
000101 (0x05)	reserved
000110 (0x06)	MOVB
000111 (0x07)	reserved
001000 (0x08)	MOVZL
001001 (0x09)	MOVZW
001010 (0x0A)	MOVZB
001011 (0x0B)	LEA
001100 (0x0C)	CLZ, CTZ, CLO, CTO, POPCNT and 17 more (sub-opcodes in the entries)
001101 (0x0D)	MCPY, MMOV, MSET, MCMP, MSCN and 2 more (sub-opcodes in the entries)
001110 (0x0E)	DIV, DIVU, MOD, MODU, MULHU and 6 more (sub-opcodes in the entries)
001111 (0x0F)	MOVUB, MOVUW, MOVUL, MOVUQ, ADDM and 3 more (sub-opcodes in the entries)
010000 (0x10)	FDIV, FSQRT, FADD32, FSUB32, FMUL32 and 49 more (sub-opcodes in the entries)
010001 (0x11)	CAS, CASDB, SWAP, SWAPDB, XADD and 17 more (sub-opcodes in the entries)
010010 (0x12)	JMPI, CALLI, JTAG
010011 (0x13)	CLR, COM, INC, DEC, NEG and 11 more (sub-opcodes in the entries)
010100 (0x14)	NOP, RTI, RTT, RET, HALT and 29 more (sub-opcodes in the entries)
010101 (0x15)	BTAG, BNTAG
010110 (0x16)	ADD
010111 (0x17)	SUB
011000 (0x18)	BIC
011001 (0x19)	BIS
011010 (0x1A)	CMP
011011 (0x1B)	BIT
011100 (0x1C)	XOR
011101 (0x1D)	AND
011110 (0x1E)	MUL
011111 (0x1F)	MULH
100000 (0x20)	SHL
100001 (0x21)	SHR
100010 (0x22)	SAR
100011 (0x23)	spare ALU slot (decodes, traps)
100100 (0x24)	FADD
100101 (0x25)	FSUB
100110 (0x26)	FMUL
100111 (0x27)	FCMP

Opcode	Use
101000 (0x28)	CBNE, CBEQ, CBPL, CBMI, CBVC and 9 more (sub-opcodes in the entries)
101001 (0x29)	reserved
101010 (0x2A)	reserved
101011 (0x2B)	reserved
101100 (0x2C)	reserved

Opcode	Use
101101 (0x2D)	reserved
101110 (0x2E)	reserved
101111 (0x2F)	reserved
110000 (0x30)	BR
110001 (0x31)	BNE
110010 (0x32)	BEQ
110011 (0x33)	BPL
110100 (0x34)	BMI
110101 (0x35)	BVC
110110 (0x36)	BVS
110111 (0x37)	BCC
111000 (0x38)	BCS
111001 (0x39)	BGE
111010 (0x3A)	BLT
111011 (0x3B)	BGT
111100 (0x3C)	BLE
111101 (0x3D)	BHI
111110 (0x3E)	BLOS
111111 (0x3F)	SOB

Page 2

Opcode	Name
000000 (0x00)	ld.q
000001 (0x01)	st.q
000010 (0x02)	ld.l
000011 (0x03)	st.l
000100 (0x04)	ld.w
000101 (0x05)	st.w
000110 (0x06)	ld.b
000111 (0x07)	st.b
001000 (0x08)	ldz.l
001001 (0x09)	ldz.w
001010 (0x0A)	ldz.b
001011 (0x0B)	lea.sp
001100 (0x0C)	ldq.sp0
001101 (0x0D)	ldq.sp1
001110 (0x0E)	stq.sp
010000 (0x10)	ldl.sp0
010001 (0x11)	ldl.sp1
010010 (0x12)	stl.sp0
010011 (0x13)	stl.sp1
010100 (0x14)	ldq.d1
010101 (0x15)	ldq.d2
010110 (0x16)	ldq.d3
010111 (0x17)	ldq.d4
011000 (0x18)	stq.d1
011001 (0x19)	stq.d2
011010 (0x1A)	ldl.d1
011011 (0x1B)	ldl.d2
011100 (0x1C)	ldl.d3
011101 (0x1D)	ldl.d4
011110 (0x1E)	pushm8
011111 (0x1F)	popm8
100000 (0x20)	sub.sp
100001 (0x21)	add.sp
100010 (0x22)	movq.i
100011 (0x23)	shl.i
100100 (0x24)	shr.i
100101 (0x25)	sar.i
100110 (0x26)	and.i
100111 (0x27)	bis.i
101000 (0x28)	xor.i

Opcode	Name
101001 (0x29)	add.i

Opcode	Name
101010 (0x2A)	pushx
101011 (0x2B)	popx
101100 (0x2C)	isync
101101 (0x2D)	hint

The bit layouts of every opcode


Every opcode of the original encoding has a chart here: one for each distinct layout (class of instruction, length, and body) that the grammar admits. The fields and their widths are the bit rules of `spec/pdp64.hbnf.in` (parcel 0 is `len opcode reg low`, and the body that follows is chosen by the guards of its alternatives), the numbers are the enumerations of `spec/pdp64-mnemonics.hbnf`, and what a field is called is `spec/pdp64-layout.hbnf`. The charts are generated from those files by `tools/mkmanual.py`; changing a field in a grammar changes the chart.

How to read a chart. Each row is one 16-bit parcel, bit 15 on the left, the bit numbers above the boxes. A shaded box has a fixed value, written in it; a white box is a field of the instruction. Fields are named `opN.part` for the part of the Nth operand of the assembly syntax (`op1.d` is the displacement of the first operand); a field the layout splits is `name[1]`, `name[2]` from the top. A register field of 3 or 4 bits holds an index into the hot-register table of the ABI, not a register number.

The charts

Moves, address formation and the ALU


r20-mem-0: Moves, address formation and the ALU, one parcel (`len = 00`)



`reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
MOVQ	000000 (0x00), 000001 (0x01)
MOVL	000010 (0x02), 000011 (0x03)
MOVW	000100 (0x04), 000101 (0x05)
MOVB	000110 (0x06), 000111 (0x07)
MOVZL	001000 (0x08)
MOVZW	001001 (0x09)
MOVZB	001010 (0x0A)
LEA	001011 (0x0B)
ADD	010110 (0x16)
SUB	010111 (0x17)
BIC	011000 (0x18)
BIS	011001 (0x19)
CMP	011010 (0x1A)
BIT	011011 (0x1B)
XOR	011100 (0x1C)
AND	011101 (0x1D)
MUL	011110 (0x1E)
MULH	011111 (0x1F)
SHL	100000 (0x20)
SHR	100001 (0x21)
SAR	100010 (0x22)
FADD	100100 (0x24)
FSUB	100101 (0x25)
FMUL	100110 (0x26)
FCMP	100111 (0x27)

r20-mem-1: Moves, address formation and the ALU, two parcels (`len = 01`)




Addressing modes (`low`) that use this layout: `base` 0000, `postinc` 0110, `predec` 0111.

`reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
MOVQ	000000 (0x00), 000001 (0x01)
MOVL	000010 (0x02), 000011 (0x03)
MOVW	000100 (0x04), 000101 (0x05)
MOVB	000110 (0x06), 000111 (0x07)
MOVZL	001000 (0x08)
MOVZW	001001 (0x09)
MOVZB	001010 (0x0A)
LEA	001011 (0x0B)
ADD	010110 (0x16)
SUB	010111 (0x17)
BIC	011000 (0x18)
BIS	011001 (0x19)
CMP	011010 (0x1A)
BIT	011011 (0x1B)
XOR	011100 (0x1C)
AND	011101 (0x1D)
MUL	011110 (0x1E)
MULH	011111 (0x1F)
SHL	100000 (0x20)
SHR	100001 (0x21)
SAR	100010 (0x22)
FADD	100100 (0x24)
FSUB	100101 (0x25)
FMUL	100110 (0x26)
FCMP	100111 (0x27)

r20-mem-1-2: Moves, address formation and the ALU, two parcels (`len = 01`)



Addressing modes (`low`) that use this layout: `index` 0001.

`reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
MOVQ	000000 (0x00), 000001 (0x01)
MOVL	000010 (0x02), 000011 (0x03)
MOVW	000100 (0x04), 000101 (0x05)
MOVB	000110 (0x06), 000111 (0x07)
MOVZL	001000 (0x08)
MOVZW	001001 (0x09)
MOVZB	001010 (0x0A)

Mnemonic	Opcode
LEA	001011 (0x0B)
ADD	010110 (0x16)
SUB	010111 (0x17)
BIC	011000 (0x18)
BIS	011001 (0x19)
CMP	011010 (0x1A)
BIT	011011 (0x1B)
XOR	011100 (0x1C)
AND	011101 (0x1D)
MUL	011110 (0x1E)
MULH	011111 (0x1F)
SHL	100000 (0x20)
SHR	100001 (0x21)
SAR	100010 (0x22)
FADD	100100 (0x24)
FSUB	100101 (0x25)
FMUL	100110 (0x26)
FCMP	100111 (0x27)

r20-mem-1-3: Moves, address formation and the ALU, two parcels (`len = 01`)




Addressing modes (`low`) that use this layout: `pcrel` 0010, `imm` 0100, `abs` 0101.

`reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
MOVQ	000000 (0x00), 000001 (0x01)
MOVL	000010 (0x02), 000011 (0x03)
MOVW	000100 (0x04), 000101 (0x05)
MOVB	000110 (0x06), 000111 (0x07)
MOVZL	001000 (0x08)
MOVZW	001001 (0x09)
MOVZB	001010 (0x0A)
LEA	001011 (0x0B)
ADD	010110 (0x16)
SUB	010111 (0x17)
BIC	011000 (0x18)
BIS	011001 (0x19)
CMP	011010 (0x1A)
BIT	011011 (0x1B)
XOR	011100 (0x1C)
AND	011101 (0x1D)
MUL	011110 (0x1E)
MULH	011111 (0x1F)
SHL	100000 (0x20)
SHR	100001 (0x21)
SAR	100010 (0x22)
FADD	100100 (0x24)
FSUB	100101 (0x25)
FMUL	100110 (0x26)
FCMP	100111 (0x27)

r20-mem-1-4: Moves, address formation and the ALU, two parcels (`len = 01`)




Addressing modes (`low`) that use this layout: `dp` 0011.

`reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
MOVQ	000000 (0x00), 000001 (0x01)
MOVL	000010 (0x02), 000011 (0x03)
MOVW	000100 (0x04), 000101 (0x05)
MOVB	000110 (0x06), 000111 (0x07)
MOVZL	001000 (0x08)
MOVZW	001001 (0x09)
MOVZB	001010 (0x0A)
LEA	001011 (0x0B)
ADD	010110 (0x16)
SUB	010111 (0x17)
BIC	011000 (0x18)
BIS	011001 (0x19)
CMP	011010 (0x1A)
BIT	011011 (0x1B)
XOR	011100 (0x1C)
AND	011101 (0x1D)
MUL	011110 (0x1E)
MULH	011111 (0x1F)
SHL	100000 (0x20)
SHR	100001 (0x21)
SAR	100010 (0x22)
FADD	100100 (0x24)
FSUB	100101 (0x25)
FMUL	100110 (0x26)
FCMP	100111 (0x27)

r20-mem-2: Moves, address formation and the ALU, three parcels (`len = 10`)




Addressing modes (`low`) that use this layout: `base` 0000, `postinc` 0110, `predec` 0111.

`reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
MOVQ	000000 (0x00), 000001 (0x01)
MOVL	000010 (0x02), 000011 (0x03)
MOVW	000100 (0x04), 000101 (0x05)

Mnemonic	Opcode
MOVB	000110 (0x06), 000111 (0x07)
MOVZL	001000 (0x08)
MOVZW	001001 (0x09)
MOVZB	001010 (0x0A)
LEA	001011 (0x0B)
ADD	010110 (0x16)
SUB	010111 (0x17)
BIC	011000 (0x18)
BIS	011001 (0x19)
CMP	011010 (0x1A)
BIT	011011 (0x1B)
XOR	011100 (0x1C)
AND	011101 (0x1D)
MUL	011110 (0x1E)
MULH	011111 (0x1F)
SHL	100000 (0x20)
SHR	100001 (0x21)
SAR	100010 (0x22)
FADD	100100 (0x24)
FSUB	100101 (0x25)
FMUL	100110 (0x26)
FCMP	100111 (0x27)

r20-mem-2-2: Moves, address formation and the ALU, three parcels (`len = 10`)




Addressing modes (`low`) that use this layout: `index` 0001.
`reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
MOVQ	000000 (0x00), 000001 (0x01)
MOVL	000010 (0x02), 000011 (0x03)
MOVW	000100 (0x04), 000101 (0x05)
MOVB	000110 (0x06), 000111 (0x07)
MOVZL	001000 (0x08)
MOVZW	001001 (0x09)
MOVZB	001010 (0x0A)
LEA	001011 (0x0B)
ADD	010110 (0x16)
SUB	010111 (0x17)
BIC	011000 (0x18)
BIS	011001 (0x19)
CMP	011010 (0x1A)
BIT	011011 (0x1B)
XOR	011100 (0x1C)
AND	011101 (0x1D)
MUL	011110 (0x1E)
MULH	011111 (0x1F)
SHL	100000 (0x20)
SHR	100001 (0x21)
SAR	100010 (0x22)
FADD	100100 (0x24)

Mnemonic	Opcode
FSUB	100101 (0x25)
FMUL	100110 (0x26)
FCMP	100111 (0x27)


r20-mem-2-3: Moves, address formation and the ALU, three parcels (`len = 10`)



Addressing modes (`low`) that use this layout: `pcrel` 0010, `imm` 0100, `abs` 0101.
`reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
MOVQ	000000 (0x00), 000001 (0x01)
MOVL	000010 (0x02), 000011 (0x03)
MOVW	000100 (0x04), 000101 (0x05)
MOVB	000110 (0x06), 000111 (0x07)
MOVZL	001000 (0x08)
MOVZW	001001 (0x09)
MOVZB	001010 (0x0A)
LEA	001011 (0x0B)
ADD	010110 (0x16)
SUB	010111 (0x17)
BIC	011000 (0x18)
BIS	011001 (0x19)
CMP	011010 (0x1A)
BIT	011011 (0x1B)
XOR	011100 (0x1C)
AND	011101 (0x1D)
MUL	011110 (0x1E)
MULH	011111 (0x1F)
SHL	100000 (0x20)
SHR	100001 (0x21)
SAR	100010 (0x22)
FADD	100100 (0x24)
FSUB	100101 (0x25)
FMUL	100110 (0x26)
FCMP	100111 (0x27)

r20-mem-2-4: Moves, address formation and the ALU, three parcels (`len = 10`)




Addressing modes (`low`) that use this layout: `dp` 0011.

`reg` is the register `Rd` (the source of a store); `low` is a second register (`Rs`) at `len = 00` and the addressing mode from `len = 01`; the extension parcels hold the operand (section 9.5).

Mnemonic	Opcode
MOVQ	000000 (0x00), 000001 (0x01)
MOVL	000010 (0x02), 000011 (0x03)
MOVW	000100 (0x04), 000101 (0x05)
MOVB	000110 (0x06), 000111 (0x07)
MOVZL	001000 (0x08)
MOVZW	001001 (0x09)
MOVZB	001010 (0x0A)
LEA	001011 (0x0B)
ADD	010110 (0x16)
SUB	010111 (0x17)
BIC	011000 (0x18)
BIS	011001 (0x19)
CMP	011010 (0x1A)
BIT	011011 (0x1B)
XOR	011100 (0x1C)
AND	011101 (0x1D)
MUL	011110 (0x1E)
MULH	011111 (0x1F)
SHL	100000 (0x20)
SHR	100001 (0x21)
SAR	100010 (0x22)
FADD	100100 (0x24)
FSUB	100101 (0x25)
FMUL	100110 (0x26)
FCMP	100111 (0x27)

Conditional branches

r20-br-0: Conditional branches, one parcel (`len = 00`)




The displacement is signed and counts 2-byte parcels from the first parcel of the instruction.

Mnemonic	Opcode
BR	110000 (0x30)
BNE	110001 (0x31)
BEQ	110010 (0x32)
BPL	110011 (0x33)
BMI	110100 (0x34)
BVC	110101 (0x35)
BVS	110110 (0x36)
BCC	110111 (0x37)
BCS	111000 (0x38)

Mnemonic	Opcode
BGE	111001 (0x39)
BLT	111010 (0x3A)
BGT	111011 (0x3B)
BLE	111100 (0x3C)
BHI	111101 (0x3D)
BLOS	111110 (0x3E)


r20-br-1: Conditional branches, two parcels (`len = 01`)



The displacement is signed and counts 2-byte parcels from the first parcel of the instruction.

Mnemonic	Opcode
BR	110000 (0x30)
BNE	110001 (0x31)
BEQ	110010 (0x32)
BPL	110011 (0x33)
BMI	110100 (0x34)
BVC	110101 (0x35)
BVS	110110 (0x36)
BCC	110111 (0x37)
BCS	111000 (0x38)
BGE	111001 (0x39)
BLT	111010 (0x3A)
BGT	111011 (0x3B)
BLE	111100 (0x3C)
BHI	111101 (0x3D)
BLOS	111110 (0x3E)

r20-br-2: Conditional branches, three parcels (`len = 10`)



The displacement is signed and counts 2-byte parcels from the first parcel of the instruction.

Mnemonic	Opcode
BR	110000 (0x30)
BNE	110001 (0x31)
BEQ	110010 (0x32)
BPL	110011 (0x33)
BMI	110100 (0x34)
BVC	110101 (0x35)
BVS	110110 (0x36)
BCC	110111 (0x37)
BCS	111000 (0x38)
BGE	111001 (0x39)
BLT	111010 (0x3A)
BGT	111011 (0x3B)

Mnemonic	Opcode
BLE	111100 (0x3C)
BHI	111101 (0x3D)
BLOS	111110 (0x3E)

Compare and branch


r20-cb-1: Compare and branch, two parcels (`len = 01`)



`low` is the condition; the immediate and the displacement are signed.

Mnemonic	Opcode	low
CBNE	101000 (0x28)	0001 (0x1)
CBEQ	101000 (0x28)	0010 (0x2)
CBPL	101000 (0x28)	0011 (0x3)
CBMI	101000 (0x28)	0100 (0x4)
CBVC	101000 (0x28)	0101 (0x5)
CBVS	101000 (0x28)	0110 (0x6)
CBCC	101000 (0x28)	0111 (0x7)
CBCS	101000 (0x28)	1000 (0x8)
CBGE	101000 (0x28)	1001 (0x9)
CBLT	101000 (0x28)	1010 (0xA)
CBGT	101000 (0x28)	1011 (0xB)
CBLE	101000 (0x28)	1100 (0xC)
CBHI	101000 (0x28)	1101 (0xD)
CBLOS	101000 (0x28)	1110 (0xE)


r20-cb-1-2: Compare two registers and branch, two parcels (`len = 01`)



Parcel 1 starts with the condition; `Ra` and `Rb` are compared.

Mnemonic	Opcode	low
CBNE	101010 (0x2A)	0001 (0x1)
CBEQ	101010 (0x2A)	0010 (0x2)
CBPL	101010 (0x2A)	0011 (0x3)
CBMI	101010 (0x2A)	0100 (0x4)
CBVC	101010 (0x2A)	0101 (0x5)
CBVS	101010 (0x2A)	0110 (0x6)
CBCC	101010 (0x2A)	0111 (0x7)
CBCS	101010 (0x2A)	1000 (0x8)
CBGE	101010 (0x2A)	1001 (0x9)
CBLT	101010 (0x2A)	1010 (0xA)
CBGT	101010 (0x2A)	1011 (0xB)
CBLE	101010 (0x2A)	1100 (0xC)
CBHI	101010 (0x2A)	1101 (0xD)
CBLOS	101010 (0x2A)	1110 (0xE)


r20-cb-2: Compare and branch, three parcels (`len = 10`)



`low` is the condition; the immediate and the displacement are signed.

Mnemonic	Opcode	`low`
CBNE	101000 (0x28)	0001 (0x1)
CBEQ	101000 (0x28)	0010 (0x2)
CBPL	101000 (0x28)	0011 (0x3)
CBMI	101000 (0x28)	0100 (0x4)
CBVC	101000 (0x28)	0101 (0x5)
CBVS	101000 (0x28)	0110 (0x6)
CBCC	101000 (0x28)	0111 (0x7)
CBCS	101000 (0x28)	1000 (0x8)
CBGE	101000 (0x28)	1001 (0x9)
CBLT	101000 (0x28)	1010 (0xA)
CBGT	101000 (0x28)	1011 (0xB)
CBLE	101000 (0x28)	1100 (0xC)
CBHI	101000 (0x28)	1101 (0xD)
CBLOS	101000 (0x28)	1110 (0xE)


r20-cb-2-2: Compare and branch, three parcels (`len = 10`)



`low` is the condition; the immediate and the displacement are signed.

Mnemonic	Opcode	`low`
CBNE	101001 (0x29)	0001 (0x1)
CBEQ	101001 (0x29)	0010 (0x2)
CBPL	101001 (0x29)	0011 (0x3)
CBMI	101001 (0x29)	0100 (0x4)
CBVC	101001 (0x29)	0101 (0x5)
CBVS	101001 (0x29)	0110 (0x6)
CBCC	101001 (0x29)	0111 (0x7)
CBCS	101001 (0x29)	1000 (0x8)
CBGE	101001 (0x29)	1001 (0x9)
CBLT	101001 (0x29)	1010 (0xA)
CBGT	101001 (0x29)	1011 (0xB)
CBLE	101001 (0x29)	1100 (0xC)
CBHI	101001 (0x29)	1101 (0xD)
CBLOS	101001 (0x29)	1110 (0xE)

r20-cb-2-3: Compare two registers and branch, three parcels (`len = 10`)




Parcel 1 starts with the condition; `Ra` and `Rb` are compared.

Mnemonic	Opcode	low
CBNE	101010 (0x2A)	0001 (0x1)
CBEQ	101010 (0x2A)	0010 (0x2)
CBPL	101010 (0x2A)	0011 (0x3)
CBMI	101010 (0x2A)	0100 (0x4)
CBVC	101010 (0x2A)	0101 (0x5)
CBVS	101010 (0x2A)	0110 (0x6)
CBCC	101010 (0x2A)	0111 (0x7)
CBCS	101010 (0x2A)	1000 (0x8)
CBGE	101010 (0x2A)	1001 (0x9)
CBLT	101010 (0x2A)	1010 (0xA)
CBGT	101010 (0x2A)	1011 (0xB)
CBLE	101010 (0x2A)	1100 (0xC)
CBHI	101010 (0x2A)	1101 (0xD)
CBLOS	101010 (0x2A)	1110 (0xE)

SOB


r20-sob-1: SOB, two parcels (`len = 01`)



The displacement is signed and counts parcels.

Mnemonic	Opcode
SOB	111111 (0x3F)

r20-sob-2: SOB, three parcels (`len = 10`)




The displacement is signed and counts parcels.

Mnemonic	Opcode
SOB	111111 (0x3F)

Tag branches


r20-tag-1: Tag branches, two parcels (`len = 01`)



`sense` is 0 for `BTAG` and 1 for `BNTAG`; `tag` is the 3-bit tag.

Mnemonic	Opcode
BTAG	010101 (0x15)
BNTAG	010101 (0x15)

r20-tag-2: Tag branches, three parcels (`len = 10`)




`sense` is 0 for `BTAG` and 1 for `BNTAG`; `tag` is the 3-bit tag.

Mnemonic	Opcode
BTAG	010101 (0x15)
BNTAG	010101 (0x15)

Single operand (SOP)

r20-sop-0: Single operand (SOP), one parcel (`len = 00`)




The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
CLR	010011 (0x13)	0000 (0x0)
COM	010011 (0x13)	0001 (0x1)
INC	010011 (0x13)	0010 (0x2)
DEC	010011 (0x13)	0011 (0x3)
NEG	010011 (0x13)	0100 (0x4)
TST	010011 (0x13)	0101 (0x5)
ADC	010011 (0x13)	0110 (0x6)
SBC	010011 (0x13)	0111 (0x7)
ASL	010011 (0x13)	1000 (0x8)
ASR	010011 (0x13)	1001 (0x9)
PUSHM	010011 (0x13)	1010 (0xA)
POPM	010011 (0x13)	1011 (0xB)
JMP	010011 (0x13)	1100 (0xC)

Mnemonic	Opcode	reg
CALL	010011 (0x13)	1101 (0xD)
PUSH	010011 (0x13)	1110 (0xE)
POP	010011 (0x13)	1111 (0xF)


r20-sop-1: Single operand (SOP), two parcels (`len = 01`)



Addressing modes (`low`) that use this layout: `base` 0000, `postinc` 0110, `predec` 0111.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
CLR	010011 (0x13)	0000 (0x0)
COM	010011 (0x13)	0001 (0x1)
INC	010011 (0x13)	0010 (0x2)
DEC	010011 (0x13)	0011 (0x3)
NEG	010011 (0x13)	0100 (0x4)
TST	010011 (0x13)	0101 (0x5)
ADC	010011 (0x13)	0110 (0x6)
SBC	010011 (0x13)	0111 (0x7)
ASL	010011 (0x13)	1000 (0x8)
ASR	010011 (0x13)	1001 (0x9)
PUSHM	010011 (0x13)	1010 (0xA)
POPM	010011 (0x13)	1011 (0xB)
JMP	010011 (0x13)	1100 (0xC)
CALL	010011 (0x13)	1101 (0xD)
PUSH	010011 (0x13)	1110 (0xE)
POP	010011 (0x13)	1111 (0xF)

r20-sop-1-2: Single operand (SOP), two parcels (`len = 01`)




Addressing modes (`low`) that use this layout: `index` 0001.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
CLR	010011 (0x13)	0000 (0x0)
COM	010011 (0x13)	0001 (0x1)
INC	010011 (0x13)	0010 (0x2)
DEC	010011 (0x13)	0011 (0x3)
NEG	010011 (0x13)	0100 (0x4)
TST	010011 (0x13)	0101 (0x5)
ADC	010011 (0x13)	0110 (0x6)
SBC	010011 (0x13)	0111 (0x7)
ASL	010011 (0x13)	1000 (0x8)
ASR	010011 (0x13)	1001 (0x9)
PUSHM	010011 (0x13)	1010 (0xA)
POPM	010011 (0x13)	1011 (0xB)
JMP	010011 (0x13)	1100 (0xC)
CALL	010011 (0x13)	1101 (0xD)
PUSH	010011 (0x13)	1110 (0xE)

Mnemonic	Opcode	reg
POP	010011 (0x13)	1111 (0xF)


r20-sop-1-3: Single operand (SOP), two parcels (`len = 01`)



Addressing modes (`low`) that use this layout: `pcrel` 0010, `imm` 0100, `abs` 0101.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
CLR	010011 (0x13)	0000 (0x0)
COM	010011 (0x13)	0001 (0x1)
INC	010011 (0x13)	0010 (0x2)
DEC	010011 (0x13)	0011 (0x3)
NEG	010011 (0x13)	0100 (0x4)
TST	010011 (0x13)	0101 (0x5)
ADC	010011 (0x13)	0110 (0x6)
SBC	010011 (0x13)	0111 (0x7)
ASL	010011 (0x13)	1000 (0x8)
ASR	010011 (0x13)	1001 (0x9)
PUSHM	010011 (0x13)	1010 (0xA)
POPM	010011 (0x13)	1011 (0xB)
JMP	010011 (0x13)	1100 (0xC)
CALL	010011 (0x13)	1101 (0xD)
PUSH	010011 (0x13)	1110 (0xE)
POP	010011 (0x13)	1111 (0xF)


r20-sop-1-4: Single operand (SOP), two parcels (`len = 01`)



Addressing modes (`low`) that use this layout: `dp` 0011.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
CLR	010011 (0x13)	0000 (0x0)
COM	010011 (0x13)	0001 (0x1)
INC	010011 (0x13)	0010 (0x2)
DEC	010011 (0x13)	0011 (0x3)
NEG	010011 (0x13)	0100 (0x4)
TST	010011 (0x13)	0101 (0x5)
ADC	010011 (0x13)	0110 (0x6)
SBC	010011 (0x13)	0111 (0x7)
ASL	010011 (0x13)	1000 (0x8)
ASR	010011 (0x13)	1001 (0x9)
PUSHM	010011 (0x13)	1010 (0xA)
POPM	010011 (0x13)	1011 (0xB)
JMP	010011 (0x13)	1100 (0xC)
CALL	010011 (0x13)	1101 (0xD)
PUSH	010011 (0x13)	1110 (0xE)
POP	010011 (0x13)	1111 (0xF)


r20-sop-2: Single operand (SOP), three parcels (`len = 10`)



Addressing modes (`low`) that use this layout: `base` 0000, `postinc` 0110, `predec` 0111.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	`reg`
CLR	010011 (0x13)	0000 (0x0)
COM	010011 (0x13)	0001 (0x1)
INC	010011 (0x13)	0010 (0x2)
DEC	010011 (0x13)	0011 (0x3)
NEG	010011 (0x13)	0100 (0x4)
TST	010011 (0x13)	0101 (0x5)
ADC	010011 (0x13)	0110 (0x6)
SBC	010011 (0x13)	0111 (0x7)
ASL	010011 (0x13)	1000 (0x8)
ASR	010011 (0x13)	1001 (0x9)
PUSHM	010011 (0x13)	1010 (0xA)
POPM	010011 (0x13)	1011 (0xB)
JMP	010011 (0x13)	1100 (0xC)
CALL	010011 (0x13)	1101 (0xD)
PUSH	010011 (0x13)	1110 (0xE)
POP	010011 (0x13)	1111 (0xF)

r20-sop-2-2: Single operand (SOP), three parcels (`len = 10`)




Addressing modes (`low`) that use this layout: `index` 0001.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	`reg`
CLR	010011 (0x13)	0000 (0x0)
COM	010011 (0x13)	0001 (0x1)
INC	010011 (0x13)	0010 (0x2)
DEC	010011 (0x13)	0011 (0x3)
NEG	010011 (0x13)	0100 (0x4)
TST	010011 (0x13)	0101 (0x5)
ADC	010011 (0x13)	0110 (0x6)
SBC	010011 (0x13)	0111 (0x7)
ASL	010011 (0x13)	1000 (0x8)
ASR	010011 (0x13)	1001 (0x9)
PUSHM	010011 (0x13)	1010 (0xA)
POPM	010011 (0x13)	1011 (0xB)

Mnemonic	Opcode	reg
JMP	010011 (0x13)	1100 (0xC)
CALL	010011 (0x13)	1101 (0xD)
PUSH	010011 (0x13)	1110 (0xE)
POP	010011 (0x13)	1111 (0xF)


r20-sop-2-3: Single operand (SOP), three parcels (`len = 10`)



Addressing modes (`low`) that use this layout: `pcrel` 0010, `imm` 0100, `abs` 0101.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
CLR	010011 (0x13)	0000 (0x0)
COM	010011 (0x13)	0001 (0x1)
INC	010011 (0x13)	0010 (0x2)
DEC	010011 (0x13)	0011 (0x3)
NEG	010011 (0x13)	0100 (0x4)
TST	010011 (0x13)	0101 (0x5)
ADC	010011 (0x13)	0110 (0x6)
SBC	010011 (0x13)	0111 (0x7)
ASL	010011 (0x13)	1000 (0x8)
ASR	010011 (0x13)	1001 (0x9)
PUSHM	010011 (0x13)	1010 (0xA)
POPM	010011 (0x13)	1011 (0xB)
JMP	010011 (0x13)	1100 (0xC)
CALL	010011 (0x13)	1101 (0xD)
PUSH	010011 (0x13)	1110 (0xE)
POP	010011 (0x13)	1111 (0xF)

r20-sop-2-4: Single operand (SOP), three parcels (`len = 10`)




Addressing modes (`low`) that use this layout: `dp` 0011.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
CLR	010011 (0x13)	0000 (0x0)
COM	010011 (0x13)	0001 (0x1)
INC	010011 (0x13)	0010 (0x2)
DEC	010011 (0x13)	0011 (0x3)
NEG	010011 (0x13)	0100 (0x4)
TST	010011 (0x13)	0101 (0x5)

Mnemonic	Opcode	reg
ADC	010011 (0x13)	0110 (0x6)
SBC	010011 (0x13)	0111 (0x7)
ASL	010011 (0x13)	1000 (0x8)
ASR	010011 (0x13)	1001 (0x9)
PUSHM	010011 (0x13)	1010 (0xA)
POPM	010011 (0x13)	1011 (0xB)
JMP	010011 (0x13)	1100 (0xC)
CALL	010011 (0x13)	1101 (0xD)
PUSH	010011 (0x13)	1110 (0xE)
POP	010011 (0x13)	1111 (0xF)

Indirect transfers (XFER)


r20-xfer-0: Indirect transfers (XFER), one parcel (`len = 00`)



The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
JMPI	010010 (0x12)	0000 (0x0)
CALLI	010010 (0x12)	0001 (0x1)
JTAG	010010 (0x12)	0010 (0x2)


r20-xfer-1: Indirect transfers (XFER), two parcels (`len = 01`)



Addressing modes (`low`) that use this layout: `base` 0000, `postinc` 0110, `predec` 0111.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
JMPI	010010 (0x12)	0000 (0x0)
CALLI	010010 (0x12)	0001 (0x1)
JTAG	010010 (0x12)	0010 (0x2)

r20-xfer-1-2: Indirect transfers (XFER), two parcels (`len = 01`)



Addressing modes (`low`) that use this layout: `index` 0001.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	reg
JMPI	010010 (0x12)	0000 (0x0)
CALLI	010010 (0x12)	0001 (0x1)
JTAG	010010 (0x12)	0010 (0x2)


r20-xfer-1-3: Indirect transfers (XFER), two parcels (`len = 01`)



Addressing modes (`low`) that use this layout: `pcrel` 0010, `imm` 0100, `abs` 0101.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	`reg`
JMPI	010010 (0x12)	0000 (0x0)
CALLI	010010 (0x12)	0001 (0x1)
JTAG	010010 (0x12)	0010 (0x2)


r20-xfer-1-4: Indirect transfers (XFER), two parcels (`len = 01`)



Addressing modes (`low`) that use this layout: `dp` 0011.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	`reg`
JMPI	010010 (0x12)	0000 (0x0)
CALLI	010010 (0x12)	0001 (0x1)
JTAG	010010 (0x12)	0010 (0x2)


r20-xfer-2: Indirect transfers (XFER), three parcels (`len = 10`)



Addressing modes (`low`) that use this layout: `base` 0000, `postinc` 0110, `predec` 0111.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	`reg`
JMPI	010010 (0x12)	0000 (0x0)
CALLI	010010 (0x12)	0001 (0x1)
JTAG	010010 (0x12)	0010 (0x2)


r20-xfer-2-2: Indirect transfers (XFER), three parcels (`len = 10`)



Addressing modes (`low`) that use this layout: `index` 0001.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	`reg`
`JMPI`	`010010 (0x12)`	`0000 (0x0)`
`CALLI`	`010010 (0x12)`	`0001 (0x1)`
`JTAG`	`010010 (0x12)`	`0010 (0x2)`


r20-xfer-2-3: Indirect transfers (XFER), three parcels (`len = 10`)



Addressing modes (`low`) that use this layout: `pcrel` 0010, `imm` 0100, `abs` 0101.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	`reg`
`JMPI`	`010010 (0x12)`	`0000 (0x0)`
`CALLI`	`010010 (0x12)`	`0001 (0x1)`
`JTAG`	`010010 (0x12)`	`0010 (0x2)`

r20-xfer-2-4: Indirect transfers (XFER), three parcels (`len = 10`)




Addressing modes (`low`) that use this layout: `dp` 0011.
The `reg` field is the sub-opcode; the operand is `rm` with its mode, at any length.

Mnemonic	Opcode	`reg`
`JMPI`	`010010 (0x12)`	`0000 (0x0)`

Mnemonic	Opcode	reg
CALLI	010010 (0x12)	0001 (0x1)
JTAG	010010 (0x12)	0010 (0x2)

Bits and fields (BESC)


r20-besc-1: Bits and fields (BESC), two parcels (`len = 01`)



From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
CLZ	001100 (0x0C)	00000000 (0x00)
CTZ	001100 (0x0C)	00000001 (0x01)
CLO	001100 (0x0C)	00000010 (0x02)
CTO	001100 (0x0C)	00000011 (0x03)
POPCNT	001100 (0x0C)	00000100 (0x04)
BSWAP	001100 (0x0C)	00000101 (0x05)
BSWAPW	001100 (0x0C)	00000110 (0x06)
BSWAPL	001100 (0x0C)	00000111 (0x07)
BITREV	001100 (0x0C)	00001000 (0x08)
ROR	001100 (0x0C)	00010000 (0x10)
DSHR	001100 (0x0C)	00100000 (0x20)
EXTB	001100 (0x0C)	00100001 (0x21)
EXTZB	001100 (0x0C)	00100010 (0x22)
INSB	001100 (0x0C)	00100011 (0x23)
XNORPOP	001100 (0x0C)	00110000 (0x30)
CLMULL	001100 (0x0C)	00110001 (0x31)
CLMULH	001100 (0x0C)	00110010 (0x32)
UTF8LEN	001100 (0x0C)	01000000 (0x40)
UTF8DEC	001100 (0x0C)	01000001 (0x41)
UTF8ENC	001100 (0x0C)	01000010 (0x42)


r20-besc-1-2: Bits and fields (BESC), two parcels (`len = 01`)



From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
RORI	001100 (0x0C)	00010001 (0x11)
RORI32	001100 (0x0C)	00010010 (0x12)


r20-besc-2: Bits and fields (BESC), three parcels (`len = 10`)



From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
CLZ	001100 (0x0C)	00000000 (0x00)
CTZ	001100 (0x0C)	00000001 (0x01)
CLO	001100 (0x0C)	00000010 (0x02)
CTO	001100 (0x0C)	00000011 (0x03)
POPCNT	001100 (0x0C)	00000100 (0x04)
BSWAP	001100 (0x0C)	00000101 (0x05)
BSWAPW	001100 (0x0C)	00000110 (0x06)
BSWAPL	001100 (0x0C)	00000111 (0x07)
BITREV	001100 (0x0C)	00001000 (0x08)
ROR	001100 (0x0C)	00010000 (0x10)
XNORPOP	001100 (0x0C)	00110000 (0x30)
CLMULL	001100 (0x0C)	00110001 (0x31)
CLMULH	001100 (0x0C)	00110010 (0x32)
UTF8LEN	001100 (0x0C)	01000000 (0x40)
UTF8DEC	001100 (0x0C)	01000001 (0x41)
UTF8ENC	001100 (0x0C)	01000010 (0x42)


r20-besc-2-2: Bits and fields (BESC), three parcels (`len = 10`)



From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
RORI	001100 (0x0C)	00010001 (0x11)
RORI32	001100 (0x0C)	00010010 (0x12)

r20-besc-2-3: Bits and fields (BESC), three parcels (`len = 10`)




From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
DSHR	001100 (0x0C)	00100000 (0x20)
EXTB	001100 (0x0C)	00100001 (0x21)
EXTZB	001100 (0x0C)	00100010 (0x22)
INSB	001100 (0x0C)	00100011 (0x23)

Block memory (MBLK)


r20-mblk-1: Block memory (MBLK), two parcels (`len = 01`)



`reg` is the destination pointer, `low` the source pointer (or the value register), `Rn` the count register.

Mnemonic	Opcode	Sub-opcode
MCPY	001101 (0x0D)	00000000 (0x00)
MMOV	001101 (0x0D)	00000001 (0x01)
MSET	001101 (0x0D)	00000010 (0x02)
MCMP	001101 (0x0D)	00000011 (0x03)
MSCN	001101 (0x0D)	00000100 (0x04)
MSCNN	001101 (0x0D)	00000101 (0x05)
MVAL	001101 (0x0D)	00000110 (0x06)

r20-mblk-2: Block memory (MBLK), three parcels (`len = 10`)




`reg` is the destination pointer, `low` the source pointer (or the value register), `Rn` the count register.

Mnemonic	Opcode	Sub-opcode
MCPY	001101 (0x0D)	00000000 (0x00)
MMOV	001101 (0x0D)	00000001 (0x01)
MSET	001101 (0x0D)	00000010 (0x02)

Mnemonic	Opcode	Sub-opcode
MCMP	001101 (0x0D)	00000011 (0x03)
MSCN	001101 (0x0D)	00000100 (0x04)
MSCNN	001101 (0x0D)	00000101 (0x05)
MVAL	001101 (0x0D)	00000110 (0x06)

Arithmetic (AESC)


r20-aesc-1: Arithmetic (AESC), two parcels (`len = 01`)



From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
DIV	001110 (0x0E)	00000000 (0x00)
DIVU	001110 (0x0E)	00000001 (0x01)
MOD	001110 (0x0E)	00000010 (0x02)
MODU	001110 (0x0E)	00000011 (0x03)
MULHU	001110 (0x0E)	00000100 (0x04)
ABS	001110 (0x0E)	00001000 (0x08)
MIN	001110 (0x0E)	00010000 (0x10)
MINU	001110 (0x0E)	00010001 (0x11)
MAX	001110 (0x0E)	00010010 (0x12)
MAXU	001110 (0x0E)	00010011 (0x13)
SET	001110 (0x0E)	00100000 (0x20)

r20-aesc-2: Arithmetic (AESC), three parcels (`len = 10`)




From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
DIV	001110 (0x0E)	00000000 (0x00)
DIVU	001110 (0x0E)	00000001 (0x01)
MOD	001110 (0x0E)	00000010 (0x02)
MODU	001110 (0x0E)	00000011 (0x03)
MULHU	001110 (0x0E)	00000100 (0x04)
ABS	001110 (0x0E)	00001000 (0x08)
MIN	001110 (0x0E)	00010000 (0x10)
MINU	001110 (0x0E)	00010001 (0x11)
MAX	001110 (0x0E)	00010010 (0x12)
MAXU	001110 (0x0E)	00010011 (0x13)
SET	001110 (0x0E)	00100000 (0x20)

Floating point (FESC)

r20-fesc-1: Floating point (FESC), two parcels (`len = 01`)




From `len = 01`. In this group `low` is a register, never a mode.

Mnemonic	Opcode	Sub-opcode
FDIV	010000 (0x10)	00000000 (0x00)
FSQRT	010000 (0x10)	00000001 (0x01)
FADD32	010000 (0x10)	00001000 (0x08)
FSUB32	010000 (0x10)	00001001 (0x09)
FMUL32	010000 (0x10)	00001010 (0x0A)
FDIV32	010000 (0x10)	00001011 (0x0B)
FSQRT32	010000 (0x10)	00001100 (0x0C)
FCMP32	010000 (0x10)	00001101 (0x0D)
FMADD	010000 (0x10)	00010000 (0x10)
FMSUB	010000 (0x10)	00010001 (0x11)
FNMADD	010000 (0x10)	00010010 (0x12)
FNMSUB	010000 (0x10)	00010011 (0x13)
FMADD32	010000 (0x10)	00011000 (0x18)
FMSUB32	010000 (0x10)	00011001 (0x19)
FNMADD32	010000 (0x10)	00011010 (0x1A)
FNMSUB32	010000 (0x10)	00011011 (0x1B)
FNEG	010000 (0x10)	00100000 (0x20)
FABS	010000 (0x10)	00100001 (0x21)
FCOPYSIGN	010000 (0x10)	00100010 (0x22)
FMIN	010000 (0x10)	00100011 (0x23)
FMAX	010000 (0x10)	00100100 (0x24)
FCLASS	010000 (0x10)	00101000 (0x28)
FCLASS32	010000 (0x10)	00101001 (0x29)
FRINT	010000 (0x10)	00110000 (0x30)
FRINTZ	010000 (0x10)	00110001 (0x31)
FRINTM	010000 (0x10)	00110010 (0x32)
FRINTP	010000 (0x10)	00110011 (0x33)
FRINTA	010000 (0x10)	00110100 (0x34)
FCVTDQ	010000 (0x10)	00111000 (0x38)
FCVTQD	010000 (0x10)	00111001 (0x39)
FCVTDS	010000 (0x10)	00111010 (0x3A)
FCVTSD	010000 (0x10)	00111011 (0x3B)
FCVTSL	010000 (0x10)	00111100 (0x3C)
FCVTLS	010000 (0x10)	00111101 (0x3D)
FCVTDQU	010000 (0x10)	00111110 (0x3E)
FCVTQUD	010000 (0x10)	00111111 (0x3F)
FSFLAGS	010000 (0x10)	01000000 (0x40)
FADD16	010000 (0x10)	01010000 (0x50)
FSUB16	010000 (0x10)	01010001 (0x51)
FMUL16	010000 (0x10)	01010010 (0x52)

Mnemonic	Opcode	Sub-opcode
FDIV16	010000 (0x10)	01010011 (0x53)
FSQRT16	010000 (0x10)	01010100 (0x54)
FCMP16	010000 (0x10)	01010101 (0x55)
FMADD16	010000 (0x10)	01011000 (0x58)
FMSUB16	010000 (0x10)	01011001 (0x59)
FNMADD16	010000 (0x10)	01011010 (0x5A)
FNMSUB16	010000 (0x10)	01011011 (0x5B)
FCLASS16	010000 (0x10)	01011100 (0x5C)
FCVTSH	010000 (0x10)	01100000 (0x60)
FCVTHS	010000 (0x10)	01100001 (0x61)
FCVTDH	010000 (0x10)	01100010 (0x62)

Mnemonic	Opcode	Sub-opcode
FCVTHD	010000 (0x10)	01100011 (0x63)
FCVTHL	010000 (0x10)	01100100 (0x64)
FCVTLH	010000 (0x10)	01100101 (0x65)

r20-fesc-2: Floating point (FESC), three parcels (`len = 10`)



From `len = 01`. In this group `low` is a register, never a mode.


Mnemonic	Opcode	Sub-opcode
FDIV	010000 (0x10)	00000000 (0x00)
FSQRT	010000 (0x10)	00000001 (0x01)
FADD32	010000 (0x10)	00001000 (0x08)
FSUB32	010000 (0x10)	00001001 (0x09)
FMUL32	010000 (0x10)	00001010 (0x0A)
FDIV32	010000 (0x10)	00001011 (0x0B)
FSQRT32	010000 (0x10)	00001100 (0x0C)
FCMP32	010000 (0x10)	00001101 (0x0D)
FMADD	010000 (0x10)	00010000 (0x10)
FMSUB	010000 (0x10)	00010001 (0x11)
FNMADD	010000 (0x10)	00010010 (0x12)
FNMSUB	010000 (0x10)	00010011 (0x13)
FMADD32	010000 (0x10)	00011000 (0x18)
FMSUB32	010000 (0x10)	00011001 (0x19)
FNMADD32	010000 (0x10)	00011010 (0x1A)
FNMSUB32	010000 (0x10)	00011011 (0x1B)
FNEG	010000 (0x10)	00100000 (0x20)
FABS	010000 (0x10)	00100001 (0x21)
FCOPYSIGN	010000 (0x10)	00100010 (0x22)
FMIN	010000 (0x10)	00100011 (0x23)
FMAX	010000 (0x10)	00100100 (0x24)
FCLASS	010000 (0x10)	00101000 (0x28)
FCLASS32	010000 (0x10)	00101001 (0x29)
FRINT	010000 (0x10)	00110000 (0x30)
FRINTZ	010000 (0x10)	00110001 (0x31)
FRINTM	010000 (0x10)	00110010 (0x32)
FRINTP	010000 (0x10)	00110011 (0x33)
FRINTA	010000 (0x10)	00110100 (0x34)
FCVTDQ	010000 (0x10)	00111000 (0x38)
FCVTQD	010000 (0x10)	00111001 (0x39)
FCVTDS	010000 (0x10)	00111010 (0x3A)
FCVTSD	010000 (0x10)	00111011 (0x3B)
FCVTSL	010000 (0x10)	00111100 (0x3C)
FCVTLS	010000 (0x10)	00111101 (0x3D)
FCVTDQU	010000 (0x10)	00111110 (0x3E)
FCVTQUD	010000 (0x10)	00111111 (0x3F)
FSFLAGS	010000 (0x10)	01000000 (0x40)
FADD16	010000 (0x10)	01010000 (0x50)
FSUB16	010000 (0x10)	01010001 (0x51)
FMUL16	010000 (0x10)	01010010 (0x52)

Mnemonic	Opcode	Sub-opcode
FDIV16	010000 (0x10)	01010011 (0x53)
FSQRT16	010000 (0x10)	01010100 (0x54)
FCMP16	010000 (0x10)	01010101 (0x55)

Mnemonic	Opcode	Sub-opcode
FMADD16	010000 (0x10)	01011000 (0x58)
FMSUB16	010000 (0x10)	01011001 (0x59)
FNMADD16	010000 (0x10)	01011010 (0x5A)
FNMSUB16	010000 (0x10)	01011011 (0x5B)
FCLASS16	010000 (0x10)	01011100 (0x5C)
FCVTSH	010000 (0x10)	01100000 (0x60)
FCVTHS	010000 (0x10)	01100001 (0x61)
FCVTDH	010000 (0x10)	01100010 (0x62)
FCVTHD	010000 (0x10)	01100011 (0x63)
FCVTHL	010000 (0x10)	01100100 (0x64)
FCVTLH	010000 (0x10)	01100101 (0x65)

Atomics (ATOM)


r20-atom-1: Atomics (ATOM), two parcels (`len = 01`)



From `len = 01`. The placement of the operands is not specified.

Mnemonic	Opcode	Sub-opcode
CAS	010001 (0x11)	00000000 (0x00)
CASDB	010001 (0x11)	00000001 (0x01)
SWAP	010001 (0x11)	00000010 (0x02)
SWAPDB	010001 (0x11)	00000011 (0x03)
XADD	010001 (0x11)	00000100 (0x04)
XADDDB	010001 (0x11)	00000101 (0x05)
XAND	010001 (0x11)	00000110 (0x06)
XANDDB	010001 (0x11)	00000111 (0x07)
XOR_	010001 (0x11)	00001000 (0x08)
XOR_DB	010001 (0x11)	00001001 (0x09)
XXOR	010001 (0x11)	00001010 (0x0A)
XXORDB	010001 (0x11)	00001011 (0x0B)
XMAX	010001 (0x11)	00001100 (0x0C)
XMAXDB	010001 (0x11)	00001101 (0x0D)
XMIN	010001 (0x11)	00001110 (0x0E)
XMINDB	010001 (0x11)	00001111 (0x0F)
XMAXU	010001 (0x11)	00010000 (0x10)
XMAXUDB	010001 (0x11)	00010001 (0x11)
XMINU	010001 (0x11)	00010010 (0x12)
XMINUDB	010001 (0x11)	00010011 (0x13)
LL	010001 (0x11)	00100000 (0x20)
SC	010001 (0x11)	00100001 (0x21)

r20-atom-2: Atomics (ATOM), three parcels (`len = 10`)




From `len = 01`. The placement of the operands is not specified.

Mnemonic	Opcode	Sub-opcode
CAS	010001 (0x11)	00000000 (0x00)
CASDB	010001 (0x11)	00000001 (0x01)
SWAP	010001 (0x11)	00000010 (0x02)
SWAPDB	010001 (0x11)	00000011 (0x03)
XADD	010001 (0x11)	00000100 (0x04)
XADDDB	010001 (0x11)	00000101 (0x05)
XAND	010001 (0x11)	00000110 (0x06)
XANDDB	010001 (0x11)	00000111 (0x07)
XOR_	010001 (0x11)	00001000 (0x08)
XOR_DB	010001 (0x11)	00001001 (0x09)
XXOR	010001 (0x11)	00001010 (0x0A)
XXORDB	010001 (0x11)	00001011 (0x0B)
XMAX	010001 (0x11)	00001100 (0x0C)
XMAXDB	010001 (0x11)	00001101 (0x0D)
XMIN	010001 (0x11)	00001110 (0x0E)
XMINDB	010001 (0x11)	00001111 (0x0F)
XMAXU	010001 (0x11)	00010000 (0x10)
XMAXUDB	010001 (0x11)	00010001 (0x11)
XMINU	010001 (0x11)	00010010 (0x12)
XMINUDB	010001 (0x11)	00010011 (0x13)
LL	010001 (0x11)	00100000 (0x20)
SC	010001 (0x11)	00100001 (0x21)

Memory escape (MESC)

r20-mesc-1: Memory escape (MESC), two parcels (`len = 01`)




Addressing modes (`low`) that use this layout: `base` 0000, `index` 0001, `pcrel` 0010, `dp` 0011, `imm` 0100, `abs` 0101, `postinc` 0110, `predec` 0111.

`low` of parcel 0 is an addressing mode; parcel 1 holds the sub-opcode, `rm` and the first 8 bits of the displacement.

Mnemonic	Opcode	Sub-opcode
MOVUB	001111 (0x0F)	0000 (0x0)
MOVUW	001111 (0x0F)	0010 (0x2)
MOVUL	001111 (0x0F)	0100 (0x4)
MOVUQ	001111 (0x0F)	0110 (0x6)
ADDM	001111 (0x0F)	1000 (0x8)
SUBM	001111 (0x0F)	1001 (0x9)
BICM	001111 (0x0F)	1010 (0xA)
BISM	001111 (0x0F)	1011 (0xB)

r20-mesc-2: Memory escape (MESC), three parcels (`len = 10`)




Addressing modes (`low`) that use this layout: `base` 0000, `index` 0001, `pcrel` 0010, `dp` 0011, `imm` 0100, `abs` 0101, `postinc` 0110, `predec` 0111.

`low` of parcel 0 is an addressing mode; parcel 1 holds the sub-opcode, `rm` and the first 8 bits of the displacement.

Mnemonic	Opcode	Sub-opcode
MOVUB	001111 (0x0F)	0000 (0x0)
MOVUW	001111 (0x0F)	0010 (0x2)
MOVUL	001111 (0x0F)	0100 (0x4)
MOVUQ	001111 (0x0F)	0110 (0x6)
ADDM	001111 (0x0F)	1000 (0x8)
SUBM	001111 (0x0F)	1001 (0x9)
BICM	001111 (0x0F)	1010 (0xA)
BISM	001111 (0x0F)	1011 (0xB)

System, no operand


r20-sysn-0: System, no operand, one parcel (`len = 00`)



The `reg` field is the class (0); class 0 takes a minor opcode from `low`.

Mnemonic	Opcode	reg	low
NOP	010100 (0x14)	0000 (0x0)	0000 (0x0)
RTI	010100 (0x14)	0000 (0x0)	0001 (0x1)
RTT	010100 (0x14)	0000 (0x0)	0010 (0x2)
RET	010100 (0x14)	0000 (0x0)	0011 (0x3)
HALT	010100 (0x14)	0000 (0x0)	0100 (0x4)
BPT	010100 (0x14)	0000 (0x0)	0101 (0x5)
FENCE	010100 (0x14)	0000 (0x0)	0110 (0x6)
WFE	010100 (0x14)	0000 (0x0)	0111 (0x7)
SEV	010100 (0x14)	0000 (0x0)	1000 (0x8)
LPAD	010100 (0x14)	0000 (0x0)	1001 (0x9)
TLBIA	010100 (0x14)	0000 (0x0)	1010 (0xA)
TLBSYNC	010100 (0x14)	0000 (0x0)	1011 (0xB)
ICINVA	010100 (0x14)	0000 (0x0)	1100 (0xC)


r20-sysn-1: System, no operand, two parcels (`len = 01`)



The `reg` field is the class (0); class 0 takes a minor opcode from `low`.

Mnemonic	Opcode	reg	low
NOP	010100 (0x14)	0000 (0x0)	0000 (0x0)
RTI	010100 (0x14)	0000 (0x0)	0001 (0x1)
RTT	010100 (0x14)	0000 (0x0)	0010 (0x2)
RET	010100 (0x14)	0000 (0x0)	0011 (0x3)
HALT	010100 (0x14)	0000 (0x0)	0100 (0x4)
BPT	010100 (0x14)	0000 (0x0)	0101 (0x5)
FENCE	010100 (0x14)	0000 (0x0)	0110 (0x6)
WFE	010100 (0x14)	0000 (0x0)	0111 (0x7)
SEV	010100 (0x14)	0000 (0x0)	1000 (0x8)
LPAD	010100 (0x14)	0000 (0x0)	1001 (0x9)
TLBIA	010100 (0x14)	0000 (0x0)	1010 (0xA)
TLBSYNC	010100 (0x14)	0000 (0x0)	1011 (0xB)
ICINVA	010100 (0x14)	0000 (0x0)	1100 (0xC)

r20-sysn-2: System, no operand, three parcels (`len = 10`)



The `reg` field is the class (0); class 0 takes a minor opcode from `low`.

Mnemonic	Opcode	reg	low
NOP	010100 (0x14)	0000 (0x0)	0000 (0x0)
RTI	010100 (0x14)	0000 (0x0)	0001 (0x1)
RTT	010100 (0x14)	0000 (0x0)	0010 (0x2)
RET	010100 (0x14)	0000 (0x0)	0011 (0x3)
HALT	010100 (0x14)	0000 (0x0)	0100 (0x4)
BPT	010100 (0x14)	0000 (0x0)	0101 (0x5)
FENCE	010100 (0x14)	0000 (0x0)	0110 (0x6)
WFE	010100 (0x14)	0000 (0x0)	0111 (0x7)
SEV	010100 (0x14)	0000 (0x0)	1000 (0x8)
LPAD	010100 (0x14)	0000 (0x0)	1001 (0x9)
TLBIA	010100 (0x14)	0000 (0x0)	1010 (0xA)
TLBSYNC	010100 (0x14)	0000 (0x0)	1011 (0xB)
ICINVA	010100 (0x14)	0000 (0x0)	1100 (0xC)

System, SYSX


r20-sysx-0: System, SYSX, one parcel (`len = 00`)



Class 0, minor 15: the sub-opcode is in parcel 1.

Mnemonic	Opcode	reg	low	Sub-opcode
PUSHX	010100 (0x14)	0000 (0x0)	1111 (0xF)	00000000 (0x00)
POPX	010100 (0x14)	0000 (0x0)	1111 (0xF)	00000001 (0x01)
ISYNC	010100 (0x14)	0000 (0x0)	1111 (0xF)	00000010 (0x02)
HINT	010100 (0x14)	0000 (0x0)	1111 (0xF)	00000011 (0x03)

r20-sysx-1: System, SYSX, two parcels (`len = 01`)




Class 0, minor 15: the sub-opcode is in parcel 1.

Mnemonic	Opcode	reg	low	Sub-opcode
PUSHX	010100 (0x14)	0000 (0x0)	1111 (0xF)	00000000 (0x00)
POPX	010100 (0x14)	0000 (0x0)	1111 (0xF)	00000001 (0x01)
ISYNC	010100 (0x14)	0000 (0x0)	1111 (0xF)	00000010 (0x02)
HINT	010100 (0x14)	0000 (0x0)	1111 (0xF)	00000011 (0x03)

System registers (MFSR, MTSR)


r20-sysreg-0: System registers (MFSR, MTSR), one parcel (`len = 00`)



Class 0: the system register number is in parcel 1.

Mnemonic	Opcode	reg	low
MFSR	010100 (0x14)	0000 (0x0)	1101 (0xD)
MTSR	010100 (0x14)	0000 (0x0)	1110 (0xE)

r20-sysreg-1: System registers (MFSR, MTSR), two parcels (`len = 01`)




Class 0: the system register number is in parcel 1.

Mnemonic	Opcode	reg	low
MFSR	010100 (0x14)	0000 (0x0)	1101 (0xD)
MTSR	010100 (0x14)	0000 (0x0)	1110 (0xE)

System

r20-sys-0: System, one parcel (`len = 00`)




The `reg` field is the class; the other classes take a register or a 4-bit immediate from `low`.

Mnemonic	Opcode	reg
MTPS	010100 (0x14)	0001 (0x1)
MFPS	010100 (0x14)	0010 (0x2)
SPL	010100 (0x14)	0011 (0x3)
TRAP	010100 (0x14)	0100 (0x4)
TLBI	010100 (0x14)	0101 (0x5)
MTASID	010100 (0x14)	0110 (0x6)

Mnemonic	Opcode	reg
MFASID	010100 (0x14)	0111 (0x7)
MTDP	010100 (0x14)	1000 (0x8)
MFDP	010100 (0x14)	1001 (0x9)
MTDMW	010100 (0x14)	1010 (0xA)
MFCPUID	010100 (0x14)	1011 (0xB)
ICINV	010100 (0x14)	1100 (0xC)
PROBER	010100 (0x14)	1101 (0xD)
PROBEW	010100 (0x14)	1110 (0xE)
TRAPL	010100 (0x14)	1111 (0xF)


r20-sys-1: System, two parcels (`len = 01`)



The `reg` field is the class; the other classes take a register or a 4-bit immediate from `low`.

Mnemonic	Opcode	reg
MTPS	010100 (0x14)	0001 (0x1)
MFPS	010100 (0x14)	0010 (0x2)
SPL	010100 (0x14)	0011 (0x3)
TRAP	010100 (0x14)	0100 (0x4)
TLBI	010100 (0x14)	0101 (0x5)
MTASID	010100 (0x14)	0110 (0x6)
MFASID	010100 (0x14)	0111 (0x7)
MTDP	010100 (0x14)	1000 (0x8)
MFDP	010100 (0x14)	1001 (0x9)
MTDMW	010100 (0x14)	1010 (0xA)
MFCPUID	010100 (0x14)	1011 (0xB)
ICINV	010100 (0x14)	1100 (0xC)


r20-sys-1-2: System, two parcels (`len = 01`)



The `reg` field is the class; the other classes take a register or a 4-bit immediate from `low`.

Mnemonic	Opcode	reg
PROBER	010100 (0x14)	1101 (0xD)
PROBEW	010100 (0x14)	1110 (0xE)


r20-sys-1-3: System, two parcels (`len = 01`)



The `reg` field is the class; the other classes take a register or a 4-bit immediate from `low`.

Mnemonic	Opcode	reg
TRAPL	010100 (0x14)	1111 (0xF)

r20-sys-2: System, three parcels (`len = 10`)




The `reg` field is the class; the other classes take a register or a 4-bit immediate from `low`.

Mnemonic	Opcode	reg
MTPS	010100 (0x14)	0001 (0x1)
MFPS	010100 (0x14)	0010 (0x2)
SPL	010100 (0x14)	0011 (0x3)
TRAP	010100 (0x14)	0100 (0x4)
TLBI	010100 (0x14)	0101 (0x5)
MTASID	010100 (0x14)	0110 (0x6)
MFASID	010100 (0x14)	0111 (0x7)
MTDP	010100 (0x14)	1000 (0x8)
MFDP	010100 (0x14)	1001 (0x9)
MTDMW	010100 (0x14)	1010 (0xA)
MFCPUID	010100 (0x14)	1011 (0xB)
ICINV	010100 (0x14)	1100 (0xC)
PROBER	010100 (0x14)	1101 (0xD)
PROBEW	010100 (0x14)	1110 (0xE)
TRAPL	010100 (0x14)	1111 (0xF)

Page 2

r20-page2: Page 2: a one-parcel instruction with its own opcode map



The index of the mnemonics

For every mnemonic, the charts in which it is a sub-opcode or the whole leaf.

- ABS: r20-aesc-1, r20-aesc-2
- ADC: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- ADD: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- ADDM: r20-mesc-1, r20-mesc-2
- AND: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- ASL: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- ASR: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- BCC: r20-br-0, r20-br-1, r20-br-2
- BCS: r20-br-0, r20-br-1, r20-br-2
- BEQ: r20-br-0, r20-br-1, r20-br-2
- BGE: r20-br-0, r20-br-1, r20-br-2
- BGT: r20-br-0, r20-br-1, r20-br-2

- BHI: r20-br-0, r20-br-1, r20-br-2
- BIC: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- BICM: r20-mesc-1, r20-mesc-2
- BIS: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- BISM: r20-mesc-1, r20-mesc-2
- BIT: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- BITREV: r20-besc-1, r20-besc-2
- BLE: r20-br-0, r20-br-1, r20-br-2
- BLOS: r20-br-0, r20-br-1, r20-br-2
- BLT: r20-br-0, r20-br-1, r20-br-2
- BMI: r20-br-0, r20-br-1, r20-br-2
- BNE: r20-br-0, r20-br-1, r20-br-2
- BNTAG: r20-tag-1, r20-tag-2
- BPL: r20-br-0, r20-br-1, r20-br-2
- BPT: r20-sysn-0, r20-sysn-1, r20-sysn-2
- BR: r20-br-0, r20-br-1, r20-br-2
- BSWAP: r20-besc-1, r20-besc-2
- BSWAPL: r20-besc-1, r20-besc-2
- BSWAPW: r20-besc-1, r20-besc-2
- BTAG: r20-tag-1, r20-tag-2
- BVC: r20-br-0, r20-br-1, r20-br-2
- BVS: r20-br-0, r20-br-1, r20-br-2
- CALL: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- CALLI: r20-xfer-0, r20-xfer-1, r20-xfer-1-2, r20-xfer-1-3, r20-xfer-1-4, r20-xfer-2, r20-xfer-2-2, r20-xfer-2-3, r20-xfer-2-4
- CAS: r20-atom-1, r20-atom-2
- CASDB: r20-atom-1, r20-atom-2
- CBCC: r20-cb-1, r20-cb-1-2, r20-cb-2, r20-cb-2-2, r20-cb-2-3
- CBCS: r20-cb-1, r20-cb-1-2, r20-cb-2, r20-cb-2-2, r20-cb-2-3
- CBEQ: r20-cb-1, r20-cb-1-2, r20-cb-2, r20-cb-2-2, r20-cb-2-3
- CBGE: r20-cb-1, r20-cb-1-2, r20-cb-2, r20-cb-2-2, r20-cb-2-3
- CBGT: r20-cb-1, r20-cb-1-2, r20-cb-2, r20-cb-2-2, r20-cb-2-3
- CBHI: r20-cb-1, r20-cb-1-2, r20-cb-2, r20-cb-2-2, r20-cb-2-3
- CBLE: r20-cb-1, r20-cb-1-2, r20-cb-2, r20-cb-2-2, r20-cb-2-3
- CBLOS: r20-cb-1, r20-cb-1-2, r20-cb-2, r20-cb-2-2, r20-cb-2-3
- CBLT: r20-cb-1, r20-cb-1-2, r20-cb-2, r20-cb-2-2, r20-cb-2-3
- CBMI: r20-cb-1, r20-cb-1-2, r20-cb-2, r20-cb-2-2, r20-cb-2-3
- CBNE: r20-cb-1, r20-cb-1-2, r20-cb-2, r20-cb-2-2, r20-cb-2-3
- CBPL: r20-cb-1, r20-cb-1-2, r20-cb-2, r20-cb-2-2, r20-cb-2-3
- CBVC: r20-cb-1, r20-cb-1-2, r20-cb-2, r20-cb-2-2, r20-cb-2-3
- CBVS: r20-cb-1, r20-cb-1-2, r20-cb-2, r20-cb-2-2, r20-cb-2-3
- CLMULH: r20-besc-1, r20-besc-2
- CLMULL: r20-besc-1, r20-besc-2
- CLO: r20-besc-1, r20-besc-2
- CLR: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- CLZ: r20-besc-1, r20-besc-2
- CMP: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4

- `COM`: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- `CTO`: r20-besc-1, r20-besc-2
- `CTZ`: r20-besc-1, r20-besc-2
- `DEC`: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- `DIV`: r20-aesc-1, r20-aesc-2
- `DIVU`: r20-aesc-1, r20-aesc-2
- `DSHR`: r20-besc-1, r20-besc-2-3
- `EXTB`: r20-besc-1, r20-besc-2-3
- `EXTZB`: r20-besc-1, r20-besc-2-3
- `FABS`: r20-fesc-1, r20-fesc-2
- `FADD`: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- `FADD16`: r20-fesc-1, r20-fesc-2
- `FADD32`: r20-fesc-1, r20-fesc-2
- `FCLASS`: r20-fesc-1, r20-fesc-2
- `FCLASS16`: r20-fesc-1, r20-fesc-2
- `FCLASS32`: r20-fesc-1, r20-fesc-2
- `FCMP`: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- `FCMP16`: r20-fesc-1, r20-fesc-2
- `FCMP32`: r20-fesc-1, r20-fesc-2
- `FCOPYSIGN`: r20-fesc-1, r20-fesc-2
- `FCVTDH`: r20-fesc-1, r20-fesc-2
- `FCVTDQ`: r20-fesc-1, r20-fesc-2
- `FCVTDQU`: r20-fesc-1, r20-fesc-2
- `FCVTDS`: r20-fesc-1, r20-fesc-2
- `FCVTHD`: r20-fesc-1, r20-fesc-2
- `FCVTHL`: r20-fesc-1, r20-fesc-2
- `FCVTHS`: r20-fesc-1, r20-fesc-2
- `FCVTLH`: r20-fesc-1, r20-fesc-2
- `FCVTLS`: r20-fesc-1, r20-fesc-2
- `FCVTQD`: r20-fesc-1, r20-fesc-2
- `FCVTQUD`: r20-fesc-1, r20-fesc-2
- `FCVTSD`: r20-fesc-1, r20-fesc-2
- `FCVTSH`: r20-fesc-1, r20-fesc-2
- `FCVTSL`: r20-fesc-1, r20-fesc-2
- `FDIV`: r20-fesc-1, r20-fesc-2
- `FDIV16`: r20-fesc-1, r20-fesc-2
- `FDIV32`: r20-fesc-1, r20-fesc-2
- `FENCE`: r20-sysn-0, r20-sysn-1, r20-sysn-2
- `FMADD`: r20-fesc-1, r20-fesc-2
- `FMADD16`: r20-fesc-1, r20-fesc-2
- `FMADD32`: r20-fesc-1, r20-fesc-2
- `FMAX`: r20-fesc-1, r20-fesc-2
- `FMIN`: r20-fesc-1, r20-fesc-2
- `FMSUB`: r20-fesc-1, r20-fesc-2
- `FMSUB16`: r20-fesc-1, r20-fesc-2
- `FMSUB32`: r20-fesc-1, r20-fesc-2
- `FMUL`: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4

- FMUL16: r20-fesc-1, r20-fesc-2
- FMUL32: r20-fesc-1, r20-fesc-2
- FNEG: r20-fesc-1, r20-fesc-2
- FNMADD: r20-fesc-1, r20-fesc-2
- FNMADD16: r20-fesc-1, r20-fesc-2
- FNMADD32: r20-fesc-1, r20-fesc-2
- FNMSUB: r20-fesc-1, r20-fesc-2
- FNMSUB16: r20-fesc-1, r20-fesc-2
- FNMSUB32: r20-fesc-1, r20-fesc-2
- FRINT: r20-fesc-1, r20-fesc-2
- FRINTA: r20-fesc-1, r20-fesc-2
- FRINTM: r20-fesc-1, r20-fesc-2
- FRINTP: r20-fesc-1, r20-fesc-2
- FRINTZ: r20-fesc-1, r20-fesc-2
- FSFLAGS: r20-fesc-1, r20-fesc-2
- FSQRT: r20-fesc-1, r20-fesc-2
- FSQRT16: r20-fesc-1, r20-fesc-2
- FSQRT32: r20-fesc-1, r20-fesc-2
- FSUB: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- FSUB16: r20-fesc-1, r20-fesc-2
- FSUB32: r20-fesc-1, r20-fesc-2
- HALT: r20-sysn-0, r20-sysn-1, r20-sysn-2
- HINT: r20-sysx-0, r20-sysx-1
- ICINV: r20-sys-0, r20-sys-1, r20-sys-2
- ICINVA: r20-sysn-0, r20-sysn-1, r20-sysn-2
- INC: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- INSB: r20-besc-1, r20-besc-2-3
- ISYNC: r20-sysx-0, r20-sysx-1
- JMP: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- JMPI: r20-xfer-0, r20-xfer-1, r20-xfer-1-2, r20-xfer-1-3, r20-xfer-1-4, r20-xfer-2, r20-xfer-2-2, r20-xfer-2-3, r20-xfer-2-4
- JTAG: r20-xfer-0, r20-xfer-1, r20-xfer-1-2, r20-xfer-1-3, r20-xfer-1-4, r20-xfer-2, r20-xfer-2-2, r20-xfer-2-3, r20-xfer-2-4
- LEA: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- LL: r20-atom-1, r20-atom-2
- LPAD: r20-sysn-0, r20-sysn-1, r20-sysn-2
- MAX: r20-aesc-1, r20-aesc-2
- MAXU: r20-aesc-1, r20-aesc-2
- MCMP: r20-mblk-1, r20-mblk-2
- MCPY: r20-mblk-1, r20-mblk-2
- MFASID: r20-sys-0, r20-sys-1, r20-sys-2
- MFCPUID: r20-sys-0, r20-sys-1, r20-sys-2
- MFDP: r20-sys-0, r20-sys-1, r20-sys-2
- MFPS: r20-sys-0, r20-sys-1, r20-sys-2
- MFSR: r20-sysreg-0, r20-sysreg-1
- MIN: r20-aesc-1, r20-aesc-2
- MINU: r20-aesc-1, r20-aesc-2
- MMOV: r20-mblk-1, r20-mblk-2
- MOD: r20-aesc-1, r20-aesc-2
- MODU: r20-aesc-1, r20-aesc-2

- `MOVB`: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- `MOVL`: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- `MOVQ`: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- `MOVUB`: r20-mesc-1, r20-mesc-2
- `MOVUL`: r20-mesc-1, r20-mesc-2
- `MOVUQ`: r20-mesc-1, r20-mesc-2
- `MOVUW`: r20-mesc-1, r20-mesc-2
- `MOVW`: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- `MOVZB`: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- `MOVZL`: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- `MOVZW`: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- `MSCN`: r20-mblk-1, r20-mblk-2
- `MSCNN`: r20-mblk-1, r20-mblk-2
- `MSET`: r20-mblk-1, r20-mblk-2
- `MTASID`: r20-sys-0, r20-sys-1, r20-sys-2
- `MTDMW`: r20-sys-0, r20-sys-1, r20-sys-2
- `MTDP`: r20-sys-0, r20-sys-1, r20-sys-2
- `MTPS`: r20-sys-0, r20-sys-1, r20-sys-2
- `MTSR`: r20-sysreg-0, r20-sysreg-1
- `MUL`: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- `MULH`: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- `MULHU`: r20-aesc-1, r20-aesc-2
- `MVAL`: r20-mblk-1, r20-mblk-2
- `NEG`: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- `NOP`: r20-sysn-0, r20-sysn-1, r20-sysn-2
- `POP`: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- `POPCNT`: r20-besc-1, r20-besc-2
- `POPM`: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- `POPX`: r20-sysx-0, r20-sysx-1
- `PROBER`: r20-sys-0, r20-sys-1-2, r20-sys-2
- `PROBEW`: r20-sys-0, r20-sys-1-2, r20-sys-2
- `PUSH`: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- `PUSHM`: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- `PUSHX`: r20-sysx-0, r20-sysx-1
- `RET`: r20-sysn-0, r20-sysn-1, r20-sysn-2
- `ROR`: r20-besc-1, r20-besc-2
- `RORI`: r20-besc-1-2, r20-besc-2-2
- `RORI32`: r20-besc-1-2, r20-besc-2-2
- `RTI`: r20-sysn-0, r20-sysn-1, r20-sysn-2
- `RTT`: r20-sysn-0, r20-sysn-1, r20-sysn-2

- SAR: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- SBC: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- SC: r20-atom-1, r20-atom-2
- SET: r20-aesc-1, r20-aesc-2
- SEV: r20-sysn-0, r20-sysn-1, r20-sysn-2
- SHL: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- SHR: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- SOB: r20-sob-1, r20-sob-2
- SPL: r20-sys-0, r20-sys-1, r20-sys-2
- SUB: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- SUBM: r20-mesc-1, r20-mesc-2
- SWAP: r20-atom-1, r20-atom-2
- SWAPDB: r20-atom-1, r20-atom-2
- TLBI: r20-sys-0, r20-sys-1, r20-sys-2
- TLBIA: r20-sysn-0, r20-sysn-1, r20-sysn-2
- TLBSYNC: r20-sysn-0, r20-sysn-1, r20-sysn-2
- TRAP: r20-sys-0, r20-sys-1, r20-sys-2
- TRAPL: r20-sys-0, r20-sys-1-3, r20-sys-2
- TST: r20-sop-0, r20-sop-1, r20-sop-1-2, r20-sop-1-3, r20-sop-1-4, r20-sop-2, r20-sop-2-2, r20-sop-2-3, r20-sop-2-4
- UTF8DEC: r20-besc-1, r20-besc-2
- UTF8ENC: r20-besc-1, r20-besc-2
- UTF8LEN: r20-besc-1, r20-besc-2
- WFE: r20-sysn-0, r20-sysn-1, r20-sysn-2
- XADD: r20-atom-1, r20-atom-2
- XADDDB: r20-atom-1, r20-atom-2
- XAND: r20-atom-1, r20-atom-2
- XANDDB: r20-atom-1, r20-atom-2
- XMAX: r20-atom-1, r20-atom-2
- XMAXDB: r20-atom-1, r20-atom-2
- XMAXU: r20-atom-1, r20-atom-2
- XMAXUDB: r20-atom-1, r20-atom-2
- XMIN: r20-atom-1, r20-atom-2
- XMINDB: r20-atom-1, r20-atom-2
- XMINU: r20-atom-1, r20-atom-2
- XMINUDB: r20-atom-1, r20-atom-2
- XNORPOP: r20-besc-1, r20-besc-2
- XOR: r20-mem-0, r20-mem-1, r20-mem-1-2, r20-mem-1-3, r20-mem-1-4, r20-mem-2, r20-mem-2-2, r20-mem-2-3, r20-mem-2-4
- XOR_: r20-atom-1, r20-atom-2
- XOR_DB: r20-atom-1, r20-atom-2
- XXOR: r20-atom-1, r20-atom-2
- XXORDB: r20-atom-1, r20-atom-2

Generated by `tools/mkmanual.py`; do not edit.

Part III — Appendices

Appendix A — Possible improvements not decided on

These are ideas that would make the machine better in one respect or another and that are not decisions. They come from the reports on kernel pain points, hardware vulnerabilities and OpenBSD's mitigations, and from the open items of the instruction-set text. Each is stated as a possibility, with its benefit, its cost and what other machines do, so that it can be taken up, rejected or promoted to a decision in appendix B. Nothing here is built or specified unless it says so. The same ordering principle as the rest of the manual applies: code size, then easy recoverability, then speed and efficiency through fewer gates and tighter hot loops.

A.1 Reserve a page bit that enforces landing pads

A.1.1 The `LPAD` instruction marks a legal target of an indirect jump or call; a page bit could make the hardware fault when an indirect transfer lands anywhere else, with enforcement off in ABI version 1 and on from version 2.

A.1.2 A page bit that gates landing pads is approved, with the fault attributed to the branch, to be specified (errata 84, item 5). *(D)*

Commentary. **Precedent.** `LPAD` already exists, and the ABI leaves landing pads off in version 1, with no switch to enforce them. **Trade-offs.** The bit costs one comparator and two bytes per address-taken function, and deciding later gets more expensive because every binary built in the meantime lacks the pads. **Benefits.** It blocks jump-oriented attacks at the transfer, with no recovery code beyond the fault handler that already exists. **Modern comparables.** Intel's indirect-branch tracking and ARM's branch target identification, both of which OpenBSD enforces by default where the hardware has them. **Impact.** *Kernel:* A landing-pad violation is a fault the handler already handles; the kernel sets the page bit at exec time. *Compiler:* The compiler emits `LPAD` at every address-taken function, two bytes each. *Hardware:* One page bit and one comparator on an indirect-transfer target.

A.2 A page bit that says a system call may be made from here

A.2.1 A page-table bit could let the hardware refuse a system call from any page not so marked, so that the kernel's check of where a call came from moves into the instruction.

A.2.2 A page bit for system-call entry (the `SYS` page bit) is approved, to be specified (errata 84, item 8). *(D)*

Commentary. **Precedent.** OpenBSD's `msyscall` and `pinsyscalls` restrict where system calls may be issued from. **Trade-offs.** One bit and one gate; the kernel would no longer need to check the origin on every call. **Benefits.** About four instructions removed from every system call, and region pinning with no hot-path check. **Modern comparables.** No architecture surveyed has this bit; it is done by the kernel in software. **Impact.** *Kernel:* The kernel no longer checks where a system call came from on every call, which removes about four instructions from each. *Compiler:* None. *Hardware:* One page bit and one gate at the `TRAP` decode.

A.3 A check of the stack pointer at system-call entry

A.3.1 The hardware could check that the stack pointer lies in a region registered as a stack when a system call or a fault is taken.

A.3.2 A stack-limit register is approved, to be specified (errata 84, item 4). *(D)*

Commentary. **Precedent.** OpenBSD checks the stack pointer against a `MAP_STACK` region on system calls and faults. **Trade-offs.** It adds a comparison to entry, which is the path the design most wants short, and gives no benefit over the kernel making the same check. **Verdict.** Not recommended; recorded because the question is natural. **Impact.** *Kernel:* None over the check the kernel already makes. *Compiler:* None. *Hardware:* A comparator and a region register on the entry path, which is the path the design most wants short.

A.4 Protecting the return address

A.4.1 The return address lives on the data stack, because `CALL` pushes it and there is no link register; there are four ways to protect it: software canaries and OpenBSD's return-address protection in the compiler, a hardware return stack, a shadow stack, and nothing.

A.4.2 The mirror shadow stack is approved with its recommendations (errata 85, study item 6); return-address authentication is deferred (errata 84, item 7). *(D)*

Commentary. **Precedent.** x86 has the same exposure and uses stack canaries, `retguard` in OpenBSD's clang, and the shadow stacks of Intel's control-flow enforcement; ARM has pointer authentication. **Trade-offs.** A shadow stack is the strongest and brings the most recovery code (a second stack to overflow, switch and unwind), so the analysis does not recommend it by default; software detection costs a few instructions per function and no hardware. **Benefits.** Detection with little or no recovery code. **Verdict.** Start with the compiler; consider a hardware mechanism only if code size allows. **Impact.** *Kernel:* A shadow stack is a second stack for the kernel to manage and unwind; software detection needs only a fault handler. *Compiler:* The compiler adds a canary or a return-address check per function. *Hardware:* Software costs nothing; a hardware return stack or a shadow stack costs a second stack structure and its control.

A.5 Tag or key bits in pointers

A.5.1 The 25 spare bits of a 64-bit pointer (a 39-bit virtual address, the three-level form, uses the rest; 48 and 57 bits leave fewer) could carry a tag or a key, as a memory-tagging or pointer-authentication scheme does.

A.5.2 Full 128-bit CHERI is rejected, and a valid-pointer tag per register and per 8-byte word (stage 1) is kept, with bounds deferred (errata 86, study item 3); granule colouring and reserved colours for uninitialised and freed memory are approved, to be specified, and spend pointer bits that the canonical-address rule refuses to software, so that rule must be restated (errata 84, open). *(D)*

Commentary. **Precedent.** ARM's top-byte-ignore, pointer authentication and memory tagging. **Trade-offs.** The cost is canonical-address rules: pointers must be masked before use, and the hardware must define what a tagged pointer does. **Verdict.** No threat that the operating system asked for requires it; it costs gates and state, so it is not recommended. **Impact.** *Kernel:* The kernel would have to define what a tagged pointer means across the user and kernel boundary. *Compiler:* Every pointer use needs masking, and pointer arithmetic must preserve tags. *Hardware:* Gates and state in the address path.

A.6 A physical address wider than 40 bits: decided, with the entry format open

A.6.1 The physical address is 40 to 64 bits (errata 102, *(D)*), which lets petabytes of memory and device windows be mapped; the present page-table entry holds the physical page number in bits 12 to 39 and keeps bits 40 to 63 zero, so the entry format has to grow its page number into them or change. The format is open. *(S)*

Commentary. **Trade-offs.** The author's reason is that mapping petabytes needs those bits (errata 97). The cost is a wider page number in the entry, in every translation-buffer entry and in every bus address; the benefit is room for devices and memory in one address space without a decoding bit. **Modern comparables.** x86-64 and AArch64 define physical addresses of up to 52 bits and RISC-V up to 56 (stated from memory, not confirmed in the sources read). **Impact.** *Kernel:* a wider entry and a physical-address width to discover. *Compiler:* none. *Hardware:* more bits in the walker, the translation buffer and the bus.

A.7 A second page-table base register

A.7.1 A second page-table base for the kernel half of the address space would let a kernel and a user program run with different tables without flushing, if a speculative core ever needs the isolation.

Commentary. **Precedent.** The cost of separating kernel and user page tables on x86 after Meltdown was about 5% typical and about 30% in the worst case in the developers' own estimates, and the tagged translation buffers (PCID) made it tolerable. **Trade-offs.** The single base is correct and free on a core that does not speculate; the second base register costs a register and a rule, and the question is whether to pay it before the need exists. **Benefits.** The isolation is in the hardware from the start. **Modern comparables.** AArch64 has two translation-table base registers, one for each half of the address space. **Impact.** *Kernel:* The kernel switches one base register at the privilege change instead of managing a shared table. *Compiler:* None. *Hardware:* A second base register and a rule choosing which half uses which.

A.8 Two-byte forms of the user-memory guard instructions

A.8.1 `STUA` and `CLUA` could have one-parcel page-2 forms, saving four bytes per user-copy routine.

Commentary. **Trade-offs.** It uses two of the 19 reserved page-2 slots, which is not worth it until a kernel exists to count the copy routines. **Benefits.** Smaller and faster user copies. **Verdict.** Hold the slots and decide when the kernel exists. **Impact.** *Kernel:* Each user copy routine is four bytes smaller. *Compiler:* None. *Hardware:* Two reserved page-2 slots used.

A.9 Thirty-two-bit forms of add, subtract and shift

A.9.1 If the extension instructions the compiler emits after narrow arithmetic are more than a few percent of the code, 32-bit forms of the common operations on page 2 would remove them.

Commentary. **Precedent.** AArch64's `W` forms and RISC-V's `ADDW` family. **Trade-offs.** A second set of opcodes in the page-2 map against extension instructions in the compiled code; the overhead has never been measured over the whole corpus. **Verdict.** Measure first; it is one script over the compiled corpus. **Impact.** *Kernel:* None. *Compiler:* The compiler stops emitting an extension after common 32-bit operations. *Hardware:* A second set of opcodes in the page-2 map and a little ALU decode.

A.10 Packed-lane instructions in the integer registers

A.10.1 A small set of lane operations (add, subtract, saturating add, compare, minimum, maximum, average, sum of absolute differences, shuffle on 8, 16 and 32-bit lanes) in the existing registers could speed up string, codec and image loops.

Commentary. **Precedent.** Alpha's motion-video instructions and PA-RISC's multimedia instructions did exactly this, in integer registers. **Trade-offs.** It adds no state and little hardware, but it is 64 bits wide so the gain per instruction is modest, and compilers use it poorly. **Verdict.** Collect the evidence first: the compiler corpus was built at a size setting that hides how much vectorisable code there is (appendix B, S1). **Impact.** *Kernel:* String and checksum routines get faster. *Compiler:* Vectorisation into integer lanes is weak, so the library routines would be hand-written. *Hardware:* A lane-aware ALU: little extra hardware and no new state.

A.11 Streaming and non-temporal block operations

A.11.1 A large `MCPY` evicts the whole data cache for data never read again; a non-temporal variant or a streaming memory type would avoid it.

Commentary. **Precedent.** x86 has non-temporal stores; ARM has non-temporal load and store pairs. **Trade-offs.** It shows immediately on an 8 KB cache; the fix is an opcode or a memory type, the non-fix is to leave the cache alone. **Verdict.** Open; decide when the memory system is built. **Impact.** *Kernel:* Large copies would not evict the kernel's working set. *Compiler:* `memcpy` would choose the streaming form above a size. *Hardware:* A non-temporal write path in the cache.

A.12 Smaller possibilities

- **`MULHSU`** (the high half of a signed-by-unsigned product, for a signed top limb meeting an unsigned one) is reserved in the arithmetic escape; it is one correction step in software and has one caller, a bignum library's innermost loop.
- **Hardware page zeroing**, and **guard-page states in the page-table entry that do not consume translation-buffer entries**, would make the allocator hardening of OpenBSD's `malloc` cheaper.
- **A mixed leaf size for the kernel's text** is needed if the kernel is to be write-xor-execute with one-gigabyte leaf pages.
- **Hardware breakpoints and debug registers** are not designed; a debugger has only the breakpoint instruction and the trace bit.
- **A sealed (immutable) page bit and a hardware mask for `pledge`** have no benefit over the kernel doing the checks, and are rejected.

Commentary. **Trade-offs.** None of these is ranked above the decisions in appendix B; the first four sections of this appendix (landing pads, the system-call page bit, the stack check and return-address protection) are the ones OpenBSD's developers have shown the most interest in.

Appendix B — Decisions pending

These are the open decisions, each with its question, the proposed answer, and the precedent, trade-offs and benefits that surround it. Each has five options with their costs in the working document `../decisions-pending.md` (the identifiers P, R, S, N and B below are that document's), and the boot choices are worked through in `../boot.md`. Decided items are not repeated here. Each entry is judged by the three principles in order: code size, easy recoverability (less recovery code), and speed and efficiency through fewer gates and tighter hot loops. Every entry is a proposal *(P)* until it is decided.

B.1 The instruction set and the system

B.1.1 The wake rule of `WFE` (P1)

B.1.1.1 The question is whether `WFE` ends its sleep when an interrupt is pending even if the priority masks it; the proposal is yes. *(P)*

Commentary. **Precedent.** An idle loop must check for work and sleep without a gap, or an interrupt that arrives between the two is lost. V7's idle routine lowered the priority and executed `wait` inside a loop that rechecked the run queue after every interrupt, so a lost wake-up cost at most one clock tick. **Trade-offs.** With priority 7 on entry, "lower the priority, then sleep" misses an interrupt that lands between the two, and "sleep at priority 7" never wakes. **Benefits.** The idle loop becomes `spl #7`, check for work, `wfe`, `spl #0`, with no gap and no timer tick to bound it; no opcode, a few gates. **Modern comparables.** AArch64 and RISC-V `wfi` resume on a pending enabled interrupt (RISC-V's manual says the global enable bit is ignored and that an implementation may wake for any reason, so "the same as RISC-V" holds only if the pdp64's priority mask is treated like that bit); x86 closes the gap with the one-instruction interrupt shadow of `STI`, which is hidden state. **Impact.** *Kernel:* The idle loop needs no tick to bound a lost wake-up. *Compiler:* Spin-wait and idle code use `WFE` and `HINT #1`. *Hardware:* A pending-interrupt line into the wait logic, a few gates.

B.1.2 An unprivileged time counter (P3)

B.1.2.1 The proposal is `RDTIME rd`, an unprivileged read of a free-running, constant-rate, monotonic counter. *(P)*

Commentary. **Precedent.** The PDP-11 and VAX kept the time in memory updated by a line clock and read it with a system call. **Trade-offs.** A user-readable counter is a timing side channel, so the kernel needs an enable bit; the counter's width and rate become architecture. **Benefits.** A clock read without a trap, which is what a fast `clock_gettime` in a shared page needs. **Modern comparables.** x86 `RDTSC`, RISC-V `rdtime`, PowerPC `mftb`, s390 `STCKF`, MIPS `RDHWR`, LoongArch `rdtime`; the x86 counter's history of unreliability is the argument for fixing monotonicity and constant rate at the start. **Use.** Timestamps, timeouts, and the fast path of every library's clock call. **Impact.** *Kernel:* A fast `clock_gettime` with no trap. *Compiler:* An intrinsic for the counter read. *Hardware:* One counter, a user-read enable bit and a `SYSX` decode.

B.1.3 Feature and identification registers (P4)

B.1.3.1 The proposal is a block of read-only system registers (numbers 13 and up) giving the version, the optional features, the cache geometry, the page sizes and the address width. *(P)*

Commentary. **Precedent.** The VAX had a system-identification register the kernel switched on; x86 has `CPUID`, which has grown hundreds of leaves and traps under virtualisation. **Trade-offs.** Each register's layout must be written once in a grammar so it cannot drift. **Benefits.** One binary adapts to the machine, and a kernel need not patch itself per model (OpenBSD carries 75 references to its boot-time patching). **Modern comparables.** AArch64's identification registers, RISC-V's `misa`. **Impact.** *Kernel:* The kernel need not patch itself per model. *Compiler:* Runtime selection of routines by feature bits. *Hardware:* A small block of read-only registers.

B.1.4 TLB invalidation by address-space tag (P5)

B.1.4.1 The proposal is one new instruction, `TLBIASID`, that invalidates every translation of one address space, broadcast like `TLBI`. *(P)*

Commentary. **Precedent.** The VAX flushed process translations on every context switch and kept system ones; x86 added tags (PCID) and `INVPCID` much later. **Trade-offs.** A flush-all works until the first rollover of the tag numbers, after which every process loses its translations. **Benefits.** Process exit and tag reuse become cheap. **Modern comparables.** AArch64 `TLBI ASIDE1IS`, RISC-V `sfence.vma` with an address-space operand, x86 `INVPCID`. **Impact.** *Kernel:* Process exit and tag reuse become one broadcast. *Compiler:* None. *Hardware:* A tag compare in the translation buffer's invalidate path.

B.1.5 What a multi-register instruction leaves behind when it faults (P12)

B.1.5.1 The proposal is a rule and a test: every multi-access instruction (`PUSHM`, `POPM`, `PUSHX`, `POPX`, the block operations) is either all-or-nothing or safe to repeat from the start, and an emulator test interrupts each at every access and checks that a restart reaches the same state. *(P)*

Commentary. **Precedent.** The PDP-11 needed a status register (`MMR1`) and, on the 11/40, a kernel routine that decoded the faulting instruction to undo it; the VAX needed a first-part-done bit; ARM's load-multiple restarts with the base register restored. **Trade-offs.** The area below the stack pointer is dead memory, so a partial push is invisible; the risk is another observer (a device or core) seeing a half-written area. **Benefits.** The fault handler restarts blindly, with no instruction-specific cases, which is what recoverability means. **Modern comparables.** RISC-V has no multi-register instruction; ARM and the VAX restart as above. **Impact.** *Kernel:* The fault handler restarts every multi-access instruction blindly. *Compiler:* None. *Hardware:* Each multi-access instruction checks every address before acting, or is repeatable.

B.1.6 Priority 7 on interrupt entry as well as exception entry (P14)

B.1.6.1 Exceptions enter at priority 7, which is decided; the open question is whether interrupts do too, which the implementation does. *(exceptions D; interrupts P)*

Commentary. **Precedent.** The PDP-11 loaded each vector's own priority and pushed the old state on a stack, so an interrupt at any time could not lose it; trap vectors conventionally held priority 7. **Trade-offs.** Entering in registers needs the priority raised, or a higher-level interrupt could overwrite the saved state before the handler stores it; the cost is one `SPL` in a handler that wants to be interruptible. The alternatives are per-vector priority (the PDP-11's choice), a hardware push, and an interrupt shadow. **Modern comparables.** x86, AArch64 and RISC-V all mask interrupts on entry. **Impact.** *Kernel:* One `SPL` in a handler that wants to be interruptible. *Compiler:* None. *Hardware:* Priority 7 loaded into the new status word at entry.

B.1.7 A prefetch instruction (P15)

B.1.7.1 The proposal is none, with the shape of a non-faulting `PREFETCH` with a memory operand reserved on a free sub-opcode. *(P)*

Commentary. **Precedent.** Neither the PDP-11 nor the VAX had one; caches there were transparent. **Trade-offs.** The kernel survey counts over a hundred prefetch instructions across the four kernels, mostly in tuned list and copy code; an in-order core with no data cache gains nothing. **Modern comparables.** AArch64 `PRFM`, ARM `PLD`, PowerPC `DCBT`, x86 `PREFETCHT0`. **Impact.** *Kernel:* List walks and copy loops can warm the cache. *Compiler:* `PREFETCH` would need compiler heuristics. *Hardware:* A non-faulting load path with no destination; nothing on a core with no data cache.

B.1.8 Performance counters (P16)

B.1.8.1 The proposal is two free-running counters, cycles and instructions retired, readable in user mode, added after the clock (P3) with the same enable bit. *(P)*

Commentary. **Precedent.** Unix profiled by sampling the program counter at clock ticks. **Trade-offs.** A user-readable cycle counter is a timing channel; a full counter block with event selection costs a large block and interrupt machinery. **Modern comparables.** x86 `RDPMC`, the AArch64 PMU, RISC-V's `hpm` counters. **Impact.** *Kernel:* A profiler reads counters instead of sampling at ticks. *Compiler:* Intrinsics. *Hardware:* Two counters and an enable bit.

B.1.9 Constant-time execution (P17)

B.1.9.1 The question is how to guarantee that instruction time does not depend on operand values; the proposal is a core set of instructions that is always constant-time plus a mode bit that extends the promise to divide, `MSCN`, `MCMP` and floating point. *(P)*

B.1.9.2 Closed in part: the branch-free select is adopted, at least one secure core has every timing channel removed (all instructions and cache fetches take fixed time, no periodic tick), and on that core each instruction takes a time independent

of its data, with no ticks or timing interrupts introduced to achieve it (errata 85, 86; `docs/crypto-secure-core.md`); the mode bit of the proposal above is superseded for the secure core. *(D)*

Commentary. **Trade-offs.** Making all integer instructions constant-time would cost about 1% on average by a rough estimate, because divide is only 0.04% of compiled instructions (149 of 370,115; multiply costs nothing, since a fixed-latency multiplier needs less logic than one with an early-out); the mode bit keeps fast paths for ordinary code. A constant-time instruction does not make code constant-time: a secret-dependent branch or table index still leaks through the predictor and the cache. **Precedent.** Neither ancestor addressed it; the PDP-11's multiply and divide were microcoded with operand-dependent times. **Modern comparables.** Arm's `DIT` bit, Intel's data-operand-independent timing mode, RISC-V's scalar-crypto timing subset. **Use.** Cryptography on secret keys. The performance cost of those modes is not established. **Impact.** *Kernel:* Crypto code sets the mode around secret-dependent work. *Compiler:* The back end must not turn a constant-time sequence into a variable-time one. *Hardware:* The core set costs nothing; the mode bit needs the fast paths of divide and the scanners to be gateable.

B.1.10 The literal pool and execute-only code (P18)

B.1.10.1 The proposal is an ABI rule: literal pools move out of `.text` into a read-only section beside it, so code pages hold only instructions and can be execute-only. *(P)*

Commentary. **Precedent.** The PDP-11's immediates sit in the instruction stream, and with separate instruction and data spaces a program could not read its own instructions as data. **Trade-offs.** The PC-relative reach limits how far the pool may be, and the linker must keep the two sections near each other. **Benefits.** Zero hardware; a memory-disclosure bug no longer reveals code. **Modern comparables.** OpenBSD makes code execute-only on amd64 and arm64; ARM compilers offer a flag to keep pools out of code. **Impact.** *Kernel:* None. *Compiler:* Pools are emitted into a read-only section beside the text. *Hardware:* None; the linker keeps the sections within PC-relative reach.

B.1.11 Vector and SIMD math (S1 to S6)

B.1.11.1 The device route is decided: the processor has no vector register file and no SIMD instruction set, and wide data-parallel work (graphics, AI and large-language-model inference, the array languages APL and K) is done by memory-mapped devices (chapter 8). *(D)*

B.1.11.2 Open are the number formats and operations of the devices and the reconciliation of the device descriptors with the standard descriptor; the six questions are: where data-parallel work lives (coprocessor, packed lanes in the integer registers, a fixed-width vector file, a scalable one, a matrix unit); which registers hold vectors; fixed or scalable length; how the machine state is saved on a context switch and whether the kernel may use it; which number formats (half precision, bfloat16, 8-bit integer dot products, 8-bit floating point); and the ABI and compiler support. *(P)*

Commentary. **Precedent.** The PDP-11 sent heavy numerical work to attached array processors; the VAX had a vector extension on its 6000 series, with 16 vector registers of 64 elements, supported by VMS; neither Unix used it much. **Trade-offs.** A fixed-width vector file brings a second register file and its context-switch cost, opcodes, and a new width for every generation (the history of SSE, AVX and AVX-512); a scalable design runs one binary on a small and a large implementation at the price of the most complex specification. Lazy saving of vector state was a security hole on x86, and Linux went back to eager restore. **Benefits.** The coprocessor needs no opcodes and no processor state. **Modern comparables.** ARM SVE and RISC-V V (scalable), ARM NEON, x86 AVX, PowerPC VSX, Alpha MVI. **Use.** Neural-network inference (the LB64 accelerator), graphics, signal processing and the library's string and memory routines. The evidence needed first: compile the corpus at higher optimisation and count vectorised loops, measure the share of time in memory and string routines, and decide the target workloads. **Impact.** *Kernel:* No vector state to save. *Compiler:* No vectoriser for the processor; the runtime lowers array primitives to descriptors. *Hardware:* No register file; the devices carry the width.

B.2 The bus, boot and devices

B.2.1 Data-cache maintenance by address (P6)

B.2.1.1 The proposal is to reserve nothing: DMA buffers are uncached, so no cache instruction is needed until a non-coherent device appears. *(P)*

Commentary. **Precedent.** The 11/70's cache watched DMA writes; the VAX's adapter had data paths to purge. **Trade-offs.** Uncached buffers are slow to read; cache maintenance would speed them and needs three reserved sub-opcodes.

Modern comparables. ARM, MIPS and embedded PowerPC with non-coherent DMA wrap cache maintenance in a DMA-mapping layer; x86 DMA is coherent. **Impact.** *Kernel:* Drivers need no cache code. *Compiler:* None. *Hardware:* No cache-maintenance operations.

B.2.2 Firmware calls (P7)

B.2.2.1 The proposal is none: everything goes through devices, with a required reset register and a watchdog in the bus controller. The kernel survey disagrees and would specify a firmware-call convention on reserved trap vectors. *(P)*

Commentary. **Precedent.** The PDP-11 kernel never called firmware; the VAX had console registers the kernel read and wrote. **Trade-offs.** No firmware means no firmware to trust and no extra privilege level, and every platform must say where its console and reset registers are, which the others get from firmware. **Modern comparables.** RISC-V's supervisor binary interface, ARM's PSCI and secure monitor calls, Alpha's PALcode, SPARC's Open Firmware. **Impact.** *Kernel:* Reboot and power-off through a device register and a watchdog. *Compiler:* None. *Hardware:* A reset register and a watchdog timer in the controller.

B.2.3 Double-width compare-and-swap and a random-number instruction (P8, P9)

B.2.3.1 The proposals are to add neither: the evidence for a 128-bit compare-and-swap is one Linux use (software can tag a pointer with the 25 spare bits instead), and random numbers come from an entropy device on the bus rather than an instruction. *(P)*

B.2.3.2 The random-number pool is one device shared by all cores, with no per-process pool, no version register and no updatable firmware; it assists the operating system's own generator (errata 85). *(D)*

Commentary. **Precedent.** The VAX solved the lock-free queue with whole-queue interlocked instructions; no machine of the period had a random-number instruction. **Modern comparables.** x86 `CMPXCHG16B`, AArch64 `CASP`, RISC-V `AMOCAS.Q`; x86 `RDRAND` and `RDSEED`, PowerPC `DARN`, s390 `PRNO`, AArch64 `RNDR`. **Impact.** *Kernel:* Entropy from a device at boot. *Compiler:* Tagged pointers in software if a double-width compare-and-swap is not wanted. *Hardware:* An entropy source device; no new opcode.

B.2.4 The interrupt controller and routing to cores (R1)

B.2.4.1 The proposal is wired interrupt lines to core 0 with a per-line target register, keeping the eight priority levels, with message-signalled interrupts as an extension. *(P)*

Commentary. **Precedent.** The PDP-11 had no controller; a device asserted one of four request lines and supplied its vector. **Trade-offs.** The smallest design adds no new failure cases and cannot give a fast multi-queue device its own interrupt. **Modern comparables.** x86's APIC, ARM's GIC, RISC-V's PLIC and AIA. **Impact.** *Kernel:* A handler sees one interrupt model. *Compiler:* None. *Hardware:* Wired lines to one core with a target register.

B.2.5 Inter-processor interrupts and starting other cores (R2, B2)

B.2.5.1 The proposal is a per-core doorbell register and a per-core start register in the bus controller (4.7), with `SEV` and `WFE` for waiting. *(P)*

Commentary. **Precedent.** The VAX's console processor started the other processors. **Modern comparables.** x86's INIT and START-UP sequence, ARM's PSCI and spin table, RISC-V's hart-start call. **Impact.** *Kernel:* One register write per core and one per doorbell. *Compiler:* None. *Hardware:* A start register and a doorbell per core.

B.2.6 How coherence scales (R3)

B.2.6.1 The proposal is to keep snooping for the four cores of the first device; the ceiling is now sixteen or more (errata 92), and the protocol for that many is open (7.7.4). *(P)*

Commentary. **Trade-offs.** Directory protocols scale and are large; software coherence is cheap and fragile. **Modern comparables.** x86's snoop filters and directories across sockets, ARM's coherent interconnects. **Impact.** *Kernel:* Cache coherence is invisible to the kernel. *Compiler:* None. *Hardware:* Snooping on two to four cores.

B.2.7 The bus transport (R4)

B.2.7.1 Closed: the transport is PCI Express, with the pdp64's convenience and security circuitry on top (errata 75, 80). *(D)*

Commentary. **Trade-offs.** An ordinary PCI Express device works unchanged, and the Unibus's lock is not a native transaction (the atomics are a monitor, section 2.10). **Modern comparables.** Every current system board. **Impact.** *Kernel:* None. *Compiler:* None. *Hardware:* A standard root complex.

B.2.8 The device layout and the descriptor (R5)

B.2.8.1 Closed: the device interface is virtio, the 16-byte descriptor and the available and used rings of chapter 5 (errata 95). *(D)* The feature subset of each device is open. *(S)*

Commentary. **Precedent.** The RK11 and the DEUNA, as in chapter 5. **Trade-offs.** A standard interface gives up the freedom to shape the registers and gains every existing driver. **Modern comparables.** `virtio`, NVMe, SATA's command lists, Intel Ethernet's done bit. **Impact.** *Kernel:* One transport driver and a thin driver per class. *Compiler:* The descriptor is a generated C structure. *Hardware:* Standard devices.

B.2.9 DMA addressing and protection (R6)

B.2.9.1 Superseded: an IOMMU is part of the design and its five recommendations are accepted (errata 75, 85); bits 40 to 63 of its leaf are free. *(D)*

Commentary. **Precedent.** The Unibus carried only 18 address bits, so the VAX and the larger PDP-11s had map registers that translated device addresses, in effect a simple translation unit for necessity. **Trade-offs.** No protection from a faulty or malicious device; a translation unit matters when virtualisation or untrusted devices do. **Modern comparables.** x86 VT-d, ARM SMMU, the RISC-V IOMMU; Linux's bounce buffers for limited devices. **Impact.** *Kernel:* A driver passes physical addresses. *Compiler:* None. *Hardware:* No translation unit for devices.

B.2.10 Errors raised by devices and the bus (R7)

B.2.10.1 The proposal is the precise and imprecise paths the ISA already has plus a small register block in the bus controller for the cause. *(P)*

Commentary. **Precedent.** A PDP-11 bus timeout trapped through vector 4 and usually ended in a panic; the VAX had a machine-check frame. **Modern comparables.** x86's machine-check banks and PCI Express error reporting, ARM's RAS extension. **Impact.** *Kernel:* One recovery path for device errors. *Compiler:* None. *Hardware:* A small error register block in the controller.

B.2.11 Virtualisation (R8)

B.2.11.1 The proposal is to declare it out of scope for System v1 and fix five constraints: privileged state stays privileged or controllable, the page-table walker could be wrapped by a second level, interrupts are injectable, system-register access can trap, and the translation-enable bit and software accessed and dirty bits are reviewed for what a hypervisor would need. *(P)*

Commentary. **Precedent.** The PDP-11 was not designed for virtualisation and has sensitive instructions that do not trap in user mode; the VAX was not cleanly virtualisable either, and a 1991 paper described the changes needed. **Trade-offs.** Adding virtualisation late cost the VAX instruction changes; settling the constraints early costs a paragraph. **Modern comparables.** x86 VMX with nested paging, ARM exception level 2, the RISC-V hypervisor extension, IBM's trap-and-emulate machines. **Impact.** *Kernel:* A hypervisor could be added without changing a guest. *Compiler:* None. *Hardware:* Constraints on privileged state, the walker and interrupt injection.

B.2.12 Enumeration and hot-plug (N1 to N3)

B.2.12.1 The proposals are enumeration by PCI Express configuration space with the windows placed in the physical address space (N1, closed in outline by errata 80; the placement is open), an interrupt and a rescan on a hot-plug event (N2), and an absent mark with a precise fault and the queued work left in memory (N3). *(P)*

Commentary. See section 2.4 and its commentary: the VAX's nexus scan, PCI's configuration space and all-ones reads, USB's status-change endpoint. **Impact.** *Kernel:* Enumeration and hot-plug are one loop and one rescan. *Compiler:* None. *Hardware:* A standard root complex and the precise fault for an absent device.

B.2.13 The boot decisions (B1, B3, B4, B5, B8)

B.2.13.1 The proposals are a boot ROM that reads block 0 (B1), a boot-information block of memory, cores, the root complex's address and the boot device and console (B3), an `INIT` bit with an optional firmware descriptor (B4) and a block list in the protective MBR's boot code (B8). *(P)* There is no UEFI, with a hand-off and a second stage simple enough for a shim (B5, decided by the author, errata 109, 4.9). *(D)*

Commentary. See chapter 4 and `../boot.md`: the PDP-11's block 0 and ODT, the VAX's boot block and restart parameter block, the BIOS and UEFI (4.9 for the UEFI decision and the shim). **Impact.** *Kernel:* A boot-information struct and a core start register. *Compiler:* The loader and first block are built by the project's compiler. *Hardware:* A boot ROM, a block-0 reader and per-core start registers.

B.2.14 How USB attaches, and virtio first

B.2.14.1 Closed in part: USB is attached over PCI Express, and virtio-net, virtio-gpu and virtio-snd are the standard network, graphics and audio interfaces (errata 75, 79). *(D)* What those decisions do not say is whether USB is a conventional ring-based host controller driven by an existing operating-system USB stack, the proposal of chapter 5, or a controller that does the protocol itself.

Commentary. **Trade-offs.** A controller that does the protocol moves it into the chip and takes the stack out of the operating system; the conventional controller uses code that already exists. `virtio` reuses OpenBSD's existing drivers in the emulator and in silicon. **Modern comparables.** xHCI for the conventional controller; `virtio-mmio` on every emulated RISC-V and ARM board. **Impact.** *Kernel:* A disk driver serves a USB disk; virtio reuses the existing drivers. *Compiler:* None. *Hardware:* USB protocol in the controller costs gates; virtio costs nothing for the emulator.

Appendix C — Glossary

Terms the manual uses, collected in one place. Each entry gives the plain meaning and, in brackets, the chapter or section where the manual deals with it. Terms for the instruction groups (the "escape" opcodes) are listed by name and opcode; the full encodings are in the instruction-set text `../pdp64-isa.md`.

C.1 Architecture and encoding

Term	Meaning
pdp64	the 64-bit extension of the PDP-11 this manual describes, as the PDP-11 extended the PDP-10's ideas down and the VAX extended the PDP-11 up (chapter 1)
tested alternative	pdp64/r20 or pdp64/16: an encoding built and measured against pdp64/32, which is the pdp64, and documented in its own manual (1.8)
parcel	a 16-bit unit of instruction encoding; an instruction is one to three parcels, two to six bytes (9.4)
`len`	bits 15 and 14 of the first parcel: the number of extension parcels for `00`, `01` and `10`; the value `11` selects the second opcode page (9.4)
page 1, page 2	the two opcode maps. Page 1 has 64 top-level opcodes, 58 assigned; page 2 (`len = 11`) has 64 one-parcel entries, 45 defined, each an exact abbreviation of a page-1 instruction (9.1)
top-level opcode	the six bits that select an instruction group; reserved for an operation whose common case is register-to-register (9.1)
escape opcode	a top-level opcode that selects a group by a sub-opcode: `BESC` (bits, `0x0C`), `MBLK` (block memory, `0x0D`), `AESC` (arithmetic, `0x0E`), `MESC` (unaligned and memory ALU, `0x0F`), `FESC` (floating point, `0x10`), `ATOM` (atomics, `0x11`), `XFER` (indirect transfers, `0x12`), `SOP` (single operand, `0x13`), `SYS` (system, `0x14`), `TAGOP` (tag branch, `0x15`)
`CBCC`	compare-immediate-and-branch on condition, opcode `0x28`, the one fused compare and branch (9.10)
`RORI32`	rotate right by an immediate, 32-bit, sign-extended result, a `BESC` sub-opcode
`SOB`	subtract one and branch, either direction (9.10)
`MCPY`, `MMOV`, `MSET`, `MCMP`, `MSCN`, `MSCNN`	the block operations: copy, move (overlap-safe), fill, compare, scan for a byte, scan for the first byte not equal; progress is held in registers so a fault restarts for free (9.11)
`MVAL`	block scan of valid UTF-8, one of the string instructions of the same family (9.9)
`PUSHM`, `POPM`	push and pop a register set named by a mask; the useful half of the VAX's `CALLS` without the frame (9.11)
`JMPI`, `CALLI`	jump and call through a memory word; the only deferred forms, used for PLT stubs and imports (9.10, 9.16)
`JTAG`, `TAGOP`	multiway dispatch on a pointer's low tag bits, and the tag-branch group (9.10)
`LPAD`	marks a legal target of an indirect jump or call; optional in ABI version 1 (appendix A.1)
`CLMUL`	carry-less multiply, the primitive under every CRC and Galois-field operation (9.9)
`XNORPOP`, `POPCNT`	bit-population instructions used by binary operations and bitsets (8.3)
`SET cc, rd`	set a register to 0 or 1 from a condition (9.7)
`DP`	the direct pointer: in user mode it is the thread pointer, in kernel mode the per-CPU pointer; a descendant of the 6502's zero page (9.3, 9.16)
`PSW`	the processor status word: flags, mode, priority and the guard bit (6.2)
`N Z V C`	the four condition flags: negative, zero, overflow, carry (9.3)
canonical address	a 64-bit address whose bits above the top bit of the virtual address (bit 38, 47 or 56 with three, four or five levels) equal that bit; any other value faults, so software cannot hide tags in the high bits (6.6)
`lowtag`	a type tag stored in the low bits of a pointer, free because objects are quad-aligned (instruction-set text, section 6.2; not otherwise used in this manual)
SWAR	SIMD within a register: using one wide scalar register as several narrow lanes through masking and carry-aware arithmetic (instruction-set text, glossary; the manual's bit and byte instructions of 9.9 make it effective)
`FPSR`	the sticky floating-point exception flag register, read and written by `FSFLAGS` (9.12)
ulp	unit in the last place: the spacing between adjacent floating-point numbers, the unit of rounding error
Payne–Hanek	the argument-reduction algorithm that computes x mod π/2 to full precision for large x; what hardware transcendentals cannot do (instruction-set text, section 9.7.1; the manual's account of floating point is 9.12)
Table Maker's Dilemma	that correct rounding of a transcendental may need unboundedly many bits to resolve a near-tie, so no fixed-time circuit can guarantee it (instruction-set text, section 9.7.1)
block floating point	integer mantissas sharing one exponent, used by the LB64 accelerator so fixed-point accumulation is exact (8.3)

C.2 Memory, protection and the kernel

Term	Meaning
`MT`	memory type, a two-bit page attribute: normal cached, normal uncached, device strongly ordered (2.3, 6.7)
`ASID`	address space identifier: tags translation-buffer entries so a context switch flushes nothing (6.8)
`G` **bit**	global: a translation-buffer entry that ignores the `ASID` (6.8)
TLB	translation lookaside buffer: the cache of page-table entries; `TLBI` invalidates one, `TLBIA` all, `TLBSYNC` waits for other cores (7.5)
`DMW`	direct mapping window: a region translated by a fixed offset with no page table; stored without effect, the format is open (6.9)
`MMUCTL`	the register that enables translation and sets the table base (6.5, 6.8)
virtual address, physical address	the number a program uses, and the number the memory answers to; the page tables translate one into the other (6.6)
page, frame, page table	a 4 KB piece of virtual space, a 4 KB piece of physical memory, and the tree of tables of 512 entries that says which frame holds which page (6.6)
PTE	page-table entry: one 64-bit word with the valid, permission, accessed, dirty, global and memory-type bits and the physical page number (6.7)
leaf, pointer	the two kinds of page-table entry: one that maps a page (`R`, `W` or `X` set) and one that points to the next table (6.7)
`KT11`, `PAR`, `PDR`	the PDP-11's memory-management unit, with eight pairs of page address and page descriptor registers for each mode (6.1, 6.6)
`EPC`, `EPSW`, `EVA`, `ECAUSE`	the registers that exception entry writes: where to resume, the old status word, the faulting address, the vector number (6.3)
`VBR`	the vector base register: where the table of 512 eight-byte entries begins (6.3)
`ISYNC`	makes earlier writes to system registers take effect: wait for earlier instructions, discard later ones, fetch again (6.5)
`MFSR`, `MTSR`	move from and to a system register, by number (6.5)
software-managed `A`, `D`	accessed and dirty bits set by the kernel's page-fault handler, never by the walker (6.8)
shootdown	removing a stale translation from the buffers of other cores; on the pdp64 `TLBI` broadcasts and `TLBSYNC` waits (6.8)
walker	the hardware that reads page-table entries on a translation-buffer miss (6.6)
`STUA` / `CLUA`	set and clear the user-access guard bit, which lets kernel code touch user memory only inside the copy routines (6.10)
`PROBER` / `PROBEW`	test whether an address is readable or writable in a given mode without faulting (6.10, 6.13)
W^X	write xor execute: no page is both writable and executable; OpenBSD enforces it (appendix A)
PIE	position-independent executable: loadable at any address; costs nothing here (9.16)
GOT, PLT	global offset table and procedure linkage table: the indirection that lets position-independent code reach imported symbols (9.16)
ABI	application binary interface: calling convention, register use, data layout; version 1 is given in appendix D
trap, exception, interrupt	a deliberate entry (`TRAP #n`), a fault raised by an instruction, and a signal from a device; all enter through the vector table (6.3)
precise fault	a fault after which every earlier instruction has completed and no later one has changed state (6.4)
`SPL`	set the interrupt priority level (6.3)
`WFE`, `SEV`	wait for an event and send an event: the idle and wake-up pair (7.6)
`FENCE`	orders memory accesses; owed to devices and to other cores (2.8, 7.2)
`ATOM`, **monitor**	the atomic operations, built on a reservation monitor as in AXI and ARM, not a locked bus cycle (7.3)
SMP	symmetric multiprocessing: several identical cores sharing memory (chapter 7)
core class	the read-only register of each core that gives its class and capacity, so that software can tell an in-order core from an out-of-order one (7.8.4)
secure core	a core with every timing channel removed (every instruction and cache fetch takes a time independent of its data), private cache lines and no periodic tick (7.8.6)
dedicated core	a core given to one job, graphics, network or audio; proposed (7.8.7)
coherence, snooping MSI	the protocol that keeps each core's cache consistent with the others; snooping means each cache watches the bus; MSI is its three states (modified, shared, invalid) (7.7)
sequential consistency	the memory model in which all cores see all accesses in one order; the pdp64 declares it (7.2)

C.3 The bus, devices and boot

Term	Meaning
Q64	the system bus: the PDP-11 Q-bus lineage widened to 64-bit data and a physical address of 40 to 64 bits (2.3)
Unibus, Q-bus	the PDP-11's buses; Q64 keeps their programming model, with devices in the address space (2.3)
`DATIP` / `DATO`	Unibus and Q-bus transaction types forming a locked read-modify-write (2.10)
window	a region of the physical address space that a device's base-address register describes, a whole number of pages, found by enumeration (2.4, 5.3)
root complex	the PCI Express root of Q64: it enumerates the functions, assigns their windows, and reports arrivals and departures (2.4)
bridge	a function that is itself a bus: it presents the functions behind it, so arbitrary buses (PCI Express, USB) can be connected to Q64 and enumerated to any depth (2.4.3)
MMIO	memory-mapped input/output: device registers reached by ordinary loads and stores (5.3)
DMA	direct memory access: a device moving data to or from memory without the processor (5.10)
virtqueue, descriptor, available ring, used ring, doorbell	the common device protocol: a table of 16-byte descriptors in memory, a ring in which the driver offers chains, a ring in which the device returns them, and a write that tells the device to look (5.4)
`device_status`	the common-configuration field through which the driver and the device handshake; writing zero resets the device (5.4, 5.5)
virtio	a standard family of devices of the same queue-and-descriptor shape, the pdp64's device interface (5.4)
virtio-blk	the standard disk: a virtqueue of read, write and flush requests (5.6.1, 5.6.2)
NVMe, SCSI, ATA, SATA	storage interfaces, each a command queue in memory and a doorbell, which is the same device pattern (5.4); an NVMe device may be attached as any PCI Express device may, but the standard disk is virtio-blk
driver, strategy routine, device switch, probe, attach	the kernel code for one kind of device; the routine that queues one block transfer; the table of such routines indexed by the major device number (`bdevsw`, `cdevsw`); the routines that test whether a device is present and set it up (5.1, 5.5)
`INIT` and `READY`	the PDP-11 CSR's reset command and done bit; on the pdp64 the `device_status` handshake (5.5)
softc, `cfattach`	OpenBSD's per-device structure and the table of a driver's `match` and `attach` functions (5.13)
HDMI transmitter	the chip that takes a pixel stream and does the link protocol; the pdp64 side is a pixel generator and registers (3.12)
`VIC-64X`, `SID-64X`, `BLT64`	the video, sound and blitter devices of the graphics terminal, which is based on the Commodore 64 (video and sound chips) and the Blit terminal (framebuffer and bit-block transfer) (chapter 3)
Blit	Rob Pike's bit-mapped windowing terminal: an 8 MHz Motorola 68000 machine that received downloaded code, characters and editing messages from its host over a serial line and drew every pixel itself (its description as a precursor of the X11 protocol and of NeWS is stated by no source read *(S)*; the lineage the sources confirm runs from its `mux` to 8½ and `rio`); a framebuffer in the address space and a bit-block-transfer operation, done in software, that moves rectangles of pixels; with the C64, one of the two machines the pdp64's terminal is based on (3.1)
blitter, raster operation	a device that copies and combines rectangles of pixels; the raster operation says how source and destination combine (3.8)
scanout, tearing, double buffering	the display reading the picture out of memory row by row at a fixed rate; the seam where a picture changed during the reading shows old above and new below; drawing the next frame in a hidden second picture and swapping at the vertical blank (3.17)
glyph map, glyph atlas	a table of slots each holding the picture of one glyph, filled by a TrueType engine (3.9); the GPU form is one texture holding every glyph the screen uses (3.7)
rio, NeWS	Plan 9's window system, in which each window is a private screen served as files, a descendant of the Blit's `mux` through 8½; and Sun's window server that programs downloaded from the host could extend (3.19)
mixer, ring buffer, underrun	the program that sums the sample streams of several programs into one after converting their rates and formats; the circular buffer the sound device reads at the converter's clock; the reader reaching samples not yet written, audio's tear (3.20)

Term	Meaning
GPU, shader	a graphics processing unit, thousands of simple lanes; a shader is a small program it runs for every vertex or every pixel (3.6)
bootstrap, boot ROM, block 0	the program that loads programs; the ROM in the controller chip that reads the first block of the boot device into memory and jumps to it; that first 512-byte block (4.1, 4.4)
BIOS	the PC's firmware: bring-up and self-test, the first sector, a library of services called by software interrupt, and setup; the pdp64's "BIOS" is its boot ROM and monitor, with no resident services; open source (4.2, 4.3)
first stage, second stage, `installboot`	the program in block 0, which carries a list of where the next program lies; the C program that reads the label and the file system and loads `/bsd`; the tool that writes the first stage and its list (4.3, 4.5, 4.6)
partition, MBR, protective MBR	a named region of a disk; the PC's first sector, with 446 bytes of boot code, a four-entry table and `0xAA55`; the MBR of a GPT disk, with one entry of type `0xEE` covering the disk (4.2, 4.5)
GPT, disk label	the GUID partition table wrapped around the disk's own label so other systems see the disk is in use; the BSD label that names the root, swap and other partitions inside one partition (4.2, 4.5)
boot-information block	the structure whose address the second stage passes in `r1`: memory ranges, cores, the root complex, the boot device, the console, the screen, the command line (4.6)
UEFI, PE/COFF, shim	the PC's later firmware standard, which runs a loader file of the PE/COFF format and offers it boot services; not used by the pdp64; a shim is the small program that would offer those services over virtio to an existing loader (4.2, 4.9)
`ODT`, monitor, watchdog	the PDP-11's console debugger; the ROM's console program for examine, deposit, load and start; a timer that restarts the machine if the kernel stops writing to it (4.1, 4.10)
INIT, START-UP, spin table, hart	x86's signals that start another core; ARM's table the waiting cores poll; RISC-V's word for a core; the pdp64 writes a start register instead (4.7)
LB64, MX64, VEC64	the inference accelerator and its companions: sign-flip-accumulate layers, floating-point multiply-accumulate for attention, and element-wise vector work (8.3)
APL, K	array languages whose primitives work on whole arrays; one primitive maps to one descriptor (8.4)

C.4 Process and sources

Term	Meaning
errata	the numbered decision log of the project (`../errata.md`, appendix F)
fair corpus	the 827 or 841 C files that every back end compiles, used for all size comparisons (1.5)
`pcc`	the portable C compiler the project extends to emit pdp64 code (1.5)
`sim64`, QEMU	the instruction-set simulator and the full-system emulator the tests run on (1.5, 10.4; not otherwise described in this manual)
(D), (P), (S)	the tags on a numbered statement: decided, proposed, stub (index)
Impact	the line ending each decision's commentary: effect on the kernel, on the compiler and on the hardware layout (index)

Appendix D — The ABI, version 1

The application binary interface fixes how compiled code, the linker and the operating system agree: the sizes of types, which registers carry arguments and results, who saves what, how the stack looks, and how position-independent code reaches its data. These are decided choices (section 9.16 states what the instruction set makes cheap). The source is `../abi.md`; the compiler, the assembler and the linker follow it, and the version number allows a later change without breaking old binaries; in version 1 `long double` is `double`.

D.1 The conventions

Data model	LP64: `char` 8, `short` 16, `int` 32, `long` 64, `long long` 64, pointers 64. Little-endian. `char` is signed. `long double` is `double`.
Alignment	natural; the stack pointer is a multiple of **8** at all times (data alignment is architectural, ISA 7.4: a quad access to an address not a multiple of 8 aborts; the 2-byte parcel alignment is for instructions only). No 16-byte alignment: no type or register is wider than a quad.
Registers	`R0-R5` arguments, `R0` (and `R1`) results, `R0-R7` and `R12` caller-saved; `R8-R11`, `R15` callee-saved; `R12` linker scratch; `R13` frame pointer (callee-saved, optional); `R14` stack pointer.
Floating point	`binary64` in a general register, `binary32` in the low 32 bits sign-extended (ISA 2.3); passed and returned exactly like integers.
Arguments	in order in `R0-R5` (a struct of up to 16 bytes takes one or two consecutive, as many as needed); the rest pushed right to left, each in an 8-byte slot (a larger struct in as many slots as it needs, by value).
Results	`R0`; `R0:R1` for a 128-bit pair or a struct up to 16 bytes; a larger struct through a hidden pointer passed in `R0` (the arguments then start at `R1`), and returned in `R0`.
Calls	`CALL`/`CALLI` push the return address; `RET` pops it. The caller removes stack arguments.
Varargs	the callee stores `R0-R5` in a save area directly below the stack arguments; `va_list` is a pointer into the area, then on into the stack arguments. One area suffices because floats use the same registers.
Red zone	none (version 1).
Symbols	no leading underscore.
Landing pads	off in version 1; the assembler provides `.lpad`.
PIC	globals through `d(PC)`; imported symbols through `MOVQ got(PC),Rd`; calls to imports through `CALLI got(PC)`; TLS local-exec `MOVQ off(DP),Rd`.

D.2 Variadic calls

In a call to a function declared with …, every argument goes in an 8-byte slot, in order: slots 0-5 are `r0-r5`, later slots are on the stack. A structure of any size is passed by value in consecutive slots and may split between `r5` and the stack. A variadic callee leaves its named parameters in their slots (`fp+16+8k`) and `va_start` is the address after the last named slot; `va_list` is a `char *` and `va_copy` is assignment. The prologue pops the return address, pushes `r5`..`r0` and pushes the return address again, so the register save area is contiguous with the stack arguments.

D.3 What the ABI leaves open

Lazy against eager binding, mandatory landing pads and whether imports are always called without a PLT stub beyond version 1 are open (section 9.16, decisions in appendix B).

Appendix E — The assembly language and the object format

The assembler's source layout is the V7 assembler's, `as`; its lexical rules are C's. This appendix is the syntax of a source file: lines, labels, numbers, strings, operators, directives, registers, the operand modes, the mnemonic conventions and the object format. The grammar itself is `spec/pdp64-asm.hbnf`; the source of this appendix is `../asm-syntax.md`. The mnemonics are in the instruction dictionary.

The grammar is `spec/pdp64-asm.hbnf` (hbnf text rules); `tools/check-asmsyntax.sh` generates the parser and runs `tests/asmsyntax.c` over it, and `tools/check-as64.sh` assembles `tests/asm/*.s` and compares the bytes with hand-worked expectations.

- **Lines.** One statement to a line. `;` starts a comment that runs to the end of the line.
- **Labels.** `name:` defines a label; `1:` defines a numeric label, referenced as `1b` (the nearest one before) or `1f` (the nearest after). `sym = expr` assigns. `.` is the location counter. Names are letters, digits, `_`, `.` and `$` and any non-ASCII code point (`café`, `Ж–ブ`); a name may start with a digit as long as the whole bareword is not a number (`3dfx:` is a label; `3`, `0x3d`, `0b101`, `0o17` are numbers; `1f` and `1b` are local references), and a bareword of digits only is a numeric local label. Names are case-sensitive and never truncated. ELF symbol names are any bytes, so a name with other characters is written in double quotes (`"odd name!"`). A mnemonic or register name cannot be a label, and neither can `r` followed only by digits: `r16` is an error, not a name (`r2d2` is a name).
- **UTF-8.** A source file is UTF-8, and the parser refuses anything that is not (a stray byte, an overlong form, a surrogate, a truncated sequence), in names, strings, characters and comments alike; a NUL byte is refused too. In a string, UTF-8 text is copied as bytes and `\u00e9`, `\U0001F600` are written as UTF-8; `'é'` is the code point 0xE9, as is `'\u00e9'`.
- **Numbers and characters** are C's: decimal by default (`010` is ten), `0x`, `0b` or `0o` when asked for; `'a'`, `'\n'`, `'\x41'`, `'\101'`.
- **Strings** are `"text\n"` with C's escapes (`\n \t \r \a \b \f \v \0 \\ \' \" \xHH \ooo`), in `.byte` and `.ascii`.
- **Operators** are C's: `* / % & << >>` and `+ - | ^`, unary `- ~ !`, and parentheses. `/` is division. `*`, `/`, `%`, `&` and the shifts need constants; `+` and `-` accept one relocatable symbol, and the difference of two symbols of one section is a constant.
- **Directives.** `.text .data .bss .globl .comm .byte .word .long .quad .ascii .even .align .space .lpad .pool. .word` is 16 bits, `.long` 32, `.quad` 64 (the ISA's PDP-11 terminology). `.align n` aligns to n bytes (a power of two).
- **Registers.** `r0`..`r15`; `sp` is `r14`, `fp` is `r13`. `pc` and `dp` appear only as a base: `d(pc)`, `d(dp)`.
- **Operand modes** (ISA section 5): `rN`; `#expr`; `@expr`; `expr(rN)` and `(rN)`; `expr(rN)(rX*s)` with `s` 1, 2, 4 or 8; `expr(pc)`; `expr(dp)`; `(rN)+` and `(rN)+d`; `-(rN)` and `(rN)-d`; a bare expression is a PC-relative reference.
- **Mnemonics** are lowercase (`movq`, `add`, `bne`). A multi-register instruction writes its destination last: `add src, rd`, `xnorpop ra, rb, rd`. `cmp` is the exception, `cmp rd, src`, because the encoding computes `rd - src`.
- **Compare and branch.** `cbCC rd, #imm, label` compares `rd` with a 5-bit signed immediate (-16 to 15) and branches on the condition: `cbeq r3, #5, label`. The mnemonics are `cbne cbeq cbpl cbmi cbvc cbvs cbcc cbcs cbge cblt cbgt cble cbhi cblos` and the aliases of the branch group (ISA §4.4.1). With a register as the second operand, `cbCC ra, rb, label` compares two registers (`cbeq r1, r2, label`, ISA §4.4.1), in four bytes or, beyond 4 KB, six. `rori32 rs, #n, rd` rotates the low 32 bits right and sign-extends the result (ISA §4.6). The immediate of `cbCC` may be up to 16 bits (`cbeq r3, #255, label`); the assembler chooses the four-byte, the wide or the long encoding, and refuses a wide immediate whose target is more than 64 KB away (ISA §4.4.1).
- **Literal pool: `=expr`.** An operand written with a leading `=` is syntactic sugar for a pooled constant and has no other meaning: `movq =0x123456789ABC, r1` puts the 64-bit value in the literal pool and loads it with one PC-relative `movq`. It is accepted where a quad memory source is (`movq`, `push`, the ALU group with the register first for `cmp`: `cmp rd, =K`, and the floating-point ALU ops), and refused for sized moves, shifts, stores, `lea` and a relocatable symbol. `=` always pools, even a small value; use `#imm` for a constant that fits the signed 32-bit field. A bare `#K` that does not fit that field is an error ("use =K to load it from the literal pool"): the assembler never pools silently. Entries are 8 bytes, 8-byte aligned, one per distinct value per pool, in order of first use, emitted into `.text` at the end of the section or at the directive `.pool` (flush now; code must jump over a mid-section pool). The `=` marks the sugar on the page, which is why it is allowed.

- **Length.** The assembler chooses the shortest encoding, including the one-parcel forms of page 2 (ISA §4.18); those forms have no mnemonics of their own, so `movq (r3), r1` assembles to the one-parcel form when it fits and to the long form when it does not.
- **Invocation.** `as64 -m pdp64/r20|pdp64/16|pdp64/32 [-o obj] file.s`: `-m` selects the encoding (the default is `pdp64/r20`; `r20`, `16`, `32` and `old` are accepted) and the object records it in its `e_flags`; `ld64 [-M] [-o out] objects...` refuses to link objects of different encodings.
- **`llvm-mc`.** The LLVM back end's assembler (`llvm/`, ISA-checked against `as64` by `llvm/check.sh`) accepts this syntax with these exceptions: no literal pool (`=K` and `.pool`), no names that start with a digit, no non-ASCII names, and `.comm` needs its alignment written (`as64` implies 8). `(pc)` and `(dp)` without a displacement are accepted by `as64` (displacement 0) and by `llvm-mc`.
- **Object format.** ELF64, little-endian, `e_machine` 0xF064 (`EM_PDP64`); relocations `R_PDP64_D64`, `R_PDP64_D32`, `R_PDP64_INSN_ABS`, `R_PDP64_INSN_PC`, `R_PDP64_INSN_BR` (`as64/relocs.h`; LLVM: `ELFRelocs/PDP64.def`).

What it leaves out of V7 `as`: octal numbers by default, `<string>` and the `'\e` escape, `\/ \< \>` and `[ ]` in expressions, `.if`, `.stabs`, symbols cut to eight characters.

Appendix F — The evidence behind the manual

The manual states decisions; these are the documents that hold the evidence, the surveys and the long arguments they were drawn from. Each is a document of the repository, not a chapter of this manual, and each says in its own opening what it is based on and what it did not check. They are listed with what they hold and their status; the *Why it is here* paragraphs of the instruction entries and the *Impact* lines cite them.

F.1 The architecture, in full

Document	What it holds
pdp64-isa.md	the full instruction-set text with every encoding, the rejected features, the idioms lost and restored, the comparison with the PDP-11 and the VAX
pdp64-system-architecture.md	privilege, exceptions, interrupts, memory management and boot as an operating system sees them, with what is undefined stated plainly
pdp64-system-design.md	System v1: the options, how others do it, and how the choices serve the project's goals
pdp64-q64-bus.md	the system bus and its devices
boot.md	boot and bring-up: how the main systems start themselves, whether UEFI is worth having, and the proposal
pdp64-in-order-and-out-of-order.md and pdp64-ooo-readiness.md	what the in-order design point costs and buys, and what the architecture must decide to stay ready for an out-of-order core
pdp64-fpga-plan.md and pdp64-lb64-accelerator.md	the FPGA build plan and the inference accelerator
abi.md and asm-syntax.md	the ABI and the assembly language (appendices D and E are drawn from them)
roadmap.md	the order of work from the present toolchain to an OpenBSD that can be logged into

F.2 The record of decisions

Document	What it holds
errata.md	every decision, numbered, with the reasons
decisions-pending.md	every open decision, with the need, five options, the survey of what other systems do and what the PDP-11 and VAX did (appendix B is drawn from it)
fact-check-2026-10-22.md	the comparison of statements about the outside world with a source where one could be read; the claims it could not check are marked "not confirmed" in the manual

F.3 Measurements and surveys

Document	What it holds
codegen-analysis.md	what compiled C says about the instruction set: instruction use, operand forms, the instructions never emitted
kernel-asm-survey.md	what Linux, FreeBSD, NetBSD and OpenBSD write in assembly, and what pdp64 can learn from it
kernel-pain-points.md	what hurts kernel developers: tight loops, pain points and workarounds in the current kernels, from the source trees and the mailing lists, compared with pdp64
hardware-vulnerabilities.md	the processor, memory and system flaws of the last decade that needed mitigations, and the rules that keep pdp64 from repeating them, including the evidence on constant-time modes
openbsd-mitigations.md	OpenBSD's memory-safety and exploit mitigations, what pdp64 gives for free and what would make the rest soft and easy
sim64.md	the reference emulator
smp-decisions.md	the open symmetric-multiprocessing decisions, proposals awaiting the author's annotations (tag P)

Document	What it holds
crypto-secure-core.md, security-proposals.md, study-proposals.md, retire-stage-candidates.md	the proposals on the secure core, the security mechanisms, the studied instructions and the retire-stage mechanisms, with the author's replies in errata 84 to 86
priority-lists.md	the lists of priorities that errata 83 settled

The data behind the tables is in `docs/codegen-data/`, the generators are in `tools/`, and the sources of the design discussions are `chat01.txt` and the archive of the working session.

Appendix G — The evolution of the design

The design began as a small question and grew by steps. In the author's words of 2026-11-10: "we started off as a pdp16 modernized a tiny bit, then got more and more ambitious", and "the initial idea was, could a pdp16 run effectively today with a blit terminal and off-loaded 8-register nic", with "the blit being a mashup with the c64 for audio". This appendix lists, in point form, how it grew and which influences, inspirations and precedents entered, each with the date and time (UTC) of the message in which it first appeared.

G.1 How it grew

- 2026-08-23 05:50 — the founding question, in his first message about it: an Ethernet card "that held the entire tcp ip udp icmp stack inside itself ... so that a pdp11 could plug it in and use it", and whether the PDP-11 could use the Blit terminal (813:0)
- 2026-08-23 05:58 — wider addresses: "was there a 22 bit pdp11?" (813:6); at 06:19: "What if all addresses were expanded to 22 bit? ... an update to the pdp11 arch" (813:10)
- 2026-08-23 06:21 — "Is there pdp11 fpga?" (813:12); at 06:46: "Could I have dozens of pdp11 on a postage stamp? How about the blit?" with 24-bit colour and 1024x768 (813:18)
- 2026-08-23 19:54 — "combine 8 pdp11 systems plus one blit system and a smart nic ethernet card all together on one silicon die" (519:2)
- 2026-08-28 19:31 — "if one implemented pdp11 without the peripherals, what is involved?" (792:0)
- 2026-08-29 00:29 — the first design brief: "assume mmu and fp units"; in the same message the C64 graphics and audio, a modern USB keyboard and mouse and an NVMe disk are asked for (531:0)
- 2026-08-29 00:29 — the Blit as the terminal, mashed up with the C64: "could we revamp the blit to be c64 adjacent", since "c64 is superior to blit terminal in many ways" (531:0)
- 2026-08-29 00:49 — the 8502 chosen over the plain C64 as the partner: "they seem much closer to each other"; the same message fixes little-endian and a 200 to 300 MHz FPGA clock (531:4)
- 2026-08-30 09:13 — the 32-bit step skipped: "skip 32 bit version and go straight to 64bit" (533:8)
- 2026-08-30 09:15 — and the widening stated: "basically upgrade pdp-11 straight to 64 bit" (533:10)
- 2026-08-30 09:30 — a constraint on the widening: "only 2 byte memory alignment; don't put 8 byte memory alignment constraints" (533:14)
- 2026-10-20 19:59 — devices become standard hardware on the bus: "we can put standard gpu on the bus too?" (533:36)
- 2026-10-20 22:44 — multiprocessing enters: what the design needs "to allow smp, symmetric mutiprocessing" (533:61)
- 2026-10-22 16:16 — the ambition of a large machine: "ready for the out of order large scale design" (1889:2236)
- 2026-10-22 20:35 — the early rule of no mode bits becomes "a very soft rule" (1889:2500)
- 2026-10-22 20:48 — the priorities written down: "code size, easy recoverability, and speed/efficiency through fewer gates and tighter hot loops" (1889:2506)
- 2026-10-22 23:01 — security as a design goal: "there should be constant time flag ... so instructions always take an equal amount of time" (1889:2605)
- 2026-10-23 00:49 — the terminal takes the C64's audio: a Blitter terminal "based on a modernized and updated c64 with sid chip and also modern 48 bit audio and 48 bit pixels" (1889:2704)
- 2026-10-23 00:53 — the VAX idea of a device space in the address map is added to the book (1889:j79495)
- 2026-11-04 00:07 — the bus becomes PCI Express with NVMe and USB, with the security fixes of the pain-points document
- 2026-11-04 00:57 — cores dedicated to devices: "also one core for audio processing, doing midi, dsp, etc." (1882:j541)
- 2026-11-04 08:07 — a new instruction encoding: "an encoding scheme that minimizes code size and fits them all in with 32 reg and with 16 reg" (1882:172)

- 2026-11-04 09:57 — "the pdp64 now has children, the pdp64/32 and pdp64/16" (1882:j2434)
- 2026-11-04 19:21 — the first device: "4 cores is enough hopefully that fits on the fpga" (1882:258)
- 2026-11-08 02:37 — the link between Commodore and DEC found: "I found the evidence, there IS a link between C64 and DEC!" (1882:354). The source, a Commodore history of the industrial designer Ira Velinsky, shows one designer who worked for both companies (section 1.1). The author's own description, 2026-11-10 06:47: "the smoking gun that there was indeed intercourse between dec and commodore" (1882:j7644)
- 2026-11-09 07:02 — virtio across the board for the devices, approved for the bus chapter (592:15)
- 2026-11-10 05:30 — "pdp64/32 is the decided upon pdp64"; r20 and pdp64/16 are tested alternatives, no longer part of it (1882:j4575)

G.2 The influences, inspirations and precedents, in the order they were introduced

- Each line: date and time of the first message that named it · the referent · who named it · its stance when introduced (**chosen**: the choice follows it; **rejected**: turned down; **considered**: compared or cited, not decided) · the part of the design it bears on · the source in parentheses (archive thread and message number, or `j` for a message found only in the session files).
- "Later" gives the first date and time at which its stance changed, where it did.
- Only what the messages say: a referent proposed by the assistant is marked so, and counts as an influence only where its line says it was accepted.
- 2025-07-23 22:43 · MS-DOS console font · named by the author · considered — C64 console (c64x), the earlier SDL console: font "reminiscent of the old Commodore 64 font, or the old MSDOS console font" (2224:0)
- 2026-06-18 00:31 · kitty · named by the author · considered — C64 console font and 9p interface: c64x is much the same "but with peek/poke instead of byte stream" (397:9)
- 2026-06-18 00:31 · xterm-256color subset shim · named by the author · chosen — C64 console font and 9p interface: "we'll have a shim that implements xterm-256color subset" (397:9)
- 2026-06-18 00:48 · 9P · named by the author · chosen — C64 console font and 9p interface: "9p all the way"; also a 9p server for window info [397:9] (397:12)
- 2026-06-18 00:48 · vsock · proposed by the assistant, not taken up · considered — C64 console font and 9p interface: he "didn't understand" the vsock question (397:12)
- 2026-06-18 02:54 · Commodore 64 · named by the author · chosen — C64 console (c64x), the earlier SDL console: "as sweet and usable as the C64" (397:44); later rejected 2026-06-25 05:41
- 2026-06-18 02:54 · newLISP · named by the author · chosen — C64 console (c64x), the earlier SDL console: as driver of the console (397:44)
- 2026-06-25 05:41 · RPi 500 keyboard · named by the author · chosen — C64 in spirit, not the hardware: "adequate" (1058:12)
- 2026-06-25 05:57 · original Lisp · named by the author · chosen — newlisp environment: bare function name at beginning of a line (1058:18)
- 2026-06-25 05:57 · Tcl · named by the author · chosen — newlisp environment: some idioms incorporated (1058:18)
- 2026-06-25 05:57 · Smalltalk · named by the author · chosen — newlisp environment: idioms and code browser, but showing all contexts (1058:18)
- 2026-06-25 05:57 · vim · named by the author · chosen — newlisp environment: "incorporate some of vim" into the environment (1058:18)
- 2026-08-23 05:51 · Blit · named by the author · considered — asked how much memory it needs and whether the PDP-11 could use it (813:0); later chosen 2026-10-23 18:57
- 2026-08-23 06:10 · Plan 9 · named by the author · considered — asked how Plan 9 did demand paging (813:8)
- 2026-08-23 06:28 · VAX ISA and DEC Alpha · named by the author · considered — asked how the VAX instruction set compares with the Alpha and the PDP-11 (813:14)
- 2026-08-23 06:36 · DEUNA and DELUA network cards · named by the author · considered — asked about their history and how much of the sockets API and TCP stack they provided (813:16)
- 2026-08-23 06:54 · SIMH · named by the author · considered — asked what it supports (813:22); later chosen 2026-10-13 17:05

- 2026-08-23 06:55 · Qbus and Unibus against PCI and SCSI · named by the author · considered — asked how they differ from modern buses (813:24)
- 2026-08-23 19:45 · Linux and Plan 9 virtual memory · named by the author · considered — asked which is better for the 32V virtual-memory retrofit (519:0)
- 2026-08-29 00:28 · PDP-11 · named by the author · chosen — Mashup of PDP-11 with C64 / M8502: "use pdp-11 as the base" (788:0); later rejected 2026-08-29 00:49, considered 2026-08-30 08:56
- 2026-08-29 00:29 · SID · named by the author · chosen — FPGA target and clock: fold in the good parts of c64 (531:0); later considered 2026-10-24 23:11
- 2026-08-29 00:29 · USB · named by the author · chosen — Modern I/O hardware (USB, NVMe): modern usb keyboard, mouse and hard drive (531:0)
- 2026-08-29 00:29 · NVMe · named by the author · chosen — Modern I/O hardware (USB, NVMe): "nvme hard drive" (531:0)
- 2026-08-29 00:29 · Raspberry Pi SD-card storage · named by the author · considered — Modern I/O hardware (USB, NVMe): asked how those little SanDisk drives interface with rpi (531:0)
- 2026-08-29 00:40 · QNX/QUNIX · named by the author · considered — Mashup of PDP-11 with C64 / M8502: fold design decisions into V7 for realtime guarantees (531:2)
- 2026-08-29 00:40 · Commodore 128 · named by the author · considered — Blit and C64 as the terminal model: asked what advances it had over the c64 (531:2); later chosen 2026-11-04 00:58
- 2026-08-29 00:40 · V7 Unix · named by the author · chosen — Realtime V7 with QNX ideas: "assume v7 source code as the base" (531:2); later considered 2026-10-22 07:46
- 2026-08-29 00:49 · middle-endian longword order · named by the author · rejected — Endianness: "none of this middle endian stuff, that gets fixed right now" (531:4)
- 2026-08-29 00:49 · 6502 · named by the author · considered — Endianness: 8-bit, so word order did not matter there (531:4)
- 2026-08-29 00:49 · IEEE 754 floating point · named by the author · chosen — Floating-point format: new FP unit compatible with the modern representation (531:4)
- 2026-08-29 00:49 · m8502 · named by the author · chosen — FPGA target and clock: mash it up with the PDP-11 instead of the c64, they seem closer (531:4)
- 2026-08-29 01:38 · 8502/6502 compatibility in FPGA · named by the author · considered — Spec revisions and write-up: all registers readable by holding the rdy pin (531:24)
- 2026-08-29 01:38 · 8502 RDY pin hold · named by the author · chosen — C64 island: 8502 registers readable from outside: freeze the CPU to read and write registers (531:24)
- 2026-08-29 07:52 · HDMI · named by the author · chosen — Video output (HDMI): drive it however we want (531:29)
- 2026-08-29 07:52 · PAL/NTSC · named by the author · considered — Video output (HDMI): 50 fps only for legacy code, backwards compat (531:29)
- 2026-08-30 08:23 · x86 · named by the author · chosen — Backward compatibility: adopt what is needed from it to keep transistor count down (533:2)
- 2026-08-30 08:23 · Strecker VAX-11/780 paper · proposed by the assistant, not taken up · considered — Backward compatibility: DEC considered extending PDP-11; opcode-space exhaustion was the reason (533:2)
- 2026-08-30 08:23 · M8502 and x86 · named by the author · chosen — MMU and FP units included: adopt what is needed from them, low transistor count (533:2)
- 2026-08-30 08:23 · VAX-11 · proposed by the assistant, not taken up · considered — Widening the PDP-11 to 64 bits: widened PDP-11 pleasant to write and target (533:2); later chosen 2026-10-20 22:44
- 2026-08-30 09:08 · x86 ah/al · named by the author · considered — Register width: asked for 64-bit registers addressable as two 32-bit halves, sort of like ah/al (533:6)
- 2026-08-30 09:13 · UTF-8 · named by the author · chosen — Word size: showed how the length-first encoding can be done (533:8)
- 2026-08-30 09:13 · ARM32 LDRD / MIPS32 FP pairs · proposed by the assistant, not taken up · considered — Word size: register-pair cost of 32-bit FP, in the case against a 32-bit version (533:8)

- 2026-08-30 09:30 · AArch64 · proposed by the assistant, not taken up · considered — Spec revisions and write-up: holds both rules at once; cited for partial writes (533:14)
- 2026-08-30 09:50 · Lisp machine · named by the author · chosen — Tagged pointers: tagged pointers; hardware tag checking on dereference not added (533:18)
- 2026-10-12 13:17 · dmr cc · named by the author · chosen — dmr optimizations: goal and scope: make the modern pcc pdp11 backend emit identical code, including optimizer (1889:0); later considered 2026-10-13 18:37
- 2026-10-12 13:42 · modern pcc -xssa · named by the author · chosen — dmr optimizations: goal and scope: run in parallel with dmr optimizations (1889:j968)
- 2026-10-12 13:42 · modern pcc SSA optimizations · named by the author · considered — SSA and pcc optimizations alongside dmr: allowed alongside dmr; dropped meanwhile for getnum bug (1889:j968)
- 2026-10-12 13:46 · dmr optimization pass · named by the author · chosen — SSA and pcc optimizations alongside dmr: other optimizations should run after it (1889:44)
- 2026-10-13 15:50 · VAX and x86 platforms · named by the author · chosen — dmr optimizations on other targets: final step after the pdp-11 backend is complete (1889:j5862)
- 2026-10-13 17:22 · pcc · named by the author · chosen — Upstream PortableCC: keep tree up to date with it; keep upstream's fix (1889:j7146); later considered 2026-10-14 00:43
- 2026-10-13 17:54 · VAX backend · named by the author · chosen — mips backend: prioritised over mips (1889:406)
- 2026-10-13 17:54 · nova second pass in pcc · named by the author · considered — mips backend: if pcc ships it, bring the dmr c2 pass in too (1889:406)
- 2026-10-13 18:10 · V7 disk image · named by the author · chosen — simh testing: used for the simh tests (1889:j7762)
- 2026-10-13 18:36 · 32V assembler · named by the author · chosen — VAX output for the 32V assembler: flag so the vax backend emits what 32v as accepts (1889:j7879)
- 2026-10-13 19:46 · 32V cc · named by the author · chosen — dmr optimizations on other targets: original cc, checked for optimizations beyond dmr package (1889:j8486)
- 2026-10-13 19:57 · dmr and VAX tricks · named by the author · chosen — x86 backend changes: document how they worked and bring them to x86 and other backends (1889:434)
- 2026-10-13 19:57 · VAX pcc as good as dmr on PDP-11 · named by the author · considered — x86 backend changes: remarked it sounds like VAX pcc was about as good (1889:434)
- 2026-10-13 19:57 · VAX pcc / 32V · named by the author · considered — Optimization tricks document and optimization docs: "about as good as dmr was on pdp11" (1889:434)
- 2026-10-13 19:57 · x86, then VAX · named by the author · chosen — Optimization tricks document and optimization docs: "do the x86 ones first, then vax" (1889:434)
- 2026-10-17 09:28 · optim2.c · named by the author · chosen — Optimizer placement (optim2.c): put whatever possible there (1889:601)
- 2026-10-17 10:25 · original Unix code (dmr) · named by the author · considered — Documenting bugs and defects: "note any dmr errors in the docs" (1889:j16765)
- 2026-10-17 10:59 · pdp11/vax/x86 backends only · named by the author · chosen — Optimization tricks document and optimization docs: other backends left alone for now (1889:j17625)
- 2026-10-17 21:39 · V7 and 32V old K&R forms · named by the author · considered — Old forms and long long libc documentation: forms pcc doesn't support; cost of supporting them (1889:j24650)
- 2026-10-17 21:39 · C99 · named by the author · considered — Old forms and long long libc documentation: regressions from C99 if old forms were supported (1889:j24650)
- 2026-10-18 06:30 · V7/32V libc side · named by the author · rejected — Long long support and libc helpers: asked to do longlong helpers on pcc side instead (1889:j29864)
- 2026-10-18 07:33 · PDP-11 and VAX-11 · named by the author · considered — Documenting bugs and defects: asks whether pre-existing bugs are only pdp11 or vax too (1889:1075); later chosen 2026-10-22 06:52
- 2026-10-18 16:03 · clang -Os · named by the author · considered — aarch64 against clang -Os: asked if -xdmr beats clang -Os on aarch64 (1889:1114); later chosen 2026-10-22 07:18
- 2026-10-18 16:36 · Lua and SQLite · named by the author · chosen — Benchmark report and corpus: fetch them as test corpora, use for each arch (1889:1124)

- 2026-10-18 16:57 · clang · named by the author · considered — Benchmark report and corpus: asked which backends pcc and clang share; test all (1889:1135)
- 2026-10-18 18:03 · yacc · named by the author · chosen — as32v in the v7unix-toolchain repo and tool naming: use it for the old-yacc grammar (1889:j41256)
- 2026-10-18 18:06 · v7as / v7cc prefix naming · named by the author · rejected — as32v in the v7unix-toolchain repo and tool naming: change policy to asv7, ccv7, cppv7 suffixes (1889:j41544)
- 2026-10-18 22:43 · 32V pcc · named by the author · considered — Benchmark and size reports: name to use for the 32V cc (1889:j44109)
- 2026-10-18 23:52 · modern C inline semantics · named by the author · considered — Benchmark freeze and fixes against stock: inline is a hint, not a command (1889:j44538)
- 2026-10-19 01:56 · GCC 4.7 or older (plain C) · proposed by the assistant, not taken up · considered — gcc cross-build and gcc comparison: would avoid C++ host build; judged not worth the trouble (1889:1291)
- 2026-10-19 04:13 · upstream git history · named by the author · chosen — Upstream PortableCC: source for the pattern of what ragge accepts (1889:j46712)
- 2026-10-19 04:41 · PR #47 aarch64 backend · named by the author · chosen — aarch64 PR 47 reconciliation: compare ours with it and fold in anything good (1889:1346)
- 2026-10-19 07:16 · Debian multiarch include path · proposed by the assistant, accepted · chosen — aarch64 PR 47 reconciliation: /usr/include/aarch64-linux-gnu (1889:1410)
- 2026-10-19 07:16 · Apple Mach-O variadic convention · proposed by the assistant, accepted · chosen — aarch64 PR 47 reconciliation: fix variadic calls for Mach-O (1889:1410)
- 2026-10-19 07:57 · libgcc __addtf3 family · proposed by the assistant, accepted · chosen — aarch64 binary128 support: stage 3: arithmetic and conversions through library calls (1889:1421)
- 2026-10-19 09:22 · GNU libgcc runtime · proposed by the assistant, not taken up · considered — aarch64 long double default (A64QUAD): option 1; depends on GCC being installed (1889:1431)
- 2026-10-19 09:22 · own runtime tools/a64quad/tf.c · proposed by the assistant, not taken up · considered — aarch64 long double default (A64QUAD): option 2; assistant's recommendation, not chosen (1889:1431)
- 2026-10-19 09:27 · gcc cross-compilers for pdp11 and vax · named by the author · chosen — gcc cross-build and gcc comparison: built and measured as comparison reference (1889:1436)
- 2026-10-19 10:33 · gcc -Os · proposed by the assistant, accepted · considered — Benchmark and size reports: size gap explained as GCC deleting undefined-behaviour code (1889:j53715); later chosen 2026-10-21 08:03
- 2026-10-19 20:58 · gcc · named by the author · chosen — Fair corpus and compiler comparison: files gcc cannot compile excluded from the fair corpus (1889:j55479)
- 2026-10-19 22:05 · sjpcc · named by the author · chosen — Fair corpus and compiler comparison: include in the evaluation on vax and pdp11 (1889:j57024)
- 2026-10-20 19:59 · LoongArch64 / AArch64 · named by the author · considered — R7 as a view of the PC: asked how they handle the PC (533:36)
- 2026-10-20 19:59 · LoongArch64 · named by the author · considered — ISA comparison table: asked how they handle the PC (533:36)
- 2026-10-20 20:28 · GPU · named by the author · considered — GPU and accelerator meaning, helper chips: meant as "a helper/accelerator that uses the same ram, does dma" (533:51)
- 2026-10-20 20:28 · SIMD/AVX · named by the author · considered — GPU and accelerator meaning, helper chips: helps like a GPU's, "the simd/avax stuff" (533:51)
- 2026-10-20 20:28 · Samsung LittleBit-2 · named by the author · considered — GPU and accelerator meaning, helper chips: a GPU optimized purely for its encoding (533:51)
- 2026-10-20 23:14 · ror over rol · named by the author · chosen — Mnemonic and width spelling: assistant made the case; assembler could map rol to ror (533:93)
- 2026-10-21 13:17 · Ockham ("ockam") · named by the author · chosen — Efficiency order for PIE: entity-multiplication rule (533:117)
- 2026-10-21 15:20 · asv7 and ldv7 · named by the author · chosen — pdp64 toolchain elements and build plan: port them to assemble and link pdp64 (1889:1699)

- 2026-10-21 15:21 · ELF · named by the author · chosen — pdp64 toolchain elements and build plan: “actually.... elf linker is ok” (1889:j68834)
- 2026-10-21 15:21 · QEMU · named by the author · chosen — QEMU and LLVM targets: wants a plan for a qemu backend for the pdp64 (1889:j68877)
- 2026-10-21 15:29 · V7 a.out with 64-bit variant · proposed by the assistant, not taken up · considered — pdp64 toolchain elements and build plan: assistant’s alternative to ELF64 output (1889:1706)
- 2026-10-21 15:29 · GNU ld / lld · proposed by the assistant, not taken up · considered — pdp64 toolchain elements and build plan: no back end for this ISA; judged more work (1889:1706)
- 2026-10-21 15:29 · ELF64 output (widen ld.c) · proposed by the assistant, accepted · chosen — Spec revisions and write-up: said “yes to all” to the assistant’s proposal (1889:1706)
- 2026-10-21 15:29 · V7 a.out 64-bit variant · proposed by the assistant, not taken up · considered — Spec revisions and write-up: offered as the smaller change (1889:1706)
- 2026-10-21 15:45 · PDP-11 and x86 signed char · proposed by the assistant, accepted · chosen — pdp64 ABI and long double: signed char matches their tradition (1889:1712)
- 2026-10-21 15:45 · modern ELF symbol names (no underscore) · proposed by the assistant, accepted · chosen — pdp64 ABI and long double: instead of V7 leading underscore (1889:1712)
- 2026-10-21 15:45 · software 128-bit long double · proposed by the assistant, not taken up · considered — pdp64 ABI and long double: alternative to same-as-double (1889:1712)
- 2026-10-21 20:37 · asv7 (V7 as) · named by the author · rejected — Assembler syntax and names: not to copy its warts or anachronisms (1889:1745)
- 2026-10-21 20:38 · V7 octal-default numbers · named by the author · rejected — Assembler syntax and names: numbers default to decimal (1889:j69889)
- 2026-10-21 20:46 · C syntax for numbers and strings · named by the author · chosen — Assembler syntax and names: instead of V7 <...> strings and comment slash (1889:1753)
- 2026-10-21 20:48 · modern ELF symbol names · named by the author · chosen — Assembler syntax and names: names and labels follow it (1889:1757)
- 2026-10-21 22:09 · PowerPC 601 · named by the author · considered — Opcode usage, instruction count and pruning: cited as the measure pdp64 already beats; against cutting to about 70 (1889:1845); later chosen 2026-10-23 00:15
- 2026-10-21 22:13 · C round() / libm · proposed by the assistant, accepted · chosen — FP rounding variants: ties-away-from-zero rounding added as a qualifier (1889:1847)
- 2026-10-21 22:16 · carry-less multiply · named by the author · chosen — CRC instructions: replaces both CRC variants (1889:1851)
- 2026-10-21 22:27 · cmov/csel/fsel · named by the author · considered — Integer abs/min/max and conditional select: wants to know more; abs/min/max as assembler aliases on top (1889:j71358)
- 2026-10-21 22:36 · ARM csel family · proposed by the assistant, not taken up · considered — Integer abs/min/max and conditional select: select variants nearly free once the first exists (1889:1865)
- 2026-10-22 06:21 · manpage-style SEE ALSO section · named by the author · chosen — Links and navigation between docs: wants “a manpage style section at the bottom” listing repos and docs (1889:1969)
- 2026-10-22 07:46 · LLVM · named by the author · considered — Undefined items: asks how hard one would be (1889:2073); later chosen 2026-10-23 00:04
- 2026-10-22 07:46 · Linux port (GCC or LLVM back end) · proposed by the assistant, not taken up · considered — Undefined items: a BSD or V7-style Unix is closer to the toolchain (1889:2073)
- 2026-10-22 08:09 · gcc -Os x86-64 / clang -Os · proposed by the assistant, not taken up · considered — One-parcel forms: pdp64 averages 3.36 bytes per instruction against 3.66 and 3.78 (1889:2102)
- 2026-10-22 15:37 · OpenBSD · named by the author · considered — QEMU and LLVM targets: “how does openbsd bring up a new architecture?” vs going straight to 3bsd (1889:2199); later chosen 2026-10-22 18:52
- 2026-10-22 15:37 · 3BSD · named by the author · considered — QEMU and LLVM targets: premise of his question: going straight to 3bsd (1889:2199); later rejected 2026-10-22 18:52

- 2026-10-22 15:38 · LLVM target sources under llvm/ in pdp64 repo · proposed by the assistant, not taken up · considered — QEMU and LLVM targets: assistant proposal, not a GitHub fork; he answered only about machine (1889:2202)
- 2026-10-22 15:47 · major operating systems and architectures · named by the author · considered — Comparison with other architectures: asked how the options compared against them (1889:2207)
- 2026-10-22 15:47 · gcc cross-compilers on other arches · named by the author · considered — System doc: asks what cross-compile infrastructure exists (1889:2207)
- 2026-10-22 16:00 · out-of-order design · named by the author · considered — System doc: asks what supporting it needs and what refusing it costs (1889:2215)
- 2026-10-22 16:16 · ARM32 SRS/RFE · proposed by the assistant, not taken up · considered — PUSHX and POPX: same idea; assistant said from memory, unchecked (1889:2236)
- 2026-10-22 16:28 · Linux and BSD kernel assembly · named by the author · considered — Kernel assembly survey: survey for instructions like popx/pushx that compilers never emit (1889:2258); later chosen 2026-10-22 16:28
- 2026-10-22 16:28 · clang backends · named by the author · considered — Kernel assembly survey: compile the corpus with each to find instructions to adopt (1889:2258)
- 2026-10-22 16:28 · each clang backend that we have · named by the author · chosen — Comparison with other architectures: compile the fair corpus with each to find instructions to adopt (1889:2258)
- 2026-10-22 16:29 · other backends with -Os · named by the author · considered — pdp64 measurement against clang and gcc: asked how pdp64 compares with them (1889:j75313)
- 2026-10-22 16:37 · VAX svpctx/ldpctx · proposed by the assistant, not taken up · considered — Kernel assembly survey document: hardware context switch sidebar (1889:2277)
- 2026-10-22 18:52 · Unix/32V · named by the author · chosen — First operating system port: fallback "if openbsd proves too hard"; has demand paging (1889:2401)
- 2026-10-22 18:56 · AArch64 ldtr/sttr and m68k moves · proposed by the assistant, not taken up · considered — Decisions document: option B: separate access-as-user load and store forms (1889:2406)
- 2026-10-22 18:56 · x86, ARM and RISC-V kernels (incl. OpenBSD) · proposed by the assistant, not taken up · considered — Decisions document: assistant's reason for recommending option A (1889:2406)
- 2026-10-22 19:03 · unix on PDP-11 and VAX-11 · named by the author · considered — Decisions document: asked to compare decisions with what they used to do, and tradeoffs (1889:2413)
- 2026-10-22 19:22 · VAX/PDP · named by the author · considered — SMP and its decisions document: survey "what all major modern os and cpu do, plus vax/pdp" (1889:2426)
- 2026-10-22 20:07 · TUHS source · named by the author · chosen — Fact-checking: already on the box, no download needed (1889:2456)
- 2026-10-22 20:23 · kernel source code · named by the author · considered — Fact-checking: suggested instead of hard-to-access manuals (1889:2484)
- 2026-10-22 20:35 · PDP-11 SR0 / VAX MAPEN · proposed by the assistant, not taken up · considered — Mode bits and the "no mode bits" rule: translation on/off switch, called the heritage choice by the assistant (1889:2500)
- 2026-10-22 20:56 · Linux and BSD current kernel source · named by the author · chosen — Pain-points research: current version only, not full history (1889:2519)
- 2026-10-22 21:01 · mailing lists · named by the author · chosen — Pain-points research: expected pain points from mailing lists, not only source (1889:2526)
- 2026-10-22 21:11 · lwn.net · named by the author · rejected — Browser use, politeness and site bans: avoided after it triggered spammer code; later ban removed [1889:j82932] (1889:2542); later considered 2026-10-22 21:12
- 2026-10-22 23:01 · Spectre · named by the author · rejected — Constant-time execution: design must not repeat it (1889:2605)
- 2026-10-22 23:01 · Rowhammer · named by the author · rejected — Constant-time execution: written as "hammer-row"; design must not repeat it (1889:2605)
- 2026-10-22 23:01 · timing channel attacks · named by the author · rejected — CPU vulnerability avoidance: wants a constant-time flag so instructions take equal time (1889:2605)

- 2026-10-22 23:01 · OpenBSD mitigations · named by the author · chosen — Memory safety from OpenBSD mitigations: make memory-safety mitigations "soft and easy"; improvements "theo would love" (1889:j78280)
- 2026-10-22 23:05 · Linux security · named by the author · chosen — Pain-points research: same list from its people (1889:2612)
- 2026-10-22 23:08 · UEFI · named by the author · considered — Boot process, BIOS and open firmware: asked to look into it (1889:2614)
- 2026-10-22 23:15 · OpenBSD disk partitioning · named by the author · considered — Boot process, BIOS and open firmware: asked where it originated and how it differs (1889:2620)
- 2026-10-22 23:15 · GPT · named by the author · considered — Boot process, BIOS and open firmware: asked how it plays into boot (1889:2620); later chosen 2026-10-22 23:23
- 2026-10-22 23:23 · majority boot block offset · named by the author · chosen — Disk label and boot block: "follow the majority as far as boot block offset" (1889:j78553)
- 2026-10-23 00:12 · PDP-10, PDP-11 and VAX-11 · named by the author · chosen — Manual: deliverable and chapter order: manual to cover what was so great about programming them (1889:2668)
- 2026-10-23 00:14 · old Sanskrit books (aphorism plus commentary) · named by the author · chosen — Manual purpose, style and notation: style: aphorism followed by commentary (1889:j78927)
- 2026-10-23 00:14 · Mishnah and Gemara · named by the author · chosen — Manual purpose, style and notation: same aphorism-then-commentary structure (1889:j78927)
- 2026-10-23 00:17 · VAX and PDP-11 (minimality) · named by the author · considered — Design philosophy and optimization layers: pdp64 is "even more minimal" in hindsight (1889:j78988)
- 2026-10-23 00:41 · ARM-style memory-mapped device · named by the author · chosen — SIMD and vector work: "mmap device arm style route" for SIMD/AVX2 vector work (1889:j79318)
- 2026-10-23 00:41 · AVX2 · named by the author · considered — SIMD and vector work: the SIMD work the chapter covers (1889:j79318)
- 2026-10-23 00:41 · APL/K · named by the author · chosen — SIMD and vector work: mention as making vector languages easier to support (1889:j79318)
- 2026-10-23 00:49 · HDMI, SATA, USB · named by the author · considered — Standard GPU, NIC and audio interfaces: "standard kit", our interface goes through mmio (1889:2704)
- 2026-10-23 00:53 · VAX I/O space · proposed by the assistant, accepted · considered — Address space (VAX I/O space): memory low, I/O above; to be noted in the book (1889:j79495)
- 2026-10-23 01:06 · SCSI/ATA/SATA/NVMe · named by the author · considered — Physical address bit that selects device space: all follow the same device pattern, not limited to 8-register mmio (1889:2713)
- 2026-10-23 01:47 · mkbook.py · named by the author · rejected — Book toolchain, build image and aports: reimplementing what buildabook does (1889:2744)
- 2026-10-23 08:12 · alpine:edge docker with ada-on-alpine · named by the author · chosen — Book toolchain, build image and aports: build and install all the aports on it (1889:2796)
- 2026-10-23 08:57 · buildabook · named by the author · chosen — Book toolchain, build image and aports: replace mkbook.py and push buildabook (1889:2828)
- 2026-10-23 19:01 · USB enumerated over PCIe · named by the author · chosen — Bus enumeration and attached buses: model for q64 enumerating arbitrary attached buses (1889:2941)
- 2026-10-23 20:06 · Plan 9 draw(3)/devdraw · proposed by the assistant, not taken up · considered — Architecture recommendations and open proposals: compared with ring-based command encoding for BLT64 (1889:2962)
- 2026-11-04 00:07 · PCI Express · named by the author · chosen — Q64 bus: DMA design, document and PCI Express base: pcie for the q64 bus, with pain points solved or mitigated (1882:23)
- 2026-11-04 00:07 · IOMMU mapping of C64/C128 · named by the author · considered — Q64 bus: DMA design, document and PCI Express base: "i think we should, but that is extraneous" (1882:23)
- 2026-11-04 15:28 · Steve Johnson pcc VAX optimizations · named by the author · chosen — Dual-encoding toolchain, mnemonics and integration: fold into the -xdmr flag (1882:j2662)
- 2026-11-04 15:30 · hbnf · named by the author · chosen — Grammar as the single source of truth: source of truth for the tools (1882:j2701)

- 2026-11-04 15:30 · Python pivot · named by the author · rejected — Grammar as the single source of truth: "undo your pivot to python" (1882:j2701)
- 2026-11-05 06:58 · hbnf C, Ada, Rust and Zig backends · proposed by the assistant, not taken up · considered — hbnf layout grammar and templates: chart backend would sit alongside them (1882:304)
- 2026-11-05 06:58 · Python chart generator · proposed by the assistant, not taken up · considered — hbnf layout grammar and templates: interim, behind one layout model (1882:304)
- 2026-11-05 07:01 · Mustache · named by the author · rejected — hbnf layout grammar and templates: "the mustache templates are going away" once rewrite rules exist (1882:307)
- 2026-11-05 07:39 · hbnf %emit{} %action{} with prologue/epilogue · named by the author · considered — hbnf layout grammar and templates: asks if C code in the grammar can do the job until rewrite rules land (1882:329)
- 2026-11-08 05:33 · Velinsky (DEC Rainbow and Commodore designer) · proposed by the assistant, accepted · considered — Velinsky link between C64 and DEC: common designer as link between DEC and Commodore (1882:363)
- 2026-11-08 05:34 · C64 and PDP-11 similarities · named by the author · considered — Velinsky link between C64 and DEC: commonalities found, cited as evidence (1882:365)
- 2026-11-09 06:52 · PCIe/NVMe/USB · named by the author · chosen — Device register model: native 8-register devices to virtio: standardizing on the latest buses (592:13)
- 2026-11-09 06:52 · 12 register + dma · named by the author · considered — Device register model: native 8-register devices to virtio: compared with virtio devices (592:13)
- 2026-11-09 07:02 · virtio · named by the author · chosen — Q64 bus: DMA design, document and PCI Express base: "virtio across the board" (592:15); later considered 2026-11-09 07:14
- 2026-11-09 07:02 · native 8-register devices · named by the author · rejected — Q64 bus: DMA design, document and PCI Express base: "forget the native 8 register devices. gone." (592:15)
- 2026-11-09 07:02 · Loongson 5-level TLB · named by the author · considered — Physical address bit that selects device space: asked what else is affected if pdp64 had it (592:15)
- 2026-11-09 09:10 · RISC-V · named by the author · considered — Prefix-coded encodings, 16-register and 32-register grammars: faulted for no comparison of opcode counts or bit layouts with pdp64 (592:38)